
ROAD SIGNS
DETERMINATION OF SUPPORTS AND FOUNDATIONS



DESIGN CHART 1
FREE STANDING SUPPORT

SCALE - N.T.S

NOTE:

1. REFERENCE PLANS

   THIS PLAN FORMS PART OF AND MUST BE READ IN CONJUNCTION WITH DRAWING TD-R-RS-1001

2. DESIGN LOADING

   NOMINAL WIND LOAD ACTING ON THE SIGN FACE HAS BEEN ASSUMED AS FOLLOWS:-

   AVERAGE SIGN HEIGHT L < 2m : 0,75 kPa

   AVERAGE SIGN HEIGHT L > 6m : 1,25 kPa

   WIND LOADING IS ASSUMED TO VARY LINEARLY FOR AVERAGE SIGN HEIGHTS FALLING BETWEEN THE ABOVE LIMITS.

3. FOUNDING MATERIAL

   FOUNDATIONS FOR FREE STANDING SUPPORTS DEPEND ON SOIL TYPE ENCOUNTERED.

   THE GRAPHS FOR "MEDIUM HARD GROUND" ARE APPLICABLE FOR ANY MATERIAL WHICH REQUIRES A PICK FOR EXCAVATION.

   FOR SOFTER FOUNDING MATERIAL THE GRAPH FOR "SAND OR SOFT CLAY" MUST BE USED.

   FOUNDATIONS FOR SIGNS USING BRACED SUPPORTS ARE INDEPENDENT OF FOUNDING MATERIAL TYPE.

   FOUNDATIONS FOR SIGNS LOCATED IN HARD ROCK MAY REQUIRE SPECIAL DESIGNS.

4. DESIGN PROCEDURE

   i) FROM TABLE 1 ON PLAN No. C-02-v1 DETERMINE FOR SIGN WIDTH W , THE NUMBER OF SUPPORTS N AND DIMENSIONS B AND C

   ii) CALCULATE THE EFFECTIVE SIGN AREA A = $\frac{W \times H}{N}$ (m²) AND AVERAGE HEIGHT L (m)

   iii) FROM DESIGN CHART 1 (FREE STANDING SUPPORT), DETERMINE THE FOLLOWING:-

   a) THE TOP DIAMETER OF THE POLE

   b) THE FOUNDATION DIAMETER AND DEPTH FOR THE APPLICABLE FOUNDING MATERIAL. (SEE NOTE 3)

   iv) WHERE THE EFFECTIVE SIGN AREA EXCEEDS 6m² OR WHERE NECESSARY AS INDICATED ON DESIGN CHART 1 , CHART 2 FOR BRACED SUPPORTS MUST BE USED. IN THIS CASE THE POLE TOP DIAMETER AND FOUNDATION SIZES OBTAINED ARE APPLICABLE TO BOTH THE UPRIGHT AND DIAGONAL BRACE MEMBERS.

   v) DETERMINE FROM TABLE 2 THE DIAMETER OF HOLES TO BE DRILLED IN THE POLES AS SHOWN IN DETAIL "A"

5. EXAMPLE (FREE STANDING SUPPORT)

   W = 5m H = 1,8m L = 2,7m

   FROM TABLE 1

   N = 3m B = 0,830m C = 1,670m

   A = $\frac{5 \times 1,8}{3}$ = 3,0m²

   FROM DESIGN CHART 1

   FOR A = 3,0m² AND L = 2,7m


   POLE TOP DIA. = 175mm

   FOUNDATION SIZE = 1,2m DIA. 0,9m DEEP (MEDIUM HARD GROUND)

   OR 1,2m DIA. 1,5m DEEP (SAND OR SOFT CLAY)

   FROM TABLE 2

   HOLES TO BE DRILLED (DETAIL A = 40mm DIA.)



DESIGN CHART 2
BRACED SUPPORT

SCALE - N.T.S

No.	DATE	REVISION
V1	08/03/2024	ORIGINAL VERSION

HEAD OFFICE
48 Tambotie Avenue
Val de Grace
Pretoria
0184

PO Box 415
Pretoria 0001
South Africa

Tel: (012) 844 8000

SANRAL
SOUTH AFRICAN NATIONAL ROADS AGENCY SOC LTD
BUILDING SOUTH AFRICA THROUGH BETTER ROADS

WESTERN REGION
1 Havenga Street
Oakdale
Bellville
7530

Private Bag X19
Bellville
7535

Tel: (021) 957 4600

ACCEPTANCE

THIS ACCEPTANCE IS FOR PROCEDURAL AND ADMINISTRATIVE REVIEW PURPOSES ONLY AND DOES NOT ATTRACT LEGAL LIABILITY OR LIABILITY OF ANY KIND FROM WHATSOEVER CAUSE OR HOWEVER ARISING

for the SA NATIONAL ROADS AGENCY SOC LTD.

Date:

PROJECT DESCRIPTION

THE CAPACITY IMPROVEMENT OF NATIONAL ROUTE 1 SECTION 1 FROM OLD OAK INTERCHANGE (KM 18.90) TO KOELENHOF INTERCHANGE (KM 33.00)

ROAD SIGNS
SUPPORTS AND FOUNDATIONS
DETERMINATION SHEET 2 OF 2

SCALE @ A0: AS SHOWN SHEET 2 OF 2

PROJECT NUMBER	N001-010-2021/1	
DRAWING LOCATION DATA	START	END
ROUTE	N01	N01
SECTION	01	01
DRAWING km DISTANCE	18.900	33.000
DRAWING TYPE	ROADS - ROAD SIGNS	
BRIDGE/STRUCTURE No.	N/A	
CONSULTANT DRAWING No.	312-00827-01-TD30	VER
SANRAL DOCUMENT #	XXXXXX	V1

312-00827-01-TD30