

Noth Elevation
Scale 1:100



East Elevation
Scale 1:100



South Elevation
Scale 1:100



West Elevation
Scale 1:100

INSPECTION & APPROVAL BY ENVIRO-LOO SPECIALIST / SUPPLIER :
Allow two site visits to be made by the enviro-loo suppliers to assist/support the contractor in the installation of the enviro-loo and final inspection to ascertain the enviro-loo has been installed correctly at which time a certificate of compliance should between the end-user department and enviro loo supplier

CARBOLINEUM WOOD PRESERVER
All exposed structural timber is to receive two coats carbolineum. Timber must be dry and carbolineum applied to the entire overhanging roof member sections before the application of roof sheets.

GUTTER / DOWNPIPE
150 x 100 x 0.5mm thick pre-coated zincalume seamless gutter, including matching rivet-fixed mitres and end caps internally sealed using Silicon Mastic, hung by nail fixed internal aluminium hangers at 500mm centres with 100 x 75 x 0.8mm thick rectangular fluted downpipes to 5000L horizontal RWHT

Enviro-Loo CER/ABS-V1 (code FG-1040) Furniture :
- Purpose Made Steel Brackets Fixed to Wall
- 220 Diameter Extractor vent by enviro-loo
- Moulded polyurethane tank cover with a manhole
- Wind-master Extractor Cowl

Stormwater Control :
New cast in-situ re enforced concrete stormwater v-drains to Engineers detail

ROOF
Factory painted 0.6mm Chromadek IBR profile roof sheeting @ 9 Degrees on 50x76mm S.A. pine purlins fixed to rafters @ 750 mm c/c spacing on 38x114 S.A. c/c spacings, on prefabricated timber trusses @ max. of 1200