

Cost Summary	
Site Name	Harding Post Office
Site Size	522 m ²
Site Location :	Harding
City	Harding
Municipality	Umziwabantu Local Munic
Street Address	Corner Field &, Murchison St, Harding
GPS Coordinates	
Expected Period	40 days

Public area	
DDT Storage	
Passage	
Toilets	
Kitchen	
Rest Room	
Cage	
Room 12	
Sorting Area	
Printer Room	
Counters	
Branch Managers Office	
Roof	
Plumbing	

TOTAL COST BEFORE VAT	
15% VALUE ADDED TAX	
TOTAL COST INCLUDING VAT	

AMOUNT TO BE CARRIED OVER TO RFQ DOCUMENT	

				Site Name	Harding PO
Item	Description	UNIT	QTY	RATE	AMOUNT
1	Public area				
1.1	Replace all faulty light fitting with new radiant recessed ceiling lights wired for LED T5 3x18W	each	8		
1.2	Replace missing and damaged 1200 X 600 suspended ceiling tiles including hangs and tee's	each	4		
1.3	Replace missing and damaged timber skirting with 76 x 16mm PVC Skirting's, SPVC100	m	22		
1.4	Remove and dispose damage indoor split air con unit	each	2		
1.5	Replace damaged trellidor cylinder lock	each	1		
1.6	Replace damaged 3 lever motice lock set	each	2		
2	DDT Storage				
2.2	Replace damaged rhino board ceiling including painting ceiling white	m ²	3		
3	Passage				
3.1	Replace damaged rhino board ceiling including painting ceiling white	m ²	178		
3.2	Replace missing Cornices	m	1		
3.3	Supply and install electrical feed to lights in ceiling void, 12m cable (red, black and earth 2.5mm) to DB	each	2		
4	Toilets				
4.1	Replace damaged ad missing vinyl tile with new tiles	m ²	5		
4.2	Repair damaged rhino board ceiling including painting ceiling white	m ²	4		
4.3	Supply and install electrical feed to hand dryers in wall trunking & ceiling void, 12m cable (red, black and earth 2.5mm) to DB	each	2		
4.4	Supply and install electrical feed lights ceiling void, 10m cable (red, black and earth 2.5mm) to DB	each	1		
4.5	Replace damaged WHB with Vitreous china 510 x 405 mm rounded "Hibiscus" basin with two tap hole(colour code 7150)supported on Vaal universal floor mounted pedestel(code7150) including one pair Cobra Half inch Luxury square pattern basin pillar tap no.114 with Carina handles and chrome plated 62mm flange80mm longshank slotted with backnut,plug chain and stay(code310).	each	2		
4.6	Supply and fit 1/2" square pattern basin pillar tap no 114 with Carina handles. Do all necessary hot, cold and waste plumbing connections.	each	4		
4.7	Replace damaged WC with Vitreous china "Hibiscus" with close-coupled 90 degrees outlet open rim pan (Code: 772600) and matching 9-litre cistem (Code: 710531) complete with lid and fitments, colour - White. Complete all plumbing connections, test flush and ensure that correct water level has been set and that operating overflow tube height confirms and operates according to local by-laws and S.A.B.S. specifications, colour - white. Supply and install to each water closet 1 x Cobra Watertech 770 1 3/4" BETA flushing valve. Including white solid PVC (Code B2) toilet seat.	each	2		
4.8	Replace missing Domical grating, Spreader Include concealed or exposed flush valve (Flush master joined - Code F36000) complete with F.I.T. 5/3 flush pines connected up to new urinal	each	1		

5.	Kitchen				
5.1	Supply and fit 1/2" square pattern basin pillar tap no 114 with Carina handles. Do all necessary hot, cold and waste plumbing connections.	each	2		
5.2	Replace faulty bawl light fittings with Fluorescent Light Assembly 1200mm long double T5 light-emitting diode(LED)Fitting including two 28W cool White lamp, White plug round single mounted in ceiling void cable tray, 3m fly leads to cable tray, 12m cable (red, black and earth bare copper 2,5mm) to DB	each	2		
6	Rest Room				
6.1	Repair damaged rhino board ceiling including painting ceiling white	m ²	6		
6.2	Replace faulty bawl light fittings with Fluorescent Light Assembly 1200mm long double T5 light-emitting diode(LED)Fitting including two 28W cool White lamp, White plug round single mounted in ceiling void cable tray, 3m fly leads to cable tray, 12m cable (red, black and earth bare copper 2,5mm) to DB	each	2		

7	Cage				
7.1	Repair damaged rhino board ceiling including painting ceiling white	m ²	1		
7.2	Supply and install electrical feed to lights in ceiling void, 12m cable (red, black and earth 2,5mm) to DB	each	1		
8	Room 12				
8.1	Repair damaged rhino board ceiling including painting ceiling white	m ²	2		
8.2	Supply and install electrical feed to lights in ceiling void, 12m cable (red, black and earth 2,5mm) to DB	each	1		
8.3	Supply and install electrical feed to isolator on wall & in ceiling void, 12m cable (red, black and earth 2,5mm) to DB	each	1		
9	Sorting Area				
9.1	Replace and Repair damaged rhino board ceiling including painting ceiling white	m ²	22		
9.2	Supply and install electrical sub main feed to dedicated plugs DB on wall & in ceiling void, 12m cable to DB	each	1		
9.3	Replace Dedicated plugs DB to comply with Post Office requirements complete with rewiring, Provide electrical CoC on completion.	each	1		
10	Printer Room				
10.1	Replace and Repair damaged rhino board ceiling including painting ceiling white	m ²	1		
11	Counters				
11.1	Replace and Repair damaged rhino board ceiling including painting ceiling white	each	2		
11.2	Remove and dispose damage indoor split air con unit	each	1		
12	Branch Managers Office				
12.1	Repair damaged timber partitioning	m ²	1		
13	Roof				
13.1	Replace damaged roof underlay	m ²	15		
13.5	Clean gutters	m	134		
13.6	Replace and repair damaged section of graduated length asbestors tiles	m ²	15		
14	Plumbing				
14.1	Supply and install a 10m of 22mm polycope pipe including all fittings for toilets and kitchen	item	1		
14.2	Supply and connect all water supply to WC,WHB,Urenal and Kitchen sink using 15mm copper pipes (internally)	item	1		
14.3	Supply and connect all waster lines for WHB and Kitchen sink	item	1		
14.4	sundries	item	1		