

	Tender Questions and Answers	Document Identifier	559-222407715	Rev	1
		Effective Date	July 2024		
		Review Date	July 2027		

To whom it may concern	Date	05 August 2026
	Enquiries	Tshane Lekgoati
	E-mail address	lekgoat@ntcsa.co.za

Dear Sir/Madam

Enquiry Number	E3244NTCSAMWP
Description / Project Title	ACACIA SUBSTATION 33kV CABLE SYSTEM
Tender Questions Closing Date	Ten (10) working days before the deadline for tender submission.

Item	Questions	Answers	Clarity Published Dates
1.	I would like to get clarification on the briefing meeting attendance. Do tenderers attend briefing on Microsoft teams or the meeting will be held in person on site and not online? Please clear the confusion.	Tenderers are required to attend compulsory site clarification meeting on 29 July 2026 at Acacia Substation just off Montague Road / Edgemoed Drive in Edgemoed, Cape Town. The compulsory Site Clarification Meeting will be held in person on site.	23/07/2026
2.	The HV Cable required for this project shall it have Eskom cable marking, or is it not a requirement?	The cable shall have Eskom's marking in accordance with 240-56030625 (Attached).	05 August 2026

Controlled Disclosure

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system. No part of this document may be reproduced in any manner or form by third parties without the written consent of NTCSA SOC Ltd, © copyright NTCSA SOC Ltd, Reg No 2021/539129/30

	Tender Questions and Answers	Document Identifier	559-222407715	Rev	1
		Effective Date	July 2024		
		Review Date	July 2027		

3.	Will the scope of the Removal of existing cable sealing-end structures by civil contractor and six new cable sealing-end structures be complete by the time of mobilisation to site?	We are not removing the existing cable sealing end structures as those belong to the customer (Transnet). We will remove the Isolator structures and foundations in front of the existing (Transnet Cable Sealing Ends) to cast new foundations and Cable Sealing End structures for this cable to be installed. The new Cable Sealing End foundations and structures will be ready when the contractor come to site to install the cable. It must be noted as discussed in the Site Clarification Meeting, that currently we can take out both bays and install the cables at the same time, but there is a risk that Transnet may ask for load (not currently supplied from these bays to them), which will then cause for us to perform the work one bay at a time. The work therefore is outage dependant and we did indicate that the tenderers must make provision for 4 x site returns. Th contractor will have to give us a program for the works, for us to influence and ensure that the work align with the outages.	05 August 2026
----	---	---	----------------

Controlled Disclosure

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system. No part of this document may be reproduced in any manner or form by third parties without the written consent of NTCSA SOC Ltd, © copyright NTCSA SOC Ltd, Reg No 2021/539129/30

	Tender Questions and Answers	Document Identifier	559-222407715	Rev	1
		Effective Date	July 2024		
		Review Date	July 2027		

		Tenderers must not forget that there are two sets of Cable Sealing Ends for each of the two Transformer Bays.	
4.			

Controlled Disclosure

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorized version on the system. No part of this document may be reproduced in any manner or form by third parties without the written consent of NTCSA SOC Ltd, © copyright NTCSA SOC Ltd, Reg No 2021/539129/30