

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
E	SABS 1200	SCHEDULE E: SPECTATOR FENCING				
E.1	C	SITE CLEARANCE				
E.1.1	PS C5.1	Clear and grub area of 2m wide along the length of the proposed chain link fence.	m	150		
E.2		EARTHWORKS				
E.2.1	D 8.3.1.2 (LIC)	Foundation excavation 600 x 600 x 600mm for straight posts	m ³	12		
E.2.2	D 8.3.2(2)	Extra over item E.2.1 for excavation in hard rock.	m ³	1,8		
E.3		FOUNDATIONS				
E.3.1	LIC	Unreinforced concrete foundations, 600 x 600 x 600mm, 15MPa/19mm concrete, 1500mm C/C.	m ³	12		
E.4		CLEARVIEW FENCE				
E.4.1	LIC	Supply and installation of 1.8m high Wiretech 76 x 12.7 (3mm dia) PVC coated Clearview fence, including 2400mm square posts (60x60x2mm) complete with caps and bolts and cover plates, spaced 3110mm c/c. Allow for the supply and installation of manufacturer specified spikes along the full perimeter of the fence.	m	150		
E.5		GATES				
E.5.1	LIC	Supply and install Clearview panel lockable sliding gates, frame to be hot dip galvanised (1200 W x 1800 H), complete with guiding rollers, tracks cast into concrete, wheels/ rollers fitted to gate frames	No.	1		
TOTAL CARRIED FORWARD TO SUMMARY						