

Clarification No. 3 (04.03.2025)

TENDER MPKRI11468GX: The Procurement and Installation Of 3x LP Heaters 4 For A Period Of 5 Years on An as and When Required Basis at Kriel Power Station.

Query

With reference to document “474-12770 Kriel LP Heaters 4 Replacement Technical Specification (Rev 1)” Section 4.4.2:

In section 4.4.2 it states that the U-bends must be heat treated or annealed after bending. If we were to do new 90° bends must the bends still be heat treated or annealed?

Eskom Response

The same heat treatment requirements, as detailed for U-bends, shall apply should any new 90° bends in the tubes be required.

NB: A reminder that the communication platform is the Eskom e-tender portal and that of National Treasury and the responsibility of the tenderer to visit regularly for possible updates. Any revised documents after site meeting, clarification information and minutes will be uploaded as such.