




| Item No. | Description | Unit | Quantity | Unit Price-ZAR, Excl VAT | Total Price-ZAR, Excl VAT |
|----------|---|------|----------|--------------------------|---------------------------|
| 1 | Provision for All Preliminary and General Requirements | Sum | 1 | | |
| 2 | Provision of Health and Safety File | Sum | 1 | | |
| 3 | Site preparation and clearing | m | 2500 | | |
| 4 | Supply and installation of ClearVu/Similar approved fencing (2.4m) | m | 2500 | | |
| 5 | Supply and installation of 30-strand piggyback electric fence | m | 2500 | | |
| 6 | Supply and installation of pedestrian gates | No. | 4 | | |
| 7 | Supply and installation of vehicle gates (truck compatible)-Including Motor | No. | 2 | | |
| 8 | Supply and Installation of Swing Type Gates -Including Motor | No | 2 | | |
| 9 | Supply and installation of PTZ cameras | Sum | 1 | | |
| 10 | Supply and installation of fixed motion detection cameras | Sum | 1 | | |
| 11 | Supply and installation of security horns | Sum | 1 | | |
| 12 | UPS Backup System | Sum | 1 | | |
| 13 | AntiBurrow Fence Installation - 450mm Deep (Minimum 19MPa >28 Days) | m | 2500 | | |
| 14 | Control Room Monitors and Infrastructure | Sum | 1 | | |

| Additional Allowance for Section of Fence in Swamp Area | | | | | |
|---|--|----------------|-----|-------------------------|--|
| 15 | Excavation and Spoil Removal in Swamp Area | m ³ | 450 | | |
| 16 | Supply and installation of Geotextile Membrane | m ² | 300 | | |
| 17 | Supply and installation of 150mm Compacted G5 Subbase Layer | m ³ | 45 | | |
| 18 | Supply and installation of Reinforced Concrete Plinths (25MPa @ 28 days) | m | 150 | | |
| 19 | Reinforced foundation piles for posts (min 2.5m depth with 300mm dia) | No. | 30 | | |
| 20 | Galvanized Post Extensions and Bracing for Stability | No. | 30 | | |
| 21 | Subsoil Drainage System – French Drain with perforated pipe and gravel | m | 150 | | |
| 22 | Final commissioning and handover | Sum | 1 | | |
| | | | | Total (Excl VAT) | |
| | | | | VAT @ 15% | |
| | | | | Total (Incl VAT) | |

| | |
|---|--|
| Compiled By: Qaasim Soeker ,Plant Engineer  Date: 22.05.2025 | Reviewed By : Malusi Biyela , Project Manager  23 May 2025 Date |
| Approved By : Duma Mnqumevu , Head of Projects  Date: 23/05/2025 | |