



26 August 2025

Email: admin@tekrodce.co.za

Enq: Mr Tekani Maswanganyi

CONTRACT NO. MHLM/MIG/02/2025/2026: REHABILITATION OF LEBOYA STREET FROM KGAKALA EXT 4 TO TLADI STREET AND MUTHOBI RINGROAD IN KGAKALA)

Re Addendum to Tender – Addendum No 1

Bidders are informed that the bill of quantities (BoQ) has been revised. Bidders are advised to replace the entire BoQ in the tender document with the attached BoQ on annexure A.


This addendum is issued in terms of the tender document and shall form part of the tender document.

This addendum does not change/impact the nature of the tender. As such, the closing date shall remain the same as indicated on the tender document.

Kindly acknowledge receipt of this addendum by completing the ACKNOWLEDGEMENT OF ADDENDUM below and send it back to admin@tekrodce.co.za. ***Please return only the acknowledgement form only via email.***

Ensure that the addendum is included in the tender document. Failure to acknowledge this addendum may invalidate the Tender.

Regards,



Tekani Maswanganyi For Tekrod Consulting Engineers

On behalf of Maquassi Hills Local Municipality (Client)



ACKNOWLEDGEMENT OF ADDENDUM NO.01

I _____

Representing Messrs _____

Hereby acknowledge that I have received the above Addendum No 1 and that I am conversant with the contents thereof.

SIGNATURE: _____ **DATE:** _____

This Addendum is to be read in conjunction with tender document and shall be deemed to form part of the Contract Documents.

You must therefore acknowledge receipt of this addendum by emailing this form to TEKROD CONSULTING ENGINEERS at admin@tekrodce.co.za and the original must be attached to the Returnable Schedules.

Failure to acknowledge receipt of this addendum` may invalidate the Tender.

ANNEXURE A

TENDER - BOQ

SCHEDULE A : GENERAL

SECTION 1200

GENERAL REQUIREMENTS AND PROVISIONS

ITEM NO	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
	GENERAL REQUIREMENTS AND PROVISIONS				
	(SECTION 1200)				
12.01-LI	Locating Existing Services (to be instructed by the Engineer)	Prov Sum	1	R 25 000,00	R 25 000,00
12.02-LI	Hand excavation to determine				
	The positions of existing services				
	To determine the positions of the existing services	m ³	100		
12.03	Quality Control Test Ordered by the Engineer				
	Provisional sum for the payment of Quality Control Test Ordered by the Engineer	Prov Sum	1	R 75 000,00	R 75 000,00
12.04	Community Liason Officer				
	(a) Salary of Liason Officer and PSC Members	Prov Sum	1	R 68 000,00	R 68 000,00
	(b) Extra over item for contractor's overheads, administration charges and costs.	%	68 000		
12.05	Compliance with Mine Health and Safety				
	(a) Health and Safety Obligations	Month	8		
	(b) Special information sign	Item	1		
	(c) Provision of Security guards	Prov Sum	1	R 100 000,00	R 100 000,00
	(d) Provision of Stock-proof security fencing	Prov Sum	1	R 35 000,00	R 50 000,00
	(e) Handling cost and profit in respect of sub item B12.05(c) and(d)	%	R 150 000,00		
	(f) Provision for rehabilitating of borrow pit	Prov Sum	1	R 15 000,00	R 15 000,00
	(g) Provision of Royalties payment	Prov Sum	1	R 50 000,00	R 50 000,00
	(h) Handling cost and profit in respect of sub item B12.05(f) and(g)	%	R 65 000,00		
	(i) Preparation of Safety File	Item	1		
12.06-LI	Provisional Sum For Protection And/Or Relocation Of Services By Others				
	Provisional Sum for Protection and/or relocation of services by others	Prov Sum	1	R 100 000,00	R 100 000,00
12.07	Provisional Sum For Payment Of Contract Notice Board As Instructed By The Engineer				
	Contractor to Provide Contract Name Board as per Dwg: 01D012	No	2		
12.08	Provisional Sum For Payment Of Engineer's				
	Representative Cellular Phone Account				
	Provisional Sum for payment of Engineer's				
	Representative Cellular Phone Account	Prov Sum	1	R 80 000,00	R 80 000,00
12.09-LI	Cable Ducts				
	Supply, Lay & Backfill 150mm Cable Ducts	m	60		Rate Only
12.10-LI	Relocation Of Services By Contractor				
	(a) uPVC Class 9, 110mm	m	100		Rate Only
	(b) uPVC Class 9, 75mm	m	60		Rate Only
	(c) uPVC Class 10, 50mm	m	100		Rate Only
	(d) uPVC Class 10, 32mm	m	50		Rate Only
12.11	Percentage For Charges And Profit On The Provisional Sums For Contractor's Cost And Profit				
	Percentage for charges and profit on the provisional sums for Items B12.01; B12.03; B12.06 and B12.08	%	R 280 000,00		
12.12	Training For Targeted Labour				
	(a) Training allowance for formal training	Prov Sum	1	R 80 000,00	R 80 000,00
	(b) Extra over for administration of payment of training	%	R 80 000,00		
12.13	Environmental Control Officer				
	(a) EIA & EMP Compliance	Prov Sum	1	R 120 000,00	R 120 000,00
	(b) Extra over for administration of payment of EIA & EMP	%	R 120 000,00		
12.14	Additional Survey as requested by the engineer				
	(a) Additional surveying to be directed by the Engineer	Prov Sum	1	R 40 000,00	R 40 000,00
	(b) Extra over for administration of additional surveying	%	R 40 000,00		
1200	TOTAL CARRIED TO SUMMARY				

[illegible]

SCHEDULE A : GENERAL**SECTION 1400****HOUSING, OFFICES AND LABORATORIES FOR THE ENGINEER'S SITE PERSONNEL**

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
14.01	Office and laboratory accommodation (office Containers with aircon)				
	(a) Offices (interior floor space - engineer's office and conference room)	m ²	50		
	(e) Ablution units	m ²	6		
14.02	Office and laboratory furniture:				
	(a) Chairs	No.	12		
	(c) Desks, complete with drawers and locks	No.	2		
	(d) Conference tables	No.	2		
14.03	Office and laboratory fittings fittings installations and equipment:				
	(a) Items measured by number:				
	(i) 220/250 volt power points	No.	2		
	(ii) Double 80 watt fluorescent light fittings complete with ballast and tubes	No.	2		
	(iii) Single incandescent light fittings complete with 100 watt globes.	No.	1		
	(vii) Fire extinguishers, 2,5kg BCF type complete, mounted on wall with brackets	No.	2		
	(vii) Air-conditioning units with 2.2kW minimum capacity, mounted & with own power connection	No.	2		
14,04	Car ports:				
	Car ports, as specified, at offices and laboratory buildings	No.	4		
14,07	Rented, hotel and other accommodation:				
	(a) Provisional sum for providing rented housing, hotel or other accommodation as described in subsub-clause 14.03(c)(ii)	PC Sum	1	R 144 000,00	R 144 000,00
	(b) Handling costs and profit in re- spect of subitem 14.07(a)	%	R 144 000,00		
1400	TOTAL CARRIED FORWARD				

SCHEDULE B : ROADWORKS
SECTION 1500
ACCOMMODATION OF TRAFFIC

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
15.01	Accommodating traffic and maintaining deviations				
		km	1.8		
15.02	Earthworks for temporary deviations				
	(a) Shaping of deviations	km	1.8		
15.03	Temporary traffic-control facilities:				
	(b) Portable STOP and GO-RY signs	No.	12,00		
	(e) Road signs, R- and TR- series;				
	(i) 1200mm	No.	10,00		
	(f) Road signs, TW- series, dia. 900				
	(i) 1500mm	No.	10,00		
	(g) Road signs, STW-, DTG-, TGS- and TG-series excluding delineators and barricades				
	(i) 1600mm x 1200mm	m ²	15,00		
	(h) Delineators DTG50J, size indicated:				
	(i) Single	No.	8,00		
	(ii) Mounted back to back	No.	8,00		
	(i) Movable barricade/road sign combination, size 1800 x 300 and 900 dia.	No.	8,00		
15.06	Watering of deviations	kl	400,00		
15.07	Blading of by-passes and existing roads used as deviations by grader	km-pass	5,00		
1500	TOTAL CARRIED TO SUMMARY				

[illegible]

[illegible]

[illegible]

SCHEDULE B : ROADWORKS
PREFABRICATED CULVERTS
SECTION 2200

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
22.01- LI	Excavation:				
	(a) Excavating soft material situated within the following depth ranges below the surface level:				
	(i) 0 m up to 1,5m	m ³	10		
	(ii) Exceeding 1,5m and up to 3,0m	m ³	5		
	(b) Extra over item B22.01(a) for excavation in hard material, irrespective of depth	m ³	10		
22.02-LI	Backfilling:				
	(a) Using the excavated material	m ³	15		
	(b) Using imported selected material:	m ³	5		
	(c) Extra over subitems B22.02 (a) and (b)(i) for soil cement back-filling : (4% of Portland cement by volume)	m ³	5		
22.03	Concrete pipe culverts:				
	(a) 450mm dia. Type 75D	m			Rate Only
	(b) 600mm dia. Type 75D	m	10		
22.03	Portal and rectangular culverts (Complete with prefabricated floor) :				
	(a) 600mm x 300mm Type SANS	m	18		Rate Only
	(b) 750 mm x 600mm Type SANS	m	36		Rate Only
	(c) 1500 mm x 1200mm Type SANS	m	144		Rate Only
22.07-LI	Cast in-situ concrete and formwork:				
	(a) In class A bedding, screeds and the encasing for pipes, including formwork (class 20/19)	m ³	5		
22,18	Brickwork				
	(a) 230mm thick	m ²	10		Rate Only
2200	TOTAL CARRIED FORWARD				

SCHEDULE B : ROADWORKS

SECTION 2300

CONCRETE KERBING, CONCRETE CHANNELING, OPEN CHUTES AND CONCRETE LININGS FOR OPEN DRAINS

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
23,01	Concrete kerbing:				
	(a) Prefabricated concrete kerb SABS 927 fig. 8c or similar approved	m	3600		
	(b) Prefabricated concrete kerb SABS 927 fig. 3	m	5		Rate Only
23,03	Concrete Shuts				
	(a) Cast In-situ class 25/19 concrete (1m wide x 150mm thickness) to be directed by the engineer on site	m	30		
23,06	Inlet, Outlet, transition and similar structures				
	in situ concrete (class 25 Mpa/19 mm) In inlet and outlet structures including kerbs, chutes and downpipes, skewed ends, catchpits, manholes, thrust and anchor blocks, including formwork and Class U2 surfacing finish	m ³	5		
23,07	Trimming of excavations for concrete-lined open drain:				
	(a) in soft material	m ²	100		
	(b) in hard material	m ²	15		
23,08	Concrete lining for open drains:				
	(a) Concrete channel (Class 25/19)	m ³	80		
	(b) Class u2 surface finish to cast in situ concrete	m ²	150		
23,09	Formwork to cast in situ concrete lining for open drains:				
	(b) To sides with formwork on both internal and external faces	m ²	200		
23,12	Steel reinforcement				
	Welded steel fabric (193 mesh wire)	kg	290		
23,1	Sealed joints in concrete linings of open drains:				
	(a) sealed joints in concrete linings of opne drain	m	80		
2300	TOTAL CARRIED TO SUMMARY				

[illegible]

ITEM	DESCRIPTION	UNIT	QUANTITY	RATE	AMOUNT
33.01	Cut and borrow to fill, including freehaul up to 1,0 km.				
	(a) Gravel material in compacted layer thickness of 150mm				
	(i) Compacted to 90% of modified AASHTO density	m³	100		
33.03	Extra over item 33.01 for excavating and breaking down material in:				
	(a) Intermediate excavation	m³	50		
	(b) Hard excavation	m³	50		
33.04	Cut to spoil, including free haul up to 1,0 km. Material obtained from :				
	(a) Soft excavation	m³	5 040		
	(b) Intermediate excavation	m³	50		
	(c) Hard excavation	m³	50		
	(e) Boulder Excavation class B	m³	5		
33.10	Roadbed preparation and the compaction of material				
	(b) Compaction to 93% of modified AASHTO density	m³	1 890		
B33.12	In situ treatment of roadbed:				
	(a) In situ treatment by ripping	m³	100		
	(b) In situ treatment by blasting	m³	10		
33/16.01	free-haul distance of 0.5km up to or through 1km for hard rock and boulders)	m³km	300		
33/16.02	Overhaul (extra over items 33.01 on material hauled in excess of the free-haul distance of 1km (ordinary overhaul)	m³km	15 120		
3300	TOTAL CARRIED TO SUMMARY				

[illegible]

[illegible]

[illegible]

[illegible]

SUMMARY OF SCHEDULE OF QUANTITIES

ITEM	DESCRIPTION	AMOUNT
	SUMMARY OF SCHEDULE A : GENERAL	
1200	GENERAL REQUIREMENTS AND PROVISIONS	
1300	CONTRACTOR'S ESTABLISHMENT ON SITE AND GENERAL OBLIGATIONS	
1400	HOUSING, OFFICES AND LABORATORY FOR THE ENGINEER'S SITE PERSONNEL	
	SUMMARY OF SCHEDULE B : ROADWORKS	
1500	ACCOMMODATION OF TRAFFIC	
1700	CLEARING AND GRUBBING	Rate Only
1800	DAYWORKS AND HIRE OF CONSTRUCTION PLANT	
2100	DRAINS	
2200	PREFABRICATED CULVERTS	
2300	CONCRETE KERBING, CONCRETE, CHANNELING, OPEN CHUTES AND CONCRETE LININGS FOR OPEN DRAINES	
3100	BORROW MATERIALS	
3300	MASS EARTHWORKS	
3400	PAVEMENT LAYERS OF GRAVEL MATERIAL	
3500	STABILIZATION	
5100	PITCHING, STONWORK AND PROTECTION AGAINST EROSION	
5600	ROAD SIGNS	
5700	ROAD MARKINGS	
5900	FINISHING THE ROAD AND ROAD RESERVE AND TREATMENT OF OLD ROADS	
7300	CONCRETE BLOCK PAVING FOR ROADS	
1	NET TOTAL = (SCHEDULE A & B)	
2	TOTAL BROUGHT FORWARD = (1)	
3	CONTINGENCIES AT 10% = (10% OF 2)	
4	SUB TOTAL A = (2 + 3)	
5	ADD 15% VAT = (15% of 4)	
6	TOTAL TO FORM OF OFFER (TENDER AMOUNT) = (4 + 5)	