



CONDUCTOR AND HARDWARE SCHEDULE		SIZE	QUANT.		
A	CONDUCTOR	BUSBAR	φ250 Al TUBE -		
		DROPPER	3x800 mm <sup>2</sup> 240 m		
		EQUIPMENT EARTHING	50x3 Cu - m		
B	HARDWARE - ITEM TO 0.54/412 AND 240-53113927	DESCRIPTION	MK	ITEM	QUANT.
		STRINGER STRAIN ASSY. LONGROD POLYMERIC	1	BB40	6
		LONGROD INSULATOR	2	-	6
		CORONA CONTROL RING FOR UNIVERSAL STRAIN ASSBLY	3	ECRST-LH	6
			ECRST-RH	6	
	TRIPPLE CONDUCTOR SPACER	4	ES-E	21	

**ELEVATION ON ELECTRICAL EQUIPMENT**  
 NOTE:  
 1. SPACER MK 4 TO BE AT 2m CTRS ON DROPPERS AND 8m (MIN) ON STRINGERS  
 2. ADDITIONAL SPACERS TO BE INSTALLED WITHIN 500MM FROM ALL JUMPER AND DROPPER TERMINAL CLAMPS.

EQUIPMENT SUPPORT FOUNDATION PLAN

ARROW INDICATES ORIENTATION OF THIS ARRANGEMENT WHEN LINED UP WITH SIMILAR LAYOUT DRAWING.

**FINAL DESIGN FOR CONSTRUCTION**  
 ORIGINAL DRG #: N/A  
 CONCEPT DRG #: N/A  
 DETAIL DRG #: MOO21P05-SE-D16-47 REV 0

0	FIRST ISSUE				28/08/2025
REV	REVISION DESCRIPTION	BY	CHKD	AUTH	DATE
		Eskom Holdings SOC Ltd Reg No 2002/015527/30			
		<b>MOOKODI</b> 400kV FEEDER 5 (SPARE) BAY			
Moo21P05-SE-E13		SHEET NUMBER	47	REVISION	0