

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
D		SCHEDULE D: SOCCER/ RUGBY FIELD				
D.2.1		SITE CLEARANCE				
D.2.1.1	8.2.1	Clear and grub complete area of infield.	m ²	10346		
D.2.2	SANS 1200 D	EARTHWORKS				
D.2.2.1	PS D8.3.2(a)	Excavate in all materials and use for fill compacted to 100% MOD AASHTO density				
D.2.2.1.1	8.3.2 a)	Excavations to infield to a nominal depth of 150mm	m ³	1152		
D.2.2.2	8.3.4	Importing of Materials				
D.2.2.2.1	LIC	Import 25mm layer of course river sand from commercial sources and spread to given levels of soccer/ rugby field.	m ³	260		
D.2.2.2.2	LIC	Import 100mm layer of red (weed-free) soil from commercial sources, spread and cultivate to given levels of soccer/ rugby field.	m ³	1035		
D.2.3	SANS 1200 MK	KERBING AND CHANNELLING				
D.2.3.1	LIC	Excavation and preparation of concrete bedding for the laying of kerbing as specified.	m	368		
D.2.3.2	8.2.1 (LIC)	Supply and laying of Ref. E3 Edging (Curved)	m	0		
D.2.3.3	8.2.2 (LIC)	Supply and laying of Ref. E3 Edging and Ref. C1 Channel to form stormwater drain complete (Straight)	m	0		
D.2.4	SANS 1200 D	GRASSING				
D.2.4.1	PS D 8.3.11 (LIC)	Supply and implantation of Kikuyu roll on grass according to Particular Specifications for playing field.	m ²	10346		
D.2.4.2	PD 3.3.4 PD6.1 (LIC)	Supply and apply fertilizer as required and described in section PD 6.1.	100kg	15		
D.2.4.3	LIC	Supply and spread well rotten compost layer of ± 20mm prior to planting of grass, worked into the top 40mm imported topsoil	m ²	10346		
TOTAL CARRIED FORWARD						

ITEM NO.	PAYMENT	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
TOTAL BROUGHT FORWARD						
D.2.4.4	LIC	Spread 15mm layer of sand dressing over the grassed surface and smooth	m ²	10346		
D.2.5		GOAL POSTS Item include all costs related to the manufacturing (painted with durable steel primer and two coats of white enamel paint) and of a set of goal posts.				
D.2.5.1		100mm Pipe frame for set of soccer posts (mobile) 7.32m wide x 2.44m high and 2.0m deep.	No. Sets	1		
D.2.5.2		100mm and 75mm pipe frame for set of rugby posts. Rugby post foundation to be 500x500x1000mm class 20MPa/19mm concrete. Poles to be 5.5m apart with horizontal bar 5m above ground level and upright pole lengths above crossbar 3.2m.	No. Sets	1		
TOTAL CARRIED FORWARD TO SUMMARY						