

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO. 1</u></p> <p><u>BILL NO. 1</u></p> <p><u>PRELIMINARIES</u></p> <p><u>BUILDING AGREEMENT AND PRELIMINARIES</u></p> <p>The JBCC Series 2000 Edition 4.1 Code 2101 March 2005 2005 edition prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter described</p> <p>The Preliminaries for use with the JBCC Series 2000 Principal Building Agreement (May 2005 edition) prepared by the Joint Building Contracts Committee, shall be deemed to be incorporated in these bills of quantities</p> <p>Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents</p> <p>Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"</p> <p>Notwithstanding anything to the contrary contained in any of the contract documents including the Principal Building Agreement and the Preliminaries, the provision of the "Preliminaries" as hereinafter set forth shall prevail and shall take precedence</p> <p style="text-align: right;">Carried Forward</p> <p>Bill No. 1 P's and G's</p> <p>R MAHANGE & ASSOCIATES</p>			R

Item No	Brought Forward	Quantity	Rate	Amount
	<p>PREAMBLES FOR TRADES</p> <p>The Model Preambles for Trades (1999 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained</p> <p>Supplementary preambles to the Model Preambles covering clauses of a general nature, clauses pertaining to specific materials and amendments to clauses in the Model Preambles are incorporated in these bills of quantities to satisfy the requirements of this project</p> <p>The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preambles</p>		R	
	<p>GENERAL</p> <p>If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "T" or "V" as the case may be below such item, where "F" denotes a fixed amount (amount not to be varied), "T" denotes an amount variable in proportion to time and "V" denotes an amount variable in proportion to value</p>			
	<p>SECTION A - PRINCIPAL BUILDING AGREEMENT</p> <p>Definitions (A1)</p> <p>Definitions and interpretation (clause 1)</p> <p>F: V: T:</p>	Item		
	<p>Bill No. 1 P's and G's</p> <p>R MAHANGE & ASSOCIATES</p>	Carried Forward	R	

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	<u>Objective and Preparation (A2 to A14)</u>			
	Offer acceptance and performance (clause 2)			
	F:..... V:..... T:.....	Item		
	Documents (clause 3)			
	F:..... V:..... T:.....	Item		
	Design responsibility (clause 4)			
	F:..... V:..... T:.....	Item		
	Employer's agents (clause 5)			
	F:..... V:..... T:.....	Item		
	The principal agent shall:			
	- monitor and control progress and scheduling			
	- monitor all contract conditions, and			
	- coordinate the efforts of the employer's agents, the contractor and subcontractors			
	The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part			
	Carried Forward			
			R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process		R	
	Site representative (clause 6)			
	F: V: T:		Item	
	Compliance with regulations (clause 7)			
	F: V: T:		Item	
	Works risk (clause 8)			
	F: V: T:		Item	
	Indemnities (clause 9)			
	F: V: T:		Item	
	Works insurances (clause 10)			
	F: V: T:		Item	
	Liability insurances (clause 11)			
	F: V: T:		Item	
	Effecting insurance (clause 12)			
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	NO CLAUSE (Clause 13)			
	Security (clause 14)			
	F:..... V:..... T:.....	Item		
	<u>Execution (A15-A23)</u>			
	Preparation for and execution of the works (clause 15)			
	F:..... V:..... T:.....	Item		
	Access to the works (clause 16)			
	F:..... V:..... T:.....	Item		
	Contract instructions (clause 17)			
	F:..... V:..... T:.....	Item		
	Setting out of the works (clause 18)			
	F:..... V:..... T:.....	Item		
	The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc. exist in order that the necessary arrangements may be made for the rectification of any such encroachments			
	Assignment (clause 19)			
	F:..... V:..... T:.....	Item		
	The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer			
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Nominated subcontractors (clause 20)			
	F:..... V:..... T:.....	Item		
	Selected subcontractors (clause 21)			
	F:..... V:..... T:.....	Item		
	Written proof is required from subcontract tenderers at tendering that they can meet the JBCC Selected Subcontract Agreement or other tender agreements and provide security in terms of the agreement. If the above is not provided the tender may not be accepted			
	All amounts allowed under Provisional Amounts are intended to be awarded to Selected Subcontractors			
	Employer's Direct Contractors (clause 22)			
	F:..... V:..... T:.....	Item		
	Contractor's Domestic Sub-Contractors (Clause 23)			
	F:..... V:..... T:.....	Item		
	<u>Completion (A24-A30)</u>			
	Practical completion (clause 24)			
	F:..... V:..... T:.....	Item		
	Works completion (clause 25)			
	F:..... V:..... T:.....	Item		
	Final completion (clause 26)			
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	Latent defects liability period (clause 27)			
	F:..... V:..... T:.....	Item		
	Sectional completion (clause 28)			
	F:..... V:..... T:.....	Item		
	Revision of date of practical completion (clause 29)			
	F:..... V:..... T:.....	Item		
	The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3)			
	Penalty for non-completion (clause 30)			
	F:..... V:..... T:.....	Item		
	<u>Payment (A31 - A35)</u>			
	Interim payment to the contractor (clause 31)			
	F:..... V:..... T:.....	Item		
	Adjustment to the contract value (clause 32)			
	F:..... V:..... T:.....	Item		
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing			
	Recovery of expense and loss (clause 33)			
	F:..... V:..... T:.....		Item	
	Final account and final payment (clause 34)			
	F:..... V:..... T:.....		Item	
	The employer shall not pay any interest on amounts payable to the contractor for one hundred and forty two (142) days after the date of issue of the certificate of practical completion			
	The employer shall, however, pay interest to the contractor at the rate stipulated in clause 34.11 on any amounts payable to the contractor more than one hundred and forty two (142) days after the date of issue of the certificate of practical completion but only for such period as the settlement of the final account is delayed by the non-performance of the principal agent or the employer or his agents. In evaluating non-performance for purposes of this clause a reasonable time shall be allowed to the employer or his agents to respond to any matter brought to his/their attention and which may affect the settlement of the final account			
	Payment to other parties (clause 35)			
	F:..... V:..... T:.....		Item	
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>Cancellation (A36-A39)</u>			
	Cancellation by employer - contractor's default (clause 36) F:..... V:..... T:.....	Item		
	Cancellation by employer - loss and damage (clause 37) F:..... V:..... T:.....	Item		
	Cancellation by contractor - employer's default (clause 38) F:..... V:..... T:.....	Item		
	Cancellation - cessation of the works (clause 39) F:..... V:..... T:.....	Item		
	<u>Dispute (A40)</u>			
	Dispute Settlement (clause 40) F:..... V:..... T:.....	Item		
	<u>Substitute Provisions (A41)</u>			
	State clauses (Clause 41) F:..... V:..... T:.....	Item		
	Information necessary for the completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder			
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
	<u>THE SCHEDULE</u> Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder			R
	Pre-tender information (clause 42) F:..... V:..... T:.....	Item		
	<u>42.1 CONTRACTING AND OTHER PARTIES</u>			
	42.1.1 Employer: THE MVULA TRUST			
	42.1.2 Principal Agent: R Mahange and Associates			
	Carried Forward			R
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	<p>42.2 CONTRACT DETAILS</p> <p>42.2.1 Works Description: Construction of sanitation facilities</p> <p>42.2.2 Site Description: as per the information on the tender data</p> <p>42.2.3 Work or installations by direct contractors: N/A</p> <p>42.2.4 This agreement is for a government contract where there are specific options that are applicable to a State organ only Yes</p> <p>42.2.5 Date on which possession of the site is intended to be given: As per the information provided in the Tender Data</p> <p>42.2.6 Period for the commencement of the works after the contractor takes possession of site: 7 DAYS</p> <p>42.2.7 For the works as a whole. Intended date of practical completion and the penalty per calendar day Intended Date of Practical Completion: As per the information provided in the Tender Data</p> <p>Penalty Amount: The penalty per calendar day shall be 7.5 cents per R100 of the Tendered Amount (inclusive of value added tax)</p> <p>42.2.8 For the works in sections: Intended date of practical completion and the penalty per calendar day N/A</p> <p>42.2.9 The law applicable to this agreement shall be that of</p>			
	Carried Forward		R	

Bill No. 1
P's and G's

R MAHANGE & ASSOCIATES

Item No		Quantity	Rate	Amount
	Brought Forward <i>South Africa (country)</i>			R
	42.3 INSURANCES			
	42.3.1 Contract works insurance to be effected by: <i>Contractor: For the Sum of R Contract Amount + 10.00 % With a deductible of - to be determined by the contractor</i>			
	42.3.2 Supplementary insurance is required <i>No</i>			
	42.3.3 Public liability insurance to be effected by: <i>Contractor: For the Sum of R 5 000 000-00 With a deductible of - to be determined by the contractor</i>			
	42.4 DOCUMENTS			
	42.4.1 Waivers of contractors lien or right of continuing possession is required <i>Yes</i>			
	42.4.2 Number of construction document copies to be supplied to the contractor free of charge: <i>3 Number of</i>			
	42.4.3 Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with: "Standard System of Measuring Builders' Work"			
	42.4.4 On acceptance of the tender the bills of quantities/lump sum document is to be submitted within <i>5 working days</i>			
	Carried Forward Bill No. 1 P's and G's			R
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<i>The priced bills of quantities must be handed in with the tender</i>			
	42.4.5 JBCC Engineering General Conditions are to be included in the contract documents :			
	No			
	42.4.6 The contract value is to be adjusted using escalation adjustment indices			
	No			
	Where JBCC CPAP is to be used			
	Base Month N/A			
	42.4.7 Details of changes made to the provision of JBCC standard documentation:			
	Part 1 - Contract Data completed by Employer			
SECTION B: PRELIMINARIES				
Definitions and interpretation (B1)				
Definition and interpretation (B1.1 - B1.4.6)				
F: V: T:				
Documents (B2)				
Checking of documents (B2.1)				
F: V: T:				
Provisional bills of quantities (B2.2)				
F: V: T:				
Carried Forward				
Bill No. 1 P's and G's			R	
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	Availability of construction documentation (B2.3)			
	F: V: T:	Item		
	Interests of agents (B2.4)			
	F: V: T:	Item		
	Priced documents (B2.5)			
	F: V: T:	Item		
	Tender submission (B2.6)			
	F: V: T:	Item		
	Defined works area (B3.1)			
	F: V: T:	Item		
	<u>The site (B3)</u>			
	Geotechnical investigation (B3.2)			
	F: V: T:	Item		
	Inspection of the site (B3.3)			
	F: V: T:	Item		
	Existing premises occupied (B3.4)			
	F: V: T:	Item		
	Carried Forward			R
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	Specific requirements: The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines.		R	
	Previous work - dimensional accuracy (B3.5) F:..... V:..... T:.....	Item		
	Previous work - defects (B3.6) F:..... V:..... T:.....	Item		
	Services - known (B3.7) F:..... V:..... T:.....	Item		
	Services - unknown (B3.8) F:..... V:..... T:.....	Item		
	Protection of trees etc. (B3.9) F:..... V:..... T:.....	Item		
	Articles of value (B3.10) F:..... V:..... T:.....	Item		
	Inspection of adjoining properties etc. (B3.11) F:..... V:..... T:.....	Item		
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	<u>Management of contract (B4)</u>			
	Management of the works (B4.1)			
	F:..... V:..... T:.....		Item	
	Programme for the works (B4.2)			
	F:..... V:..... T:.....		Item	
	Progress meetings (B4.3)			
	F:..... V:..... T:.....		Item	
	Technical meetings (B4.4)			
	F:..... V:..... T:.....		Item	
	Labour and Plant records (B4.5)			
	F:..... V:..... T:.....		Item	
	<u>Samples, Shop Drawings and Manufacturer's Instructions (B5)</u>			
	Samples of materials (B5.1)			
	F:..... V:..... T:.....		Item	
	Workmanship samples (B5.2)			
	F:..... V:..... T:.....		Item	
	Shop drawings (B5.3)			
	Carried Forward			
			R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	Compliance with Manufacturer's Instructions (B5.4)			
	F:..... V:..... T:.....	Item		
	<u>Temporary works and plant (B6)</u>			
	Deposits and fees (B6.1)			
	F:..... V:..... T:.....	Item		
	Enclosure of the works (B6.2)			
	F:..... V:..... T:.....	Item		
	Advertising (B6.3)			
	F:..... V:..... T:.....	Item		
	Plant, equipment, sheds and offices (B6.4)			
	F:..... V:..... T:.....	Item		
	Main notice board (B6.5)			
	F:..... V:..... T:.....	Item		
	Subcontractors' notice board (B6.6)			
	F:..... V:..... T:.....	Item		
	<u>Temporary services (B7)</u>			
	Location (B7.1)			
	F:..... V:..... T:.....	Item		
	Water (B7.2)			
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Option [A] shall apply			
	F:..... V:..... T:.....	Item		
	Electricity (B7.3)			
	Option [A] shall apply			
	F:..... V:..... T:.....	Item		
	Telecommunication facilities (B7.4)			
	F:..... V:..... T:.....	Item		
	Ablution facilities (B7.5)			
	Option [A] shall apply			
	F:..... V:..... T:.....	Item		
	<u>Prime cost amounts (B8)</u>			
	Responsibility for prime cost amounts (B8.1)			
	F:..... V:..... T:.....	Item		
	<u>Attendance on N/S Subcontractors (B9)</u>			
	General attendance (B9.1)			
	F:..... V:..... T:.....	Item		
	Special attendance (B9.2)			
	F:..... V:..... T:.....	Item		
	Commissioning - Fuel, water and power (B9.3)			
	F:..... V:..... T:.....	Item		
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	<u>Financial aspects (B10)</u>			
	Statutory taxes, duties and levies (B10.1)			
	F:..... V:..... T:.....	Item		
	Payment of preliminaries (B10.2)			
	Option [B] shall apply			
	F:..... V:..... T:.....	Item		
	Adjustment of preliminaries (B10.3)			
	Option [A] shall apply			
	F:..... V:..... T:.....	Item		
	Payment certificate cash flow (B10.4)			
	F:..... V:..... T:.....	Item		
	<u>General (B11)</u>			
	Protection of works (B11.1)			
	F:..... V:..... T:.....	Item		
	Protection/isolation of existing/sectionally occupied works (B11.2)			
	F:..... V:..... T:.....	Item		
	Security of the Works (B11.3)			
	F:..... V:..... T:.....	Item		
	Notice before covering work (B11.4)			
	Carried Forward			
			R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	Disturbance (B11.5)			
	F:..... V:..... T:.....	Item		
	Environmental Disturbance (B11.6)			
	F:..... V:..... T:.....	Item		
	Works cleaning and clearing (B11.7)			
	F:..... V:..... T:.....	Item		
	Vermin (B11.8)			
	F:..... V:..... T:.....	Item		
	Overhand work (B11.9)			
	F:..... V:..... T:.....	Item		
	Instruction manuals and guarantees (B11.10)			
	F:..... V:..... T:.....	Item		
	As built information (B11.11)			
	F:..... V:..... T:.....	Item		
	Tenant Installations (B11.12)			
	F:..... V:..... T:.....	Item		
	Carried Forward		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	Schedule of variables (B12)			
	Pre-tender information (B12.1)			
	F: V: T:		Item	
	12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional:			
		No		
	12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete			
		No		
	12.1.3 Interest of agents (B2.4)			
	12.1.4 Defined works area (B3.1)			
	12.1.5 Geotechnical investigation (B3.2)			
		N/A		
	12.1.6 Existing premises occupied (B3.4)			
	12.1.7 Previous work - dimensional accuracy (B3.4)			
	12.1.8 Previous work - defects (B3.5)			
	12.1.9 Services - known (B3.7)			
	12.1.10 Protection of trees (B3.9)			
	All trees should be protected and only on instruction of the Principal Agent may any trees be removed			
	12.1.11 Inspection of adjoining properties (B3.11)			
	12.1.12 Enclosure of the works (B6.2)			
		Carried Forward		
	Bill No. 1 P's and G's		R	
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	12.1.13 Offices (B6.4.3) Specific requirements: The contractor shall provide, maintain and remove, on completion of the works, an office for the exclusive use of the principal agent, minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with boarded floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times.			
	12.1.14 Main notice board (B6.5) YES			
	12.1.15 Subcontractors notice board (B6.6) A notice board is required Yes			
	12.1.16 Water (B7.2) Alternative Selected: A			
	12.1.17 Electricity (B7.3) Alternative selected: A			
	12.1.18 Telecommunications (B7.4)			
	12.1.19 Ablution facilities (B7.5) Alternative selected: A			
	12.1.20 Protection of existing/sectionally occupied works (B11.2)			
	12.1.21 Special attendance (B9.2)			
	Subcontractor (1) details: N/A			
	12.1.22 Protection of the works (B11.1) N/A			
	12.1.23 Disturbance (B11.5)			
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	N/A			
	12.1.24 Environmental Disturbance (B11.6)			
	N/A			
	<u>Post tender information (B12.2)</u>			
	12.2.1 Payment of preliminaries Alternative selected: B			
	12.2.2 Adjustment of preliminaries Alternative selected: A			
	12.2.3 Additional agreed preliminaries items N/A			
	<u>SECTION C: SPECIFIC PRELIMINARIES</u>			
	Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included			
	Site instructions			
	Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor			
	F: V: T:	Item		
	Black economic empowerment and training			
	F: V: T:	Item		
	Proprietary branded products			
	F: V: T:	Item		
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Testing of flat roof waterproofing for water tightness Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing F:..... V:..... T:.....		Item	
	The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative		Item	
	Contract instructions F:..... V:..... T:.....		Item	
	Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor		Item	
	Labour record F:..... V:..... T:.....		Item	
	At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesmen and labourers employed by him and all subcontractors on the works each day of that week		Item	
	Plant record F:..... V:..... T:.....		Item	
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	<p>At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week</p> <p>Guarantees</p> <p>F:..... V:..... T:.....</p> <p>Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement</p> <p>Overtime</p> <p>F:..... V:..... T:.....</p> <p>Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer</p>	Item	R	
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	Co-operation of contractor for cost management F: V: T:	Item	R	
	It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors			
	Occupational Health and Safety Specification F: V: T:	Item	R	
	Carried Forward			
Bill No. 1 P's and G's			R	
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
	<p>The contractor shall comply with all the requirements set out in the Construction Regulations, 2003 issued under the Occupational Health and Safety Act, 1993 (Act No 85 of 1993)</p> <p>It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document.</p> <p>The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.</p> <p>Provision for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause, as well as the clauses that follow hereafter and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under these clauses and no additional claims in this regard shall be entertained.</p> <p>The contractor shall also comply with the additional requirements with regard to the Coronavirus pandemic in terms of all Covid-19 legislation, regulations and guidelines. It is explicitly pointed out that all requirements of the aforementioned are deemed to be priced under this clause and the specific related clauses hereafter and no additional claims in this regard shall be entertained.</p> <p>Occupational Health and Safety Specification</p>		R	
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	Preparation of contractor's site specific health and safety plan, including compliance with Covid-19 legislation, regulations and guidelines			
	Occupational Health and Safety Specification F:..... V:..... T:.....	Item		
	Principal contractor's initial obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc			
	Occupational Health and Safety Specification F:..... V:..... T:.....	Item		
	Principal contractor's time related obligations in respect of the Health and Safety Act, Construction Regulations and Covid-19 regulations, etc.			
	Provision of personal protective equipment (PPE) F:..... V:..... T:.....	Item		
	Provision of reflective vests			
	Provision of personal protective equipment (PPE) F:..... V:..... T:.....	Item		
	Provision of hard hats			
	Provision of personal protective equipment (PPE) F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	Provision of protective footwear		R	
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of earplugs			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of dust masks			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of gloves			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of high visibility overalls to SARTSM Chapter 13 Level 3			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of SANS approved ear defenders			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Provision of face masks (Covid -19)			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of face shields (Covid-19)			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of gloves (Covid-19)			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of hand sanitiser (min 70% alcohol), foot press stands and paper towels (Covid-19)			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of covered refuse bins and refuse bags and waste (including hazardous) management (Covid -19)			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of digital infra red non-contact body thermometer (Covid-19, minimum of two per site entrance)			
	Provision of personal protective equipment (PPE)			
		Carried Forward		
Bill No. 1 P's and G's			R	
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	F:..... V:..... T:.....	Item		
	Provision of perspex screens for office staff (Covid-19, minimum size 600 x 500mm)	Item		
	Provision of personal protective equipment (PPE)	Item		
	F:..... V:..... T:.....	Item		
	Provision of signage, including Covid-19 related signage	Item		
	Provision of personal protective equipment (PPE)	Item		
	F:..... V:..... T:.....	Item		
	Provision of full time construction health and safety officer (SACPCMP Registered)	Item		
	Provision of personal protective equipment (PPE)	Item		
	F:..... V:..... T:.....	Item		
	Medical certificates and medical surveillance including initial (baseline) medical examinations, periodic examinations, and exit examinations	Item		
	Provision of personal protective equipment (PPE)	Item		
	F:..... V:..... T:.....	Item		
	Medical screenings, examinations, etc. in terms of Covid 19 regulations	Item		
	Provision of personal protective equipment (PPE)	Item		
	F:..... V:..... T:.....	Item		
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Induction training, including Covid-19 training			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Provision of first aid boxes to GSR requirements			
	Provision of personal protective equipment (PPE)			
	F:..... V:..... T:.....	Item		
	Noise monitoring including establishment of noise zones (plant), audio grams (personnel), etc.			
	F:..... V:..... T:.....	Item		
	Submission of health and safety file			
	HIV/AIDS Awareness			
	F:..... V:..... T:.....	Item		
	It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document. Provision for pricing of HIV/AIDS awareness is made under items C11.1 to C11.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained.			
	Carried Forward		R	
	Bill No. 1 P's and G's			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<p>The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment.</p>			
	<u>SUMMARY OF CATEGORIES</u>			
1	Category : Fixed R.....		Item	
2	Category : Value R.....		Item	
3	Category : Time R.....		Item	
	Carried to Summary		R	
Bill No. 1 P's and G's				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	<p><u>DEMOLITIONS AND ALTERATIONS</u></p> <p><u>SECTION NO.2</u></p> <p><u>BILL NO.1</u></p> <p><u>ALTERATIONS</u></p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p><u>View site</u></p> <p>Before submitting his tender the contractor shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained.</p> <p><u>Explosives</u></p> <p>No explosives whatsoever may be used for demolition.</p> <p><u>General</u></p> <p>The contractor shall carry out the whole of the works with as little mess and noise as possible and with a minimum of disturbance to adjoining premises and their tenants. He shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the principal agent.</p> <p style="text-align: right;">Carried Forward</p> <p>Bill No. 2 Alterations</p> <p>R MAHANGE & ASSOCIATES</p>			R

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<p>Water supply pipes and other piping that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings, to the satisfaction of the principal agent.</p> <p>Doors, fanlights, fittings, frames, linings, etc which are to be re-used shall be thoroughly overhauled before re-fixing including taking off, easing and rehanging, cramping up, re-wedging as required and making good cramps, dowels, etc, and easing, oiling, adjusting and repairing ironmongery as necessary, replacing any glass damaged in removal or subsequently and stopping up all nail and screw holes with tinted plastic wood to match timber, unless otherwise described. Re-painting or re-varnishing is given separately.</p> <p>Prices for taking out of doors, windows, etc shall include for removal of all beads, architraves, ironmongery, etc.</p> <p>Prices for taking out and removing doors and frames shall include for removing door stops, cabin hooks, etc and making good floor and wall finishes to match existing.</p> <p>With regard to building up of openings in existing walls, cement screeds and pavings, granolithic, tops of walls, etc, shall be levelled and prepared for raising of brickwork.</p>			
	DEMOLITIONS AND ALTERATIONS			
	DEMOLITIONS OF EXISTING TOILET STRUCTURES			
1	Demolish existing pit toilet structures, made from bricks with an approximate quantity of 36m ² , including hacking up and removing foundations and surface beds, doors, windows and door frames, ironmongery and plumbing fittings complete. All pits are to be filled with soil	No	4	R
	Carried Forward			
	Bill No. 2 Alterations			
	R MAHANGE & ASSOCIATES			

THE MVULA TRUST
MAKOPUNG PRIMARY SCHOOL
TMT-LDOE-2023/24-BATCH06LPCL3J
BILL NO. 2

Item No		Quantity	Rate	Amount
	Brought Forward			R
2	Demolish existing pit toilet structures, made from bricks with an approximate quantity of 30m ² , including hacking up and removing foundations and surface beds, doors, windows and door frames, ironmongery and plumbing fittings complete. All pits are to be filled with soil	No	2	
3	Demolish existing pit toilet structures, made from metal sheeting with an approximate quantity of 22m ² , including hacking up and removing foundations and surface beds, doors, windows and door frames, ironmongery and plumbing fittings complete. All pits are to be filled with soil	No	2	
4	Demolish all existing ground slab (max strength and size, 25MPa and 30m ² respectively) with mesh reinforcement for pit toilets that have been abandoned. All pits are to be filled with soil.	No	3	
	Carried to Summary			R
	Bill No. 2 Alterations			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.3</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</p> <p>SUPPLEMENTARY PREAMBLES</p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> <p style="text-align: right;">Carried Forward</p> <p>Bill No. 3 Gr R3 - Waterborne</p> <p>R MAHANGE & ASSOCIATES</p>			R

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Soil poisoning Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent			
	<u>SITE CLEARANCE ETC</u>			
	Site clearance			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	55	
2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	55	
	<u>EXCAVATION, FILLING, ETC</u>			
	Excavation in earth not exceeding 2m deep			
3	Trenches	m3	12	
4	Thickening under aprons	m3	6	
	Extra over trench and hole excavations in earth for excavation in			
5	Soft rock	m3	5	
6	Hard rock	m3	5	
	Extra over all excavations for carting away			
7	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	23	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Risk of collapse of excavations			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	30	
	Keeping excavations free of water			
9	Keeping excavations free of all water other than subterranean water		Item	
	Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density			
10	Under floors, steps, paving, etc	m3	5	
11	Backfilling to trenches, holes, etc	m3	6	
	Compaction of surfaces			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	35	
	Under floors, steps, paving, etc.			
	Prescribed density tests on filling			
13	Modified AASHTO Density	No	5	
	SOIL POISONING			
	Weedkiller mixed in accordance to supplier's specifications			
14	To bottoms and sides of trenches, etc.	m2	51	
15	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	50	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Soil insecticide			
16	To bottoms and sides of trenches etc	m2	51	
17	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	50	
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
<u>SECTION NO.5</u>				
<u>BILL NO. 2</u>				
<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>				
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades				
UNREINFORCED CONCRETE, ETC.				
15MPa/19mm concrete				
18	Surface blinding under footings and bases	m3	0.2	
25MPa/19mm concrete				
19	Strip footings	m3	6	
REINFORCED CONCRETE				
25MPa/19mm concrete				
20	Surface beds and apron	m3	7	
TEST CUBES				
21	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	2.0	
CONCRETE SUNDRIES				
Finishing top surfaces of concrete smooth with a wood float/steel trowel				
22	Surface beds, slabs, etc	m2	32	
SMOOTH FORMWORK (DEGREE OF ACCURACY I)				
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No			Quantity	Rate	Amount
		Brought Forward		R	
	Smooth formwork to sides				
23	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	20		
	REINFORCEMENT (PROVISIONAL)				
	Mild steel reinforcement to structural concrete work				
24	8mm Diameter bars	t	0.30		
25	10mm Diameter bars	t	0.30		
	Fabric Reinforcement				
26	Mesh ref. No. 395 fabric reinforcement fixed horizontally in surface beds etc.	m2	17		
		Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne				
	R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
	SECTION NO.3			R
	BILL NO. 3			
	MASONRY			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	SUPPLEMENTARY PREAMBLES			
	BRICKWORK			
	Sizes in descriptions			
	Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick			
	Face bricks			
	Bricks shall be ordered timely to obtain uniformity in size and colour			
	Pointing			
	Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc			
	FOUNDATIONS (PROVISIONAL)			
	Brickwork of NFP bricks in class II mortar			
27	One brick walls	m ²	14	
28	Half brick walls	m ²	5	
		Carried Forward		R
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	SUPERSTRUCTURE		R	
	Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints			
	FACE BRICKWORK			
29	Half brick walls	m ²	20	
30	One brick walls	m ²	60	
	Face bricks brick-on-edge header course coping, sills, etc. pointed with recessed joints on all exposed faces:			
31	Extra over brickwork for brick-on-edge header course lintel	m	6	
32	110mm Wide sill set level and slightly projecting	m	6	
33	220mm Wide sill set sloping and slightly protecting outside	m	6	
34	Fair cutting fitting around pipe not exceeding 100mm	No	6	
35	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	4	
	BRICKWORK SUNDRIES			
	Brickwork reinforcement			
36	75mm Wide reinforcement built in horizontally	m	75	
37	150mm Wide reinforcement built in horizontally	m	250	
	Galvanised wire ties etc			
38	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	20	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Turning pieces to lintels etc.			
39	115mm Wide turning pieces	m	6	
40	230mm Wide turning pieces	m	3	
	Prestressed fabricated lintels			
41	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	7	
	Air bricks etc.			
42	230 x 152mm terra-cotta vermin proofed louvered air brick	No	30	
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	SECTION 3			
	BILL NO. 4			
	WATERPROOFING			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	DAMP-PROOFING OF WALLS AND FLOORS			
	One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course			
43	In walls	m ²	7	
	One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"			
44	Under surface beds	m ²	43	
	FLOOR AND WALL SEALERS			
	Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight			
45	Around steel windows and door frames	m	30	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.3</u>			
	<u>BILL NO. 5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	PROFILED METAL SHEETING AND ACCESSORIES			
	0,6mm "Kliplok" roof sheeting in Chromadek finish fixed-nailed to timber purlins (elsewhere measured) in the colour Traffic Green			
46	Roof covering with pitch not exceeding 25 degrees	m ²	27	
	ROOF AND WALL INSULATION			
47	12" Thermal resistance sisalition laid on purlins	m ²	27	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	<u>SECTION NO.3</u>			R
	<u>BILL NO. 6</u>			
	<u>CARPENTRY AND JOINERY</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	ROOFS, ETC.			
	Sawn softwood grade 6			
48	76 x 38mm Wall plates	m	25	
49	38 x 114mm Rafters in lengths exceeding 3,9m	m	30	
50	50 x 76mm Purlins in lengths exceeding 3,9m	m	37	
	Sundries			
51	Two coats creosote on sawn timbers	m2	20	
52	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	35	
53	Hurricane clips	No	30	
54	Roofing nails 100mm	No	50	
	EAVES, VERGES, ETC			
	Pressed fibre-cement:			
55	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	35	
	DOORS, ETC			
	Carried Forward			R
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Wrought meranti doors hung to steel frames			
56	44mm framed, ledged and braced door 813 x 2032mm high including external weather bar (D1)	No	2	
57	44mm framed, ledged and braced door 813 x 1882mm high (door raised by 150mm from bottom) (D2)	No	3	
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
	SECTION NO.3			R
	BILL NO. 7			
	IRONMONGERY			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	HINGES, BOLTS, ETC			
	100mm Chrome plated "D" type handle 3 by solid brace hinges			
	CATCHES, CABIN HOOKS, ETC			
58	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	3	
	LOCKS			
	Approved			
59	Three lever mortice lock set	No	2	
60	Indicator lock set	No	3	
61	Security double throw dead lock (no latch)	No	2	
	HANDLES, ETC.			
	Aluminium Pull Handle			
62	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.	No		
	SUNDRIES			
		Carried Forward		R
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	ASSA ABLOY			
63	38mm Diameter rubber door stop plugged	No	2	
	Vaal Paragon			
64	32mm Type 9 back grab rail 800mm long plugged	No		
65	32mm Type 8 side grab rail 900mm girth plugged	No		
	LETTERS, NAMEPLATES, ETC			
	Dorma:			
66	DSS-132 Engraved "Male/Female" information sign, plugged	No	1	
67	DSS-133 Engraved "Disabled" information sign, plugged	No		
	BATHROOM FITTINGS			
	Sundries			
	Kimberley-Clark or Similar			
68	SQ2 code 405607B white none lockable toilet roll holder	No	3	
	stainless Steel			
69	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	1	
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.3</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	WELDED SCREENS, GATES, ETC			
	Gates to external doors			
70	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	2	
	PRESSED STEEL DOOR FRAMES			
	1,2mm Double rebated frames suitable for half brick walls			
71	Frame for door size 813 x 2032mm high	No	3	
	1,2mm Double rebated frames suitable for one brick walls			
72	Frame for door size 813 x 2032mm high	No	2	
	STEEL WINDOWS, DOORS, ETC			
	Nty steel or similar approved school windows with standard burlgar bars formed of 20 x 5mm thick flat bars to all sashes			
73	Window type NE1, size 533 x 654mm high	No	3	
74	Window type NE7, size 1022 x 654mm high	No	1	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.3</u>			
	<u>BILL NO. 9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	GRANOLITHIC			
	Untinted granolithic on concrete			
75	20mm Thick on floors	m2	29	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	SECTION NO.3			R
	BILL NO. 10			
	PLUMBING AND DRAINAGE(PROVISIONAL)			
	RAINWATER DISPOSAL			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	Aluminium Zinc Seamless Gutters			
76	100 x 100mm standard rainwater gutters fixed with gutter brackets	m	10	
77	Extra over eaves gutter for stopped end	No	2	
78	75 x 100mm Diameter rainwater down pipes fixed to wall	m	10	
79	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
80	Ditto for shoe	No	2	
	SANITARY FITTINGS			
	"Vaal" or similar and approved			
81	Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	2	
82	WC suite, comprising with pan and double flap heavy duty plastic seat and matching cistern with flush pipe, complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	3	
	Carried Forward			R
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	PRECAST CONCRETE WASH HAND TROUGH			
83	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1	
	Rainwater tank, etc.			
84	5000 Litre watertank fitted onto and secured to tank platforms including fastening cables	No	1	
	SOIL DRAINAGE			
	uPVC pipes			
85	110mm Pipes laid in and including trenches not exceeding 1m deep	m	50	
	Extra over uPVC pipes for fittings			
86	110mm Bend	No	3	
87	110mm Junction	No	3	
	uPVC gulleys			
88	110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete sorround etc.	No	3	
	WASTE UNIONS ETC			
	"Cobra Watertech"			
89	Cobra Watertech 32mm chrome plated basin waste (code: 308) with 62mm diameter flange, 80mm long shank and plug	No	2	
	TRAPS ETC			
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	"Cobra Watertech"			
90	Cobra Ref. 365/40" CP bottle trap	No	2	
	Marley			
91	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	1	
	TAPS, VALVES, ETC			
92	Cobra Watertech 15mm compression type angle regulating valve with 10mm bendable copper outlet tube service connection (Code: 232/350).	No	2	
93	Cobra Watertech 15mm chrome plated bibtap (Code: NM-500-21B) with blue indice and elbow action lever, manufactured in accordance with SANS 226:2009 Type 2 (BS 5412).	No	2	
	SANITARY PLUMBING			
	uPVC pipes			
94	50mm Pipes	m	50	
	Extra over uPVC pipes for fittings			
95	50mm Bend	No	6	
96	50mm Access bend	No	6	
97	50mm Junction	No	6	
	WATER SUPPLIES			
	Class 0 copper pipes			
98	15mm Pipes	m	50	
99	22mm Pipes	m	65	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Brought Forward	Quantity	Rate	Amount
	Extra over class 0 copper pipes for capillary fittings			R	
100	15mm Fittings	No	50		
101	22mm Pipes	No	20		
	SUNDRIES				
102	Extra over excavation in earth for pipe trenches, chambers, etc for excavation in soft rock	m3	201		
103	Ditto, but in hard rock	m3	10		
104	Extra over excavation for pipe trenches, chambers, etc for carting away surplus material to a dumping site to be located by the contractor	m3	30		
105	Extra over backfilling to drain trenches, chambers, etc for suitable earth backfilling supplied by the contractor	m3	15		
	TESTING				
106	Allow for testing all drains, sanitary plumbing, water supplies and installation to the satisfaction of the Principle Agent.		Item		
		Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne				
	R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.3</u>			
	<u>BILL NO. 12</u>			
	<u>GLAZING</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	GLAZING TO STEEL WITH PUTTY			
	6,38mm Obscure safety glass			
107	Panes not exceeding 0,1 m ²	m ²	7	
	Carried Forward		R	
	Bill No. 3 Gr R3 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
SECTION NO.3				
BILL NO. 13				
PAINTWORK				
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades				
PAINTWORK ETC TO NEW WORK				
PREPARATORY WORK TO EXISTING WORK				
Previously painted plastered surfaces				
Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth				
Previously painted metal surfaces				
Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal				
Previously painted wood surfaces				
Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth				
ON FIBRE-CEMENT				
Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint				
108	On fascias and barge boards	m ²	10	
	Carried Forward		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	ON METAL			
	Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.			
109	On door frames	m ²	10	
	Spot priming defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel			
110	On windows with burglar bars	m ²	5	
	1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)			
111	On gates (Measured over the full flat area of both sides)	m ²	20	
	ON WOOD			
	Under coat and minimum 2 coats gloss enamel, colour TBC			
112	On doors (External)	m ²	15	
113	On doors (Internal)	m ²	19	
	Carried to Summary		R	
Bill No. 3 Gr R3 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	<p><u>SECTION NO.5</u></p> <p><u>BILL NO. 1</u></p> <p><u>EARTHWORKS (PROVISIONAL)</u></p> <p>For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades</p> <p><u>SUPPLEMENTARY PREAMBLES</u></p> <p>Nature of ground</p> <p>Use "assumed to be" if no trial holes, soils investigations, etc have been carried out - discuss with engineer. Use "Trial holes indicate that" where the ground has been investigated by means of trial holes</p> <p>Nature of ground</p> <p>A soils investigation has been carried out on site by the engineer and the report is annexed to these bills of quantities. Descriptions of excavations shall be deemed to include all ground conditions classifiable as "earth" described in the above report and where conditions of a more difficult character are indicated these are separately measured</p> <p>Carting away of excavated material</p> <p>Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the building site</p> <p>Filling</p> <p>Notwithstanding the reference to prescribed multiple handling in clause 1 page 6 of the Standard System of Measuring Building Work, prices for filling and backfilling shall include for all selection and any multiple handling of material</p> <p>Carried Forward</p> <p>Bill No. 4 SD5 - Waterborne</p> <p>R MAHANGE & ASSOCIATES</p>		R	

Item No	Brought Forward	Quantity	Rate	Amount
	Soil poisoning Ant and weed poisoning will be applied in accordance to SABS specifications by Registered and Approved Specialists who will issue a five (5) year guarantee. The contractor will only be paid for this items once they have produced the said certificate to the Principal Agent		R	
	<u>SITE CLEARANCE ETC</u>			
	Site clearance			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	101	
2	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	101	
	<u>EXCAVATION, FILLING, ETC</u>			
	Excavation in earth not exceeding 2m deep			
3	Trenches	m3	15	
4	Thickening under aprons	m3	5	
	Extra over trench and hole excavations in earth for excavation in			
5	Soft rock	m3	5	
6	Hard rock	m3	5	
	Extra over all excavations for carting away			
7	Surplus material from excavations on site to a dumping site to be located by the contractor	m3	7	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Risk of collapse of excavations			
8	Sides of trench and hole excavations not exceeding 1,5m deep	m2	74	
	Keeping excavations free of water			
9	Keeping excavations free of all water other than subterranean water		Item	
	Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density			
10	Under floors, steps, paving, etc	m3	7	
11	Backfilling to trenches, holes, etc	m3	5	
	Compaction of surfaces			
12	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	35	
	Under floors, steps, paving, etc.			
	Prescribed density tests on filling			
13	Modified AASHTO Density	No	6	
	<u>SOIL POISONING</u>			
	Weedkiller mixed in accordance to supplier's specifications			
14	To bottoms and sides of trenches, etc.	m2	183	
15	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	65	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Soil insecticide			
16	To bottoms and sides of trenches etc	m2	183	
17	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	65	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
SECTION NO.5				
BILL NO. 2				
CONCRETE, FORMWORK AND REINFORCEMENT				
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades				
UNREINFORCED CONCRETE, ETC.				
15MPa/19mm concrete				
18 Surface blinding under footings and bases	m3	2		
25MPa/19mm concrete				
19 Strip footings	m3	14		
REINFORCED CONCRETE				
25MPa/19mm concrete				
20 Surface beds	m3	7		
TEST CUBES				
21 Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith	Sets	3.0		
CONCRETE SUNDRIES				
Finishing top surfaces of concrete smooth with a wood float/steel trowel				
22 Surface beds, slabs, etc	m2	40		
SMOOTH FORMWORK (DEGREE OF ACCURACY I)				
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Smooth formwork to sides			
23	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	50	
	REINFORCEMENT (PROVISIONAL)			
	Mild steel reinforcement to structural concrete work			
24	8mm Diameter bars	t	0.50	
25	10mm Diameter bars	t	0.50	
	Fabric Reinforcement			
26	Mesh ref. No. 395 fabric reinforcement fixed horizontally in surface beds etc.	m ²	39	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
<u>SECTION NO.4</u>				
<u>BILL NO. 3</u>				
<u>MASONRY</u>				
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades				
<u>SUPPLEMENTARY PREAMBLES</u>				
<u>BRICKWORK</u>				
Sizes in descriptions				
Where sizes in descriptions are given in brick units, "one brick" shall represent the length and "half brick" the width of a brick				
Face bricks				
Bricks shall be ordered timeously to obtain uniformity in size and colour				
Pointing				
Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc				
<u>FOUNDATIONS (PROVISIONAL)</u>				
Brickwork of NFP bricks in class II mortar				
27 One brick walls	m2	20		
28 Half brick walls	m2	45		
<u>SUPERSTRUCTURE</u>				
	Carried Forward		R	
Bill No. 4				
SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	FACEBRICK			
	Face bricks (purchase price of R5 000.00/1000 delivered to site excluding VAT) pointed with flush horizontal and vertical joints			
29	Half brick walls in beamfilling .	m2	7	
30	Half brick walls	m2	35	
31	One brick walls	m2	80	
	FACE BRICKWORK			
32	Extra over brickwork for face brickwork	m2	74	
	Corobrick "Letaba Satin Face bricks" Brick-on-edge header course copings, sills, etc pointed with recessed joints on all exposed faces:			
33	Extra over brickwork for brick-on-edge header course lintel	m	15	
34	110mm Wide sill set level and slightly projecting	m	8	
35	220mm Wide sill set sloping and slightly protecting outside	m	13	
36	Fair cutting fitting around pipe not exceeding 100mm	No	10	
37	Fair cutting fitting around pipe exceeding 100mm and not exceeding 200mm diameter	No	10	
	<u>BRICKWORK SUNDRIES</u>			
	Brickwork reinforcement			
38	75mm Wide reinforcement built in horizontally	m	50	
39	150mm Wide reinforcement built in horizontally	m	360	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Galvanised wire ties etc			
40	6mm Diameter roof tie 2m long with one end fixed to timber and other end built into brickwork	No	12	
	Turning pieces to lintels etc.			
41	115mm Wide turning pieces	m	6	
42	230mm Wide turning pieces	m	6	
	Prestressed fabricated lintels			
43	110 x 75mm Lintels in lengths exceeding 3m and not exceeding 6m	m	15	
	Air bricks etc.			
44	230 x 152mm terra-cotta vermin proofed loured air brick	No	15	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.4</u>			
	<u>BILL NO. 4</u>			
	<u>WATERPROOFING</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>DAMP-PROOFING OF WALLS AND FLOORS</u>			
	One layer of 375 micron Consol Plastic Brikgrip DPC" embossed damp proof course			
45	In walls	m ²	10	
	One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"			
46	Under surface beds	m ²	35	
	<u>FLOOR AND WALL SEALERS</u>			
	Secomastic non setting mastic sealant applied cold with a hand pressure caulking gun and leave perfectly watertight			
47	Around steel windows and door frames	m	100	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward			R
	<u>SECTION NO. 5</u>			
	<u>BILL NO. 5</u>			
	<u>ROOF COVERINGS ETC</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>PROFILED METAL SHEETING AND ACCESSORIES</u>			
	0,6mm "Kliplok" roof sheeting in chromadek finish fixed to timber purlins (elsewhere)			
48	Roof covering with pitch not exceeding 25 degrees	m2	55	
	<u>ROOF AND WALL INSULATION</u>			
49	12" Thermal resistance sisalition laid on purlins	m2	55	
	Carried Forward			R
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
			R	
	<u>SECTION NO.4</u>			
	<u>BILL NO. 6</u>			
	<u>CARPENTRY AND JOINERY</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>ROOFS, ETC.</u>			
	<u>Sawn softwood grade 6</u>			
50	76 x 38mm Wall plates	m	25	
51	38 x 114mm Rafters in lengths exceeding 3,9m and not exceeding 6,6m	m	50	
52	50 x 76mm Purlins in lengths exceeding 3,9m and not exceeding 6,6m	m	70	
53	50 x 76mm Purlins in lengths exceeding 6,6m and not exceeding 8,1m	m	70	
	<u>Sundries</u>			
54	Two coats creosote on sawn timbers	m ²	30	
55	6mm Diameter galvanised wire tie 3000mm girth wrapped around rafter and purlin with ends tied together	No	13	
56	Hurricane clips	No	30	
	<u>EAVES, VERGES, ETC</u>			
	Pressed fibre-cement:			
57	15 x 230mm Nutec Fascias and barge boards including galvanised steel H-profile jointing strips	m	30	
	<u>DOORS, ETC</u>			
		Carried Forward		R
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	Wrought meranti doors hung to steel frames			
58	44mm framed, ledged and braced door 813 x 2032mm high including external weather bar (D1)	No	2	
59	44mm framed, ledged and braced door 813 x 1882mm high (door raised by 150mm from bottom) (D2)	No	5	
60	44mm framed, ledged and braced door 915 x 2032 high including external weather bar (disabled)	No	1	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward			R
	<u>SECTION NO.4</u>			
	<u>BILL NO. 7</u>			
	<u>IRONMONGERY</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	HINGES, BOLTS, ETC			
	100mm Chrome plated "D" type handle 3 by solid brace hinges			
	CATCHES, CABIN HOOKS, ETC			
61	100mm brace Cabin hook and eye including 70 x 70 x 20mm chamfered hardwood block twice oiled and plugged	No	5	
	LOCKS			
	Approved			
62	Three lever mortice lock set	No	3	
63	Indicator lock set	No	5	
64	Security double throw dead lock (no latch)	No	3	
	HANDLES, ETC.			
	Aluminium Pull Handle			
65	ASSA ABLOY Anodised Silver straight pull handle (Code: AL5515-300BBAS) with 300mm fixing centres.		Item	
	SUNDRIES			
		Carried Forward		R
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	ASSA ABLOY			
66	38mm Diameter rubber door stop plugged	No	3	
	Vaal Paragon			
67	32mm Type 9 back grab rail 800mm long plugged	No	1	
68	32mm Type 8 side grab rail 900mm girth plugged	No	1	
	<u>LETTERS, NAMEPLATES, ETC</u>			
	Dorma:			
69	DSS-130 Engraved "Male" information sign, plugged	No	1	
70	DSS-131 Engraved "Female" information sign, plugged	No	1	
71	DSS-133 Engraved "Disabled" information sign, plugged	No	1	
	<u>BATHROOM FITTINGS</u>			
	Sundries			
	Kimberley-Clark or Similar			
72	SQ2 code 405607B white none lockable toilet roll holder	No	6	
	stainless Steel			
73	Stainless steel mirror size: 350 x 400mm plugged to wall with chrome plated screws.	No	4	
74	Brushed stainless steel body, rust resistant, she bin, approximately 330 x 280 x 180mm etc	No	5	
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 8</u>			
	<u>METALWORK</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>WELDED SCREENS, GATES, ETC</u>			
	Gates to external doors			
75	Purpose made square hollow section mild steel single security gate and frame size to fit standard door, size 813 x 2032mm high	No	3	
	<u>PRESSED STEEL DOOR FRAMES</u>			
	1,2mm Double rebated frames suitable for half brick walls			
76	Frame for door size 813 x 2032mm high	No	5	
	1,2mm Double rebated frames suitable for one brick walls			
77	Frame for door size 813 x 2032mm high	No	2	
78	Frame for door size 914 x 2032mm high	No	1	
	<u>STEEL WINDOWS, DOORS, ETC</u>			
	Nty steel or similar approved school windows with standard burlgar bars formed of 20 x 5mm thick flat bars to all sashes			
79	Window type NE1, size 533 x 654mm high	No	8	
80	Window type NE7, size 1022 x 654mm high	No	5	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

THE MVULA TRUST
MAKOPUNG PRIMARY SCHOOL
TMT-LDOE-2023/24-BATCH06LPCL3J
BILL NO. 4

Item No	Brought Forward	Quantity	Rate	Amount
	<u>Sundries</u>			R
	Cage, etc			
81	She bin cages, to fit 330 x 280 x 180mm width, she bin to be able to open, including pad lock and locking mechanism, complete, etc	No	5	
	Carried Forward			R
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO.4</u>			
	<u>BILL NO. 9</u>			
	<u>PLASTERING</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	<u>GRANOLITHIC</u>			
	Untinted granolithic on concrete			
82	20mm Thick on floors	m2	35	
	<u>INTERNAL PLASTER</u>			
	Cement plaster on brickwork or blockwork			
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	<u>SECTION NO.4</u>			R
	<u>BILL NO. 10</u>			
	<u>PLUMBING AND DRAINAGE(PROVISIONAL)</u>			
	RAINWATER DISPOSAL			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	Aluminium Zinc Seamless Gutters			
83	100 x 100mm standard rainwater gutters fixed with gutter brackets	m	20	
84	Extra over eaves gutter for stopped end	No	2	
85	75 x 100mm Diameter rainwater down pipes fixed to wall	m	10	
86	Extra over eaves gutter for outlet for 75 x 100mm down pipe	No	2	
87	Ditto .for shoe	No	2	
	<u>SANITARY FITTINGS</u>			
	"Vaal" or similar and approved			
88	Ceramic wall mounted wash hand basin, complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	5	
89	WC suite, comprising with pan and double flap heavy duty plastic seat and matching cistern with flush pipe, complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	5	
	Carried Forward			R
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No			Quantity	Rate	Amount
	Brought Forward			R	
90	Paraplegic floor mounted suite with purpose made flush lever, etc. Complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	1		
91	Vitreous china urinal. Complete with all fittings and accessories including cutting & making good wall & floor wherever required.	No	2		
	PRECAST CONCRETE WASH HAND TROUGH				
92	Standard SABS approved Pre-Cast Concrete Double Wash Trough, 1080 x 650 x 850mm high with support legs fitted with standard 3/4 Brass Garden Taps, fixed complete to berick wall, including all necessary pipework, including soak away as per 'Engineers detail'.	No	1		
	Rainwater tank, etc.				
93	5000 Litre watertank fitted onto and secured to tank platforms including fastening cables	No	1		
	SOIL DRAINAGE				
	uPVC pipes				
94	110mm Pipes laid in and including trenches not exceeding 1m deep	m	30		
	Extra over uPVC pipes for fittings				
95	110mm Bend	No	6		
96	110mm Junction	No	6		
	uPVC gulleys				
97	110mm Gully not exceeding 750mm deep, including excavations, pre-cast concrete sorround etc.	No	5		
	WASTE UNIONS ETC				
	Carried Forward			R	
	Bill No. 4 SD5 - Waterborne				
	R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	"Cobra Watertech"			
98	Cobra Watertech 32mm chrome plated basin waste (code: 308) with 62mm diameter flange, 80mm long shank and plug	No	5	
	TRAPS ETC			
	"Cobra Watertech"			
99	Cobra Ref. 365/40" CP bottle trap	No	1	
	Marley			
100	40 x 300mm Sink combination for double bowl with deepseal "P" trap	No	1	
	TAPS, VALVES, ETC			
101	Cobra Watertech 15mm compression type angle regulating valve with 10mm bendable copper outlet tube service connection (Code: 232/350).	No	10	
102	Cobra Watertech 15mm chrome plated bibtap (Code: NM-500-21B) with blue indice and elbow action lever, manufactured in accordance with SANS 226:2009 Type 2 (BS 5412).	No	5	
	<u>SANITARY PLUMBING</u>			
	uPVC pipes			
103	50mm Pipes	m	50	
	Extra over uPVC pipes for fittings			
104	50mm Bend	No	10	
105	50mm Access bend	No	5	
106	50mm Junction	No	5	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward		Quantity	Rate	Amount		
<u>WATER SUPPLIES</u>							
Class 0 copper pipes							
107	15mm Pipes		m	50			
108	22mm Pipes		m	50			
Extra over class 0 copper pipes for capillary fittings							
109	15mm Fittings		No	20			
110	22mm Pipes		No	20			
SUNDRIES							
111	Extra over excavation in earth for pipe trenches, chambers, etc for excavation in soft rock		m3	20			
112	Ditto, but in hard rock		m3	5			
113	Extra over excavation for pipe trenches, chambers, etc for carting away surplus material to a dumping site to be located by the contractor		m3	10			
114	Extra over backfilling to drain trenches, chambers, etc for suitable earth backfilling supplied by the contractor		m3	25			
TESTING							
115	Allow for testing all drains, sanitary plumbing, water supplies and installation to the satisfaction of the Principle Agent.		Item				
Carried Forward							
Bill No. 4 SD5 - Waterborne							
R MAHANGE & ASSOCIATES							

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>SECTION NO. 4</u>			
	<u>BILL NO. 12</u>			
	<u>GLAZING</u>			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	GLAZING TO STEEL WITH PUTTY			
	6,38mm Obscure safety glass			
116	Panes for type NE1	No	8	
117	Panes for type NE7	No	5	
	Carried Forward		R	
	Bill No. 4 SD5 - Waterborne			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
SECTION NO.4				
BILL NO. 13				
PAINTWORK				
For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades				
PAINTWORK ETC TO NEW WORK				
PREPARATORY WORK TO EXISTING WORK				
Previously painted plastered surfaces				
Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth				
Previously painted metal surfaces				
Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal				
Previously painted wood surfaces				
Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth				
ON FIBRE-CEMENT				
Prepare and brush to remove all loose contaminations, apply one coat primer and two coats PVA emulsion paint				
118 On fascias and barge boards	m ²	10		
	Carried Forward		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	ON METAL			
	Prime and paint undercoat and 2 finishing coats in gloss enamel, colour TBC.			
119	On door frames	m2	17	
	Spot priming defects in pre-prime surface with zinc chromate primer and apply one universal undercoat and two coats EPWP. golden brown gloss enamel paint on steel			
120	On windows with burglar bars	m2	10	
	1 coat zinc chromate primer minimum and 2 coats gloss enamel (Exterior Quality)			
121	On gates (Measured over the full flat area of both sides)	m2	10	
	ON WOOD			
	Under coat and minimum 2 coats gloss enamel, colour TBC			
122	On doors (External)	m2	10	
123	On doors (Internal)	m2	10	
	Carried to Summary		R	
Bill No. 4 SD5 - Waterborne				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	<u>EXTERNAL WORKS</u>			
	<u>SECTION NO. 5</u>			
	<u>WATER SUPPLY</u>			
	<u>Class 10 HDPE type IV pipes</u>			
1	40mm Pipes laid in and including trenches not exceeding 1m deep	m	65	
2	50mm Pipes laid in and including trenches not exceeding 1m deep	m	40	
	<u>Extra over Class 10 HDPE type IV pipes for fittings</u>			
3	40mm Fittings	No	15	
4	40mm Reducer	No	15	
5	40mm Bend	No	15	
6	50mm Reducer	No	15	
7	50mm Bend	No	15	
8	50mm Threaded adaptor	No	15	
	<u>Galvanised medium steel pipes with screwed and socketed joints</u>			
9	50mm Pipes	m	70	
	<u>Extra over galvanised medium steel pipes with screwed and socketed joints for steel fittings</u>			
10	50mm Fittings	No	15	
11	50mm Bush	No	15	
12	50mm Elbow	No	15	
	<u>Valve boxes</u>			
		Carried Forward		R
Bill No. 5 External works				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward			R
13	600 x 600mm Stopcock box complete as per detail drawing "Valve chamber" including 400 x 400 cast iron cover and frame depth not exceeding 750mm internally.	No	1	
	<u>Sundries</u>			
14	Cutting into existing water pipe	No	1	
	Carried Forward			R
Bill No. 5 External works				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
SECTION NO.7				
WATER TANKS				
ELEVATED WATER TANKS				
SUPPLEMENTARY PREAMBLES				
For preambles see "Specifications of materials and methods to be used - PW 371"				
<u>Excavation in earth not exceeding 2m deep</u>				
15 Holes	m3	8		
<u>Extra over trench and hole excavations in earth for excavation in</u>				
16 Soft rock	m3	5		
17 Hard rock	m3	2		
<u>Extra over all excavations for carting away</u>				
18 Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor.	m3	3		
Risk of collapse of excavations				
19 Sides of trench and hole excavation not exceeding 1,5m deep.	m2	10		
<u>Keeping excavations free of water.</u>				
20 Keeping excavations free of water.		Item		
<u>Earth filling obtained from the excavations and / or prescribed stock piles on site compacted to 93 % Mod AASHTO density</u>				
21 Backfilling to trenches, holes, etc.	m3	5		
	Carried Forward		R	
Bill No. 5				
External works				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	15Mpa/19mm Concrete			
22	Blinding	m3	2	
	<u>25Mpa/19mm Concrete</u>			
23	Bases	m3	5	
24	Platform surface beds cast in panels	m3	5	
	<u>Finishing top surfaces of concrete smooth with a wood float</u>			
25	Platform surface beds	m2	23	
	<u>Finishing top surfaces of concrete smooth with a wood float</u>			
26	On top of bases	m2	5	
	<u>"Jojo" or equal approved SANS PVC water tanks</u>			
27	10 000 Litre plastic water tank fitted onto and secured to tank platforms	No	1	
	<u>Galvanized medium normalized mild steel piping</u>			
28	25mm Pipes	m	20	
29	50mm Pipes	m	20	
	<u>Extra over galvanised mild steel water supply pipes for fittings:</u>			
30	25mm Fittings.	No	10	
31	50mm Elbows.	No	10	
32	50mm Union.	No	10	
33	50mm Reducing bush.	No	5	
	Carried Forward		R	
	Bill No. 5			
	External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>"Cobra Watertech" or other equal approved</u>			
34	15mm "Cobra Ref. 108LK" brass hose biptap.	No	4	
35	50mm Fullway gate valve	No	4	
	<u>The following in structural steel tank stands</u>			
	<u>Welded steel columns in single lengths with flat base, cap, bearer and connection plates, bolted to concrete</u>			
36	80 x 80mm x 6mm angle columns	t	1.00	
	<u>Steel members and girth, bolted to steel</u>			
37	30 x 30mm x 6mm Flat-bar	t	0.20	
38	40 x 40mm x 5mm angle	t	0.20	
39	125 x 75mm x 8mm unequal angle	t	0.20	
40	125 x 50mm x 20 x 2mm Lipped channel	t	0.50	
	<u>BOLTS, FASTENERS, ETC. (LI)</u>			
41	High tensile bolts	t	0.50	
42	12mm Diameter L-shaped threaded anchor bolt 350mm girth embedded in top of concrete	No	10	
	<u>ON METAL</u>			
	<u>Undercoat and minimum 2 coat gloss enamel</u>			
43	Panting to structural steel	m ²	100	
	<u>TESTING</u>			
	<u>Testing of water tanks</u>			
44	Testing for tank		Item	
		Carried Forward	R	
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

THE MVULA TRUST
MAKOPUNG PRIMARY SCHOOL
TMT-LDOE-2023/24-BATCH06LPCL3J
BILL NO. 5

Item No		Quantity	Rate	Amount
	Brought Forward		R	
Bill No. 5 External works	Carried Forward		R	
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward			R
	SECTION NO.5			
	SEPTIC TANK			
	SEPTIC TANKS, ETC.			
	For preambles see "Model Preambles for Trades (2008 Edition)" and Supplementary preambles as specified in the Trades			
	SITE CLEARANCE ETC			
	<u>Site clearance</u>			
45	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m ²	33	
	EXCAVATION, FILLING, ETC.			
	<u>Excavation in earth exceeding 2m and not exceeding 4m deep</u>			
46	Holes	m ³	39	
	Extra over all excavations for carting away			
47	Extra over all excavations for carting away surplus material from excavations and/or stockpile on site to a dumping site to be located by the Contractor	m ³	33	
	<u>Risk of collapse of excavations</u>			
48	Sides of trench and hole excavations exceeding 1,5m deep and not exceeding not exceeding 3m deep	m ²	30	
	<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
49	Backfilling to trenches, holes, etc	m ³	6	
	Carried Forward			R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward			R
	Keeping excavations free of water			
50	Keeping excavations free of all water other than subterranean water	Item		
	REINFORCED CONCRETE			
	<u>15MPa/19mm concrete</u>			
51	15Mpa in blinding	m3	1	
	<u>25MPa/19mm concrete</u>			
52	25Mpa in base	m3	5	
53	25Mpa in slab over septic tank	m3	3	
54	Concrete haunch formed below pipes	m3	1	
	CONCRETE SUNDRIES			
	<u>Finishing top surfaces of concrete smooth with a steel trowel</u>			
55	Surface beds, slabs, etc. to falls	m2	18	
	<u>Permanent formwork to soffits</u>			
56	Slab over septic tank	m2	20	
	Smooth formwork to form			
57	Opening not exceeding 1m girth through 170mm slab	No	2	
	PRECAST CONCRETE			
58	Heavy duty lintels exceeding 3m and not exceeding 6m	m	5	
	Carried Forward			R
	Bill No. 5			
	External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward			R
	<u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u>			
	<u>Smooth formwork to sides</u>			
59	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	75	
	<u>REINFORCEMENT</u>			
	<u>Fabric reinforcement</u>			
60	Type 888 fabric reinforcement in concrete surface beds, slabs, etc	m ²	40	
	<u>MASONRY</u>			
	<u>Brickwork of NFP bricks in class II mortar</u>			
61	One brick walls	m ²	40	
62	Half brick wall	m ²	15	
	<u>Brickwork reinforcement</u>			
63	150mm Wide reinforcement built in horizontally	m	60	
	<u>BRICKWORK SUNDRIES</u>			
64	Leave of form 450 x 150mm high opening through a one brick wall	No	2	
65	Leave or form opening through one brickwall for pipe 110mm dia	No	2	
	<u>PLASTERING</u>			
	<u>Watertight cement plaster on brickwork</u>			
66	On walls	m ²	50	
	Screeed			
	Carried Forward			R
	Bill No. 5			
	External works			
	R MAHANGE & ASSOCIATES			

Item No		Brought Forward	Quantity	Rate	Amount
67	On floors <u>Two coats approved epoxy coats</u>		m2	20	R
68	On walls and floors		m2	60	
	<u>PLUMBING AND DRAINAGE</u>				
	<u>uPVC pipes</u>				
69	110mm Pipes		m	10	
	Extra over uPVC pipes for fittings				
70	110mm Tee		No	4	
	<u>Cover, etc</u>				
71	600 x 600mm Type 2A cast iron single seal manhole cover and frame		No	2	
72	Lifting key for manhole cover		No	2	
		Carried Forward		R	
	Bill No. 5 External works				
	R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward			R
	SECTION NO.5			
	FRENCH DRAINS			
	SITE CLEARANCE ETC.			
	<u>Site clearance</u>			
73	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc.	m ²	20	
	EXCAVATION, FILLING, ETC.			
	<u>Excavation in earth not exceeding 2m deep</u>			
74	Holes	m ³	15	
	<u>Extra over trench and hole excavations in earth for excavation in</u>			
75	Soft rock	m ³	1	
76	Hard rock	m ³	1	
	<u>Extra over all excavations for carting away</u>			
77	Extra over all excavations for carting away surplus material from excavations and/or stockpile on site to a dumping site to be located by the Contractor	m ³	10	
	<u>Risk of collapse of excavations</u>			
78	Sides of trench and hole excavations not exceeding 1,5m deep	m	30	
	<u>Keeping excavations free of water</u>			
79	Keeping excavations free of all water other than subterranean water		Item	
	Carried Forward			R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>Earth filling obtained from the excavations and/or prescribed stock piles on site (not compacted)</u>			
80	On top of french drain as soil cover	m3	7	
	<u>FILTER FABRIC</u>			
	<u>"Kaytech Engineered Fabric" or similar approved laid in strict accordance to the manufacturer's instructions</u>			
81	"Kaymat U14" or equal approved around stone filling in sub-soil drain trenches	m2	20	
	<u>20mm Graded stone filling or similar approved</u>			
82	In holes	m3	5	
	200 - 300mm Diameter clean washed stone filling or similar approved by engineer			
83	In holes	m3	10	
	<u>WATERPROOFING</u>			
	<u>One layer of 250 micron "Tarkon USB Green" or equal approved waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
84	On top of pipes as protection of joints	m2	15	
	<u>ROOF SHEETING</u>			
	<u>Roof sheeting</u>			
85	On top of french drain	m2	15	
	<u>uPVC pipes</u>			
86	110mm pipes laid in and including trenches	m	5	
	<u>Extra over uPVC pipes for fittings</u>			
	Carried Forward		R	
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

THE MVULA TRUST
MAKOPUNG PRIMARY SCHOOL
TMT-LDOE-2023/24-BATCH06LPCL3J
BILL NO. 5

Item No		Brought Forward	Quantity	Rate	Amount
87	110mm End cap	No	4	R	
88	110mm Bend	No	2		
		Carried Forward		R	
	Bill No. 5 External works				
	R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward			R
	SECTION NO.5			
	WATER HARVESTING TANKS			
	WATER TANKS			
	SITE CLEARANCE ETC			
	<u>Site clearance</u>			
89	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc.	m ²	60	
	EXCAVATION, FILLING, ETC.			
	<u>Excavation in earth not exceeding 2m deep</u>			
90	Trenches	m ³	20	
	Extra over trench and hole excavations in earth for excavation in			
91	Soft rock	m ³	3	
92	Hard rock	m ³	3	
	<u>Extra over all excavations for carting away</u>			
93	Surplus material from excavations on site to a dumping site to be located by the contractor	m ³	10	
	<u>Risk of collapse of excavations</u>			
94	Sides of trench and hole excavations not exceeding 1,5m deep	m ²	25	
	<u>Keeping excavations free of water</u>			
95	Keeping excavations free of all water other than subterranean water	Item		
	Carried Forward			R
	Bill No. 5			
	External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
	<u>Earth filling obtained from the excavations and /or prescribed stock piles on site including compacted to 93% Mod AASHTO density</u>			
96	Backfilling to trenches, holes, etc	m3	9	
	<u>SOIL POISONING</u>			
	<u>Soil poisoning mixed in accordance to supplier's specifications</u>			
97	To bottoms and sides of trenches, etc.	m2	15	
	<u>CONCRETE, FORMWORK AND REINFORCEMENT</u>			
	<u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u>			
	<u>25MPa/19mm concrete</u>			
98	Strip footings	m3	10	
99	Platform surface beds cast in panels	m3	4	
	<u>FINISHING TOP SURFACE OF CONCRETE</u>			
	<u>Finishing top surfaces of concrete smooth with a wood float/steel trowel</u>			
100	Surface beds, slabs, etc (rainwater tanks)	m2	20	
	<u>REINFORCEMENT</u>			
	<u>Fabric reinforcement</u>			
101	Type 295 fabric reinforcement in concrete surface beds, slabs, etc	m2	20	
	Carried Forward		R	
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward			R
	<u>TEST CUBES</u>			
102	Allow for preparing a set of three concrete strength test cubes, each size 150 x 150 x 150mm, sending them to an approved Testing Laboratory for testing and paying all charges in connection therewith.	Sets	3.0	
	<u>BRICKWORK</u>			
	<u>Brickwork of NFP bricks in class II mortar</u>			
103	One brick walls	m ²	15	
	<u>BRICKWORK SUNDRIES</u>			
	<u>Brickwork reinforcement</u>			
104	150mm Wide reinforcement built in horizontally	m	50	
	<u>FACE BRICKWORK</u>			
105	Extra over brickwork for face brickwork	m ²	25	
	<u>Brick-on-edge header course copings, sills, etc of face bricks (Purchase price R3 500.00/1000 VAT excl. delivered to site) pointed with recessed joints on all exposed faces</u>			
106	Coping on top of one brick wall	m	50	
	<u>WATERPROOFING</u>			
	<u>One layer of 250 micron "Consol Plastic USB Green" waterproof sheeting sealed at laps with "Gunplas Pressure Sensitive Tape"</u>			
107	Under surface beds	m ³	25	
	<u>WATER SUPPLIES</u>			
	<u>"Jojo" approved SANS PVC water tanks</u>			
	Carried Forward			R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

THE MVULA TRUST
 MAKOPUNG PRIMARY SCHOOL
 TMT-LDOE-2023/24-BATCH06LPCL3J
 BILL NO. 5

Item No		Quantity	Rate	Amount
	Brought Forward			R
108	5 000 Litre plastic water tank fitted onto and secured to tank platforms	No	2	
	<u>Galvanized medium normalized mild steel piping</u>			
109	25mm Pipes	m	10	
	<u>Extra over galvanised mild steel water supply pipes for fittings:</u>			
110	25mm Fittings.	No	5	
111	15mm "Cobra Ref. 108LK" brass hose biptap	No	5	
	Carried Forward			R
Bill No. 5 External works				
R MAHANGE & ASSOCIATES				

Item No	Brought Forward	Quantity	Rate	Amount
	<u>SECTION NO.5</u>			R
	<u>PAVED WALKWAYS</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	For preambles see "Specifications of materials and methods to be used - PW 371"			
	<u>Site Clearance</u>			
112	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc.	m2	250	
113	Stripping average 100mm thick layer of top soil and stockpiling on site	m2	250	
	<u>Open face excavation in earth over sloping site</u>			
114	Excavation in earth not exceeding 2m open face excavation to form platforms under parking areas etc and depositing excavated material over site, including haulage not exceeding 10m from perimeter of excavations exceeding 2m deep	m3	50	
	<u>Extra over all excavations for carting away</u>			
115	Surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor.	m3	50	
	<u>Earth filling supplied by the contractor under parking areas, roadways, etc</u>			
116	Sub-base course of G5 material in accordance with SABS 1200 DM, compacted to 93% Mod AASHTO density	m3	40	
	<u>Compaction of surfaces</u>			
		Carried Forward		R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward			R
117	Compaction of ground surface under floors etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density	m ³	40	
118	<u>Soil poisoning</u> Weedkiller (active ingredients metalaclor 102,8 g/l, terbitilasien 248,6 g/l and atrasien 248,6 g/l) mixed in the proportion of 100 ml weedkiller to 100 l water and applied at a rate of 10 l/m ² on cleared ground	m ²	200	
119	Kerbing			
120	Concrete kerbing to SANS 927 on:			
119	Bedding (4:1) river sand: cement	m ³	20	
120	Fig. 10 kerbs to sides of paving	m	220	
121	15Mpa/19mm unreinforced concrete in haunching	m ³	1	
	<u>60mm Thick precast concrete DZZ interlocking heavy duty block paving of grey paving blocks in accordance with SANS 1058, laid to falls on and including 25mm thick sand layer with joints filled in with sand, compacted with a vibration compactor:</u>			
122	25mm thick clean, dry river sand layer, spread and levelled to receive paving blocks	m ³	5	
123	Paving to toilet areas etc. to falls	m ²	150	
	Carried Forward			R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No	Brought Forward	Quantity	Rate	Amount
	<u>SECTION NO.5</u>			R
	<u>STORMWATER CONTROL</u>			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	For preambles see "Specifications of materials and methods to be used - PW 371"			
	<u>Earthworks</u>			
124	Digging up and removing rubbish, debris, vegetation, hedges, shrubs, bush and trees not exceeding 200mm girth, etc.	m2	200	
125	Excavate in earth below natural, reduced or made up ground level , not exceeding 2m deep, to reduced levels under aprons, paving, etc.	m3	30	
126	Extra over surplus material from excavations and/stock piles on site to the dumping site to be located by the Contractor.	m3	30	
127	Extra over trench or hole for excavations in soft rock	m3	15	
128	Extra over trench or hole for excavations in hard rock	m3	10	
129	Re-compaction of disturbed formation levels, including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% Mod AASHTO density	m2	200	
130	Treat soil under concrete rain water channels, etc. with an approved insecticide solution at the rate not less than 2 litre per 1m2	m2	200	
	<u>Reinforced Concrete</u>			
		Carried Forward		R
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
	Brought Forward		R	
131	25Mpa/19mm Mass concrete in V-shaped channel 2000mm wide x 75mm thick with rounded salient edges and finished on exposed surfaces with 2:1 cement mortar, with and including one layer of ref.193 mesh reinforcement, laid to falls in panels not exceeding 2,0m long with 12mm bitumen impregnated soft board movement joints with exposed edges raked out for a depth of 10mm and filled with bituminous compound including all necessary excavations and formwork	m	150	
132	Extra for fair open end	No	5	
133	Extra for fair stopped end	No	5	
134	Extra for angle intersection	No	5	
<u>FENCING</u>				
<u>SUPPLEMENTARY PREAMBLES</u>				
Fencing around Gr R and tank stands				
For preambles see "Specifications of materials and methods to be used - PW 371"				
	Carried Forward		R	
Bill No. 5 External works				
R MAHANGE & ASSOCIATES				

Item No		Quantity	Rate	Amount
	Brought Forward		R	
135	<p>Panels: 1.80m x 3.0m</p> <p>Palings 'DevilFork'; 21 palings per panel. 30 x 30 x 2mm steel angle iron paling 1.8m high. Palings are to be inserted and firmly welded to the bearers at 133mm centre to centre. The top of the paling should provide a "Devil fork" effect and the bottom will have a dove tail.</p> <p>Fence bearers: 40 x 40 x 2mm angle iron. These are places 300mm from the top of the paling and 300mm from the bottom paling (350mm from ground level). These are to be welded flash with the back of the post Painting to all joints must be smoothed off. All faux, rust, grease and loose material to be removed before painting. Apply one coat primer for steel (red oxide), apply one coat universal undercoat for all surfaces, apply one coat gloss enamel. The colour of the gloss enamel paint shall be Traffic Green unless directed otherwise by the Limpopo Department of Education (not school) No brush painting</p>	m	140	
136	<p>Posts: 76 x 76 x 2mm steel square tubing with closing pyramid caps on top. The post should be at least 2.4m high and 600mm will be planted into the concrete footing in accordance to the engineers design</p>	No	50	
	Carried Forward		R	
	Bill No. 5 External works			
	R MAHANGE & ASSOCIATES			

Item No		Quantity	Rate	Amount
137	<p style="text-align: center;">Brought Forward</p> <p>Palisade Gates Sliding Gate: 1.5m wide x 1.8m high, 40 x 40 x 2mm angle iron palings welded to a 76 x 38 x 2 mm rectangular tubing bearer frame. Palings must be placed at 133 mm apart from each other centre to centre.</p> <p>Gate post: 75mm x 75mm x 2mm steel square tubing post is to be provided on each side of the gate opening with closing pyramid caps on top. The post is to be founded in a concrete footing 450 x 450 x 600 deep. Concrete strength to be 20MPa (minimum) at 28 days</p> <p>Painting: All joints must be smoothed off. All faux, rust, grease and loose material to be removed before painting. Apply one coat primer for steel (red oxide), apply one coat universal undercoat for all surfaces, apply one coat gloss enamel. The colour of the gloss enamel paint shall be Traffic Green unless directed otherwise by the Limpopo Department of Education (not school) No brush painting</p>	No	2	R
	Carried to Summary		R	
	Bill No. 5 External works			

R MAHANGE & ASSOCIATES

THE MVULA TRUST
MAKOPUNG PRIMARY SCHOOL
TMT-LDOE-2023/24-BATCH06LPCL3J
BILL NO. 6

Item No		Quantity	Rate	Amount
1	Allow an amount of R105 000.00 (one hundred five thousand rand) for the Borehole refurbishment and borehole	Item		
2	Add profit and attendance	%		
3	Allow an amount of R----- for Reverse Osmosis	Item		
4	Add profit and attendance	%		
5	Allow an amount of R200 000.00 (two hundred thousand rand) for the Refurbishment of existing ablutions	Item		
6	Add profit and attendance	%		
7	Allow an amount of R----- for chemical toilets	Item		
8	Add profit and attendance	%		
Bill No. 6 Provisional Sums				R
R MAHANGE & ASSOCIATES				
Carried to Summary				

Bill No	FINAL SUMMARY	Page No		Amount
1	P's and G's	33		
2	Alterations	36		
3	Gr R3 - Waterborne	60		
4	SD5 - Waterborne	85		
5	External works	108		
6	Provisional Sums	109		
	Sub-total		R	
	CONTINGENCY (10%)		R	
	Sub Total		R	
	VAT (15%)		R	
	Carried to form of offer		R	
	R MAHANGE & ASSOCIATES			