

Item No	Quantity	Rate	Amount
<u>SECTION 1</u>			
<u>BILL No.1</u>			
<u>PRELIMINARIES</u>			
<u>BUILDING AGREEMENT AND PRELIMINARIES</u>			
1. The Principal Building Agreement shall be the JBCC Series Edition 4.1, March 2005 as recommended by the Joint Building Contract Committee and as amended by this Tender Enquiry. 2. The Preliminaries shall be JBCC Series 2000, May 2005 for use with the Principal Building Agreement as recommended by the Joint Building Contracts Committee and as amended by this Tender Enquiry shall be deemed to be incorporated herein. 3. Tenderers are referred to the abovementioned documents for the full intent and meaning of each clause thereof. These clauses are hereinafter referred to by clause number and heading only. 4. Where standard clauses or alternatives are not entirely applicable to this contract, such modifications, corrections or additions as are necessary, are given as far as possible under each relevant clause heading. Additional Preliminary clauses are contained in Section C hereof. 5. No claim whatsoever shall be entertained in respect of errors or omissions in pricing due to brevity of descriptions of items which are fully described when read in conjunction with the relevant clauses of the said Principal Building Agreement, Preliminaries and Preambles.			
Carried to Collection			R
Section 1			
Bill No. 1			
Preliminaries			

6. The Tenderers shall allow opposite each of the clauses whatever costs and charges he may consider necessary for the carrying out, complying with and due observance of the provisions, conditions and requirements set out herein. Only priced items will be considered in respect of any adjustment of this Section. Any items left unpriced will be understood to be provided free of charge and no claim for any extras arising out of the Tenderer's omission to price any item will be entertained.

7. Where modifications or amendments as described are made, such modifications and/or amendments shall supercede any conflicting provisions in the relevant clauses of the Standard Preliminaries or the Principal Building Agreement and the Tenderer shall make due allowance for whatever costs and charges he may consider necessary for the carrying out and observance of the provisions of the clauses as modified and/or amended.

8. Where any item is not relevant to this specific contract, such item is marked N/A.

9. If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries, each item priced is to be allocated to one or more of the three categories by insertion of "F", "V", "T" as the case may be against the price in the "rate" column immediately preceding the "amount" column, where "F" denotes a fixed amount (amount not to be varied), "V" denotes an amount variable in proportion to value, and "T" denotes an amount proportionate to time.

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

SECTION A: PRINCIPAL BUILDING AGREEMENT

DEFINITIONS

Definitions and interpretation (Clause 1).

1 F: V: T:

Item

OBJECTIVE AND PREPARATION

Offer, acceptance and performance (Clause 2).

2 F: V: T:

Item

Documents (Clause 3).

Clause 3.1 is deleted and substituted with: 'This tender is for a Government Contract. No Payment Guarantee will be provided.'

Clause 3.3 is deleted and substituted with:

The principal agent shall complete the schedule and arrange for formal signing of the agreement once the priced bill of quantities/lump sum document, security, insurances and waiver of lien, where acceptable, have been provided and effected'.

3 F: V: T:

Item

Design responsibility (Clause 4).

4 F: V: T:

Item

Employer's agents (Clause 5).

5 F: V: T:

Item

Site representative (Clause 6).

6 F: V: T:

Item

Compliance with regulations (Clause 7).

7 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Works risk (Clause 8)			
8	F: V: T: Indemnities (Clause 9). Clause 9.1.1 is deleted and substituted with: Claims from other parties consequent upon death of bodily injury or illness of any person or physical loss or damage to any property, other than the works, arising out or due to the execution of the works or occupation of the site by the contractor or his sub contractors'.	Item		
9	F: V: T: Works insurances (Clause 10).	Item		
10	F: V: T: Liability insurances (Clause 11).	Item		
11	F: V: T: Effecting insurances (Clause 12).	Item		
12	F: V: T: State Provisions (Clause 13).	Item		
13	F: V: T: Security (Clause 14).	Item		
14	F: V: T: <u>EXECUTION</u> Preparation for and execution of the works (Clause 15).	Item		
15	F: V: T: Access to the works (Clause 16).	Item		
16	F: V: T: Contract instructions (Clause 17).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

17	F: V: T: Setting out of the works (Clause 18.3). The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc., exist in order that the necessary arrangements may be made for the rectification of any such encroachments. Should incorrect information be given to the contractor in terms of 18.1 and 18.2, which causes the incorrect setting out of the works, the contractor shall not be liable for such incorrect setting out.	Item		
18	F: V: T: Assignment (Clause 19).	Item		
19	F: V: T: Nominated subcontractors (Clause 20).	Item		
20	F: V: T: Selected subcontractors (Clause 21).	Item		
21	F: V: T: Employer's Direct contractors (Clause 22).	Item		
22	F: V: T: Contractor's Domestic subcontractors (Clause 23).	Item		
23	F: V: T: <u>COMPLETION</u> Practical completion (Clause 24).	Item		
24	F: V: T: Works completion (Clause 25).	Item		
25	F: V: T: Final completion (Clause 26).	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

Latent defects liability period (Clause 27).

Clause 27.0 is amended by the addition of the following clauses:

"27.3 Any water leakage into the building, whether in the roof, external wall or other element of the building susceptible to water leakage shall, unless proven to be a design defect, or as a result of obvious storm damage, be classified as a latent defect in terms of clause 1.0 Definitions and Interpretations".

"27.4 The Contractor shall attend to defects during the Defects Liability Period on a progressive basis, to the satisfaction of the Principal Agent and will not be permitted to wait until the end of the Defect Liability Period or until the amount of defects accumulates in order to attend to a comprehensive list of defects"

26 F: V: T:

Item

Sectional completion (Clause 28).

27 F: V: T:

Item

Revision of date for practical completion (Clause 29).

28 F: V: T:

Item

Penalty for non-completion (Clause 30).

29 F: V: T:

Item

PAYMENT

Interim payment to the contractor (Clause 31).

The inclusion of materials and goods stored off site in the amount authorised for payment in terms of clause 31.3 shall be at the sole discretion of the principal agent and such inclusion shall only be considered upon the provision, by the contractor, of an approved guarantee issued by a registered commercial bank.

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

Where prices are submitted by the contractor or nominated/selected sub contractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing.

Adjustment to the contract value (Clause 32).

30 F: V: T:

Item

Recovery of expense and loss (Clause 33).

31 F: V: T:

Item

Final account and final payment (Clause 34).

32 F: V: T:

Item

Payment to other parties (Clause 35).

33 F: V: T:

Item

CANCELLATION

Cancellation by Employer - Contractor's default (Clause 36).

34 F: V: T:

Item

Cancellation by Employer - Loss and damage (Clause 37).

35 F: V: T:

Item

Cancellation by Contractor - Employer's default (Clause 38).

36 F: V: T:

Item

Cancellation - Cessation of the works (Clause 39).

37 F: V: T:

Item

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

DISPUTE

Dispute Settlement (Clause 40)

38 F: V: T:

Item

SUBSTITUTE PROVISIONS

State Clauses (Clause 41)

39 F: V: T:

Item

CONTRACT VARIABLES

The Schedule: Pre-Tender information (Clause 42).

40 F: V: T:

Item

CONTRACTING AND OTHER PARTIES (Clause 42.1)

Employer: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Principal Agent: The Mvula Trust

Postal Address: 67 Devereux Avenue, Vincent, East
London

Telephone: 043 726 2255

Facsimile: 043 726 5967

Physical address: 67 Devereux Avenue, Vincent, East
London

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

CONTRACT DETAILS (Clause 42.2)

Clause 42.2.1

Works Description: Construction of new ablution facilities.

Clause 42.2.2

Site Description: The site is the existing school.

Clause 42.2.3

Work or Installations by Others: NIL

Clause 42.2.4

This Agreement is for a State Contract :- Yes

Payment will be made for materials and goods:- Yes

Dispute resolution :- Mediation (in terms of clause 40) followed by litigation.

Arbitration rules as recommended by the Association of Arbitrators (SA) :- N/A

Clause 42.2.5

Date on which possession of the site is intended to be given on :-

To be advised.

Clause 42.2.6

Period for the commencement of the works after the contractor takes possession of the site :- 5 Working days.

Completion in Sections are required : NO

Clause 42.2.7

Intended date of practical completion and the penalty per calendar day for the works as a whole :-

To be advised.

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

Penalty amount will be R 2000.00 per Calendar day to a maximum of 10% of Contract Value.

Clause 42.2.8

Intended dates of practical completion and the penalties per calendar day for the works in sections :

N/A

Clause 42.2.9

The law applicable to this agreement shall be that of - Republic of South Africa.

INSURANCES (Clause 42.3)

Clause 42.3.1

Contract works insurance to be effected by Contractor for the sum of: Contract Sum plus 10%

With a deductible of : 5% of insured amount

Clause 42.3.2

Supplementary insurance is required : Yes

SASRIA insurance required to be effected by the Contractor for the amount of: Contract Sum plus 20% (with a deductible to be determined by the Insurance company issuing the policy).

Clause 42.3.3

Public liability insurance to be effected by Contractor

For the amount of: R 5million

With a deductible of: 5% of insured amount

DOCUMENTS (Clause 42.4)

Clause 42.4.1

Waiver of the contractor's lien is required :- YES

Clause 42.4.2

Carried to Collection

Section 1
Bill No. 1
Preliminaries

R

Number of construction document copies to be supplied to the Contractor free of charge :- 1

Clause 42.4.3

Bills of Quantities drawn up in accordance with :-

Standard System of Measuring Building Work - Seventh Edition including all amendments

Clause 42.4.4

Number of days for submission of priced documents : 5 working days from the Letter of Appointment.

Clause 42.4.5

JBCC Engineering General Conditions are to be included in the documents :- No

Clause 42.4.6

The contract value is to be adjusted using CPAP:- NO

SECTION B: PRELIMINARIES

DEFINITIONS AND INTERPRETATION (B1)

Definitions and Interpretation (B1)

41 F: V: T:

Item

DOCUMENTS (B2)

Checking of documents (B2.1)

Notwithstanding the issue of the tender drawings, it will remain the responsibility of the Tenderer to study all available drawings at the offices of the Principal Agent during normal working hours in order to acquaint himself with all the cost implications of the design, programming, phasing, etc.

42 F: V: T:

Item

Provisional Bills of Quantities (B2.2) YES

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, etc., contained herein may be omitted or reduced at the Principal Agent's sole discretion and the Contractor shall not be entitled to claim for any loss by way of reduction or omission of any discount, or percentage relating to Prime Cost Amounts, Budgetary Allowances, Provisional Amounts, Provisional Quantities, etc., or loss of profit related thereto.			
43	F: V: T: Availability of construction documentation (B2.3)	Item		
44	F: V: T: Interests of Agents (B2.4)	Item		
45	F: V: T: Priced documents (B2.5)	Item		
46	F: V: T: Tender submission (B2.6) Notwithstanding anything contained in this clause, Tenders shall be valid for a period of 20 (Twenty) weeks from the closing date of tenders.	Item		
47	F: V: T: <u>THE SITE (B3)</u> Defined works area (B3.1) The area of the works to be occupied by the contractor, any restriction on the area and the limit of access or exit will be pointed out to the contractor by the principal agent on handing over of the site. Workmen employed on the site are to be restricted to the immediate area of the site and access thereto. The Tenderer shall make all necessary provision in all rates to take into account these requirements as no claims for extras arising from these matters will be subsequently entertained or admitted.	Item		
48	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

[illegible]

[illegible]

	Plant and equipment (B6.4)			
69	F: V: T:	Item		
	Main notice board (B6.5) One notice board shall be provided by the Contractor			
70	F: V: T:	Item		
	Subcontractors notice board (B6.6) (N/A)			
71	F: V: T:	Item		
	<u>TEMPORARY SERVICES (B7)</u>			
	Location (B7.1)			
72	F: V: T:	Item		
	Water (B7.2) The contractor shall provide water for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
73	F: V: T:	Item		
	Electricity (B7.3) The contractor shall provide electricity for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
74	F: V: T:	Item		
	Telecommunication equipment (B7.4) The contractor shall provide telephones on site for the works in accordance with: Alternative A (i.e. to be provided for by the Contractor).			
75	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 Preliminaries			

	Ablution facilities (B7.5)			
	The contractor shall provide toilet facilities on site for the works in accordance with:			
	Alternative A (i.e. to be provided for by the Contractor).			
76	F: V: T:	Item		
	<u>PRIME COST AMOUNTS (B8)</u>			
	Responsibility for prime cost amounts (B8.1)			
77	F: V: T:	Item		
	<u>ATTENDANCE ON N/S SUBCONTRACTORS (B9)</u>			
	General Attendance (B9.1)			
78	F: V: T:	Item		
	Special Attendance (B9.2)			
79	F: V: T:	Item		
	Commissioning - fuel, water and power (B9.3)			
80	F: V: T:	Item		
	<u>FINANCIAL ASPECTS (B10)</u>			
	Statutory taxes, duties and levies (B10.1)			
	Provision is made in the Final Summary of these Bills of Quantities for the inclusion of Value Added Tax (VAT).			
81	F: V: T:	Item		
	Payment of Preliminaries (B10.2)			
82	F: V: T:	Item		
	Adjustment of Preliminaries (B10.3)			
83	F: V: T:	Item		
	Payment certificate cash flow (B10.4)			
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	Preliminaries			

84	F: V: T: Contractor information supply (B10.5)	Item		
85	F: V: T: <u>GENERAL (B11)</u> Protection of the Works (B11.1)	Item		
86	F: V: T: Protection/isolation of existing/sectionally occupied works (B11.2)	Item		
87	F: V: T: Site security (B11.3)	Item		
88	F: V: T: Notice before covering work (B11.4)	Item		
89	F: V: T: Disturbance (B11.5)	Item		
90	F: V: T: Works cleaning and clearing (B11.6)	Item		
91	F: V: T: Vermin (B11.7)	Item		
92	F: V: T: Overhand work (B11.8)	Item		
93	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

SECTION C: SPECIFIC PRELIMINARIES

Section C: Specific Preliminaries:

C1. Proprietary branded products

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

94 F: V: T:

Item

C2. Trade Names, etc.

All materials, fittings, finishings, etc., specified hereinafter under a trade name, catalogue number or reference, must be exactly as described. The Architect's approval in writing must be obtained for the use of any alternative to the specification before the submission of tenders otherwise the specified materials, fittings, finishings, etc., will be assumed to have been allowed for in the tender.

The Contractor must take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative.

95 F: V: T:

Item

C3. Contractors responsibility

The Employer, the Principal Agent and the other professional consultants shall not be responsible for any act or omission on the part of the Contractor which may result in any patent or latent defects, in materials or workmanship, breach or neglect of any local regulations. The Contractor shall at all times be responsible for any such neglect, deviation or wrong act, whether the same is discovered before or after the final certificate, or any other Certificate, has been approved.

96 F: V: T:

Item

C4. Overtime

Carried to Collection

R

Section 1
Bill No. 1
Preliminaries

	Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised in writing, prior to the execution thereof, that costs for such overtime are to be borne by the employer.			
97	F: V: T: C5. As built drawings The position of construction breaks and the extent of individual concrete pours are to be recorded by the contractor on the structural engineer's drawings and are to be submitted to the principal agent and the structural engineer for their records. Three full sets of as-built drawings shall be submitted to the Principal Agent no later than fourteen days after practical completion.	Item		
98	F: V: T: C6. Construction Instructions Contract instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the Contractor. The Contractor shall supply and have available at the site of the works at all times, the following site books: a) Construction Instruction Book: Receiving and recording instructions in a suitable A4 size triplicate book kept on site. Instructions issued shall be recorded by the Architect or other Employer's Agents to whom the Architect has delegated authority to in the book. Only instructions issued in such book shall be recognised. b) Daily Record Book:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

	The Contractor shall record in triplicate in a suitable A4 size triplicate book kept at the site, a daily record of work done, all site visits by the Principal Agent and other professional personnel and all events affecting the Works, such as progress, issue of plans, breakdown of machinery, etc. The labour, plant and material on site shall be recorded as well as work performed. Entries must be made by the Contractor and must be signed and forwarded to the Principal Agent for his counter-signature on a daily basis. Copies of these records shall be for the Architect, Quantity Surveyor and Contractor.			
99	F: V: T: C7. Labour record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and description of tradesmen and labourers employed by him and all subcontractors on the works each day.	Item		
100	F: V: T: C8. Plant record At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools, currently used on the works.	Item		
101	F: V: T: C9. Encroachment During the course of the building operations, the Contractor shall be held entirely responsible for any encroachment onto any adjoining properties, buildings, etc., or servitudes and the cost of any remedial measures as required by the Principal Agent shall be borne by the Contractor.	Item		
102	F: V: T: C10. Method Statement	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

	The Tenderer shall produce, when required to do so by the Principal Agent, a Method Statement outlining the methods of construction and labour and plant resources that he proposes to use in the execution of the Works. Any approval given or observation made by the Principal Agent shall not relieve the Contractor of his sole responsibility to adopt the methods of construction and to provide the labour and plant resources necessary for the due and proper timeous execution of the Works.			
103	F: V: T: C11. Unauthorised Persons/Workmen on Premises The Contractor shall at all times strictly exclude all unauthorised persons from the Works and the site and shall set up notice boards to that effect. No workmen or labourers (except security guards) are to be allowed under any circumstances to sleep or deposit any kit on the premises. The Contractor must provide any necessary independent shelter or shed required for any labour or watchmen on site, to the approval of the Employer.	Item		
104	F: V: T: C12. Mode of Procedure Notwithstanding anything to the contrary contained herein the Principal Agent at all times reserves the right to direct the order in which the various parts of the Contract are to be executed. The Contractor shall give priority to any individual section or portion of the Works that, in the opinion of the Principal Agent, requires to be expedited. Should it appear, in the Principal Agent's opinion, that work in any area is not being executed in accordance with the requirements of the Contract Programme, the Contractor shall provide additional manpower and resources and shall work additional overtime and do everything else required to bring the work back to programme to the satisfaction of the Principal Agent and to the Contractor's cost.	Item		
105	F: V: T:	Item		
	Carried to Collection Section 1 Bill No. 1 Preliminaries		R	

	C13. Location of Temporary Buildings and Temporary Services The Contractor shall provide all necessary temporary works, including temporary roads, tracks, crossings, hardstanding and services, hoardings, dust screens, tunnelling, etc., required for his own and sub-contractors use during the construction and maintenance period. There is no guarantee given or implied that Site conditions will be such that the Contractor will be able to erect such temporary works, roads, hardhats, offices, stores and temporary accommodation within the site boundaries and it shall be the Contractor's responsibility to adopt whatever measures he deems necessary in this regard and to obtain all necessary permission and pay all costs in connection therewith.			
106	F: V: T: <u>C14. Office accommodation</u> The contractor shall provide, maintain and remove on practical completion air conditioned office accommodation with suitable tables and chairs for meetings to be held on the site. Such offices shall be kept clean and fit for use at all times [12.2.18]	Item		
107	F: V: T: <u>C15. Storage Facilities</u>	Item		
108	The Contractor shall provide a Container for storage of materials.	Item		
109	F: V: T: C16. Removal and Making Good of Temporary Works, etc, on Completion The Contractor shall remove (except where specifically stated otherwise) all temporary works, roads, services and the like used for this contract and shall make good to the entire satisfaction of the Principal Agent any damage resulting therefrom.	Item		
110	F: V: T:	Item		
Carried to Collection			R	
Section 1 Bill No. 1 Preliminaries				

111	SUB - TOTAL: FIXED ITEMS	Item		
112	SUB - TOTAL: VALUE - RELATED ITEMS	Item		
113	SUB - TOTAL: TIME - RELATED ITEMS	Item		
Carried to Collection			R	
Section 1				
Bill No. 1				
Preliminaries				

Section 1

Bill No. 1

Preliminaries

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

21

Carried Forward

R

Section 1

Bill No. 1

Preliminaries

**ECDOE DISASTER PROGRAMME:
NTABA JUNIOR SECONDARY SCHOOL**

[illegible]

Item No		Quantity	Rate	Amount
	<u>SECTION 2</u>			
	<u>BILL No. 1</u>			
	<u>TEMPORARY WORKS (PROVISIONAL)</u>			
	<u>MODEL PREAMBLES</u>			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	<u>DECANTING SITE</u>			
	<u>TEMPORARY ACCOMODATION</u>			
	<u>Supply and Install Pre-fabricated Classrooms, comprising of:</u>			
	<u>Walls made of 50mm thick polystyrene panels clad with 0.5mm thick pre-painted Aluzinc sheeting on both sides</u> <u>1.1 x 0.9m high (5no. in total) Casement type Anodised aluminium window frames with 4mm clear glass with one top hung opener; Windows are to be secured with aluminium profile burglar proofing</u> <u>0.8 x 2m high (1no. in total) External door manufactured from the same materials as the walls and fitted with 3 lever mortice lock, weather boards, door stoppers and retaining hooks</u> <u>0.8 x 2m high (1no. in total) External galvanized steel gates.</u> <u>Vinyl Tiles on floors</u> <u>The chassis to be manufactured from cold rolled lipped channel welded or bolted together into a rigid ladder frame. Joists are to be manufactured from steel lipped channel. All steel to be hot dip galvanised.</u>			
	Carried to Collection		R	
	Section 2			
	Bill No. 1			
	Temporary Works			

	• <u>Mesh to the sides underneath the floor.</u> • <u>The roof is to be a dual pitched roof constructed from the same insulated panels used for the walls on single wide units and units up to 7m wide (using a king truss system)</u> • <u>Gutters and Downpipes</u> • <u>Exterior Chromadeck Skirting</u> • <u>Interior Chromadeck Skirting</u> • <u>2no. Chalkboards each size 2.4 x 1.2m and 2no. Pinning Board size 1.8 x 1.2m</u> • <u>1no. Double Teacher Cupboard</u> • <u>Steps at Entrances</u> • <u>4.5kg Fire Extinguisher with Signage</u> • <u>Electrical Installation and Connection (Surface mounted DB, Earth Leakage, 4no. SGL LED lights - 1.2m, 2no. SGL Plugs - 16AMP, 1no. Light Switch</u> • <u>All Internal electrical wiring to be designed for a 220 volt supply, in accordance with SABS 0142:1987</u>				
1	Rental of temporary accommodation size (49m2), including standard windows, burglar bars, curtains and tracks, two tier steps for access, light fittings, electrical certificate of compliance, for a period of six (3) calendar months	No	6		
2	Two tier steps for six (3) Calendar months	No	6		
3	Electrical Compliance Certificate	No	1		
4	Transportation and establishment on site and de-establishment on completion temporary accommodation units approximate size 7 x 7m wide	No	2		
Carried to Collection					
Section 2					
Bill No. 1					
Temporary Works					

Section 2

Bill No. 1

Temporary Works

COLLECTION

Total Brought Forward from Page No.

**Page
No**

26

27

Amount

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 1

Temporary Works

Item No	Quantity	Rate	Amount
<u>SECTION 2</u> <u>BILL No. 2</u> <u>ALTERATIONS.</u> <u>Note:</u> For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014). <u>SUPPLEMENTARY PREAMBLES</u> <u>View site</u> Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained <u>Explosives</u> No explosives whatsoever may be used for demolition purposes unless otherwise stated. <u>General</u> Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent. Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.			
Carried to Collection			R
Section 2 Bill No. 2 Alterations			

Removal of asbestos material

All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.

The following shall apply in respect of asbestos removal

The removal of asbestos shall be carried out by a certified entity, registered in accordance with the Occupational Health and Safety Act, 1993 and the Asbestos Regulations 2001

Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose

Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material

Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occurring, the Contractor will be held responsible contractually and may further be prosecuted criminally

The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained

Carried to Collection

Section 2
Bill No. 2
Alterations

R

TEMPORARY BARRIERS, SCREENS, ETC

Temporary barriers, screens, etc including removal

1	SANS approved weld mesh type temporary barrier fencing 1,8m high covered with a net fixed to and including 100mm diameter gum poles set securely min 300mm deep in ground at max 3m spacing including excavation, backfilling, etc	m	192
2	Extra over mesh fence for double leaf gate size 5.5 x 1,8m high.	No	1

REMOVAL OF EXISTING WORK

Taking down and removing roofs, floors, panelling, ceilings, partitions, etc completely

3	Corrugated metal roof sheeting including timber roof trusses, purlins, underlay etc.	m2	52
4	High pressure cleaning Corrugated metal roof sheeting, etc. including tying down, sealing leaks with approved waterproof agent and prepare surfaces to receive paint (new paint elsewhere measured)	m2	820
5	Gypsum plasterboard ceilings including cornices, timber bandering, etc	m2	520
6	Barge boards and fixings	m	93
7	Fascia boards and fixings	m	156
8	Rainwater gutters and fixings	m	156
9	Rainwater downpipes and fixings	m	60

Taking out and removing ironmongery

10	Damaged chalk board.	No	7
----	----------------------	----	---

Hacking up/off and removing granolithic, screeds, plaster, etc. from concrete or brickwork and preparing surfaces for new screeds, plaster, etc

11	Plaster from walls in patches	m2	307
12	Average 30mm Screed from floors.	m2	554

Carried to Collection

Section 2
Bill No. 2
Alterations

R

<u>Take off/remove floor tiles from concrete floors and preparing surfaces for new vinyl floor tiles, etc</u>							
13	Vinyl floor tiles	m2	520				
<u>Timber doors and frames</u>							
14	Take out from one brick wall and cart away steel single size 813mm wide x 1800mm high including preparing reveals to receive new frame (elsewhere).	No	23				
<u>PREPARATORY WORKS, ETC.</u>							
<u>Prepare existing surfaces for new finish</u>							
15	Clean down, etc. existing emulsion painted internal plastered walls, prepare by removing all loose and flaking paint, dirt, grease and grime to receive new enamel paint finish	m2	960				
16	Clean down, etc. existing emulsion painted external plastered walls, prepare by removing all loose and flaking paint, dirt, grease and grime to receive new enamel paint finish	m2	192				
<u>Taking out and removing glass and mirrors, etc</u>							
17	Glass from steel windows including cleaning out rebates and preparing for new glass (new glass elsewhere)	m2	76				
<u>SERVICE</u>							
<u>Steel Windows</u>							
18	Service window by means of changing windows stays, handles etc. including lubricating all ironmongery and leave in good workable condition.	No	63				
<u>STRUCTURAL REPAIRS</u>							
<u>Repairs to structural cracks, etc</u>							
19	Rake out existing minor structural crack in blockwork, remove all debris/loose material including four times shot fixing 32 x 1,6mm thick strap x 500mm long at 500mm centres and plaster over (plaster measured elsewhere).	m	192				
Carried to Collection						R	
Section 2							
Bill No. 2							
Alterations							

20	Rake out existing major structural crack in blockwork, remove all debris/loose material including embedding steel rods, cutting or drilling slots (60mm deep) in brickwork at 250mm centres to embed 8mm mild steel bars fixed between mortar joints with injected epoxy resin	m	60		
Section 2 Bill No. 2 Alterations		Carried to Collection		R	

Section 2

Bill No. 2

Alterations

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

29

30

31

32

33

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 2

Alterations

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 3</u>			
<u>ROOF COVERINGS</u>			
<u>Note:</u> For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Flashings</u>			
Flashings shall be approved by roof sheeting manufacturer and fixed to the sheeting with S10 clips to obviate any direct fixing perforations. Prior to flashings being fixed, all troughs at the apex shall be stop-ended to the full depth of the sheet in order to prevent any penetration of wind driven water. The trough shall be lipped at the eaves end to form a drip. Flashing flanges shall be notched to the sheet profile where necessary. All these operations must be performed with special tools available from the manufacturer. Care shall be taken to ensure that no sheeting or flashing will be cut with abrasive disc on roof surface in order to prevent steel splatter from penetrating colour coated areas. The flashings shall be supplied with a paint finish consisting of a full top coat silicon modified polyester Colour : White to one side			
<u>Quality Assurance</u>			
The manufacturer shall be assessed and certified as complying with ISO 9001: 2008 Quality Management System			
		R	
Section 2 Bill No. 3 Roof Coverings Etc.			
Carried to Collection			

Guarantee

Z200 Galvanized Metal or equal approved sheeting shall be laid in strict accordance with manufacturer's specifications by an approved contractor. The employer shall be provided with a ten year written guarantee on materials by the manufacturer.

Safety

The contractor shall exercise special care when handling long length sheeting, particularly in windy conditions. Should work be interrupted for any reason, all loose sheeting and incomplete sections must be adequately secured against possible movement by wind and gravity

Handling and Storage

The contractor shall ensure that all materials used on site for cladding, etc are transported, handled and stored in accordance with the manufacturer's recommendations. Material damaged shall be rejected and replaced with undamaged material at the contractor's expense. Repair of damaged material will not generally be permitted. Rates are to include for preventing damage and protecting sheets through all stages of construction

Carried to Collection

Section 2
Bill No. 3
Roof Coverings Etc.

R

Inspection Prior to Installation or Erection

Before commencing with installation, the contractor shall verify that the following items have been checked and accepted:

- a. The entire structure or the portion thereof to be sheeted has been correctly aligned, levelled and grouted
- b. Purlins and sheeting rails are at the correct spacing and are within the specified tolerances
- c. The corners of the roof are square and the wall framework is perpendicular or as specified
- d. No protrusions such as bolt heads, splice plates, cleats, etc. appear on the face of the framework
- e. All members to which roofing and cladding are to be fixed in aesthetically sensitive areas are true and square
- f. Paint and any other materials that may be incompatible with the sheeting, have been painted over or so dealt with that direct contact with the sheeting is avoided
- g. The contact faces between the purlins or the girts and the cladding are in the same plane. Should the alignment be inadequate, the contractor shall request instructions from the engineer before proceeding with the fixing of the cladding

Protrusion through Sheeted Surfaces

Protrusions such as pipes, ducts and the like, shall be adequately flashed where they pass through the sheeting surface. Where ribs have to be cut away to permit penetration, additional framing is to be installed as required to support the sheeting. Depending on the position of the penetration through the roof, special attention shall be given to back flashing the sheeting to the ridge or point of water entry. In all cases, all cutting and flashings shall be so arranged that adequate provision is made for the drainage of all troughs and corrugation

Cleaning of Roofs, etc

All debris, etc arising from the fixing of the cladding shall be removed from the sheetin as the fixing progresses. In addition, off-cuts of insulation, surplus fastners and sealants, mandrels from pop rivets, off-cuts of flashings and sheeting, surplus flashing, food packaging, cartons, bottles, cans, etc shall not be left on the roof or in the gutters. Care shall be taken to ensure that no such material enters, blocks or partially impedes the flow of water into the outlets, downpipes, etc

Carried to Collection

Section 2
Bill No. 3
Roof Coverings Etc.

R

ROOF COVERINGS

PROFILED METAL SHEETING AND ACCESSORIES

0,58mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face :

- | | | | |
|---|---|----|----|
| 1 | Roof sheeting laid to pitch not exceeding 25 degrees | m2 | 52 |
| 2 | Ridge capping 550mm girth, screwed through sheet to purlins | m | 10 |
| 3 | Standard narrow and broad flute closers. | m | 20 |

ROOF AND WALL INSULATION

"Sisalation Grade FR430" or equal approved heavy industrial insulation

- | | | | |
|---|--|----|----|
| 4 | Insulation laid taut over roof trusses (at approximately 1 100mm centres) and fixed concurrent with SA Pine purlins at 900mm centres, etc including galvanised steel straining wires | m2 | 52 |
|---|--|----|----|

Carried to Collection

Section 2
Bill No. 3
Roof Coverings Etc.

R

Section 2

Bill No. 3

Roof Coverings Etc.

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

35

36

37

38

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 3

Roof Coverings Etc.

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 4</u>			
<u>CARPENTRY & JOINERY</u>			
<u>Note:</u>			
For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>FIXING</u>			
All nailing of timber roof rafters, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.			
Carried to Collection			R
Section 2			
Bill No. 4			
Carpentry and Joinery			

CARPENTRY

Sawn softwood:

1	Design, supply and install roof truss system complete in accordance with the Standard Building Regulations to suit roof area approximate size 26m ² (measured on flat floor area inclusive of overhangs, etc) - FEMALE ABLUTION BLOCK		Item
2	Design, supply and install roof truss system complete in accordance with the Standard Building Regulations to suit roof area approximate size 26m ² (measured on flat floor area inclusive of overhangs, etc) - MALE ABLUTION BLOCK		Item
3	38 x 114mm Wall plate.	m	25
4	50 x 76mm Purlins.	m	120
5	50 x 76mm Bracing.	m	30

Sundries:

6	TRI FIX or equal approved hurricane clip fixed using 10 x 32mm galvanised clout nails (Provisional).	No	176
7	Prior to the erection of all the roof trusses the consulting engineer shall certify that he has received such working drawings and construction detail designs from the professional engineer employed by the contractor and that he has considered same and given permission to proceed with the fabrication of the trusses (TR1 certificate issued by Contractor's Engineer) and then before the roof covering commences the completed structure shall be inspected and certified as stable by the professional engineer employed by the contractor to ensure that the manufacture of the trusses and erection details have been complied with to his satisfaction (TR2 certificate issued by Contractor's Engineer).		Item

EAVES, VERGES, ETC

"Everite Nutec" or equal approved fibre cement

8	12 x 225mm Fascia board drilled and brass screwed to rafter feet including galvanised steel H-profile jointing strips, etc.	m	156
---	---	---	-----

Carried to Collection

Section 2
Bill No. 4
Carpentry and Joinery

R

[illegible]

Section 2

Bill No. 4

Carpentry and Joinery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

40

41

42

Amount

Carried Forward to Summary of Section No. 2

Section 2

Bill No. 4

Carpentry and Joinery

R

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 5</u>			
<u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u>			
<u>Note:</u> For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.			
<u>Descriptions:</u> Items described as nailed shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete. Items described as plugged shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as bolted the bolts have been given.			
<u>NAILED UP CEILINGS</u>			
<u>4mm Thick fibre-cement boards with and including 6 x 32mm wrought meranti cover strips over joints:</u>			
1	Ceilings including 38 x 38mm sawn softwood brandering at 400mm centres with cross brandering at joints, ends of sheets and at light fittings, etc.	m2	520
Carried to Collection			R
Section 2 Bill No. 5 Ceilings, Partitions and Access Flooring			

2	Extra over 4mm thick fibre cement board ceiling for forming trap door, size 630 x 630mm in clear, formed with 38 x 50mm sawn S.A. pine framing covered with ceiling boarding and set in 38 x 76mm wrought S.A. pine rebated kerb, including all necessary additional supports, trimmers, etc.	No	9		
	<u>Cornice</u>				
3	75mm gypsum coved cornice.	m	288		
	<u>100mm thick non-combustible light weight ceiling insulation 12kg/m³ closely fitted with ends butted firmly between tie beams and laid loose on top of brandering between roof timbers, all in accordance with manufacturer's recommendations.</u>				
	<u>• R-value: 2,50m² K/W</u>				
	<u>• Thermal conductivity: 0,04 W/m²/K</u>				
4	100mm Insulation laid between roof trusses and on top of brandering, etc.	m2	520		
Carried to Collection					R
Section 2					
Bill No. 5					
Ceilings, Partitions and Access Flooring					

Section 2

Bill No. 5

Ceilings, Partitions and Access Flooring

COLLECTION

Total Brought Forward from Page No.

**Page
No**

44

45

Amount

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 5

Ceilings, Partitions and Access Flooring

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 6</u>			
<u>FLOOR COVERINGS, WALL LININGS, ETC</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Proprietary products in descriptions:</u>			
Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.			
<u>Cleaning:</u>			
Rates for floor covering shall include for proper cleaning on completion.			
Carried to Collection			R
Section 2			
Bill No. 6			
Floor Coverings, Wall Linings, Etc.			

VINYL FLOOR COVERINGS

3mm thick x 300mm x 300mm wide Floorflex semi-flexible vinyl floor tiles laid in Marley No.60 Plus acrylic adhesive, or equal approved, spread with trowel having 1.5mm x 1.5mm x 1.5mm triangular notches at 4.00mm centres as per Architectural and Manufacturers specifications:

1	On floors	m2	520
---	-----------	----	-----

POLISH, SEALERS, ETC

Scrub with a diluted neutral detergent complying with SABS 825 and thoroughly rinse, Apply three coats of a water based floor dressing complying to SABS 1042 on:

2	Vinyl tile flooring	m2	520
---	---------------------	----	-----

Carried to Collection

R

Section 2
Bill No. 6
Floor Coverings, Wall Linings, Etc.

Section 2

Bill No. 6

Floor Coverings, Wall Linings, Etc.

COLLECTION

Total Brought Forward from Page No.

**Page
No**

47

48

Amount

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 6

Floor Coverings, Wall Linings, Etc.

Item No		Quantity	Rate	Amount
	<u>SECTION 2</u>			
	<u>BILL No. 7</u>			
	<u>IRONMONGERY</u>			
	<u>Note:</u>			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	<u>SUPPLEMENTARY PREAMBLES</u>			
	<u>Keys/Locks</u>			
	Each lock is to be distinctly numbered with consecutive numbers and each key is to be stamped with the corresponding number to the lock that it controls. All locks are to have two keys			
	<u>Trade Names</u>			
	Where trade names are specified other ironmongery approved by the Principal Agent may be used			
	<u>Fixing</u>			
	Fixing of ironmongery is deemed to be fixed to timber unless otherwise described			
	<u>HINGES:</u>			
1	75 x 100mm Brass Medium duty ball bearing HMP butt hinges.	Pairs	23.0	
	<u>LOCKS</u>			
2	"UNION 2277-78SS" or equal approved three lever sash mortice lockset.	No	23	
	<u>Sundries:</u>			
3	38mm Diameter black rubber door stop plugged and screwed to walls and floors.	No	23	
	Carried to Collection			
	Section 2			
	Bill No. 7			
	Ironmongery			

**PINNING BOARDS, WRITING BOARDS,
PROJECTION SCREENS, ETC**

4	4800 x 1200mm Magnetic white board or equal approved fixed to walls with an approved Aluminium frame, plugged and screwed to walls with counter sunk brass screws and cupped washers.	No	14
5	Pinning board 4800 x 1200mm High overall of 9mm "Van Dyk" or equal approved pinning board glued to 3mm masonite back plugged and screwed to wall and framed with 70 x 22mm rebated wrought Saligna frame with one vertical middle rail.	No	14

Carried to Collection

R

Section 2
Bill No. 7
Ironmongery

Section 2

Bill No. 7

Ironmongery

COLLECTION

Total Brought Forward from Page No.

**Page
No**

50

51

Amount

Carried Forward to Summary of Section No. 2

Section 2

Bill No. 7

Ironmongery

R

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 8</u>			
<u>METALWORK</u>			
<u>Note:</u> For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
The Contractor is to check and verify on site that the item specified in the BoQ matches existing prior to placing orders. Additional costs will not be borne by the client for items that do not match existing and are not approved by the Principal Agent			
<u>ALUMINIUM WINDOWS</u>			
All aluminium windows are to be manufactured by manufacturers who are members of AAAMSA. All aluminium systems to be approved by AAAMSA.			
All aluminium work is to be protected by covering with plastic sheeting fixed with low tack adhesive prior to leaving the factory. Plastic sheeting is to remain in place during construction.			
All glazing shall be in accordance with SABS 0400 - 1990, SABS 1263 - 1. All safety glazing materials (individual panes) shall be permanently marked. Such marking shall be visible after glazing process. If it is not marked, it is not safety glass.			
Carried to Collection			R
Section 2 Bill No. 8 Metalwork			

HOT DIP GALVANIZED STEEL GATES

Note: The contractor is to check on site measurements before placing of order.

Security Gate consisting of 25 x 25 x 2mm galvanised mild steel frame with 12mm galvanised mild steel square bars infill placed at 109mm centres, hung with one pair of galvanised mild steel hinges to 25 x 25 x 2mm mild steel square tube welded to form frame. including locks, handles, ironmongery complete and fixed to brickwork:

[illegible]

Section 2

Bill No. 8

Metalwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

53

54

Amount

Carried Forward to Summary of Section No. 2

Section 2

Bill No. 8

Metalwork

R

[illegible]

[illegible]

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 11</u>			
<u>GLAZING</u>			
<u>Note:</u> For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Proprietary products in descriptions:</u> Proprietary products shall be used as specified. Substitute products of similar quality and specification may only be used with prior approval by the Principal Agent.			
<u>GLAZING TO STEEL WITH PUTTY</u>			
All glazing shall be in accordance with SABS 0400 - 1990, SABS 1263 - 1. All safety flazing materials (individual panes) shall be permanently marked. Such marking shall be visible after glazing process. If it is not marked, it is not safety glass.			
<u>6.38mm clear safety glass secured into galvanized window with a compatible UV resistant sealant</u>			
1	Panes exceeding 0,1m2 and not exceeding 0,5m2	m2	76
2	Issue of Glazing Certificate.	Item	
Carried Forward to Summary of Section No. 2 Section 2 Bill No. 11 Glazing			R

Item No	Quantity	Rate	Amount
<u>SECTION 2</u>			
<u>BILL No. 12</u>			
<u>PAINTWORK</u>			
<u>Note:</u>			
For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
<u>SUPPLEMENTARY PREAMBLES</u>			
<u>Trade Names</u>			
Where trade names are specified it will read "or equal approved"			
Carried to Collection			R
Section 2			
Bill No. 12			
Paintwork			

PAINTWORK TO NEW WORK

ON WOOD

Stop, sand down and prepare wood surfaces and apply one coat wood primer, one undercoat and two coats eggshell enamel paint as per Plascon or equal approved:

1	On doors	m2	76
2	On door frames	m2	26

Two coats superior quality clear gloss varnish on smooth sanded down surfaces:

3	On doors	m2	76
4	On door frames	m2	26

Prepare and apply two coats carbolenium on:

5	On exposed timbers.	m2	84
---	---------------------	----	----

Prepare and brush surface to remove all loose contaminants and apply one coat of sanding sealer rubbed to a smooth finish followed by two coats "Wooddock" clear matt varnish or equal approved

6	Skirtings not exceeding 300mm girth	m	288
---	-------------------------------------	---	-----

ON FIBRE-CEMENT BOARD SURFACES

Apply one coat DULUX Trade alkali resistant plaster prime followed by two coats of DULUX trade 100 low sheen or equal approved coats of finishing paint or equal approved. All joints to be taped, skimmed and rubbed to a smooth finish. Colour to Architects Approval.

7	Ceilings and cornices.	m2	520
8	On fascias and barge boards.	m2	115

Carried to Collection

R

Section 2
Bill No. 12
Paintwork

PAINTWORK TO PREVIOUSLY PAINTED WORK

ON METAL SURFACE

Sand down existing surfaces and apply spot primer defects in pre-primed surfaces with zinc chromate primer UC 53, one universal undercoat and two coats Velvagro or equal and approved enamel paint

9	On metal roof covering	m2	820
10	Steel windows with burglar bars (both sides measured).	m2	76
11	Steel posts.	m2	40

ON FLOATED PLASTER

Apply one coat DULUX Trade alkali resistant plaster prime followed by two coats of DULUX trade 100 low sheen or equal approved. Colour to Architect's Approval.

12	On internal walls	m2	960
13	On external walls	m2	192

Carried to Collection

Section 2
Bill No. 12
Paintwork

R

Section 2

Bill No. 12

Paintwork

COLLECTION

Total Brought Forward from Page No.

**Page
No**

Amount

59

60

61

Carried Forward to Summary of Section No. 2

R

Section 2

Bill No. 12

Paintwork

Section 2

SECTION SUMMARY - BUILDING WORKS

**Bill
No**

**Page
No**

Amount

Temporary Works

28

Alterations

34

Roof Coverings Etc.

39

Carpentry and Joinery

43

Ceilings, Partitions and Access Flooring

46

Floor Coverings, Wall Linings, Etc.

49

Ironmongery

52

Metalwork

55

Plastering

56

Plumbing and Drainage (Provisional)

57

Glazing

58

Paintwork

62

Carried to Final Summary

R

Section 2

Item No	Quantity	Rate	Amount
<u>SECTION No. 3</u>			
<u>BILL No. 1</u>			
<u>EXTERNAL WORKS (PROVISIONAL)</u>			
<u>MODEL PREAMBLES</u>			
The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
<u>THE FOLLOWING IN STORMWATER DRAINAGE, APRONS ETC.</u>			
<u>STORMWATER CHANNELS</u>			
<u>Excavation not exceeding 2m deep</u>			
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	13
<u>Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):</u>			
2	Off site to a dumping site to be found by the Contractor.	m3	13
<u>Filling supplied by the contractor under channels</u>			
3	G7 Base course material compacted to 98% Mod AASHTO density	m3	7
4	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	7
Carried to Collection			R
Section 3			
Bill No. 1			
External Works			

Cast in-situ Ref 395 mesh reinforced concrete (25MPa) open stormwater channels having V-shaped waterway formed in top, finished smooth on all exposed surfaces in 3:1 cement plaster trowelled smooth and with angles rounded, cast in suitable lengths not exceeding 2m, including all formwork, moulds, shallow excavation, filling and ramming, laying to falls, bedding and pointing in 3:1 cement mortar. Concrete apron to be tinted, colour to be specified by the Engineer.

5	700 x 80mm thick V' channel 150mm deep in centre laid in position in ground not exceeding 2000mm sections including all formwork, reinforcement, expansion joints, smooth finishing to top of concrete surface etc.	m	64
6	Extra for 700mm angle	No	4
7	Extra for forming 200mm thick 700mm wide spreader with 200mm high edges fanning out to 1 960mm width at furthest end with hard burnt bricks pitching cast in ass diffusers including working off concrete to a smooth finish and draining onto natural ground with 150 - 200mm diameter loose stones.	No	4

Carried to Collection

R

Section 3
Bill No. 1
External Works

Section 3

Bill No. 1

External Works

COLLECTION

Total Brought Forward from Page No.

**Page
No**

64

65

Amount

Carried to Final Summary

R

Section 3

Bill No. 1

External Works

Item No	Quantity	Rate	Amount
<u>SECTION 4</u>			
<u>BILL No. 1</u>			
<u>PROVISIONAL SUMS</u>			
<u>SUPPLEMENTARY PREAMBLES</u>			
Tenderers are advised that no claim in respect of loss of profit or Preliminary charges based on the omission of these amounts will be considered and the said amounts will be omitted strictly without any financial compensation payable to the Contractor.			
Provisional sums and Budgetary allowances contained herein may be omitted or reduced at the Employer's discretion and the Contractor shall not be entitled to claim for any loss by way of reductions or omission of any discount, or percentage relating to Provisional amounts and Budgetary sums or any loss of profit related thereto.			
<u>SANITARY PLUMBING</u>			
1	Allow the Provisional sum of R 42 000.00 (Forty Two Thousand Rand) nett for sanitary plumbing to existing ablutions etc.	Item	42 000.00
2	Add: Profit on above	%	
3	Add: Attendance on above	%	
<u>REFURBISHMENT TO EXISTING PERIMETER FENCE AND REMOVAL OF TREE, ETC</u>			
4	Allow the Provisional sum of R 61 000.00 (Sixty One Thousand Rand) nett for removal of trees including refurbishment to existing fence etc.	Item	61 000.00
5	Add: Profit on above	%	
6	Add: Attendance on above	%	
Carried to Collection			R
Section 4			
Bill No. 1			
Provisional Sums			

ELECTRICAL INSTALLATION

7 Allow the Provisional sum of R 92 500.00 (Ninety Two Thousand Five Hundred Rand) nett for Electrical Work to be executed by a specialist subcontractor including all wiring, commissioning, COC's etc.

8 Add: Profit on above

9 Add: Attendance on above

COMMUNITY LIAISON OFFICER

10 Allow for the employment of a Community Liaison Officer by the Main Contractor, to be paid an allowance of R6 500.00 per month for duration of 6 Months..

11 Add: Profit on above

12 Add: Attendance on above

Item	92 500.00
------	-----------

%

%

Item	39 000.00
------	-----------

%

%

Carried to Collection

R

Section 4
Bill No. 1
Provisional Sums

Section 4

Bill No. 1

Provisional Sums

COLLECTION

Total Brought Forward from Page No.

**Page
No**

67

68

Amount

Carried to Final Summary

R

Section 4

Bill No. 1

Provisional Sums

Section No	<u>FINAL SUMMARY</u>	Page No	Amount
1	PRELIMINARIES	25	
2	BUILDING WORKS	63	
3	EXTERNAL WORKS (PROVISIONAL)	66	
4	PROVISIONAL SUMS	69	
	SUB-TOTAL		R
	<u>CONTINGENCIES</u>		
	Allow five per cent (5%) of the above sub-total for contingencies to be used as directed and deducted in whole or in part if not required.		R
	SUB-TOTAL		R
	Add Value Added Tax at the rate of 15%		R
	Carried to Form of Offer and Acceptance		R