



CITY OF CAPE TOWN
ISIXEKO SASEKAPA
STAD KAAPSTAD

FINANCE
SUPPLY CHAIN MANAGEMENT

Ncumisa Soboyce
Supply Chain Management

E: SCM.Tenders20@capetown.gov.za

NOTICE TO TENDERERS NO: 5

08 September 2026

TENDER NUMBER: 033Q/2026/27

033Q/2026/27: BUILDING CONSTRUCTION WORK OF PHILIPPI SWITCHING STATION AND BUILDING ALTERATIONS

EXTENDED CLOSING DATE OF TENDER: 15 September 2026

BOX NUMBER: 209

The following Addendum is issued in terms of this Tender. This Notice to Tenderers forms an integral part of the Contract. Tenderers should take note of the following:

1) AMENDMENTS TO THE CONTRACT DOCUMENT – REPLACEMENT PAGES

Your attention is specifically drawn to the amendments which are to be made to the Contract Document for the above in terms of Clause C.3.2 of the Standard Conditions of Tender and you will be deemed to have made any allowances necessary to provide for these amendments in your tender offer.

PAGE 103: C2.2 – BILL OF QUANTITIES

Tenderers to note that page 103-AA of Part C2 Pricing Data, C2.2 – Bills of Quantities, be replaced with the attached pages 103-AAA. (Page numbers updated)

Tenderers are to return a signed copy of this notice/addendum with the submission of their Tender. Failure to return a signed copy of the Addendum may result in the Tender being declared Non-Responsive.

Yours faithfully,

p.p.

Director: Supply Chain Management

Acknowledgement of Receipt of Notice 5 for and on Behalf of the Tenderer

TENDERER:

SIGNED ON BEHALF OF TENDERER:

.....

DATE:.....

ITEM NO	PAY REF	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
		<u>SECTION NO. 2A</u>				
		<u>BILL NO. 4</u>				
	SANS 2001-BE1	<u>EARTHWORKS GENERAL</u>				
		As specified in SANS 2001-BE1 and the project specifications				
		Excavation for general earthworks and for structures:				
	PS-BE1 4.2.2(a)	<u>Cut to Stockpile:</u>				
1		Excavation in all materials to required depths and stockpiling suitable material on site for later reuse.	m³	860		R
	PS-BE1 4.2.2(b)	<u>Cut to spoil off site:</u>				
2		Excavation in all material to required depths and disposal of surplus material to a spoil site supplied by the Contractor	m³	2 000		R
3		Extra over item 2 above for disposing Low (HR4) to Moderate (HR3) hazardous material at a suitable hazardous waste disposal site provided by the contractor. (Please refer to base rates for the disposal of special waste in CCT Annexure 6 tariffs, fees and charges booklet)	m³	1 000		R
	4.2.5	Filling:				
	4.2.5.2	<u>Filling around structures:</u>				
4		Fill around structures with excavated material from stockpile	m³	860		R
	PS-BE1 4.3	Shoring Excavations				
		<u>Shoring of proposed building excavation for depths:</u>				
5		2.5m up to 3.5m	m	130		R
	PS-BE1 4.3	Shoring for pylons for depths:				
6		Up to 1.5m	m	30		R
CARRIED TO SUMMARY						

