

DO NOT SCALE - IF IN DOUBT, ASK

1. GENERAL
- 1.1 ALL DIMENSIONS TO BE VERIFIED ON SITE PRIOR TO THE COMMENCEMENT OF ANY WORKS. ANY DISCREPANCIES TO BE REPORTED TO THE ENGINEER. DRAWINGS NOT TO BE SCALED. FIGURED DIMENSIONS ONLY TO BE ADOPTED.
2. MATERIALS
- 2.1 PRECAST CONCRETE (45MPa):
3. REINFORCEMENT
- 3.1 MILD STEEL BARS (R): 250MPa
- 3.2 HIGH YIELD BARS (Y): 450MPa
4. COVER 60mm MINIMUM CONCRETE COVER TO REINFORCEMENT UNLESS OTHERWISE NOTED
5. ALL SHARP EDGES TO BE CHAMFERED 25mmX25mm UNLESS OTHERWISE NOTED
6. LIFTING
- 6.1 LIFTING OF PRECAST UNITS TO COMMENCE UPON CONCRETE ACHIEVING MIN 25MPa STRENGTH.
- 6.2 LIFTING ARRANGEMENT TO BE APPROVED BY THE ENGINEER BEFORE LIFTING.
7. INFILL PANELS TYPE 4C PARTICULARS AND No's OFF:

TOTAL CONCRETE VOLUME	28.73m ³
TOTAL MASS	68.95t
PHASE NO	No OFF
PHASE 3	1
TOTAL No OFF	1

[illegible]