

## Scope of work-Main Reef Road Fibre Repairs

1. Acquiring of wayleaves and all the necessary permits.
2. Removal of the damaged fibre
3. Installation of 96 Core Aerial cable SM Long Span. Fibre drum to be collected at STP. Cable length to be determined after the site survey.
4. Supply of three dome joints
5. Fibre splicing services of three joints, one joint in a different location of the same route
6. OTDR tests

The fibre is damaged at 28.3 km and 31km from STP towards Nasrec. A site survey will be required to ensure the suppliers understand the full scope of work.

Location: -26.202288; 27.948763

Main Reef Road (R41), above the N1 bridge, before Commando Rd (Next to China Mall West).