

NB: Not to be returned, only for consumption

Item No	Payment Ref	Description	Unit	Quantity	Rate	Amount
		<p><b><u>SECTION 1</u></b></p> <p><b><u>PRELIMINARY AND GENERAL</u></b></p> <p><b><u>BILL NO.1: PRELIMINARIES</u></b></p> <p>PREAMBLES</p> <p>Fixed preliminary items Fixed preliminary items will be valuated and paid on a proven cost basis up to the total value</p> <p>Time related preliminary items Time related preliminary items will be paid on the proportion of: Value of the price of work done to date per the Project Manager's assessment (excluding activities directly related to materials, escalation and compensation events) over the contract value excluding preliminaries costs</p> <p><b><u>FIXED-CHARGE ITEMS</u></b></p>				
1.1		Contractual requirements	Sum	1		
1.2		Permits and Site Access	Sum	1		
1.3		Compilation and provision to the Employer of all as-built documentation and any other associated contract documentation, including but not limited to hard copy as built drawings, operations, and maintenance where applicable	Sum	1		
1.4		Tools, equipment and plant	Sum	1		
1.5		Cost compliance to Health & safety and Quality regulation.	Sum	1		
1.6		Mobilisation of all compatible equipment to site for offloading of new fenders and attachments/accessories, including and not limited to 60-to-90-	Sum	1		

Item No	Payment Ref	Description	Unit	Quantity	Rate	Amount
1.7		<p>ton mobile crane. Slings and shackles, chain sling and compressor.</p> <p>Shipping / Duties / Clearing &amp; Forwarding – DDP Incoterms</p> <p>Total Carried Forward to Section 1 Summary</p>	No.	70		R
<p><b><u>SECTION 2: SUPPLY AND DELIVERY OF CYLINDRICAL AND SUPERCONE FENDERS</u></b></p> <p><b><u>BILL 1: FENDERS</u></b></p> <p>PREAMBLES</p> <p>For preambles refer to "Model Preambles for Trades"</p> <p>SUPPLEMENTARY PREAMBLES</p> <p>Demolitions and Works on Site The Contractor will be held solely responsible for any damage to persons and property and for the safety of the structures.</p> <p>Old materials from alterations except were described to be re-used or handed over, become the property of the contractor</p> <p>Old materials to be carted away</p> <p>Old materials from alterations except were described as re-used or handed over, as well as all rubbish, etc. must be regularly carted from the site and not be allowed to accumulate on or around the site.</p> <p>Old materials to be re-used</p> <p>None of the old materials are to be used for new work except where specifically described as being set aside for re-use.</p> <p>General</p>						

Item No	Payment Ref	Description	Unit	Quantity	Rate	Amount
		<p>The contractor shall carry out the whole works with as little mess and noise as possible and with a minimum of disturbance to the occupants of the building. The contractor shall provide proper protection and provide, erect and remove when directed, any temporary tarpaulins that may be necessary during the progress of the works, all to the satisfaction of the Client's Project Manager.</p> <p><b><u>Fenders</u></b></p> <p><b><u>Cylindrical Fenders</u></b></p>				
2.1		Supply and deliver cylindrical fender unit: 1600mm OD x 800mm ID x 2000mm L with necessary equipment and cylindrical steel suspension bar with cleats: 120mm OD x 2700mm L	No.	20		
2.2		Supply and deliver cylindrical steel suspension bar with cleats: 120mm OD x 2700mm L	No.	20		
		<p><b><u>Super Cone Fenders</u></b></p>				
2.3		Supply and deliver Supercone fender unit: SCN 1300 (E2.4)	No.	50		
2.4		Supply and deliver steel fender panel: 3610x2800x300mm	No.	3		
		<p><b><u>Testing</u></b></p>				
3.1		3rd Party Inspection fee and certification	No.	70		
3.2		Factory acceptance tests	Sum	1		
		<p><b><u>Maintenance Manuals and Schedules</u></b></p>				

Item No	Payment Ref	Description	Unit	Quantity	Rate	Amount
4.1		Maintenance manuals and schedules for each component type	Sum	1		
Total Carried Forward to Section 2 Summary						R