



NO.	SPECIAL NOTES:
1.	150mm Reinforced Concrete floor: 25Mpa with a steel float finish
2.	250 Micron DPC under reinforced floor.
3.	150mm Ramps on 4m entries.
4.	100mm Ramps at 1.5m entries.
5.	1000x100mm Apron around the structure

S KONDLO  
(CHIEF ENGINEER)

OCTOBER 2024  
(DATE APPROVED)

**DEPARTMENT OF AGRICULTURE  
PROVINCE OF THE EASTERN CAPE**

ENGINEERING SERVICES  
PRIVATE BAG X015  
DOHNE ADI  
STUTTERHEIM  
4930

**MPAYIPHELI 1000 BROILER HOUSE**

**FLOOR LAY-OUT PLAN**

SCALE  
NTS

INDEX NO.  
SCMM-03/33/02

PLAN NO.  
SHEET 2 OF 8