

SCHEDULE 8 : RESERVOIR STEEL WORK ITEMS						
ITEM NO.	REF	DESCRIPTION	UNIT	QUANT	RATE	AMOUNT
8	SABS 1200HA	<u>STRUCTURAL STEELWORK (Sundry Items)</u>				
	PSHA 4.1	<u>Handrailing</u>				
8.1		a) Top mounted handrailing (galvanised) i) Reservoir	m	8		
	PSHA 4.2	<u>Cat ladders</u>				
		<u>Reservoir:</u>				
8.2		Stainless steel cat ladder Type RL1 (inside)	no	1		
8.3		Galvanised cat ladder Type RL2 (outside)	no	1		
	PSHA 4.9	<u>Open grid / chequer plate flooring</u>				
8.4		Supply and install cast-in galvanised 45 x 45 x 5 mm SS angle support complete with fishtail lugs	m²	2		
	PSHA 4.10	<u>Pipe supports</u>				
		Supply and install as per drawing (DWG N3110/W/7/102RB)				
8.5		Type A (GMS)	no	2		
8.6		Type A (SS)	no	2		
8.7		Type C (SS)	no	2		
		<u>Reservoir access manholes</u>				
	PSHA 4.5	Access manhole:				
8.8		Supply and install complete 1000x1000mm access manhole cover and frame as detailed (DWG N3110/W/8/097RA)	no	2		
	PSHA 4.6	<u>Vent pipe</u>				
8.9		Supply and install complete ventilation pipe as detailed (DWG N3110/W/7/100RA)	no	8		
	PSHA 4.7	<u>Level indicator</u>				
8.10		Supply and install complete level indicator	no	1		
TOTAL SCHEDULE 8 CARRIED FORWARD TO SUMMARY						