

Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO. 1</u></b></p> <p><b><u>PRELIMINARIES</u></b></p> <p><b><u>BUILDING AGREEMENT AND PRELIMINARIES</u></b></p> <p>The JBCC Series 2000 Principal Building Agreement (July 2007 edition 5.0 - reprint 1) prepared by the Joint Building Contract Committee shall be the applicable building agreement, amended as hereinafter described</p> <p>The JBCC Principal Building Agreement Contract Data EC and the JBCC Principal Building Agreement Contract Data CE form an integral part of this agreement</p> <p>The ASAQS Preliminaries (November 2007 edition) published by the Association of South African Quantity Surveyors for use with the said JBCC Principal Building Agreement shall be deemed to be incorporated in these bills of quantities</p> <p>Contractors are referred to the abovementioned documents for the intent and meaning of each clause thereof</p> <p>These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the abovementioned documents</p> <p>Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"</p>			
	<b>Carried to Collection</b>		R	
	<p>Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b></p>			

**PREAMBLES FOR TRADES**

The Model Preambles for Trades (2008 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claims arising from brevity of description of items fully described in the said Model Preambles will be entertained

Supplementary preambles are incorporated in these bills of quantities to satisfy the requirements of this project. Such supplementary preambles shall take precedence over the provisions of the said Model Preambles

The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the said Model Preambles and in any supplementary preambles

**PRICING OF PRELIMINARIES**

Should the contractor select Option A in terms of subclause 3.2.1 in the Contract Data - Contractor to Employer (CE) for the purpose of adjustment of these preliminaries, the amount entered into the amount column in these preliminaries is to be divided into one or more of the three categories provided namely Fixed (F), Value Related (V) and Time Related (T)

**SECTION A - PRINCIPAL BUILDING AGREEMENT**

**Definitions (A1)**

1 Clause 1.0 - Definitions and interpretation

The measuring system used for the preparation of the bills of quantities is the Standard System of Measuring Building Work (sixth edition, revised 1999) Published by the Association of South Africa Quantity Surveyors [1.1]

F:..... V:..... T:.....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

**Objective and preparations (A2 - A14)**

2 Clause 2.0 - Offer acceptance and performance obligations

F:..... V:..... T:.....

Item

3 Clause 3.0 - Documents

Refer to Annexure A for a list of the contract drawings

Provision is made in the summary page of these bills of quantities for the inclusion of Value Added Tax (VAT) [3.5]

The principal agent shall decide which portion of the priced document may be used as a specification of materials and goods or methods, if any [3.9]

F:..... V:..... T:.....

Item

4 Clause 4.0 - Design responsibility

F:..... V:..... T:.....

Item

5 Clause 5.0 - Employer's agents

F:..... V:..... T:.....

Item

6 Clause 6.0 - Contractor's site representative

F:..... V:..... T:.....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

7	<p>Clause 7.0 - Compliance with laws and regulations</p> <p>Without limiting the generally of the provisions of clause 7.0, the contractor's attention is drawn to the provisions of the Construction Regulations, 2003 issued in terms of the Occupational Health and Safety Act,1993. It is specifically stated that the employer shall prepare a document health and safety specification for the works and that the employer shall ensure that the contract has made provision for the cost health and safety measures during the execution of the works. The contractor shall price opposite this item for compliance with the act and the regulations and the reasonable provisions of the aforementioned health and safety specification [7.1]</p> <p>F:..... V:..... T:.....</p>	Item	
8	<p>Clause 8.0 - Works risk</p> <p>F:..... V:..... T:.....</p>	Item	
9	<p>Clause 9.0 - Indemnities</p> <p>F:..... V:..... T:.....</p>	Item	
10	<p>Clause 10.0 - General insurances</p> <p>F:..... V:..... T:.....</p>	Item	
11	<p>Clause 11.0 - Special insurances</p> <p>F:..... V:..... T:.....</p>	Item	
12	<p>Clause 12.0 - Effecting insurances</p> <p>F:..... V:..... T:.....</p>	Item	
13	<p>Clause 13.0 - Assignment F:..... V:..... T:.....</p>	Item	
14	<p>Clause 14.0 - Security</p> <p>F:..... V:..... T:.....</p>	Item	

**Carried to Collection**

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

R

**Execution (A15 - A23)**

15 Clause 15.0 - Preparation for and execution of the works  
F:..... V:.....  
T:.....

Item

16 Clause 16.0 - Site and access  
  
Certain 16.0 areas will be occupied during the construction period and the contractor must execute the works with as little noise and disturbance as possible to the occupants. [16.6]  
  
F:..... V:.....  
T:.....

Item

17 Clause 17.0 - Contract instructions F:.....  
V:..... T:.....

Item

18 Clause 18.0 - Setting out of the works  
  
The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc. exist in order that the necessary arrangements may be made for the rectification of any such encroachments.F:  
..... V:.....T:.....

Item

19 Clause 19.0 - Temporary works and plant  
  
Subclause 19.1.1 - Enclosure of the works  
  
Subclause 19.1.2 - Office accommodation  
  
F:..... V:.....  
T:.....

Item

20 Clause 19.1.2 - Office accommodation - provide suitable office accommodation for site meetings with tables and chairs for people  
  
F:..... V:.....  
T:.....

Item

21 Clause 20.0 - Nominated subcontractors  
F:..... V:.....  
T:.....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

22	<p>Clause 21.0 - Selected subcontractors</p> <p>General attendance of n/s subcontractors for pricing by the contractor shall be in accordance with the n/s agreement. notwithstanding this provision, general attendance shall be deemed to include for the contractor to provide free of charge to any n/s subcontractor such scaffolding as many reasonably be required by such n/s subcontractor for the execution of the relevant subcontract work</p> <p>F:..... V:..... T:.....</p>	Item	
23	<p>Clause 22.0 - Employer's direct contractors</p> <p>F:..... V:..... T:.....</p>	Item	
24	<p>Clause 23.0 - Contractor's domestic subcontractors</p> <p>F:..... V:..... T:.....</p>	Item	
<b><u>Completion (A24 - A30)</u></b>			
25	<p>Clause 24.0 - Practical completion</p> <p>F:..... V:..... T:.....</p>	Item	
26	<p>Clause 25.0 - Works completion F:..... V:..... T:.....</p>	Item	
27	<p>Clause 26.0 - Final completion F:..... V:..... T:.....</p>	Item	
28	<p>Clause 27.0 - Latent defects liability period</p> <p>F:..... V:..... T:.....</p>	Item	
29	<p>Clause 28.0 - Sectional completion F:..... V:..... T:.....</p>	Item	

**Carried to Collection**

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

R

30 Clause 29.0 - Revision of date for practical completion  
The removal and replacement of materials and/or workmanship which do not conform to specification or drawing shall not constitute grounds for the extension of the construction period nor for the adjustment of the contract value (Clause 29.3)F:.....  
V:..... T:.....

Item

31 Clause 30.0 - Penalty for late or non-completion: 0.04% of the Contract Amount inclusive of Value Added Tax per Calendar day  
F:..... V:.....  
T:.....

Item

**Payment (A31 - A35)**

32 Clause 31.0 - Interim payment  
  
Materials and goods stored off site shall not be included in the amount authorised for payment [31.6.5]  
  
F:..... V:.....  
T:.....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

33 Clause 32.0 - Adjustment to the contract value- Subject to CPAP

All fluctuations in costs, with the exception of fluctuations in the rate of Value Added Tax, shall be for the account of the contractor.

Where prices are submitted by the contractor or n/s subcontractor during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final payment certificate, it shall be in writing

The contractor shall not receive any mark-up for overheads and profit on any omission of tenant installation work or tenant installation work by others. Claims for loss of profit shall not be entertained [32.2]

F:..... V:.....  
T:.....

Item

34 Clause 33.0 - Recovery of expense and loss  
F:..... V:.....  
T:.....

Item

35 Clause 34.0 - Final account and final payment  
F:..... V:.....  
T:.....

Item

36 Clause 35.0 - Payment to other parties  
F:..... V:.....  
T:.....

Item

**Termination (A36 - A39)**

37 Clause 36.0 - Termination by employer - contractor's default  
F:..... V:.....  
T:.....

Item

38 Clause 37.0 - Termination by employer - loss and damage  
F:..... V:.....  
T:.....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**



39	Clause 38.0 - Termination by contractor - employer's default F:..... V:..... T:.....	Item	
40	Clause 39.0 - Termination - cessation of the works F:..... V:..... T:.....	Item	
<b><u>Dispute (A40)</u></b>			
41	Clause 40.0 - Settlement of disputes F:..... V:..... T:.....	Item	
<b><u>Contract variables (A41 - A42)</u></b>			
42	Clause 41.0 - Post tender provisions  The contractor is to complete and submit with his tender the JBCC Principal Building Agreement Contract Data CE F:..... V:..... T:.....	Item	
43	Clause 42.0 - Contractual agreement  The required information of the parties and the amount of the contract sum shall be inserted in the agreement for signature of the agreement by the parties F:..... V:..... T:.....	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>			

**SECTION B - PRELIMINARIES**

**Definitions and interpretation (B1)**

44 Clause 1.0 - Definitions and interpretation  
 F:..... V:.....  
 T:.....

Item

**Documents (B2)**

45 Clause 2.1 - Checking of documents  
 F:..... V:.....  
 T:.....

Item

46 Clause 2.2 - Provisional bills of quantities  
 F:..... V:.....  
 T:.....

Item

47 Clause 2.3 - Availability of construction documentation  
 The budgetary allowances and selected (nominated) subcontract amounts allocated for subsequent trades included in this document will be separately procured, based on multiple procurement of selected (nominated) subcontractors during the construction period  
 F:..... V:.....  
 T:.....

Item

**Previous work and adjoining properties (B3)**

48 Clause 3.1 - Previous work - dimensional accuracy  
 F:..... V:.....  
 T:.....

Item

49 Clause 3.2 - Previous work - defects  
 F:..... V:.....  
 T:.....

Item

50 Clause 3.3 - Inspection of adjoining properties  
 F:..... V:.....  
 T:.....

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 Preliminaries  
**Refurbishment to Sele Primary school**

**Samples, shop drawings and manufacturer's instructions (B4)**

51	Clause 4.1 - Samples of materials F:..... V:..... T:.....	Item	
52	Clause 4.2 - Workmanship samples F:..... V:..... T:.....	Item	
53	Clause 4.3 - Shop drawings F:..... V:..... T:.....	Item	
54	Clause 4.4 - Compliance with manufacturer's instructions F:..... V:..... T:.....	Item	

**Deposits and fees (B5)**

55	Clause 5.1 - Deposits and fees F:..... V:..... T:.....	Item	
----	---	------	--

**Temporary services (B6)**

56	Clause 6.1 - Water F:..... V:..... T:.....	Item	
57	Clause 6.2 - Electricity F:..... V:..... T:.....	Item	
58	Clause 6.3 - Telecommunication facilities F:..... V:..... T:.....	Item	
59	Clause 6.4 - Ablution facilities F:..... V:..... T:.....	Item	

**Prime cost amounts (B7)**

60	Clause 7.1 - Responsibility for prime cost amounts F:..... V:..... T:.....	Item	
----	--	------	--

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

**Special attendance on n/s subcontractors (B8)**

61 Clause 8.1 - Special attendance

User note

*General attendance is defined in the n/s subcontract agreement*

Insert details against this clause or where provisional sums are stated for any special attendance where specifically required for each n/s subcontractor separately

F:..... V:.....  
T:.....

Item

**General (B9)**

62 Clause 9.1 - Protection of the works F:.....  
V:..... T:.....

Item

63 Clause 9.2 - Protection/isolation of existing/sectionally occupied works

Certain areas of the site will be occupied during the construction period (see item 4 page 14)

F:..... V:.....  
T:.....

Item

64 Clause 9.3 - Security of the works F:.....  
V:..... T:.....

Item

65 Clause 9.4 - Notice before covering work  
F:..... V:.....  
T:.....

Item

66 Clause 9.5 - Disturbance F:.....  
V:..... T:.....

Item

67 Clause 9.6 - Environmental disturbance .The employer has prepared an environmental management plan (refer to Annexure for a copy of the relevant plan). The contractor shall price opposite this item for compliance with all the requirements of such environmental management plan F:.....  
V:..... T: .....

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

68	Clause 9.7 - Works cleaning and clearing F:..... V:..... T:.....	Item	
69	Clause 9.8 - Vermin F:..... V:..... T:.....	Item	
70	Clause 9.9 - Overhand work F:..... V:..... T:.....	Item	

**Schedule of variables (B10)**

Information necessary for elections and completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder. Where no information is given it shall mean that no specific requirements are expected or that the clause is not relevant to this specific contract

- 10.1 - Provisional bills of quantities [clause 2.2]  
The quantities are provisional                      Yes
  
- 10.2 - Availability of construction documentation [clause 2.3]  
Construction documentation is complete    Yes
  
- 10.3 - Previous work - dimensional accuracy [clause 3.1]
  
- 10.4 - Previous work - defects [clause 3.2]
  
- 10.5 - Inspection of adjoining properties [clause 3.3]
  
- 10.6 - Water [clause 7.2]  
Option A (by contractor)    yes  
Option B (by employer - free of charge)    no  
Option C (by employer - metered)    no
  
- 10.7 - Electricity [clause 7.3]  
Option A (by contractor)    yes  
Option B (by employer - free of charge)    no  
Option C (by employer - metered)    no

**Carried to Collection**

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

R

<p>10.8 - Telecommunications [clause 7.4]</p> <p style="margin-left: 40px;">Telephone                    <i>yes</i></p> <p style="margin-left: 40px;">Facsimile                    <i>yes</i></p> <p style="margin-left: 40px;">E-mail                         <i>yes</i></p> <p>10.9 - Ablution facilities [clause 7.5]</p> <p style="margin-left: 40px;">Option A (by contractor) <i>yes</i></p> <p style="margin-left: 40px;">Option B (by employer) <i>no</i></p> <p>10.10 - Protection of the works [clause 9.1]</p> <p>10.11 - Protection/isolation of existing/sectionally occupied works [clause 9.2] Protection/isolation is required                    <i>No</i></p> <p>10.12 - Disturbance [clause 9.5]</p> <p>10.13 - Environmental disturbance [clause 9.6]</p>				
<p><b>Carried to Collection</b></p>				<p>R</p>
<p>Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b></p>				

**SECTION C - SPECIFIC PRELIMINARIES**

Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included

71 Black economic empowerment and training

F:..... V:.....  
T:.....

Item

72 Propriety branded products

F:..... V:..... T:.....

The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturer's instructions after consultation with the manufacturer's authorised representative

Item

73 Contract Instructions

F:..... V:..... T:.....

Contract instructions issued on site are to be recorded in triplicate in a contract instruction book which is to be supplied and maintained on site by the contractor

Item

74 Labour records

F:..... V:..... T:.....

At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number and descriptions of tradesman and labourers employed by him and all subcontractors in the works each day of that week

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

75 Plant record  
 F:..... V:..... T:.....  
 At the end of each week the contractor shall provide the principal agent with a written record, in schedule form, reflecting the number, type and capacity of all plant, excluding hand tools used on the works each day of that week

Item

76 Guarantees  
 F:..... V:..... T:.....  
 Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specific period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement.

Item

77 Overtime  
 F:..... V:..... T:.....  
 Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 Preliminaries  
**Refurbishment to Sele Primary school**



78 Co-operation of contractor for cost management  
 F:..... V:..... T:.....

It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 Preliminaries  
**Refurbishment to Sele Primary school**

79 Occupational Health and Safety Specification  
 F:..... V:..... T:.....

The contractor shall comply with all the requirements set out in the Construction Regulations 2003 issued under the Occupational Health and Safety Act. 1993 (Act No 85 of 1993)

It is required of the contractor to thoroughly study the Health and Safety Specification that must be read together with and is deemed to be incorporated under this Section of the bills if quantities/ lump sum document.

The contractor must take note that compliance with the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is compulsory. In the event of partial or total non-compliance, the principal agent, notwithstanding the provisions of clause A31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including extension of time or interest, due to such delay of payment.

Provisions for pricing of the Occupational Health and Safety Act, Construction Regulations and Health and Safety Specification is made under this clause and it is explicitly pointed out that all requirements of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained.

Item

80 Allow for the compulsory equipment and clothing, ie hats, safety shoes, safety clothing, safety glasses, safety masks, harnesses, etc  
 F:..... V:..... T:.....

Item

81 Allow for all compulsory health and safety posters, boards, etc  
 F:..... V:..... T:.....

Item

**Carried to Collection**

R

Section No. 1  
 Bill No. 1  
 Preliminaries  
**Refurbishment to Sele Primary school**

82	Allow for all compulsory health and safety workshops, meetings, lecturers, demonstrations, etc  F:..... V:..... T:.....	Item	
83	Allow for all compulsory health and safety pamphlets, cards, paperwork, etc to each worker, consultant, public individual, etc coming onto the site  F:..... V:..... T:.....	Item	
84	<b>Testing of windows for watertightness</b>  Each window shall be tested for watertightness with water sprayed on using adequate pressure. If in the opinion of the principal agent, the pressure proves to be inadequate, then the pressure shall be boosted by means of compressed air or other approved means  F:..... V:..... T:.....	Item	
85	Allow for all compulsory health and safety files that must be completed daily and must be handed to the employer on completion of the contract  F:..... V:..... T:.....	Item	
86	Scope of Application as per Act No 85 of 1993  F:..... V:..... T:.....	Item	
87	Notification of Construction Work as per Act No 85 of 1993  F:..... V:..... T:.....	Item	
88	Employer's responsibilities as per Act No 85 of 1993  F:..... V:..... T:.....	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>			

89	Principal Contractor's responsibility as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
90	Supervision of construction work as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
91	Risk assessment per Act No 85 of 1993 F:..... V:..... T:.....	Item	
92	Fall protection as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
93	Structural Formwork and Support as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
94	Excavation as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
95	Demolition work as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
96	Tunnelling as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
97	Scaffolding as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
<b>Carried to Collection</b>			
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>			R

- 98 Suspended platforms as per Act No 85 of 1993  
F:..... V:..... T:.....
- 99 Botswains chairs as per Act No 85 of 1993  
F:..... V:..... T:.....
- 100 Materials hoists as per Act No 85 of 1993  
F:..... V:..... T:.....
- 101 Batch plant as per Act No 85 of 1993  
F:..... V:..... T:.....
- 102 Explosive powered tools as per Act No 85 of 1993  
F:..... V:..... T:.....
- 103 Cranes as per Act No 85 of 1993  
F:..... V:..... T:.....
- 104 Construction vehicles and mobile plant as per Act No 85 of 1993  
F:..... V:..... T:.....
- 105 Electrical installations and machinery on construction sites as per Act No 85 of 1993  
F:..... V:..... T:.....
- 106 Use and temporary storage of flammable liquids on construction sites as per Act No 85 of 1993  
F:..... V:..... T:.....

Item  
Item  
Item  
Item  
Item  
Item  
Item  
Item  
Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

107	Water environments as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
108	Housekeeping on construction sites as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
109	<b>Testing of flat roof waterproofing for watertightness</b>  Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing  F:..... V:..... T:.....	Item	
110	Stacking and storage on construction sites as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
111	Fire precautions as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
112	Construction welfare as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
113	Approved inspection Authorities as per Act No 85 of 1993 F:..... V:..... T:.....	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>			

114 Offences and penalties as per Act No 85 of 1993  
F:..... V:..... T:.....

Item

115 Repeal of regulations as per Act No 85 of 1993  
F:..... V:..... T:.....

Item

116 Short title as per Act No 85 of 1993  
F:..... V:..... T:.....

Item

117 Obligatory Sub-contracting and training  
F:..... V:..... T:.....

The contractor shall sub-contract 40% of the work to Domestic Sub-contractors as listed in the Schedule of Sub-contractors in the Returnable Schedules

The principal Agent and the Contractor shall at all times make sure that the work complies with the relevant specifications, standards and norms as contained in this tender.

The Principal Agent and the Contractor shall provide shall for the necessary skills transfer and assistance to complete the sub-contracted section of the works.

The Principal Agent and the Contractor shall provide the necessary documentation to the Domestic Sub-Contracyor for upgrading of the rating by CIDB.

BEE Sub-Contractors must be 100% black owned and have offices in Mpumalanga Province

Item

**Carried to Collection**

R

Section No. 1  
Bill No. 1  
Preliminaries  
**Refurbishment to Sele Primary school**

118	<p>Expanded Public Works Programme</p> <p>F:..... V:..... T:.....</p> <p>The Contractor shall study the guidelines for the implementation of labour-intensive infrastructure projects under the Expanded Public Works Programme (EPWP) attached to this document. The contractor shall take note of the requirements and inform all selected and other sub-contractors, as no claim afterwards will be entertained</p>	Item		
119	<p>Local and targeted labour</p> <p>F:..... V:..... T:.....</p>	Item		
120	<p>Allow for regular submission of proof of employment of local skilled and unskilled labour to Employer's representative</p> <p>F:..... V:..... T:.....</p>	Item		
121	<p>Training allowance paid to targeted labour in respect of formal training</p> <p>F:..... V:..... T:.....</p>	Item		
122	<p>Extra over for the submission of payment of training allowances to targeted labour</p> <p>F:..... V:..... T:.....</p>	Item		
123	<p>Transport and accommodation of workers for training where it is not possible to undertake the training in close proximity to the site</p> <p>F:..... V:..... T:.....</p>	Item		
124	<p>Contract Drawings</p> <p>F:..... V:..... T:.....</p>	Item		
<b>Carried to Collection</b>			R	
<p>Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b></p>				



125	<p>The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed</p> <p>Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent</p> <p>F:..... V:..... T:.....</p>			
			Item	
126	<p>C13: General Preambles</p> <p>F:..... V:..... T:.....</p>			
			Item	
127	<p>C14: Trade names</p> <p>F:..... V:..... T:.....</p> <p>Wherever a trade name form any product has been described in the bills of quantities/ lump sum document, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the principal agent being obtained prior to the closing date for submission of tenders</p> <p>If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for</p>			
			Item	
128	<p>C15: Community Liaison Officer</p> <p>F:..... V:..... T:.....</p>			
			Item	
129	<p>Allow for a Community Liaison Officer (CLO) to be appointed</p> <p>F:..... V:..... T:.....</p>			
			Item	
	<b>Carried to Collection</b>			R
	<p>Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b></p>			

130	Allow for net extra cost involved in the employment of a Community Liaison Officer (CLO) in respect of the site office  F:..... V:..... T:.....	Item	
131	Allow for net extra cost involved in the employment of a Community Liaison Officer (CLO) in respect of the toilets  F:..... V:..... T:.....	Item	
132	Allow for net extra cost involved in the employment of a Community Liaison Officer (CLO) in respect of the sheds  F:..... V:..... T:.....	Item	
133	C16: SANS 1921-6: HIV/AIDS Awareness read in conjunction with the Associated Specification Data  F:..... V:..... T:.....	Item	
134	General requirements ( Clause 4.1)  F:..... V:..... T:.....	Item	
135	HIV/AIDS awareness programme (Clause 4.2)  F:..... V:..... T:.....	Item	
136	Reporting (Clause 4.3)  F:..... V:..... T:.....	Item	
<b>Carried to Collection</b>			R
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>			

**SUMMARY OF CATEGORIES**

Category : Fixed R.....  
 Category : Value R.....  
 Category : Time R.....

**Carried to Collection**

Section No. 1  
 Bill No. 1  
 Preliminaries  
**Refurbishment to Sele Primary school**

R

Section No. 1

Bill No. 1

Preliminaries

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

1

2

3

4

5

6

7

8

9

10

11

12

13

14

15

16

17

18

19

20

**Carried Forward**

R

Section No. 1

Bill No. 1

Preliminaries

**Refurbishment to Sele Primary school**

Section No. 1  
Bill No. 1  
Preliminaries  
**COLLECTION**

	<b>Page No</b>	<b>Amount</b>
<b>Brought Forward</b>		R
Total Brought Forward from Page No.	21	
	22	
	23	
	24	
	25	
	26	
	27	
<b>Carried to Final Summary</b>		R
Section No. 1 Bill No. 1 Preliminaries <b>Refurbishment to Sele Primary school</b>		

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 1</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>Taking down and removing existing gypsum ceilings including brandering etctc</u></b>			
	<b><u>BILL NO 1</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>Taking down and removing roof sheets and purlins, floors, panelling, ceilings, partitions, etc</u></b>			
1	Removal of existing gutters and down pipes	m	68	
2	Take down existing roof sheeting ect	m2	519	
	<b><u>Take down and remove existing ceilings including brandering etc</u></b>			
3	Gypsum plasterboard ceilings including cornices, timber brandering, etc	m2	399	
	<b><u>Hacking up/off and removing ceramic tile floor and wall finishes including removing mortar bed or backing and preparing concrete or brick surfaces for new screed, plaster or tile finishes</u></b>			
4	250 x 250mm Tiles to floors	m2	399	
	<b><u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, etc</u></b>			
5	Screed from floors	m2	400	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 1			
	Alterations			
	<b>Refurbishment to Sele Primary school</b>			

<b><u>Taking out and removing glass and mirrors</u></b>				
6	Glass from steel windows including cleaning out rebates and preparing for new glass	m2	19	
<b><u>Take out and remove reinforced concrete apron</u></b>				
7	Break up and remove existing concrete apron	m3	24	
<b>Carried to Collection</b>				R

Section No. 2  
 Bill No. 1  
 Alterations  
**Refurbishment to Sele Primary school**

Section No. 2

Bill No. 1

Alterations

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

30

31

**Amount**

**Carried Forward to Summary of Section No. 2**

Section No. 2  
Bill No. 1  
Alterations

**Refurbishment to Sele Primary school**

R



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 2</u></b>			
	<b><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Cost of tests</u></b>			
	The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the architect. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the architect. (Test cubes are measured separately)			
	<b><u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></b>			
	<b><u>APRONS</u></b>			
	<b><u>15MPa/19mm concrete</u></b>			
1	Surface beds cast in panels on waterproofing	m3	24	
	<b><u>TEST BLOCKS</u></b>			
2	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No		
	<b><u>Finishing top surfaces of concrete smooth with a wood float</u></b>			
3	Surface beds, slabs, etc to falls	m2		
	<b><u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u></b>			
4	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	96	
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 2 Concrete, Formwork and Reinforcement <b>Refurbishment to Sele Primary school</b>			

**MOVEMENT JOINTS ETC**

**Expansion joints with ? softboard between vertical concrete surfaces**

5 10mm Joints not exceeding 300mm high m

**REINFORCEMENT**

**Fabric reinforcement**

6 Type ref193 fabric reinforcement in concrete surface beds, slabs, etc m2 97

Carried to Collection

R

Section No. 2  
 Bill No. 2  
 Concrete, Formwork and Reinforcement  
**Refurbishment to Sele Primary school**

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

33

34

**Carried Forward to Summary of Section No. 2**

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 3</u></b>			
	<b><u>CARPENTRY AND JOINERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>ROOFS ETC</u></b>			
	<b><u>Sawn softwood</u></b>			
1	76 x 50mm Purlins	m		
	<b><u>"Everite FC77" pressed fibre-cement</u></b>			
2	225 x 15mm Fascias and barge boards including galvanised steel H-profile jointing strips	m	123	
	<b><u>SKIRTINGS</u></b>			
3	19 x 75mm Skirting nailed	m		
	<b><u>DOORS ETC</u></b>			
	<b><u>Wrought meranti doors hung to steel frames</u></b>			
4	40mm Framed door 813 x 2032mm high Framed,ledged and braced batten door formed of 40 x 110mm stiles and top rail, 20 x 225mm bottom ledge, 20 x 150mm middle ledge and 20 x 110mm diagonal braces, filled in flush one side with 20 x 75mm tongued, grooved and v-jointed both sides vertical boarding fixed in and including grooves in stiles and top rail	No	12	
	<b>Carried Forward to Summary of Section No. 2</b>			
	Section No. 2			R
	Bill No. 3			
	Carpentry and Joinery			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 4</u></b>			
	<b><u>ROOF COVERINGS ETC</u></b>			
	<b><u>PROFILED METAL SHEETING AND ACCESSORIES</u></b>			
	<b><u>User note:</u></b>			
	Supplementary preambles in connection with fixing of sheeting and accessories and laps are to be inserted when the Model Preambles for Trades (or other preambles not covering the fixing of sheeting and accessories and laps) are used			
	When the pitch of troughed roof covering is less than 5 degrees or if dustproofing is required then the description of roof coverings "with side laps sealed" is to be used			
	Where roof coverings are fixed on top of rigid board insulation to purlins etc descriptions of roof coverings are to include therefore			
	Note that sheeting is also available in corten steel, stainless steel, copper and aluminium			
	<b><u>0.6mm Thick light industrial "colomet"IBR profile steel roof sheeting pre painted fixed to timber purlins at approximately 750mm centres according to engineers detail</u></b>			
1	Roof covering with pitch not exceeding 25 degrees	m2	519	
2	Ridge capping 1.2mm girth	m	40	
3	Narrow and broad flute closers	m		
	<b><u>ROOF AND WALL INSULATION</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 4 Roof Coverings <b>Refurbishment to Sele Primary school</b>			

4	<p><b><u>"Sisalation 410" housing grade glass fibre reinforced aluminium foil bonded insulation</u></b></p> <p>Insulation laid taut over rafters and fixed concurrent with tiling battens, purlins, etc</p>	m2	519		
	<p style="text-align: center;"><b>Carried to Collection</b></p> <p>Section No. 2          Bill No. 4          Roof Coverings  <b>Refurbishment to Sele Primary school</b></p>			R	

Section No. 2

Bill No. 4

Roof Coverings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

37

38

**Amount**

**Carried Forward to Summary of Section No. 2**

Section No. 2  
Bill No. 4  
Roof Coverings  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 5</u></b>			
	<b><u>IRONMONGERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Finishes to ironmongery</u></b>			
	Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded			
	<b><u>LOCKS</u></b>			
1	75mm four lever lockset with striking plate fixed to metal	No	12	
	<b><u>HANDLES</u></b>			
	<b><u>"Union"</u></b>			
2	63mm Brass pull handle	No		
	<b><u>BATHROOM FITTINGS</u></b>			
	<b><u>"Kimberley-Clark"</u></b>			
3	75mm Diameter chromium plated towel rail 7mm long including end brackets	No		
4	Lockable toilet roll holder plugged	No		
	<b><u>PINNING BOARDS, WRITING BOARDS, PROJECTION SCREENS, ETC</u></b>			
	<b><u>"Parrot products"</u></b>			
5	"BD0476" 2 400 x 1 200mm Aluminium framed carpet bulletin board	No	8	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2			
	Bill No. 5			
	Ironmongery			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 6</u></b>			
	<b><u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions:</u></b>			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete			
	Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere			
	<b><u>CEILINGS ETC</u></b>			
	<b><u>NAILED UP CEILINGS</u></b>			
	<b><u>6.4mm "Rhino" gypsum plasterboard with "Bischoff" H-type pressed steel jointing strips</u></b>			
1	Ceilings including 38 x 38mm sawn softwood brandering at 300mm centres	m2	399	
2	Extra over gypsum plasterboard ceiling for hinged pressed metal trap door size 600 x 600mm including all necessary ironmongery	No	2	
	<u>Sawn Softwood</u>			
3	38 x 38mm Trimmers around light fittings (elsewhere)	m	5	
4	38 x 38mm Hangers	m	5	
5	38 x 76mm Runners	m	201	
6	38 x 114mm Ceiling joists	m	2	
	<b>Carried to Collection</b>			R
	Section No. 2			
	Bill No. 6			
	Ceilings			
	<b>Refurbishment to Sele Primary school</b>			



Section No. 2

Bill No. 6

Ceilings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

41

42

**Amount**

**Carried Forward to Summary of Section No. 2**

Section No. 2

Bill No. 6

Ceilings

**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO. 7</u></b>			
	<b><u>PLASTERING</u></b>			
	Unless otherwise stated all items in this bill shall be deemed to fall into Work Group No. 142 for JBCC CPAP purposes			
	_____			
	<b><u>EXTERNAL PLASTER</u></b>			
	<u>1:5 cement plaster mix</u>			
1	On walls	m2	95	
	<u>(3:1) Cement screeds to concrete</u>			
	<u>33mm Thick</u>			
2	On floors to receive ceramic tiles (elsewhere)	m2	432	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2			
	Bill No. 7			
	Plastering			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 8</u></b>			
	<b><u>TILING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions</u></b>			
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding			
	<b><u>FLOOR TILING</u></b>			
	<b><u>250 x 250 x 22mm Non-slip terrazzo floor tiles fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted waterproof jointing compound</u></b>			
1	On floors and landings	m2	399	
2	Skirting 75mm high	m	268	
	<b>Carried Forward to Summary of Section No. 2</b>			R
	Section No. 2			
	Bill No. 8			
	Tiling			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 9</u></b>			
	<b><u>PLUMBING AND DRAINAGE (PROVISIONAL)</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>"Polycop" polypropylene pipes:</u></b>			
	Polypropylene pipes 54mm diameter and under shall be seamless copper coloured class 16 pipes jointed with "Fast-fuse" heat welded thermoplastic or brass compression fittings as designed for use with copper pipes as stated			
	Pipes shall be firmly fixed to walls etc with coloured nylon snap-in pipe clips with provision for accommodating thermal movement and jointed and fixed strictly in accordance with the manufacturer's instructions			
	All pipe diameters are nominal external			
	<b><u>RAINWATER DISPOSAL</u></b>			
	<b><u>Galvanised sheet iron</u></b>			
1	75 x 75mm Eaves gutters	m	44	
2	Extra over eaves gutter for stopped end	No	4	
3	Extra over eaves gutter for angle	No	8	
4	Extra over eaves gutter for outlet for 75mm pipe	No	8	
5	Extra over eaves gutter for outlet for 75 x 75mm pipe	No	8	
6	75mm Diameter rainwater pipes	m	24	
	<b><u>SANITARY FITTINGS</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 9 Plumbing and Drainage <b>Refurbishment to Sele Primary school</b>			

	<b><u>"Vaal"</u></b>			
7	530 x 430mm "Orbit" self-rimming drop-in vanity basin	No		
8	"Klip" low level wc suite comprising pan with double flap heavy duty plastic seat and matching 9 litre cistern with flush pipe	No		
9	"Protea Paraplegic" low level wc suite comprising pan with double flap heavy duty plastic seat and matching 9 litre cistern with flush pipe and prupose made CP side-flush lever	No		
10	415 x 315 x 275mm "Flatback" wall hung bowl urinal with spreader (flushing valve elsewhere)	No		
	<b><u>TRAPS</u></b>			
	<u>Traps, etc. including joints to steel pipes and/or fittings unless otherwise described</u>			
	<b><u>Butyl Rubber</u></b>			
11	32-40mm Butyl rubber deep seal P or S trap	No		
	<b><u>WASTE UNIONS</u></b>			
	<b><u>"Cobra Watertech"</u></b>			
12	32mm "301" Basin waste union	No		
	<b><u>"Cobra Watertech"</u></b>			
13	15mm "059CP" Extension piece with sliding wall flange	No		
	<b><u>Sanitary Plumbing</u></b>			
	<u>uPVC pipes and fittings</u>			
14	50mm Pipe fixed to walls,etc.	m		
	<u>Extra over uPVC pipes for fittings</u>			
15	50mm Reducer	No		
16	50mm Bend	No		
	<b>Carried to Collection</b>			
	Section No. 2			
	Bill No. 9			
	Plumbing and Drainage			
	<b>Refurbishment to Sele Primary school</b>			
			R	

**Water Supply**

Class O thin wall hard drawn copper pipes and fittings with capillary soldered type connections

17 15mm Pipes m

Extra over class O copper pipes for soldered capillary fittings

18 15mm Fittings No

**Carried to Collection**

Section No. 2  
 Bill No. 9  
 Plumbing and Drainage  
**Refurbishment to Sele Primary school**

R



Section No. 2

Bill No. 9

Plumbing and Drainage

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

46

47

48

**Carried Forward to Summary of Section No. 2**

R

Section No. 2  
Bill No. 9  
Plumbing and Drainage  
**Refurbishment to Sele Primary school**



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 11</u></b>			
	<b><u>PAINTWORK</u></b>			
	<b><u>PREPARATORY WORK TO EXISTING WORK</u></b>			
	<b><u>Previously painted plastered surfaces</u></b>			
	Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth			
	<b><u>Previously painted metal surfaces</u></b>			
	Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal			
	<b><u>Previously painted wood surfaces</u></b>			
	Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth			
	<b><u>PAINTWORK ETC TO PREVIOUSLY PAINTED WORK</u></b>			
	<b><u>ON FLOATED PLASTER</u></b>			
	<b><u>Paint on plaster, etc.</u></b>			
	<u>One undercoat and two coats "Plascon Double Velvet" or similar approved paint</u>			
1	On internal plastered walls	m2	643	
2	On external plastered walls	m2	140	
3	Face Brick dressing to External face brick walls	m2	196	
	<b>Carried to Collection</b>			R
	Section No. 2 Bill No. 11 Paintwork <b>Refurbishment to Sele Primary school</b>			

**ON PLASTER BOARD**

Prepare, stop and apply one coat alkali resistant pure acrylic filler coat and one full coat washable mat acrylic PVA paint

4 On internal plastered board ceilings m2 399

**ON FIBRE-CEMENT**

Prepare, stop and apply one coat alkali resistant primer and two full coats acrylic emulsion paint for exterior use

5 On external fibre-cement fascias and bargeboards including priming metal cover strips and screw heads with one coat zinc phosphate alkyd resin primer m2 59

**ON METAL**

**Paint on metal**

Prepare and apply two coats bitumen paint

6 On inside of 100 x 125mm galvanised sheet iron eaves gutter before fixing m 68

Prepare, touch up factory primer and apply one coat universal undercoat and two full coats high gloss enamel paint

7 On pressed steel door frames m2 22

8 On Mild steel window frames m2 186

9 On sashes and frames with burglar bars (both sides measured) m2 186

Prepare and apply one coat zinc phosphate alkyd resin primer, one coat universal undercoat and two full coats high gloss enamel paint

10 On grille gates and screens (both sides measured on flat) m2 30

**Carried to Collection**

R

Section No. 2  
Bill No. 11  
Paintwork  
**Refurbishment to Sele Primary school**

	<u>Prepare and apply one undercoat and two coats approved roof paint to galvanised metal roof sheeting</u>				
11	On steel galvanised roof sheeting	m2	350		
	<b><u>ON WOOD</u></b>				
	<b><u>Paint on wood</u></b>				
	<u>Prepare, stop and apply three full coats polyurethane clear eggshell varnish, lightly sanded down between coats</u>				
12	On general surfaces of doors	m2	43		
	<u>Wood preservative</u>				
13	Two coats wood preservative applied hot on wrought exposed roof timbers	m2	12		
	<b>Carried to Collection</b>				
	Section No. 2				
	Bill No. 11				
	Paintwork				
	<b>Refurbishment to Sele Primary school</b>				
				R	

Section No. 2

Bill No. 11

Paintwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

51

52

53

**Carried Forward to Summary of Section No. 2**

R

Section No. 2

Bill No. 11

Paintwork

**Refurbishment to Sele Primary school**

**SECTION SUMMARY - SECTION -2 ADMINISTRATION BLOCK A and B REN**

Bill No		Page No	Amount
1	Alterations	32	
2	Concrete, Formwork and Reinforcement	35	
3	Carpentry and Joinery	36	
4	Roof Coverings	39	
5	Ironmongery	40	
6	Ceilings	43	
7	Plastering	44	
8	Tiling	45	
9	Plumbing and Drainage	49	
10	Glazing	50	
11	Paintwork	54	
<b>Carried to Final Summary</b>			
Section No. 2 <b>Refurbishment to Sele Primary school</b>			R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 1</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>Taking out and removing doors, windows, etc from steel door frames</u></b>			
1	Timber single door and frame 813 x 2032mm high	No	4	
	<b><u>Taking down and removing roof sheets and purlins, floors, panelling, ceilings, partitions, etc</u></b>			
2	Gypsum plasterboard ceilings including cornices, timber bandering, etc	m2	255	
	<b><u>Taking out and removing sundry joinery work</u></b>			
3	Timber skirtings from brickwork	m	117	
	<b><u>Taking up and removing vinyl floor coverings, carpeting, etc</u></b>			
4	Vinyl tile floor covering including preparing screed for new tiling	m2	194	
	<b><u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, etc</u></b>			
5	Screed from floors	m2	194	
6	Internal plaster from walls and columns	m2	345	
7	External plaster from walls, columns and beams	m2	265	
	<b><u>Making good internal cement plaster</u></b>			
8	Walls in patches	m2	80	
	<b><u>Taking out and removing glass and mirrors</u></b>			
9	Glass from steel windows including cleaning out rebates and preparing for new glass	m2	6	
	<b>Carried Forward to Summary of Section No. 3</b>			R
	Section No. 3			
	Bill No. 1			
	Alterations			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 2</u></b>			
	<b><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Cost of tests</u></b>			
	The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the architect. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the architect. (Test cubes are measured separately)			
	<b><u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></b>			
	<b><u>APRONS</u></b>			
	<b><u>EXCAVATION, FILLING, ETC</u></b>			
	<b><u>Open face excavation in earth over sloping site</u></b>			
1	Open face excavation	m3	12	
	<b><u>Extra over all excavations for carting away</u></b>			
2	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	12	
	<b><u>Compaction of surfaces</u></b>			
3	Compaction of ground surface under floors etc by wetting and compacting with ? passes of a ? ton vibratory roller	m2	83	
	<b><u>SOIL POISONING</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 3 Bill No. 2 Concrete, Formwork and Reinforcement <b>Refurbishment to Sele Primary school</b>			

<b><u>Soil insecticide</u></b>					
4	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	83		
<b><u>15MPa/19mm concrete</u></b>					
5	Surface beds cast in panels on waterproofing	m3	8		
<b><u>TEST BLOCKS</u></b>					
6	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5		
<b><u>Finishing top surfaces of concrete smooth with a wood float</u></b>					
7	Surface beds, slabs, etc to falls	m2	83		
<b><u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u></b>					
8	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	92		
<b><u>MOVEMENT JOINTS ETC</u></b>					
<b><u>Expansion joints with ? softboard between vertical concrete surfaces</u></b>					
9	10mm Joints not exceeding 300mm high	m	28		
<b><u>REINFORCEMENT</u></b>					
<b><u>Fabric reinforcement</u></b>					
10	Type ref193 fabric reinforcement in concrete surface beds, slabs, etc	m2	83		
<b>Carried to Collection</b>				R	
Section No. 3 Bill No. 2 Concrete, Formwork and Reinforcement <b>Refurbishment to Sele Primary school</b>					

Section No. 3  
Bill No. 2  
Concrete, Formwork and Reinforcement

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

57

58

**Amount**

**Carried Forward to Summary of Section No. 3**

Section No. 3  
Bill No. 2  
Concrete, Formwork and Reinforcement  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 3</u></b>			
	<b><u>CARPENTRY AND JOINERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>ROOFS ETC</u></b>			
	<b><u>Sawn softwood</u></b>			
	<b><u>"Everite FC77" pressed fibre-cement</u></b>			
1	225 x 15mm Fascias and barge boards including galvanised steel H-profile jointing strips	m	95	
	<b><u>SKIRTINGS</u></b>			
2	19 x 75mm Skirting nailed	m	133	
	<b><u>DOORS ETC</u></b>			
	<b><u>Wrought meranti doors hung to steel frames</u></b>			
3	40mm Framed door 813 x 2032mm high Framed,ledged and braced batten door formed of 40 x 110mm stiles and top rail, 20 x 225mm bottom ledge, 20 x 150mm middle ledge and 20 x 110mm diagonal braces, filled in flush one side with 20 x 75mm tongued, grooved and v-jointed both sides vertical boarding fixed in and including grooves in stiles and top rail	No	7	
	<b>Carried Forward to Summary of Section No. 3</b>			R
	Section No. 3			
	Bill No. 3			
	Carpentry and Joinery			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 4</u></b>			
	<b><u>ROOF COVERINGS ETC</u></b>			
	<b><u>PROFILED METAL SHEETING AND ACCESSORIES</u></b>			
	<b><u>User note:</u></b>			
	Supplementary preambles in connection with fixing of sheeting and accessories and laps are to be inserted when the Model Preambles for Trades (or other preambles not covering the fixing of sheeting and accessories and laps) are used			
	When the pitch of troughed roof covering is less than 5 degrees or if dustproofing is required then the description of roof coverings "with side laps sealed" is to be used			
	Where roof coverings are fixed on top of rigid board insulation to purlins etc descriptions of roof coverings are to include therefore			
	Note that sheeting is also available in corten steel, stainless steel, copper and aluminium			
	<b><u>0.6mm Thick light industrial "colomet"IBR profile steel roof sheeting pre painted fixed to timber purlins at approximately 750mm centres according to engineers detail</u></b>			
1	Roof covering with pitch not exceeding 25 degrees	m2	471	
2	Ridge capping 1.2mm girth	m	34	
3	Narrow and broad flute closers	m	68	
	<b><u>ROOF AND WALL INSULATION</u></b>			
	<b>Carried to Collection</b>			
	Section No. 3 Bill No. 4 Roof Coverings <b>Refurbishment to Sele Primary school</b>			R

4	<p><b><u>"Sisalation 410" housing grade glass fibre reinforced aluminium foil bonded insulation</u></b></p> <p>Insulation laid taut over rafters and fixed concurrent with tiling battens, purlins, etc</p>	m2	471		
<b>Carried to Collection</b>					R
<p>Section No. 3          Bill No. 4          Roof Coverings  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 3

Bill No. 4

Roof Coverings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

61

62

**Amount**

**Carried Forward to Summary of Section No. 3**

Section No. 3  
Bill No. 4  
Roof Coverings  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 5</u></b>			
	<b><u>IRONMONGERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Finishes to ironmongery</u></b>			
	Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded			
	<b><u>LOCKS</u></b>			
1	75mm four lever lockset with striking plate fixed to metal	No	7	
	<b><u>HANDLES</u></b>			
	<b><u>"Union"</u></b>			
2	63mm Brass pull handle	No	7	
	<b><u>PINNING BOARDS, WRITING BOARDS, PROJECTION SCREENS, ETC</u></b>			
	<b><u>"Parrot products"</u></b>			
3	"BD0476" 2 400 x 1 200mm Aluminium framed carpet bulletin board	No	2	
	<b>Carried Forward to Summary of Section No. 3</b>			R
	Section No. 3 Bill No. 5 Ironmongery <b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 6</u></b>			
	<b><u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions:</u></b>			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete			
	Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere			
	<b><u>CEILINGS ETC</u></b>			
	<b><u>NAILED UP CEILINGS</u></b>			
	<b><u>6.4mm "Rhino" gypsum plasterboard with "Bischoff" H-type pressed steel jointing strips</u></b>			
1	Ceilings including 38 x 38mm sawn softwood brandering at 300mm centres	m2	325	
2	Extra over gypsum plasterboard ceiling for hinged pressed metal trap door size 600 x 600mm including all necessary ironmongery	No	2	
	<u>Sawn Softwood</u>			
3	38 x 38mm Trimmers around light fittings (elsewhere)	m	10	
4	38 x 38mm Hangers	m	10	
5	38 x 76mm Runners	m	1 206	
6	38 x 114mm Ceiling joists	m	5	
	<b>Carried to Collection</b>			R
	Section No. 3 Bill No. 6 Ceilings <b>Refurbishment to Sele Primary school</b>			



Section No. 3

Bill No. 6

Ceilings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

65

66

**Amount**

**Carried Forward to Summary of Section No. 3**

Section No. 3  
Bill No. 6  
Ceilings

**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO. 7</u></b></p> <p><b><u>PLASTERING</u></b></p> <p>Unless otherwise stated all items in this bill shall be deemed to fall into Work Group No. 142 for JBCC CPAP purposes</p> <hr style="width: 20%; margin-left: 40px;"/> <p><u>(3:1) Cement screeds to concrete</u></p> <p><u>33mm Thick</u></p>			
1	On floors to receive ceramic tiles (elsewhere)	m2	325	
	<b>Carried Forward to Summary of Section No. 3</b>			R
	<p>Section No. 3            Bill No. 7            Plastering  <b>Refurbishment to Sele Primary school</b></p>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 8</u></b>			
	<b><u>TILING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions</u></b>			
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding			
	<b><u>WALL TILING</u></b>			
	<b><u>152 x 152 x 5mm White glazed ceramic tiles on brickwork including cement plaster ? backing</u></b>			
1	On walls	m2		
	<b><u>FLOOR TILING</u></b>			
	<b><u>250 x 250 x 22mm Non-slip terrazzo floor tiles fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted waterproof jointing compound</u></b>			
2	On floors and landings	m2	325	
3	Skirting 75mm high	m	133	
	<b>Carried Forward to Summary of Section No. 3</b>			R
	Section No. 3			
	Bill No. 8			
	Tiling			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 11</u></b>			
	<b><u>PAINTWORK</u></b>			
	<b><u>PREPARATORY WORK TO EXISTING WORK</u></b>			
	<b><u>Previously painted plastered surfaces</u></b>			
	Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth			
	<b><u>Previously painted metal surfaces</u></b>			
	Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal			
	<b><u>Previously painted wood surfaces</u></b>			
	Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth			
	<b><u>PAINTWORK ETC TO PREVIOUSLY PAINTED WORK</u></b>			
	<b><u>ON FLOATED PLASTER</u></b>			
	<b><u>Paint on plaster, etc.</u></b>			
	<u>One undercoat and two coats "Plascon Double Velvet" or similar approved paint</u>			
1	On external plastered walls	m2	345	
2	On internal plastered walls	m2	265	
	<b><u>ON PLASTER BOARD</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 3 Bill No. 10 Paintwork <b>Refurbishment to Sele Primary school</b>			

3	<p><u>Prepare, stop and apply one coat alkali resistant pure acrylic filler coat and one full coat washable mat acrylic PVA paint</u></p> <p>On internal plastered board ceilings</p>	m2	325	
	<b><u>ON FIBRE-CEMENT</u></b>			
	<p><u>Prepare, stop and apply one coat alkali resistant primer and two full coats acrylic emulsion paint for exterior use</u></p> <p>On external fibre-cement fascias and bargeboards including priming metal cover strips and screw heads with one coat zinc phosphate alkyd resin primer</p>	m2	52	
	<b><u>ON METAL</u></b>			
	<b><u>Paint on metal</u></b>			
	<p><u>Prepare, touch up factory primer and apply one coat universal undercoat and two full coats high gloss enamel paint</u></p> <p>On pressed steel door frames</p>	m2	12	
	On Mild steel window frames	m2	99	
	On sashes and frames with burglar bars (both sides measured)	m2	99	
	<p><u>Prepare and apply one coat zinc phosphate alkyd resin primer, one coat universal undercoat and two full coats high gloss enamel paint</u></p> <p>On grille gates and screens (both sides measured on flat)</p>	m2	13	
	<b><u>ON WOOD</u></b>			
	<b><u>Paint on wood</u></b>			
	<p><u>Prepare, stop and apply three full coats polyurethane clear eggshell varnish, lightly sanded down between coats</u></p> <p>On general surfaces of doors</p>	m2	23	
	<b>Carried to Collection</b>			R
	<p>Section No. 3 Bill No. 10 Paintwork <b>Refurbishment to Sele Primary school</b></p>			



10	<p><u>Wood preservative</u></p> <p>Two coats wood preservative applied hot on wrought exposed roof timbers</p>	m2	5		
<b>Carried to Collection</b>					R
<p>Section No. 3          Bill No. 10          Paintwork  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 3

Bill No. 10

Paintwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

71

72

73

**Carried Forward to Summary of Section No. 3**

R

Section No. 3  
Bill No. 10  
Paintwork  
**Refurbishment to Sele Primary school**

<b>Bill No</b>	<b>SECTION SUMMARY - SECTION 3 - THREE CLASSROOM BLOC  1</b>	<b>Page No</b>	<b>Amount</b>
1	Alterations	56	
2	Concrete, Formwork and Reinforcement	59	
3	Carpentry and Joinery	60	
4	Roof Coverings	63	
5	Ironmongery	64	
6	Ceilings	67	
7	Plastering	68	
8	Tiling	69	
9	Glazing	70	
10	Paintwork	74	
<b>Carried to Final Summary</b>			
Section No. 3 <b>Refurbishment to Sele Primary school</b>			R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 1</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>Taking out and removing doors, windows, etc from steel door frames</u></b>			
1	Timber single door and frame 813 x 2032mm high	No	4	
	<b><u>Taking down and removing roof sheets and purlins, floors, panelling, ceilings, partitions, etc</u></b>			
2	Gypsum plasterboard ceilings including cornices, timber bandering, etc	m2	255	
	<b><u>Taking out and removing sundry joinery work</u></b>			
3	Timber skirtings from brickwork	m	117	
	<b><u>Taking up and removing vinyl floor coverings, carpeting, etc</u></b>			
4	Vinyl tile floor covering including preparing screed for new tiling	m2	194	
	<b><u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, etc</u></b>			
5	Screed from floors	m2	194	
6	Internal plaster from walls and columns	m2	345	
7	External plaster from walls, columns and beams	m2	265	
	<b><u>Making good internal cement plaster</u></b>			
8	Walls in patches	m2	80	
	<b><u>Taking out and removing glass and mirrors</u></b>			
9	Glass from steel windows including cleaning out rebates and preparing for new glass	m2	6	
	<b>Carried Forward to Summary of Section No. 4</b>			R
	Section No. 4			
	Bill No. 1			
	Alterations			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 2</u></b>			
	<b><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Cost of tests</u></b>			
	The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the architect. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the architect. (Test cubes are measured separately)			
	<b><u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></b>			
	<b><u>APRONS</u></b>			
	<b><u>EXCAVATION, FILLING, ETC</u></b>			
	<b><u>Open face excavation in earth over sloping site</u></b>			
1	Open face excavation	m3	12	
	<b><u>Extra over all excavations for carting away</u></b>			
2	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	12	
	<b><u>Compaction of surfaces</u></b>			
3	Compaction of ground surface under floors etc by wetting and compacting with ? passes of a ? ton vibratory roller	m2	83	
	<b><u>SOIL POISONING</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 4 Bill No. 2 Concrete, Formwork and Reinforcement <b>Refurbishment to Sele Primary school</b>			

<b><u>Soil insecticide</u></b>				
4	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	83	
<b><u>15MPa/19mm concrete</u></b>				
5	Surface beds cast in panels on waterproofing	m3	8	
<b><u>TEST BLOCKS</u></b>				
6	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5	
<b><u>Finishing top surfaces of concrete smooth with a wood float</u></b>				
7	Surface beds, slabs, etc to falls	m2	83	
<b><u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u></b>				
8	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	92	
<b><u>MOVEMENT JOINTS ETC</u></b>				
<b><u>Expansion joints with ? softboard between vertical concrete surfaces</u></b>				
9	10mm Joints not exceeding 300mm high	m	28	
<b><u>REINFORCEMENT</u></b>				
<b><u>Fabric reinforcement</u></b>				
10	Type ref193 fabric reinforcement in concrete surface beds, slabs, etc	m2	83	
<b>Carried to Collection</b>				
Section No. 4				
Bill No. 2				
Concrete, Formwork and Reinforcement				
<b>Refurbishment to Sele Primary school</b>				
				R

Section No. 4  
Bill No. 2  
Concrete, Formwork and Reinforcement

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

77

78

**Amount**

**Carried Forward to Summary of Section No. 4**

Section No. 4  
Bill No. 2  
Concrete, Formwork and Reinforcement  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 3</u></b>			
	<b><u>CARPENTRY AND JOINERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>ROOFS ETC</u></b>			
	<b><u>Sawn softwood</u></b>			
	<b><u>"Everite FC77" pressed fibre-cement</u></b>			
1	225 x 15mm Fascias and barge boards including galvanised steel H-profile jointing strips	m	95	
	<b><u>SKIRTINGS</u></b>			
2	19 x 75mm Skirting nailed	m	133	
	<b><u>DOORS ETC</u></b>			
	<b><u>Wrought meranti doors hung to steel frames</u></b>			
3	40mm Framed door 813 x 2032mm high Framed,ledged and braced batten door formed of 40 x 110mm stiles and top rail, 20 x 225mm bottom ledge, 20 x 150mm middle ledge and 20 x 110mm diagonal braces, filled in flush one side with 20 x 75mm tongued, grooved and v-jointed both sides vertical boarding fixed in and including grooves in stiles and top rail	No	7	
	<b>Carried Forward to Summary of Section No. 4</b>			R
	Section No. 4			
	Bill No. 3			
	Carpentry and Joinery			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO 4</u></b></p> <p><b><u>ROOF COVERINGS ETC</u></b></p> <p><b><u>PROFILED METAL SHEETING AND ACCESSORIES</u></b></p> <p><b><u>User note:</u></b></p> <p>Supplementary preambles in connection with fixing of sheeting and accessories and laps are to be inserted when the Model Preambles for Trades (or other preambles not covering the fixing of sheeting and accessories and laps) are used</p> <p>When the pitch of troughed roof covering is less than 5 degrees or if dustproofing is required then the description of roof coverings "with side laps sealed" is to be used</p> <p>Where roof coverings are fixed on top of rigid board insulation to purlins etc descriptions of roof coverings are to include therefore</p> <p>Note that sheeting is also available in corten steel, stainless steel, copper and aluminium</p> <p><b><u>0.6mm Thick light industrial "colomet"IBR profile steel roof sheeting pre painted fixed to timber purlins at approximately 750mm centres according to engineers detail</u></b></p>			
1	Roof covering with pitch not exceeding 25 degrees	m2	471	
2	Ridge capping 1.2mm girth	m	34	
3	Narrow and broad flute closers	m	68	
	<p><b><u>ROOF AND WALL INSULATION</u></b></p>			
	<b>Carried to Collection</b>			R
	<p>Section No. 4 Bill No. 4 Roof Coverings <b>Refurbishment to Sele Primary school</b></p>			

4	<p><b><u>"Sisalation 410" housing grade glass fibre reinforced aluminium foil bonded insulation</u></b></p> <p>Insulation laid taut over rafters and fixed concurrent with tiling battens, purlins, etc</p>	m2	471		
<b>Carried to Collection</b>					R
<p>Section No. 4          Bill No. 4          Roof Coverings  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 4

Bill No. 4

Roof Coverings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

81

82

**Amount**

**Carried Forward to Summary of Section No. 4**

Section No. 4  
Bill No. 4  
Roof Coverings  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 5</u></b>			
	<b><u>IRONMONGERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Finishes to ironmongery</u></b>			
	Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded			
	<b><u>LOCKS</u></b>			
1	75mm four lever lockset with striking plate fixed to metal	No	7	
	<b><u>HANDLES</u></b>			
	<b><u>"Union"</u></b>			
2	63mm Brass pull handle	No	7	
	<b><u>PINNING BOARDS, WRITING BOARDS, PROJECTION SCREENS, ETC</u></b>			
	<b><u>"Parrot products"</u></b>			
3	"BD0476" 2 400 x 1 200mm Aluminium framed carpet bulletin board	No	2	
	<b>Carried Forward to Summary of Section No. 4</b>			R
	Section No. 4			
	Bill No. 5			
	Ironmongery			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 6</u></b>			
	<b><u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions:</u></b>			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete			
	Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere			
	<b><u>CEILINGS ETC</u></b>			
	<b><u>NAILED UP CEILINGS</u></b>			
	<b><u>6.4mm "Rhino" gypsum plasterboard with "Bischoff" H-type pressed steel jointing strips</u></b>			
1	Ceilings including 38 x 38mm sawn softwood brandering at 300mm centres	m2	325	
2	Extra over gypsum plasterboard ceiling for hinged pressed metal trap door size 600 x 600mm including all necessary ironmongery	No	2	
	<u>Sawn Softwood</u>			
3	38 x 38mm Trimmers around light fittings (elsewhere)	m	10	
4	38 x 38mm Hangers	m	10	
5	38 x 76mm Runners	m	1 206	
6	38 x 114mm Ceiling joists	m	5	
	<b>Carried to Collection</b>			R
	Section No. 4			
	Bill No. 6			
	Ceilings			
	<b>Refurbishment to Sele Primary school</b>			



Section No. 4

Bill No. 6

Ceilings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

85

86

**Amount**

**Carried Forward to Summary of Section No. 4**

Section No. 4  
Bill No. 6  
Ceilings

**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO. 7</u></b></p> <p><b><u>PLASTERING</u></b></p> <p>Unless otherwise stated all items in this bill shall be deemed to fall into Work Group No. 142 for JBCC CPAP purposes</p> <hr style="width: 20%; margin-left: 40px;"/> <p><u>(3:1) Cement screeds to concrete</u></p> <p><u>33mm Thick</u></p>			
1	On floors to receive ceramic tiles (elsewhere)	m2	325	
	<b>Carried Forward to Summary of Section No. 4</b>			R
	<p>Section No. 4</p> <p>Bill No. 7</p> <p>Plastering</p> <p><b>Refurbishment to Sele Primary school</b></p>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 8</u></b>			
	<b><u>TILING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions</u></b>			
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding			
	<b><u>WALL TILING</u></b>			
	<b><u>152 x 152 x 5mm White glazed ceramic tiles on brickwork including cement plaster ? backing</u></b>			
1	On walls	m2		
	<b><u>FLOOR TILING</u></b>			
	<b><u>250 x 250 x 22mm Non-slip terrazzo floor tiles fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted waterproof jointing compound</u></b>			
2	On floors and landings	m2	325	
3	Skirting 75mm high	m	133	
	<b>Carried Forward to Summary of Section No. 4</b>			R
	Section No. 4			
	Bill No. 8			
	Tiling			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 11</u></b>			
	<b><u>PAINTWORK</u></b>			
	<b><u>PREPARATORY WORK TO EXISTING WORK</u></b>			
	<b><u>Previously painted plastered surfaces</u></b>			
	Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth			
	<b><u>Previously painted metal surfaces</u></b>			
	Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal			
	<b><u>Previously painted wood surfaces</u></b>			
	Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth			
	<b><u>PAINTWORK ETC TO PREVIOUSLY PAINTED WORK</u></b>			
	<b><u>ON FLOATED PLASTER</u></b>			
	<b><u>Paint on plaster, etc.</u></b>			
	<u>One undercoat and two coats "Plascon Double Velvet" or similar approved paint</u>			
1	On external plastered walls	m2	265	
2	On internal plastered walls	m2	345	
	<b><u>ON PLASTER BOARD</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 4 Bill No. 10 Paintwork <b>Refurbishment to Sele Primary school</b>			

3	<p><u>Prepare, stop and apply one coat alkali resistant pure acrylic filler coat and one full coat washable mat acrylic PVA paint</u></p> <p>On internal plastered board ceilings</p>	m2	325	
	<b><u>ON FIBRE-CEMENT</u></b>			
	<p><u>Prepare, stop and apply one coat alkali resistant primer and two full coats acrylic emulsion paint for exterior use</u></p> <p>On external fibre-cement fascias and bargeboards including priming metal cover strips and screw heads with one coat zinc phosphate alkyd resin primer</p>	m2	52	
	<b><u>ON METAL</u></b>			
	<b><u>Paint on metal</u></b>			
	<p><u>Prepare, touch up factory primer and apply one coat universal undercoat and two full coats high gloss enamel paint</u></p> <p>On pressed steel door frames</p>	m2	12	
	On Mild steel window frames	m2	99	
	On sashes and frames with burglar bars (both sides measured)	m2	99	
	<p><u>Prepare and apply one coat zinc phosphate alkyd resin primer, one coat universal undercoat and two full coats high gloss enamel paint</u></p> <p>On grille gates and screens (both sides measured on flat)</p>	m2	13	
	<b><u>ON WOOD</u></b>			
	<b><u>Paint on wood</u></b>			
	<p><u>Prepare, stop and apply three full coats polyurethane clear eggshell varnish, lightly sanded down between coats</u></p> <p>On general surfaces of doors</p>	m2	23	
	<b>Carried to Collection</b>			R
	Section No. 4			
	Bill No. 10			
	Paintwork			
	<b>Refurbishment to Sele Primary school</b>			

10	<p><u>Wood preservative</u></p> <p>Two coats wood preservative applied hot on wrought exposed roof timbers</p>	m2	5		
<b>Carried to Collection</b>					R
<p>Section No. 4          Bill No. 10          Paintwork  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 4

Bill No. 10

Paintwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

91

92

93

**Carried Forward to Summary of Section No. 4**

R

Section No. 4

Bill No. 10

Paintwork

**Refurbishment to Sele Primary school**

**SECTION SUMMARY - SECTION 4- THREE CLASSROOMS BLOCK 2**

Bill No		Page No	Amount
1	Alterations	76	
2	Concrete, Formwork and Reinforcement	79	
3	Carpentry and Joinery	80	
4	Roof Coverings	83	
5	Ironmongery	84	
6	Ceilings	87	
7	Plastering	88	
8	Tiling	89	
9	Glazing	90	
10	Paintwork	94	
<b>Carried to Final Summary</b>			R
Section No. 4 <b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 1</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>ALTERATIONS</u></b>			
	<b><u>Taking out and removing doors, windows, etc from steel door frames</u></b>			
1	Timber single door and frame 813 x 2032mm high	No	4	
	<b><u>Taking down and removing roof sheets and purlins, floors, panelling, ceilings, partitions, etc</u></b>			
2	Gypsum plasterboard ceilings including cornices, timber bandering, etc	m2	255	
	<b><u>Taking out and removing sundry joinery work</u></b>			
3	Timber skirtings from brickwork	m	117	
	<b><u>Taking up and removing vinyl floor coverings, carpeting, etc</u></b>			
4	Vinyl tile floor covering including preparing screed for new tiling	m2	194	
	<b><u>Hacking up/off and removing granolithic, screeds, plaster, etc from concrete or brickwork and preparing surfaces for new screeds, plaster, etc</u></b>			
5	Screed from floors	m2	194	
6	Internal plaster from walls and columns	m2	345	
7	External plaster from walls, columns and beams	m2	265	
	<b><u>Making good internal cement plaster</u></b>			
8	Walls in patches	m2	80	
	<b><u>Taking out and removing glass and mirrors</u></b>			
9	Glass from steel windows including cleaning out rebates and preparing for new glass	m2	6	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	Section No. 5			
	Bill No. 1			
	Alterations			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 2</u></b>			
	<b><u>CONCRETE, FORMWORK AND REINFORCEMENT</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Cost of tests</u></b>			
	The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the architect. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the architect. (Test cubes are measured separately)			
	<b><u>REINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></b>			
	<b><u>APRONS</u></b>			
	<b><u>EXCAVATION, FILLING, ETC</u></b>			
	<b><u>Open face excavation in earth over sloping site</u></b>			
1	Open face excavation	m3	12	
	<b><u>Extra over all excavations for carting away</u></b>			
2	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	12	
	<b><u>Compaction of surfaces</u></b>			
3	Compaction of ground surface under floors etc by wetting and compacting with ? passes of a ? ton vibratory roller	m2	83	
	<b><u>SOIL POISONING</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 5 Bill No. 2 Concrete, Formwork and Reinforcement <b>Refurbishment to Sele Primary school</b>			

<b><u>Soil insecticide</u></b>					
4	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	83		
<b><u>15MPa/19mm concrete</u></b>					
5	Surface beds cast in panels on waterproofing	m3	8		
<b><u>TEST BLOCKS</u></b>					
6	Making and testing 150 x 150 x 150mm concrete strength test cube (Provisional)	No	5		
<b><u>Finishing top surfaces of concrete smooth with a wood float</u></b>					
7	Surface beds, slabs, etc to falls	m2	83		
<b><u>ROUGH FORMWORK (DEGREE OF ACCURACY II)</u></b>					
8	Edges, risers, ends and reveals not exceeding 300mm high or wide	m	92		
<b><u>MOVEMENT JOINTS ETC</u></b>					
<b><u>Expansion joints with ? softboard between vertical concrete surfaces</u></b>					
9	10mm Joints not exceeding 300mm high	m	28		
<b><u>REINFORCEMENT</u></b>					
<b><u>Fabric reinforcement</u></b>					
10	Type ref193 fabric reinforcement in concrete surface beds, slabs, etc	m2	83		
<b>Carried to Collection</b>					R
Section No. 5					
Bill No. 2					
Concrete, Formwork and Reinforcement					
<b>Refurbishment to Sele Primary school</b>					

Section No. 5  
Bill No. 2  
Concrete, Formwork and Reinforcement

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

97

98

**Carried Forward to Summary of Section No. 5**

Section No. 5  
Bill No. 2  
Concrete, Formwork and Reinforcement  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 3</u></b>			
	<b><u>CARPENTRY AND JOINERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>ROOFS ETC</u></b>			
	<b><u>Sawn softwood</u></b>			
	<b><u>"Everite FC77" pressed fibre-cement</u></b>			
1	225 x 15mm Fascias and barge boards including galvanised steel H-profile jointing strips	m	95	
	<b><u>SKIRTINGS</u></b>			
2	19 x 75mm Skirting nailed	m	133	
	<b><u>DOORS ETC</u></b>			
	<b><u>Wrought meranti doors hung to steel frames</u></b>			
3	40mm Framed door 813 x 2032mm high Framed,ledged and braced batten door formed of 40 x 110mm stiles and top rail, 20 x 225mm bottom ledge, 20 x 150mm middle ledge and 20 x 110mm diagonal braces, filled in flush one side with 20 x 75mm tongued, grooved and v-jointed both sides vertical boarding fixed in and including grooves in stiles and top rail	No	7	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	Section No. 5			
	Bill No. 3			
	Carpentry and Joinery			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 4</u></b>			
	<b><u>ROOF COVERINGS ETC</u></b>			
	<b><u>PROFILED METAL SHEETING AND ACCESSORIES</u></b>			
	<b><u>User note:</u></b>			
	Supplementary preambles in connection with fixing of sheeting and accessories and laps are to be inserted when the Model Preambles for Trades (or other preambles not covering the fixing of sheeting and accessories and laps) are used			
	When the pitch of troughed roof covering is less than 5 degrees or if dustproofing is required then the description of roof coverings "with side laps sealed" is to be used			
	Where roof coverings are fixed on top of rigid board insulation to purlins etc descriptions of roof coverings are to include therefore			
	Note that sheeting is also available in corten steel, stainless steel, copper and aluminium			
	<b><u>0.6mm Thick light industrial "colomet"IBR profile steel roof sheeting pre painted fixed to timber purlins at approximately 750mm centres according to engineers detail</u></b>			
1	Roof covering with pitch not exceeding 25 degrees	m2	471	
2	Ridge capping 1.2mm girth	m	34	
3	Narrow and broad flute closers	m	68	
	<b><u>ROOF AND WALL INSULATION</u></b>			
	<b>Carried to Collection</b>			
	Section No. 5 Bill No. 4 Roof Coverings <b>Refurbishment to Sele Primary school</b>			R

4	<p><b><u>"Sisalation 410" housing grade glass fibre reinforced aluminium foil bonded insulation</u></b></p> <p>Insulation laid taut over rafters and fixed concurrent with tiling battens, purlins, etc</p>	m2	471		
<b>Carried to Collection</b>					R
<p>Section No. 5            Bill No. 4            Roof Coverings  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 5

Bill No. 4

Roof Coverings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

101

102

**Amount**

**Carried Forward to Summary of Section No. 5**

Section No. 5  
Bill No. 4  
Roof Coverings  
**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 5</u></b>			
	<b><u>IRONMONGERY</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Finishes to ironmongery</u></b>			
	Where applicable finishes to ironmongery are indicated by suffixes in accordance with the following list: BS Satin bronze lacquered CH Chromium plated SC Satin chromium plated SE Silver enamelled GE Grey enamelled AS Anodised silver AB Anodised bronze AG Anodised gold ABL Anodised black PB Polished brass PL Polished and lacquered PT Epoxy coated SD Sanded			
	<b><u>LOCKS</u></b>			
1	75mm four lever lockset with striking plate fixed to metal	No	7	
	<b><u>HANDLES</u></b>			
	<b><u>"Union"</u></b>			
2	63mm Brass pull handle	No	7	
	<b><u>PINNING BOARDS, WRITING BOARDS, PROJECTION SCREENS, ETC</u></b>			
	<b><u>"Parrot products"</u></b>			
3	"BD0476" 2 400 x 1 200mm Aluminium framed carpet bulletin board	No	2	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	Section No. 5			
	Bill No. 5			
	Ironmongery			
	<b>Refurbishment to Sele Primary school</b>			



Item No		Quantity	Rate	Amount
	<b><u>BILL NO 6</u></b>			
	<b><u>CEILINGS, PARTITIONS AND ACCESS FLOORING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions:</u></b>			
	Items described as "nailed" shall be deemed to be fixed with hardened steel nails or pins or shot pinned to brickwork or concrete			
	Items described as "plugged" shall be deemed to include screwing to fibre, plastic or metal plugs at not exceeding 600mm centres, and where described as "bolted" the bolts have been given elsewhere			
	<b><u>CEILINGS ETC</u></b>			
	<b><u>NAILED UP CEILINGS</u></b>			
	<b><u>6.4mm "Rhino" gypsum plasterboard with "Bischoff" H-type pressed steel jointing strips</u></b>			
1	Ceilings including 38 x 38mm sawn softwood brandering at 300mm centres	m2	325	
2	Extra over gypsum plasterboard ceiling for hinged pressed metal trap door size 600 x 600mm including all necessary ironmongery	No	2	
	<u>Sawn Softwood</u>			
3	38 x 38mm Trimmers around light fittings (elsewhere)	m	10	
4	38 x 38mm Hangers	m	10	
5	38 x 76mm Runners	m	1 206	
6	38 x 114mm Ceiling joists	m	5	
	<b>Carried to Collection</b>			R
	Section No. 5			
	Bill No. 6			
	Ceilings			
	<b>Refurbishment to Sele Primary school</b>			

	<b><u>"Aerolite" insulation</u></b>				
7	50mm Insulation closely fitted and laid on top of branding between roof timbers etc	m2	325		
	<b><u>"Rhino" gypsum plasterboard cornices</u></b>				
	<u>CORNICES</u>				
8	75mm Coved cornices	m	133		
	<b>Carried to Collection</b>				R
	Section No. 5				
	Bill No. 6				
	Ceilings				
	<b>Refurbishment to Sele Primary school</b>				

Section No. 5

Bill No. 6

Ceilings

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

105

106

**Amount**

**Carried Forward to Summary of Section No. 5**

Section No. 5  
Bill No. 6  
Ceilings

**Refurbishment to Sele Primary school**

R

Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO. 7</u></b></p> <p><b><u>PLASTERING</u></b></p> <p>Unless otherwise stated all items in this bill shall be deemed to fall into Work Group No. 142 for JBCC CPAP purposes</p> <hr style="width: 20%; margin-left: 40px;"/> <p><u>(3:1) Cement screeds to concrete</u></p> <p><u>33mm Thick</u></p>			
1	On floors to receive ceramic tiles (elsewhere)	m2	325	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	<p>Section No. 5 Bill No. 7 Plastering <b>Refurbishment to Sele Primary school</b></p>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 8</u></b>			
	<b><u>TILING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Descriptions</u></b>			
	Unless described as "fixed with adhesive to plaster (plaster elsewhere)" descriptions of tiling on brick or concrete walls, columns, etc shall be deemed to include 1:4 cement plaster backing and descriptions of tiling on concrete floors etc shall be deemed to include 1:3 plaster bedding			
	<b><u>WALL TILING</u></b>			
	<b><u>152 x 152 x 5mm White glazed ceramic tiles on brickwork including cement plaster ? backing</u></b>			
1	On walls	m2		
	<b><u>FLOOR TILING</u></b>			
	<b><u>250 x 250 x 22mm Non-slip terrazzo floor tiles fixed with adhesive to bedding (bedding elsewhere) and flush pointed with tinted waterproof jointing compound</u></b>			
2	On floors and landings	m2	325	
3	Skirting 75mm high	m	133	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	Section No. 5			
	Bill No. 8			
	Tiling			
	<b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<p><b><u>BILL NO 10</u></b></p> <p><b><u>GLAZING</u></b></p> <p><b><u>GLAZING TO STEEL WITH PUTTY</u></b></p> <p><b><u>6mm Clear float glass</u></b></p>			
1	Panes not exceeding 0,1 m2	m2	10	
	<b>Carried Forward to Summary of Section No. 5</b>			R
	<p>Section No. 5</p> <p>Bill No. 9</p> <p>Glazing</p> <p><b>Refurbishment to Sele Primary school</b></p>			

Item No		Quantity	Rate	Amount
	<b><u>BILL NO 11</u></b>			
	<b><u>PAINTWORK</u></b>			
	<b><u>PREPARATORY WORK TO EXISTING WORK</u></b>			
	<b><u>Previously painted plastered surfaces</u></b>			
	Surfaces shall be thoroughly washed down and allowed to dry completely before any paint is applied. Blistered or peeling paint shall be completely removed and cracks shall be opened, filled with a suitable filler and finished smooth			
	<b><u>Previously painted metal surfaces</u></b>			
	Surfaces shall be thoroughly rubbed and cleaned down. Blistered or peeling paint shall be completely removed down to bare metal			
	<b><u>Previously painted wood surfaces</u></b>			
	Surfaces shall be thoroughly cleaned down. Blistered or peeling paint shall be completely removed and cracks and crevices shall be primed, filled with suitable filler and finished smooth			
	<b><u>PAINTWORK ETC TO PREVIOUSLY PAINTED WORK</u></b>			
	<b><u>ON FLOATED PLASTER</u></b>			
	<b><u>Paint on plaster, etc.</u></b>			
	<u>One undercoat and two coats "Plascon Double Velvet" or similar approved paint</u>			
1	On internal plastered walls	m2	345	
2	On external plastered walls	m2	265	
	<b><u>ON PLASTER BOARD</u></b>			
	<b>Carried to Collection</b>			R
	Section No. 5 Bill No. 10 Paintwork <b>Refurbishment to Sele Primary school</b>			

3	<u>Prepare, stop and apply one coat alkali resistant pure acrylic filler coat and one full coat washable mat acrylic PVA paint</u> On internal plastered board ceilings	m2	325	
	<b><u>ON FIBRE-CEMENT</u></b>			
	<u>Prepare, stop and apply one coat alkali resistant primer and two full coats acrylic emulsion paint for exterior use</u>			
4	On external fibre-cement fascias and bargeboards including priming metal cover strips and screw heads with one coat zinc phosphate alkyd resin primer	m2	52	
	<b><u>ON METAL</u></b>			
	<b><u>Paint on metal</u></b>			
	<u>Prepare, touch up factory primer and apply one coat universal undercoat and two full coats high gloss enamel paint</u>			
5	On pressed steel door frames	m2	12	
6	On Mild steel window frames	m2	99	
7	On sashes and frames with burglar bars (both sides measured)	m2	99	
	<u>Prepare and apply one coat zinc phosphate alkyd resin primer, one coat universal undercoat and two full coats high gloss enamel paint</u>			
8	On grille gates and screens (both sides measured on flat)	m2	13	
	<b><u>ON WOOD</u></b>			
	<b><u>Paint on wood</u></b>			
	<u>Prepare, stop and apply three full coats polyurethane clear eggshell varnish, lightly sanded down between coats</u>			
9	On general surfaces of doors	m2	23	
	<b>Carried to Collection</b>			R
	Section No. 5 Bill No. 10 Paintwork <b>Refurbishment to Sele Primary school</b>			



10	<p><u>Wood preservative</u></p> <p>Two coats wood preservative applied hot on wrought exposed roof timbers</p>	m2	5		
<b>Carried to Collection</b>				R	
<p>Section No. 5          Bill No. 10          Paintwork  <b>Refurbishment to Sele Primary school</b></p>					

Section No. 5

Bill No. 10

Paintwork

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

111

112

113

**Carried Forward to Summary of Section No. 5**

R

Section No. 5

Bill No. 10

Paintwork

**Refurbishment to Sele Primary school**

Bill No	<b>SECTION SUMMARY - SECTION 5- THREE CLASSROOM BLOCK 3</b>	Page No	Amount
1	Alterations	96	
2	Concrete,Formwork and Reinforcement	99	
3	Carpentry and Joinery	100	
4	Roof Coverings	103	
5	Ironmongery	104	
6	Ceilings	107	
7	Plastering	108	
8	Tiling	109	
9	Glazing	110	
10	Paintwork	114	
<b>Carried to Final Summary</b>			R
Section No. 5 <b>Refurbishment to Sele Primary school</b>			

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO 3</u></b>			
	<b><u>BILL NO. 1</u></b>			
	<b><u>CLEARVU SECURITY FENCING</u></b>			
	<b><u>THE FOLLOWING IN EXTERNAL PERIMETER SECURITY FENCING</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	For supplementary preambles to all the following trades refer to such preambles as contained in the previous Bills of this Bills of Quantities			
	<b><u>Site Clearance</u></b>			
1	Digging up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	935	
2	Stripping average 150 mm thick layer of topsoil and stockpiling on site up and removing rubbish, debris, vegetation, hedges, shrubs and trees not exceeding 200mm girth, bush, etc	m2	935	
	<b><u>Excavation in earth not exceeding 2m deep</u></b>			
3	Holes	m3	78	
	<b><u>Extra over trench and hole excavations in earth for excavation in</u></b>			
4	Soft rock	m3	4	
5	Hard rock	m3	4	
	<b><u>Extra over all excavations for carting away</u></b>			
6	Surplus material from excavations and/or stock piles on site to a dumping site to be located by the contractor	m3	55	
	<b>Carried to Collection</b>			R
	Section No. 6 Bill No. 1 Perimeter Fencing <b>Refurbishment to Sele Primary school</b>			

<b><u>Risk of collapse of excavations</u></b>				
7	Sides of trench and hole excavations not exceeding 1,5m deep	m2	624	
<b><u>Soil insecticide</u></b>				
8	To bottoms and sides of trenches etc	m2	624	
<b><u>CLEARVIEW OR SIMMILAR FENCING</u></b>				
<b><u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES</u></b>				
<b><u>25MPa/19mm concrete</u></b>				
9	Holes	m3	26	
<b><u>FENCING</u></b>				
<b><u>Welded Mesh fencing or other equal approved invisible wall pannels</u></b>				
10	2.4 m high fence in panels 3.305m width with an aperture size (centres) 76 x 12.7 mm galvanised and black powder coated . Panel to be reinforced with 4 x 50 mm deep "V" formation horizontal recessed bands to enhance rigidity . Fem to be installed in strict accordance with manufacturers printed instructions.	m	624	
11	Galvanised and powdercoated spike bolted to high security fence installed as per manufacturers specification	m	624	
<b><u>Fence Posts</u></b>				
12	2.4 m high intermediate fence post galvanised and alu coated size 85 x 85 mm tapering to 45 mm with a depth of 85 mm with and including locking recess mechanism to secure panel edge complete with a UV stabilised polymer cap .	No	208	
13	2.4 m high Corner fence post galvanised and alu coated size 76 x 76 mm with a depth of 85 mm with and including locking recess mechanism to secure panel edge complete with a UV stabilised polymer cap .	No	7	
<b>Carried to Collection</b>				
Section No. 6				R
Bill No. 1				
Perimeter Fencing				
<b>Refurbishment to Sele Primary school</b>				

**Steel gates including rails, frames, sliding gear, locks, etc**

14 Double sliding gate size 6000 mm wide x 1800 mm high installed in strict accordance with manufacturers instructions

No 1

15 Single pedestrian gate size 1000 mm wide x 2400 mm high installed in strict accordance with manufacturers instructions

No

**Taking down and removing**

16 Take out and remove old wire mesh fencing

m 637

**Carried to Collection**

R

Section No. 6  
Bill No. 1  
Perimeter Fencing  
**Refurbishment to Sele Primary school**

Section No. 6

Bill No. 1

Perimeter Fencing

**COLLECTION**

Total Brought Forward from Page No.

**Page  
No**

**Amount**

116

117

118

**Carried to Final Summary**

R

Section No. 6

Bill No. 1

Perimeter Fencing

**Refurbishment to Sele Primary school**

Item No		Quantity	Rate	Amount
	<b><u>SECTION 9</u></b>			
	<b><u>BILL NO. 1</u></b>			
	<b><u>PROVISIONAL SUMS</u></b>			
	<b><u>FIXING OF CRACKS</u></b>			
1	Allow the sum as indicated for Fixing of cracks directed by the Principal Agent	Item		15 000.00
2	Allow the sum as indicated for replacing missing bricks directed by the Principal Agent	Item		7 500.00
	Electrical Installation from part B of the BoQ		R	247 674.20
3	Allow a provisional sum of R 20 000.00 for missing broken window furniture	Item		20 000.00
	<b>Carried to Final Summary</b>		R	
	Section No. 7 Bill No. 1 Provisional Sums <b>Refurbishment to Sele Primary school</b>			



Section No	<u>FINAL SUMMARY</u>	Page No	Amount
1	SECTION 1 - PRELIMINARIES	29	
2	SECTION -2 ADMINISTRATION BLOCK A and B RENOVATIONS	55	
3	SECTION 3 - THREE CLASSROOM BLOC1 1	75	
4	SECTION 4- THREE CLASSROOMS BLOCK 2	95	
5	SECTION 5- THREE CLASSROOM BLOCK 3	115	
6	SECTION 3 - EXTERNAL WORKS	119	
7	SECTION - 4 PROVISIONAL SUMS	120	
	SUB-TOTAL (Excluding Contingencies and Value Added Tax)		R
	Allow 2.5% of Sub-Total for Contingencies to be used as directed by the Principal Agent and deducted in whole or in part if not required		R
	Allow the sum of R 45 000.00 (Fourty Five Thousand Rand) for CLO		R                    45 000.00
	SUB-TOTAL including Value Added Tax (VAT)		R
	ADD: Value Added Tax (VAT) calculated at the rate of 15%		R
	<b>Carried to Form of Tender</b>		R
	<b>Refurbishment to Sele Primary school</b>		