



TRANSNET SOC LIMITED

TENDER NUMBER: TNPA/2025/03/0007/92662/RFQ

ADDENDUM NO. 01

DATED: 05 MAY 2025

The following information is furnished in addition to, in amplification and substitution of, matters contained in the tender documents issued in respect of the above-mentioned work.

1. Part T1 Tender Notice and Invitation

- The tender closing date has been extended from **14 May 2025 at 10:00** to **20 May 2025 at 10:00**.

2. Part C2 Pricing Data

The following documents, previously omitted, have now been added as part of the RFQ:

- C2.1 Pricing Instructions
- C2.2 Activity Schedule

3. GENERAL

All other terms and conditions remain unchanged.

This addendum must be signed and submitted with your tender.

Prepared By: Thoriso More

TMORE

Date: 05 May 2025

Approved By: Regional Procurement Manager

[Signature]

Date: 05 May 2025



FROM: _____

DATE: _____

TENDER NUMBER: TNPA/2025/03/0007/92662/RFQ

**DESCRIPTION: FOR THE PROVISION OF REFURBISHMENT, REPAIR, AND RE-INSTALLATION OF
A RECLAMATION FLOATING LINE PIPE AT A-BERTH IN THE PORT OF DURBAN**

Dear Sir/Madam

Receipt of **Addendum No. 01** dated **05 May 2025** is hereby acknowledged.

Kind regards

TENDERER

NOTE: This acknowledgment must be signed and returned to this office on or before closing date of tender.
TNPA/2025/03/0007/92662/RFQ

PART 2: PRICING DATA

Document reference	Title	No of pages
C2.1	Pricing instructions: Option A	2
C2.2	Activity Schedule	3

C2.1 Pricing Instructions: Option A

1. The *conditions of contract*

1.1. How the contract prices work and assesses it for progress payments

Clause 11 in NEC3 Engineering and Construction Contract, June 2005, (with amendments June 2006 and April 2013) (ECC) Option A states:

Identified and defined terms

- 11.2 (20) The Activity Schedule is the *activity schedule* unless later changed in accordance with this contract.
- (22) Defined Cost is the cost of the components in the Shorter Schedule of Cost Components whether work is subcontracted or not excluding the cost of preparing quotations for compensation events.
- (27) The Price for Work Done to Date is the total of the Prices for
- each group of completed activities and
 - each completed activity which is not in a group
- A completed activity is one which is without Defects which would either delay or be covered by immediately following work.
- (30) The Prices are the lump sums for each of the activities on the Activity Schedule unless later changed in accordance with this contract.

1.2. Measurement and Payment

- 1.2.1 The Activity Schedule provides the basis of all valuations of the Price for Work Done to Date, payments in multiple currencies, price adjustments for inflation and general progress monitoring.
- 1.2.2 The amount due at each assessment date is based on **completed activities and/or milestones** as indicated on the Activity Schedule.
- 1.2.3 The Activity Schedule work breakdown structure provided by the *Contractor* is based on the Activity Schedule provided by the *Employer*. The activities listed by the *Employer* are the minimum activities acceptable and identify the specific activities which are required to achieve Completion. The activity schedule work breakdown structure is compiled to the satisfaction of the *Project Manager* with any additions and/or amendments deemed necessary.
- 1.2.4 The *Contractor's* detailed Activity Schedule summates back to the Activity Schedule provided by the *Employer* and is in sufficient detail to monitor completion of activities related to the Accepted Programme in order that payment of completed activities may be assessed.

-
- 1.2.5 The short descriptions in the Activity Schedule are for identification purposes only. All work described in the Works Information is deemed included in the activities.
 - 1.2.6 The Activity Schedule is integrated with the Prices, Accepted Programme and where required the forecast rate of payment schedule.
 - 1.2.7 Activities in multiple currencies are separately identified on both the Activity Schedule and the Accepted Programme for each currency.
 - 1.2.8 The tendered total of the prices as stated in the Contract Data is obtained from the Activity Schedule summary. The tendered total of the prices includes for all direct and indirect costs, overheads, profits, risks, liabilities and obligations relative to the Contract.

C2.2 Activity Schedule

The Tenderer details his Activity Schedule below or makes reference to his Activity Schedule and attaches it to this schedule.

The details given below serve as guidelines only and the Tenderer may split or combine the activities to suit his particular methods.

Activity No	REFURBISH, REPAIR AND REINSTALLATION OF RECLAIM FLOATING LINE PIPE	Unit	Quantity	Rate	Amount
1	Provision and supply of safety file and work method statement subject to approval by project manager. Both these documents inclusive but not limited to: SHEQ safety file Site barricade and prevention of public access during execution of the works Sand blasting safety management plan	sum	1		
2	Site Establishment/ De-establishment of plants <i>Plant rates should cover for Public Holiday</i>	sum	1		
3	Safe rigging of pipe sections <i>rates should cover for Public Holiday</i>	Rate	1		
5	Refurbish of five (5) connection point from the four floating connection pieces. This includes: - Sandblasting and clearing of rust on the connection flanges. - Supply of connecting bolts and nuts for each section - Provision of rubber casket in-between floating pieces - Supply of denso tape to prevent rust on the first initial piece Replacement and installation of messenger line provided by the project manager	Sum	1		

6	Remove the floating mechanism from the floating pipeline including: - Sand blast and clean all barnacles (including chain, shackles, and swivel ball) and change if required - Undo the swivel from the red ball - Split the swivel, inspect the faces, and clean - Clean all grease line and nipples - P2 grease to be used on all section approx. 25 kg - Cut the wire at the damaged thimble and renew Bolt to be renewed as required (cut supply and fit)	sum	1		
7	Re-installation of reclaim floating pipeline Remove and place the pipe back in the water with new/ maintained components i.e., chains, seals, reclaim ball, flanges, bolts, etc.	sum	1		
8	Testing and Commissioning Run all tests required per condition assessment to ensure no leaks in the system during reclamation	sum	1		
Total Price to be carried over to the Form of Offer & Acceptance					