

Item No.	Description	Unit	Material OR Construction Procedure Labour Specification item number	Firm price per unit Excluding Vat Year 1 (from date of commencement for a period of 12 months)	Firm price per unit Excluding Vat Year 2 (from beginning of month 13 to end of month 24)	Firm price per unit Excluding Vat Year 3 (from beginning of month 25 to end of month 36)	Rate of Exchange	Manufacture Price List
2.7	Hole for pole ( 6m pole) (1000mm Depth)( concrete in hole to support pole)	each	1.1.2					
2.8	Hole for pole ( 8m pole) (1200mm Depth)( concrete in hole to support pole)	each	1.1.2					
2.9	Hole for cantilever bolt group foundation (casting of foundation measured separately)	each	1.1.2					
2.10	Hole for UPS cabinet	each	1.1.2					
2.12	Test holes (0.5 - 1metre depth)	each	1.1.2					
3	Road crossing – Includes: 1) Neat saw-cutting of road surface; 2) Excavation to right depth and width; 3) Laying of duct(s) in approved stabilized medium, 4) Backfilling and compacting with approved fill; 5) Supplying and placing compacted gravel course; 6) Reinstatement finish as shown on Drawing GE6.1 Rev B	m	5					
5	Import Material – Only for use where import is required and pre approved by Project Coordinator. Supply and deliver to site – Import and placing of material							
5.1	Sand fill	m <sup>3</sup>	3					

Item No.	Description	Unit	Material OR Construction Procedure Labour Specification item number	Firm price per unit Excluding Vat Year 1 (from date of commencement for a period of 12 months)	Firm price per unit Excluding Vat Year 2 (from beginning of month 13 to end of month 24)	Firm price per unit Excluding Vat Year 3 (from beginning of month 25 to end of month 36)	Rate of Exchange	Manufacture Price List
5.2	G5 Gravel	m³	3					
	NOTE ON BACKFILLING (Compacted) – acceptable material to be backfilled in layers no thicker than 150mm and then compacted.Final surface reinstatement measured separately(.refer to Construction Procedure section 2)							
6	Casting of plinths and foundations – includes supplying all materials (refer to specification page 225 section 3)							
6.1	Cast controller plinth	m²	2					
6.2	Cast connection pillar plinth	m²	2					
6.3	Cast Back to back UPS cabinet Plinth	m²	2					
6.4	Cast UPS cabinet foundation (Includes all materials, sand, gravel) excavation measured seperately	m²	2					
6.5	Cast Cantilever pole bolt group foundation (including all materials except bolt group) excavation measured separately	m³	2					
7	Removal of cantilever pole bolt group foundation (removal of cantilever pole measured separately)	m³	2					
8	Testing of loops –	each	13.1					
9	Reinstatement - includes neat, straight saw cutting of surface and supply of all material. All reinstatement to be of equal thickness and quality of surrounding asphalt or other surface material (refer to Construction Specification on section 6)							
9.1A	Supply of asphalt road surface	m³						
9.1B	Reinstate of asphalt road surface	m²	6					
9.1C	Supply of asphalt Footway surface	m³						

Item No.	Description	Unit	Material OR Construction Procedure Labour Specification item number	Firm price per unit Excluding Vat Year 1 (from date of commencement for a period of 12 months)	Firm price per unit Excluding Vat Year 2 (from beginning of month 13 to end of month 24)	Firm price per unit Excluding Vat Year 3 (from beginning of month 25 to end of month 36)	Rate of Exchange	Manufacture Price List
9.2	Reinstate of asphalt Footway surface	m <sup>2</sup>	6					
9.3A	Supply of brick paving	m <sup>2</sup>						
9.3B	Relay of brick paving	m <sup>2</sup>	6					
9.4A	Supply of concrete road surface	m <sup>3</sup>						
9.4B	Reinstate concrete road surface	m <sup>2</sup>	6					
10	Supply and Installation of ducts by thrust boring/ directional drilling (refer to Construction Specification on section 5)							
10.1.1	Supply ducts							
10.1.1A	Supply of 110mm duct	m	15.1					
101.12A	Supply of 160mm duct	m	15.1					
	Installation of ducts by thrust boring/ directional drilling in normal material							
10.1.1B	Install 110mm duct	m	5					
10.1.2B	Install 160mm duct	m	5					
	Installation of ducts by directional drilling in difficult material							
10.1.1C	Install of 110mm duct	m	5					
10.1..2C	Install 160mm duct	m	5					
11	Installation of kerbs stones ( rates includes supply of kerbs stones and bubble pavings where necessary as agreed by Project coordinator, refer to Construction Procedure on section 8)							
11.1A	Supply of normal kerbs	m	15.2					
11.1B	Install normal kerbs	m	8					



e) Is the tenderer liable in the Republic of <i>South Africa</i> for any form of taxation?	<input type="checkbox"/> Yes <input type="checkbox"/> No
<p>The undersigned, who warrants that he / she is duly authorised to do so on behalf of the enterprise:</p> <p>i) authorizes the Employer to obtain a tax clearance certificate from the <i>South African Revenue Services</i> that my / our tax matters are in order;</p> <p>ii) confirms that the neither the name of the enterprise or the name of any partner, manager, director or other person, who wholly or partly exercises, or may exercise, control over the enterprise appears on the Register of Tender Defaulters established in terms of the Prevention and Combating of Corrupt Activities Act of 2004 or Database of Restricted Suppliers;</p> <p>iii) confirms that no partner, member, director or other person, who wholly or partly exercises, or may exercise, control over the enterprise appears, has within the last five years been convicted of fraud or corruption;</p> <p>iv) confirms that I / we are not associated, linked or involved with any other tendering entities submitting tender offers and have no other relationship with any of the tenderers or those responsible for compiling the scope of work that could cause or be interpreted as a conflict of interest; and</p> <p>iv) confirms that the contents of this questionnaire are within my personal knowledge and are to the best of my belief both true and correct.</p>	

Signed \_\_\_\_\_ Date \_\_\_\_\_

Name \_\_\_\_\_ Position \_\_\_\_\_

*Enterprise  
name*

-----

**SIGNED ON BEHALF OF TENDERER:** .....