

GENERAL CONSTRUCTION NOTES: 1. ALL WORK, PLANS AND CONSTRUCTION TO BE DONE IN ACCORDANCE WITH THE NATIONAL BUILDING REGULATIONS AND SANS 10400 SPECIFICATIONS AND CODE OF PRACTICE.

- 2. CONTRACTOR TO CHECK AND VERIFY SUFFICIENCY OF INFORMATION, LEVELS AND DIMENSIONS ON DRAWING BEFORE COMMENCING WORK.
- 3. REPORT ANY OMISSIONS, DISCREPANCIES OR ERRORS IMMEDIATELY TO THE ARCHITECT.
- 4. DO NOT SCALE DIMENSIONS FROM DRAWING.
- 5. SHOULD THE CONTRACTOR PROCEED WITHOUT THE ABOVE APPROVAL, HE DOES SO ENTIRELY AT HIS OWN RISK.
- 6. ALL STRUCTURAL WORK TO BE CHECKED BY AN ENGINEER.
- 7. SOIL CONDITIONS TO BE APPROVED BY RELEVANT ENGINEER.
- 8. ALL WORK TO COMPLY WITH LOCAL AUTHORITY BY-LAWS.

9 All condensing units to be quorium treated and tectyled. 10 Suction lines to be insulated with armaflex insulation.

11 All internal and exposed refrigeration pipework to run in a straight line in trunking. 12 All refrigeration pipework not in trunking to run in cable tray.

13 All external cable trays to be stainless steel

galvanised after manufacture.

14. All internal cable trays to be galvanised. 15 All starters if required to be provided by a/c contractor. 16 All mild steel brackets and hangers to be hot dipped

REV	REVISION HISTORY	DATE
A	ISSUED FOR TENDER	2022.12.26

Freedom Park - Gallery of Leaders

Koch st & 7th Ave Salvokop Pretoria 0002

Freedom Park Heritage Museum

Scale 1:100

FOR TENDERING

PAPER SIZE: C. CHAGWEDERA CHECKED BY: ITADERERA 1:100 FIRST ISSUE: 26/11/22 PROJECT STATUS: Tendering DRAWING NUMBER:

REVISION: 0029-GOL_100-01 - HVAC-A1



Cnr Felstead & Northumberland Avenue

COPYRIGHT © DATE OF PRINT: 12/26/2022 3:48:27 PM