

Brought Forward		R	
20	Brick manhole 1380 x 920mm internally exceeding 1250mm and not exceeding 1500mm deep internally comprising suitable 2340 x 1880 x 250mm thick 25MPa/26mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 1840 x 1380 x 200mm thick 25MPa/26mm reinforced concrete cover slab with Y10 high tensile steel bars at 150mm centres set in both directions and rebated opening to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03. (LI)	No	5
21	Brick manhole 1380 x 920mm internally exceeding 1500mm and not exceeding 1750mm deep internally comprising suitable 2340 x 1880 x 250mm thick 25MPa/26mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 1840 x 1380 x 200mm thick 25MPa/26mm reinforced concrete cover slab with Y10 high tensile steel bars at 150mm centres set in both directions and rebated opening to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03. (LI)	No	1
22	Brick manhole 1380 x 920mm internally exceeding 1750mm and not exceeding 2000mm deep internally comprising suitable 2340 x 1880 x 250mm thick 25MPa/26mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 1840 x 1380 x 200mm thick 25MPa/26mm reinforced concrete cover slab with Y10 high tensile steel bars at 150mm centres set in both directions and rebated opening to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03. (LI)	No	2
Carried Forward		R	
Bill No. 18 External Works			

Brought Forward				R
<u>Kerb inlets for stormwater manholes (gratings and covers elsewhere)</u>				
23	Kerbside storm water inlet, overall size 3660 x 1220mm externally not exceeding 1500mm and not exceeding 1750mm deep to invert comprising, 250mm thick 25Mpa/19mm reinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, and 100mm thick precast concrete cover complete with excavation, risk of collapse, working space, hoisting in position, backfilling with selected excavated material, cart away surplus material, shoring benching, haunching, etc. all in accordance to Type D3, annexured to these Bills of Quantities for the full details, drawing number: TGC/04. (LI)	No	2	
<u>Attenuation Tank</u>				
24	Two (2) compartment attenuation tank approximate size 1710 x 740mm internally and not exceeding 1000mm deep internally comprising of 2370 x 1400 x 250mm thick 30MPa/19mm unreinforced concrete base, 230mm brickwork of NFX clay bricks (14 MPa nominal compressive strength) in class I mortar, 2170 x 1200 x 100mm thick 30Mpa/19mm reinforced concrete cover slab with Y12 high tensile steel bars at 150mm centres set in both directions and two rebated openings to accommodate cover and frame (cover and frame elsewhere measured) including all excavation, backfilling, formwork etc. all in accordance to Type 3, annexured to these Bills of Quantities for the full details, drawing number: 51660. (LI)	No	1	
25	Cementitious waterproofing system in two coats and reinforced with a non-woven propylene membrane to the inside floor and walls of the Attenuation tank	m2	7	
<u>Gratings, covers, etc</u>				
26	Light duty precast concrete 550mm diameter cover and cover slab approximate size 1010 x 1010mm all in accordance to Type A, annexured to these Bills of Quantities for the full details, drawing number: TGC/03.	No	18	
27	Heavy duty precast concrete 550mm diameter cover and cover slab approximate size 1220 x 1220mm all in accordance to Type D3, annexured to these Bills of Quantities for the full details, drawing number: TGC/04.	No	2	
Carried Forward				R
Bill No. 18 External Works				

**Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4**

Brought Forward		R	
28	550mm Diameter x 176kg, type 2A cast iron cover and frame including	No	1
29	450 x 300mm St. Gobain type 2880 heavy duty cast iron grate and frame including casting in fixing lugs into concrete	No	1
<u>Sundries</u>			
30	Extra over excavation in earth for pipe trenches, chambers, etc for excavation in soft rock (LI)	m3	61
31	Extra over excavation in earth for pipe trenches, chambers, etc for excavation in hard rock	m3	31
32	Extra over excavation for pipe trenches, chambers, etc for carting away surplus material to a dumping site to be located by the Contractor	m3	246
33	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for bedding material SANS 1200 LB 3.3, maximum aggregate 6mm compacted to 93% MOD AASHTO density in 100mm layers (LI)	m3	82
34	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for fill blanket material placed in accordance to SANS 1200 LB 3.2, maximum aggregate 10mm compacted to 93% MOD AASHTO density (LI)	m3	82
35	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for backfill material placed and compacted in accordance to SANS 1200 BD 3.5, maximum aggregate 63mm compacted in to 93% MOD AASHTO density (LI)	m3	82
<u>Testing</u>			
36	Allow for testing of the entire stormwater drainage system to Engineer's satisfaction.	Item	
<u>SOIL DRAINAGE</u>			
<u>(CPAP WORK GROUP NO. 146 UNLESS OTHERWISE STATED)</u>			
Carried Forward		R	
Bill No. 18 External Works			

Brought Forward				R
<u>Class 34 heavy duty uPVC pipes laid in class B bedding including all excavation, bedding, backfilling and compaction and disposal of surplus material</u>				
37	110mm Pipes vertically or ramped to cleaning eyes etc. (no excavation) (LI)	m	57	
38	110mm Pipes laid in and trenches not exceeding 1m deep (LI)	m	315	
39	110mm Pipes laid in and including trenches exceeding 1m and not exceeding 2m deep (LI)	m	176	
<u>Extra over class 34 uPVC pipes for fittings</u>				
40	110mm Bends (LI)	No	111	
41	110mm Access junction (LI)	No	54	
<u>Precast concrete circular inspection chambers (covers elsewhere)</u>				
Where approach grades into the manhole are 1:15 or steeper and associated with a change in direction in the manhole of 30° or more, the benching is to be brought up two pipe diameters above the pipe invert (Type B benching sewers)				
Rendering for all manhole benching shall consist of one part H.A.C. to two parts sand thoroughly mixed and applied to 'uncured' concrete surfaces to a minimum thickness of 20mm				
42	Excavate for and construct 1000mm internal diameter circular pre-cast concrete manhole exceeding 750mm but not exceeding 1000mm deep with 1130mm diameter x 250mm thick unreinforced concrete grade 25/26 base and benching and 150mm thick pre-cast cover slab as described above, including all risk of collapse, compaction and backfilling, etc. on completion (LI)	No	12	
43	Excavate for and construct 1000mm internal diameter circular pre-cast concrete manhole exceeding 1000mm but not exceeding 1250mm deep with 1130mm diameter x 250mm thick unreinforced concrete grade 25/26 base and benching and 150mm thick pre-cast cover slab as described above, including all risk of collapse, compaction and backfilling, etc. on completion (LI)	No	2	
Carried Forward				R
Bill No. 18 External Works				

**Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4**

Brought Forward			R
44	Excavate for and construct 1000mm internal diameter circular pre-cast concrete manhole exceeding 1250mm but not exceeding 1500mm deep with 1130mm diameter x 250mm thick unreinforced concrete grade 25/26 base and benching and 150mm thick pre-cast cover slab as described above, including all risk of collapse, compaction and backfilling, etc. on completion (LI)	No	3
<u>Covers, etc</u>			
45	550mm Diameter x 176kg, type 2A cast iron cover and frame including	No	17
<u>Sundries</u>			
46	Excavate for and construct gulley comprising of 110mm uPVC gulley trap with 190mm diameter uPVC hopperhead with pvc grating, all set in mass concrete and not exceeding 500mm deep. The top of the gulley to be raised 75mm above surrounding ground level and internally dished down to hopper head with smoothened render and external of raised sides to be finished neatly. (LI)	No	24
47	Extra over excavation in earth for pipe trenches, chambers, etc. for excavation in soft rock (LI)	m3	110
48	Extra over excavation in earth for pipe trenches, chambers, etc. for excavation in hard rock	m3	55
49	Extra over excavation for pipe trenches, chambers, etc for carting away surplus material to a dumping site to be located by the Contractor	m3	330
50	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for bedding material SANS 1200 LB 3.3, maximum aggregate 6mm compacted to 93% MOD AASHTO density in 100mm layers (LI)	m3	110
51	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for fill blanket material placed in accordance to SANS 1200 LB 3.2, maximum aggregate 10mm compacted in to 93% MOD AASHTO density (LI)	m3	110
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
52	Extra over backfilling to pipe trenches, chambers, etc for imported selected and approved granular material for backfill material placed and compacted in accordance to SANS 1200 BD 3.5, maximum aggregate 63mm compacted in to 93% MOD AASHTO density (LI)	m3	110	
53	110mm 'ABC" cast iron rodding eyes set in 300 x 300 x 300mm thick 15MPa/19 unreinforced concrete surround finished smooth on exposed surfaces with rounded angles	No	8	
<u>Connection to Municipal mains:</u>				
54	Allow for connection of sewer drainage system to Municipality Sewer Mains including cutting into side of existing inspection chamber for and connecting 160mm pipe, including inserting 160mm channel junction and making good concrete benching and manholes etc			Item
55	Cutting into side of existing inspection chamber for and connecting 110mm pipe, including inserting channel junction and making good concrete benching	No	1	
<u>Testing</u>				
56	Allow for testing of the entire sewer drainage system to the satisfaction of the Engineer			Item
<u>WATER SUPPLIES</u>				
<u>(CPAP WORK GROUP NO. 148 UNLESS OTHERWISE STATED)</u>				
<u>CLASS 12 PN10 Pipe laid on Class "B" bedding, including excavations in pickable material, backfilling and compacting to 95% Modified AASHTO density and all necessary risk of collapse and dewatering of trenches</u>				
57	20mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	49	
58	25mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	95	
Carried Forward				R
Bill No. 18 External Works				

Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4

Brought Forward			R
59	32mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	72
60	40mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	39
61	50mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	18
62	110mm Pipes laid in and including trenches exceeding 1m but not exceeding 2m deep (LI)	m	586
<u>Extra over HDPE pipe for 'Plasson' or other equally approved HDPE compression type fittings</u>			
63	25mm Elbow (LI)	No	18
64	25 x 20mm Elbow (LI)	No	8
65	25mm Tees (LI)	No	2
66	25 x 20mm Tees (LI)	No	26
67	32mm Elbows (LI)	No	10
68	32 x 25mm Elbow (LI)	No	2
69	32mm Tees (LI)	No	5
70	32 x 20mm Tees (LI)	No	15
71	32 x 25mm Tees (LI)	No	2
72	32 x 25mm Reducer (LI)	No	6
73	40mm Elbows (LI)	No	1
74	40 x 25mm Tees (LI)	No	1
75	40 x 32mm Tees (LI)	No	2
76	40 x 32mm Reducer (LI)	No	1
77	50 x 32mm Tees (LI)	No	1
78	50 x 40mm Reducer (LI)	No	1
Carried Forward			R
Bill No. 18 External Works			

**Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4**

Brought Forward			R
79	110mm Elbow (LI)	No	21
80	110mm Tees (LI)	No	2
81	110 x 32mm Tees (LI)	No	6
82	110 x 50mm Tees (LI)	No	1
<u>Brassware</u>			
83	110mm Gate valve	No	8
84	50mm brass non return valve	No	4
85	50mm brass in line strainer	No	5
86	20mm Coupling (LI)	No	57
87	25mm Coupling (LI)	No	8
88	32mm Coupling (LI)	No	8
<u>Valve Chambers, etc.</u>			
89	Valve box set 440 x 370mm internally and not exceeding 900mm deep internally on 610 x 540 x 100mm thick concrete base, including 110mm brickwork of NFX extra hard burnt brickwork and fitted with and including with 610 x 540mm cast iron cover and frame set level to the ground all in accordance to details 2, annexured to these Bills of Quantities for the full details, drawing number: TGC/10.	No	8
<u>Sundries</u>			
90	20Mpa/19mm Unreinforced mass concrete as anchor blocks around various fittings (LI)	m3	2
91	20Mpa/19mm Unreinforced mass concrete encasing to pipework on trenches (LI)	m3	4
92	200 x 200 x 200mm Mass concrete markers blocks	No	30
93	Extra over excavation in earth for pipe trenches, valve boxes, etc for excavation in soft rock (LI)	m3	172
94	Extra over excavation in earth for pipe trenches, valve boxes, etc for excavation in hard rock	m3	86
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
95	Cart away surplus material to a dumping site located by the contractor	m3	387
96	Import Class "B" bedding and initial backfill to 300mm above crown of pipe (LI)	m3	387
<u>Municipal connection</u>			
97	Allow for the tie in to the municipal water main	Item	
<u>Testing</u>			
98	Allow for testing the whole of the Domestic water supplies to the satisfaction of the Principal Agent and Local authority. All defective work to removed and made good at the contractors expense and the whole works to be re-tested until found satisfactory	Item	
<u>FIRE WATER MAIN</u>			
<u>(CPAP WORK GROUP NO. 148 UNLESS OTHERWISE STATED)</u>			
<u>"HDPE" or other equally approved pipes with solvent welded joints</u>			
99	32mm "HDPE 100PN 12.5" pipes laid in and including trenches not exceeding 1m deep (LI)	m	19
100	80mm "HDPE 100PN 12.5" pipes laid in and including trenches not exceeding 1m deep (LI)	m	24
101	110mm "HDPE 100PN 12.5" pipes laid in and including trenches not exceeding 1m deep (LI)	m	538
<u>Extra over HDPE Pipes for Electroweld Fusion couplings for Fittings</u>			
102	32mm Elbow (LI)	No	1
103	80mm Elbow (LI)	No	16
104	110mm Elbow (LI)	No	19
105	110mm Tees (LI)	No	14
106	110 x 32mm Tees (LI)	No	1
Carried Forward			R
Bill No. 18 External Works			

Brought Forward		R	
107	110 x 80mm Tees (LI)	No	8
108	32mm Coupling (LI)	No	1
109	110mm Coupling (LI)	No	12
<u>Isolating valve chamber</u>			
110	Excavate in ground for and build valve chamber 630 x 630 x 1000mm deep of precast concrete chamber rings with dry joints with 100mm (10MPa) thick concrete base, 150mm thick (20Mpa) concrete slab fitted with and including 102mm diameter cast iron hinged cover and frame.	No	4
<u>Extra over isolating valve chamber</u>			
111	110mm Gate Valve	No	4
<u>Sundries</u>			
112	25MPa/19mm unreinforced mass concrete as anchor blocks around various fittings (LI)	m3	19
113	Extra over excavation in earth for pipe trenches, valve boxes, etc for excavation in soft rock (LI)	m3	46
114	Extra over excavation in earth for pipe trenches, valve boxes, etc for excavation in hard rock	m3	23
115	Cart away surplus material to a dumping site located by the contractor	m3	172
116	Import Class "B" bedding and initial backfill to 300mm above crown of pipe (LI)	m3	153
117	75mm Hydrant with connection with cap and chain	No	7
118	80 x 65mm Brass double booster pump connection with caps and chains	No	1
<u>Municipal connection</u>			
119	Allow for the tie in to the municipal water main	Item	
Carried Forward		R	
Bill No. 18 External Works			

Brought Forward			R
<u>Testing</u>			
120	Allow for testing the whole of the Fire water supplies to the satisfaction of the Principal Agent and Local authority. All defective work to removed and made good at the contractors expense and the whole works to be re-tested until found satisfactory	Item	
<u>CONCRETE APRONS</u>			
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation other than bulk</u>			
121	Excavate to reduced level (LI)	m3	162
122	Edge thickening (LI)	m3	50
<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>			
123	Off site to a dumping site to be found by the Contractor.	m3	212
<u>Keeping excavations free of water</u>			
124	Keeping excavations free of all water other than subterranean water	Item	
<u>Compaction of surfaces</u>			
125	Compaction of ground surface under pavings, roads etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	541
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
126	Construct 150mm thick base layer of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density. (LI)	m3	81
<u>Prescribed density tests on filling</u>			
127	Modified AASHTO Density tests	No	14
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
	<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>		
128	Under apron, etc. (LI)	m2	541
	<u>Concrete (CPAP Work Group No. 110)</u>		
	<u>Reinforced concrete cast against excavated surfaces</u>		
	<u>30MPa/19mm concrete</u>		
129	Concrete aprons (LI)	m3	81
130	Edge thickening (LI)	m3	50
	<u>Test cubes</u>		
131	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	22
	<u>Concrete sundries</u>		
	<u>Finishing top surfaces of concrete smooth with a wood float</u>		
132	Surface beds, slabs, etc.to falls (LI)	m2	541
	<u>Formwork (CPAP Work Group No. 111)</u>		
	<u>Rough formwork to sides</u>		
133	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	959
	<u>Movement joints etc</u>		
	<u>Expansion joints with 15mm softboard between vertical concrete surfaces, including necessary formwork</u>		
134	Not exceeding 300mm high between surface beds and brickworks (LI)	m	800
	<u>Reinforcement (CPAP Work Group No. 114)</u>		
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Fabric reinforcement</u>			
135	Type Ref. 193 fabric reinforcement in concrete surface beds, slabs, etc. (LI)	m2	541
<u>Masonry (CPAP Work Group No. 116)</u>			
<u>30MPa "Corobrik" or other equally approved Cederberg Modular paving bricks</u>			
136	65mm clay paving bricks laid in herringbone pattern to SANS 1200MJ, blocks laid on 25mm river sand layer on concrete aprons (concrete aprons elsewhere measured) (LI)	m2	541
<u>Waterproofing (CPAP Work Group No. 120)</u>			
<u>One layer of 375 micron waterproof sheeting sealed at laps as per approval</u>			
137	Under surface beds (LI)	m2	541
<u>Joint sealants etc</u>			
<u>Two-part grey or other equally approved polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>			
138	15 x 10mm In horizontal expansion joints including raking out expansion joint filler as necessary	m	800
<u>CONCRETE PLATFORM</u>			
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation other than bulk</u>			
139	Excavate to reduced level (LI)	m3	24
140	Edge thickening (LI)	m3	3
<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>			
141	Off site to a dumping site to be found by the Contractor.	m3	27
Carried Forward			R
Bill No. 18 External Works			

Brought Forward		R	
<u>Keeping excavations free of water</u>			
142	Keeping excavations free of all water other than subterranean water	Item	
<u>Compaction of surfaces</u>			
143	Compaction of ground surface under pavings, roads etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	48
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
144	Construct 150mm thick base layer of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density. (LI)	m3	14
<u>Prescribed density tests on filling</u>			
145	Modified AASHTO Density tests	No	2
<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>			
146	Under concrete platform, etc. (LI)	m2	48
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Reinforced concrete cast against excavated surfaces</u>			
<u>30MPa/19mm concrete</u>			
147	Concrete aprons (LI)	m3	10
148	Edge thickening (LI)	m3	3
<u>Test cubes</u>			
149	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2
<u>Concrete sundries</u>			
Carried Forward		R	
Bill No. 18 External Works			

Brought Forward			R
	<u>Finishing top surfaces of concrete smooth with a wood float</u>		
150	Surface beds, slabs, etc.to falls (LI)	m2	48
	<u>Formwork (CPAP Work Group No. 111)</u>		
	<u>Rough formwork to sides</u>		
151	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	28
	<u>Movement joints etc</u>		
	<u>Expansion joints with 15mm softboard between vertical concrete surfaces, including necessary formwork</u>		
152	Not exceeding 300mm high between surface beds and brickworks (LI)	m	8
	<u>Reinforcement (CPAP Work Group No. 114)</u>		
	<u>Fabric reinforcement</u>		
153	Type Ref. 395 fabric reinforcement in concrete surface beds, etc. (LI)	m2	48
	<u>Waterproofing (CPAP Work Group No. 120)</u>		
	<u>One layer of 375 micron waterproof sheeting sealed at laps as per approval</u>		
154	Under surface beds (LI)	m2	48
	<u>Joint sealants etc</u>		
	<u>Two-part grey or other equally approved polysulphide sealing compound including backing cord, bond breaker , primer, etc</u>		
155	15 x 10mm In horizontal expansion joints including raking out expansion joint filler as necessary	m	8
	<u>WALKWAY</u>		
	<u>Earthworks (CPAP Work Group No. 104)</u>		
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Excavation other than bulk</u>			
156	Excavate to reduced level (LI)	m3 34	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>			
157	Off site to a dumping site to be found by the Contractor.	m3 34	
<u>Keeping excavations free of water</u>			
158	Keeping excavations free of all water other than subterranean water	Item	
<u>Compaction of surfaces</u>			
159	Compaction of ground surface under pavings, roads etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2 343	
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
160	Construct 100mm thick base layer of G2 materials obtained from commercial sources, compacted to a density of at least 98% Mod AASHTO density. (LI)	m3 34	
<u>Testing of material and filling</u>			
Descriptions of earth filling, compaction, etc shall be deemed to include for all necessary testing required in accordance with the SABS 1200 series			
The items of testing given below are for additional testing which may be required by the Engineer over and above those required in accordance with the SABS 1200 series			
<u>Additional tests required by Engineer</u>			
161	Maximum dry density and optimum moisture content test in accordance with Method A7 of TMH 1	No 4	
162	Atterberg limits test in accordance with methods A2 to A4 of TMH 1	No 2	
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
163	In-situ dry density test in accordance with method A10(b) of TMH 1		Item	
	<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>			
164	Under parking area, etc. (LI)	m2	343	
	<u>Roadwork (CPAP Work Group No. 154)</u>			
	<u>Bituminous premix road surfacing</u>			
165	Prime and lay 20mm thick. Bitumen 9.5mm Stone, laid compacted, to falls	m2	343	
	<u>Precast concrete finished smooth on exposed surfaces including bedding, jointing and pointing</u>			
166	Kerb (SABS 927 fig 6) 125 x 260mm high with 150 x 150 x 300mm unreinforced concrete haunching at back of each joint including excavation, backfilling, etc. (LI)	m	458	
	<u>RETAINING WALLS, PLANTER WALLS, RAMP AND STAIRCASES</u>			
	<u>Earthworks (CPAP Work Group No. 104)</u>			
	<u>Excavation other than bulk</u>			
167	Trenches (LI)	m3	370	
168	Excavate to reduced level (LI)	m3	117	
169	Edge thickening (LI)	m3	6	
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>			
170	Off site to a dumping site to be found by the Contractor.	m3	257	
	<u>Risk of collapse of excavations</u>			
171	Sides of trench and hole excavations not exceeding 1,5m deep	m2	925	
Carried Forward				R
Bill No. 18 External Works				

Brought Forward		R	
<u>Keeping excavations free of water</u>			
172	Keeping excavations free of all water other than subterranean water	Item	
<u>Compaction of surfaces</u>			
173	Compaction of ground surface under strip footings, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	370
174	Compaction of ground surface under ramps, staircase, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	84
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density.</u>			
175	Backfilling to trenches, holes, etc. (LI)	m3	236
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
176	Construct 150mm thick base layer of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density.	m3	59
<u>Prescribed density tests on filling</u>			
177	Modified AASHTO Density tests	No	49
<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>			
178	Under floors, etc. (LI)	m2	84
179	To sides and bottoms of trench excavations (LI)	m2	1 295
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Reinforced concrete cast against excavated surfaces /or formworks</u>			
Carried Forward		R	
Bill No. 18 External Works			

	Brought Forward			R
	<u>30MPa/19mm concrete</u>			
180	Strip footings (LI)	m3	93	
181	Edge thickening (LI)	m3	6	
182	Surface ramps (LI)	m3	54	
183	Staircase (LI)	m3	7	
	<u>Test cubes</u>			
184	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	27	
	<u>Concrete sundries</u>			
	<u>Finishing top surfaces of concrete smooth with a wood float</u>			
185	Surface beds, slabs, etc. to falls (LI)	m2	84	
	<u>Formwork (CPAP Work Group No. 111)</u>			
	<u>Rough formwork to sides</u>			
186	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	86	
187	Edges, risers, ends and reveals not exceeding 300mm high or wide set raking (LI)	m	86	
188	Sloping and stepped outer edges of stairs not exceeding 500mm high extreme (LI)	m	28	
	<u>Movement joints etc</u>			
	<u>Expansion joints with 15mm softboard between vertical concrete surfaces, including necessary formwork</u>			
189	Not exceeding 300mm high between surface beds and brickworks (LI)	m	86	
	<u>Reinforcement (CPAP Work Group No. 114)</u>			
	Carried Forward			R
	Bill No. 18			
	External Works			

Brought Forward			R
<u>Mild and high tensile steel reinforcement to structural concrete work</u>			
190	Various diameter bars (LI)	t	10,52
<u>Fabric reinforcement</u>			
191	Type Ref. 245 fabric reinforcement in concrete surface beds, slabs, etc. (LI)	m2	84
<u>Masonry (CPAP Work Group No. 116)</u>			
<u>Brickwork of NFX bricks in class II mortar</u>			
192	One brick walls in foundations (LI)	m2	145
193	One and half brick walls in foundations (LI)	m2	203
194	One brick walls (LI)	m2	146
195	One and half brick walls (LI)	m2	213
<u>Brickwork sundries</u>			
<u>2.5mm Galvanised brickwork reinforcement</u>			
196	155mm Wide reinforcement built in horizontally (LI)	m	4 391
<u>Face brickwork</u>			
<u>"Agate" travertine FBX or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints</u>			
197	Extra over brickwork for face brickwork walls in foundations (LI)	m2	118
198	Extra over brickwork for face brickwork walls (LI)	m2	359
199	Extra over brickwork for brick-on-edge header course bands one course high (LI)	m	463
<u>Waterproofing (CPAP Work Group No. 120)</u>			
<u>One layer of 375 micron waterproof sheeting sealed at laps as per approval</u>			
200	Under surface beds (LI)	m2	84
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
	<u>"RFK Chemflex" or other equally approved waterproofing slurry, with and including "Sika membrane applied as per manufacturer's instructions"</u>		
201	On walls	m2	705
	<u>Joint sealants etc</u>		
	<u>Two-part grey or other equally approved polysulphide sealing compound including backing cord, bond breaker, primer, etc</u>		
202	15 x 10mm In horizontal expansion joints including raking out expansion joint filler as necessary	m	86
	<u>Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)</u>		
	<u>Slotted HDPE flexible drainage pipes</u>		
203	110mm HDPE flexible slotted agricultural pipes laid behind retaining walls for a depth not exceeding 3m including 19mm crushed stone encasing 300 x 300mm, "Kaymat" U34 geofabric filter blanket wrapped around encasing with 150mm side and 300mm end laps including stitching and 300 x 300mm river sand. (LI)	m	325
204	Extra over for 110mm cap (LI)	No	12
205	Extra over for 110mm bend (LI)	No	36
	<u>BOUNDARY WALLS, FENCE AND GATES</u>		
	<u>Earthworks (CPAP Work Group No. 104)</u>		
	<u>Excavation other than bulk</u>		
206	Trenches (LI)	m3	550
	<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>		
207	Off site to a dumping site to be found by the Contractor.	m3	365
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Risk of collapse of excavations</u>			
208	Sides of trench and hole excavations not exceeding 1,5m deep	m2	1 572
<u>Keeping excavations free of water</u>			
209	Keeping excavations free of all water other than subterranean water		Item
<u>Compaction of surfaces</u>			
210	Compaction of ground surface under strip footings, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	367
<u>Earth filling obtained from the excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density.</u>			
211	Backfilling to trenches, holes, etc. (LI)	m3	185
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
212	Construct 150mm thick base layer, under strip footings, of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density. (LI)	m3	110
<u>Prescribed density tests on filling</u>			
213	Modified AASHTO Density tests	No	49
<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>			
214	To sides and bottoms of trench excavations (LI)	m2	1 939
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Reinforced concrete cast against excavated surfaces /or formworks</u>			
<u>30MPa/19mm concrete</u>			
215	Strip footings (LI)	m3	110
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Test cubes</u>			
216	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	18
<u>Formwork (CPAP Work Group No. 111)</u>			
<u>Rough formwork to sides</u>			
217	Stepped face of foundations (LI)	m2	24
<u>Reinforcement (CPAP Work Group No. 114)</u>			
<u>Mild and high tensile steel reinforcement to structural concrete work</u>			
218	Various diameter bars (LI)	t	11,55
<u>Masonry (CPAP Work Group No. 116)</u>			
<u>Brickwork of NFX bricks in class II mortar</u>			
219	One brick walls in foundations (LI)	m2	472
220	Piers in foundations (LI)	m3	36
221	One brick walls (LI)	m2	1 143
222	Piers (LI)	m3	99
<u>Brickwork sundries</u>			
<u>2.5mm Galvanised brickwork reinforcement</u>			
223	155mm Wide reinforcement built in horizontally (LI)	m	8 632
<u>Brickwork sundries</u>			
<u>Bagging of 1:3 cement and sand mixture</u>			
224	On brick walls, piers, etc. (LI)	m2	2 202
<u>Joint forming material in movement joints</u>			
225	12mm Bitumen impregnated fibre board built in vertically through brick walls not exceeding 300mm wide (LI)	m	74
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
226	12mm Bitumen impregnated fibre board built in vertically through brick walls exceeding 300mm wide (LI)	m2	307
	<u>Face brickwork</u>		
	<u>"Agate" travertine FBX or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints</u>		
227	Extra over brickwork for face brickwork on both sides in foundations (LI)	m2	136
228	Extra over brickwork for face brickwork to piers in foundations (LI)	m2	79
229	Extra over brickwork for face brickwork on both sides of wall (LI)	m2	1 143
230	Extra over brickwork for face brickwork to piers (LI)	m2	751
231	Extra over brickwork for brick-on-edge header course bands one course high (LI)	m	706
	<u>Waterproofing (CPAP Work Group No. 120)</u>		
	<u>Two coats emulsion bitumen emulsion waterproof coating as per approval</u>		
232	On bagged brick walls, piers, etc. (LI)	m2	2 202
	<u>Joint sealants etc</u>		
	<u>Polyurethane or other equally approved sealing compound including backing cord, bond breaker, primer, etc.</u>		
233	12 x 12mm In vertical expansion joints including raking out expansion joint filler as necessary	m	1 078
	<u>Metalwork (CPAP Work Group No. 136)</u>		
	<u>Welded Mesh Fencing or other equal approved invisible wall panels</u>		
234	2.42m High double skim clamber proof fence in panels 3.39m width with aperture size 12 x 12mm with 5x staining wires. Installed all in accordance with manufacturer's details	m	204
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
<u>Fence Posts</u>				
235	3,6m High intermediate fence post mild steel galvanised, size 85mm tapering to 45mm. Post to be built into 600mm into concrete base. Concrete base size 600 x 600 x 700mm deep with and including excavations, cart away, backfilling, etc.	No	61	
<u>Minimum 600mm high galvanised high tensile steel flat wrap razor wire fixed on 3x straining wires, straining wires fixed on metal brackets, Bracket fixed on brick wall. Installed all in accordance to manufacturer's details</u>				
236	600mm High flat wrap razor wire on top of brick walls	m	442	
<u>Minimum 600mm high galvanised high tensile steel flat wrap razor wire fixed on 3x straining wires, straining wires fixed steel posts (steel posts elsewhere measured), Installed all in accordance to manufacturer's details</u>				
237	600mm High flat wrap razor wire on top of steel fence	m	204	
<u>100mm Electro-galvanized, 2mm thick, toughened steel security spikes fixed on top of walls, fence, etc., installed all in accordance to manufacturer's details</u>				
238	100mm Electro-galvanized security spikes fixed on top of brick walls	m	442	
239	100mm Electro-galvanized security spikes fixed on top steel fence	m	204	
<u>Gates, screens, etc.</u>				
<u>Gates, etc.</u>				
240	Motorised sliding gate size 4200 x 1800mm high formed of 50 x 50 x 2mm hollow section frame and mullions and filled in with horizontal bars, with and including approved sliding track cast into 30Mpa/19mm concrete. Type G05. Tenderer's are referred to Architect's drawings annexed to these Bills of Quantities, Architect's drawing No. 132002 UKU - A - 1003 - SP10.	No	2	
Carried Forward				R
Bill No. 18 External Works				

Brought Forward				R
241	1430 x 2250mm High Titan full height free rotation turnstile by "Turnstar" or other equally approved and comprises of rotalok rotation locking mechanism and electronic control panel incorporates of anti-trap safety system, suspended Rotor technology, mechanical key override, shock absorbing rubber coupling, lockable top cover, 50mm diameter tube arms spaced 120mm apart, access control reader mounting position, rotarun perpetual base bearing, wiring side entry point, wiring bottom entry point, floor bolting positions, wall bolting positions, etc. and installed all in accordance to manufacturer's specifications. Type G04. Tenderer's are referred to Architect's drawings annexed to these Bills of Quantities, Architect's drawing No. 132002 UKU - A - 1003 - SP10.	No	1	
<u>Drainage (CPAP Work Ground No. 146 Unless Otherwise Stated)</u>				
<u>Class 34 heavy duty uPVC pipes</u>				
242	280mm Long weep pipe built into one brick walls with one end left 50mm projection in front of walls	No	1 397	
<u>DRIVEWAY AND PARKING AREA</u>				
<u>(CPAP WORK GROUP NO. 154 UNLESS OTHERWISE STATED)</u>				
<u>Excavation other than bulk</u>				
243	Excavate to reduced level	m3	2 675	
<u>Extra over all excavations for loading, carting and dumping surplus excavated material, rubble, etc. (no allowance made for increase in bulk)</u>				
244	Off site to a dumping site to be found by the Contractor.	m3	2 675	
<u>Keeping excavations free of water</u>				
245	Keeping excavations free of all water other than subterranean water	Item		
Carried Forward				R
Bill No. 18 External Works				

Brought Forward			R
<u>Compaction of surfaces</u>			
246	Compaction of ground surface under pavings, roads etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density	m2	4 718
<u>Base course of earth filling supplied by the contractor under pavings, roads, etc</u>			
247	Construct 150mm thick base layer of G7 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density.	m3	1 344
248	Construct 150mm thick base layer of G5 materials obtained from commercial sources, compacted to a density of at least 95% Mod. AASHTO density.	m3	708
249	Construct 125mm thick base layer of G2 materials obtained from commercial sources, compacted to a density of at least 98% Mod AASHTO density.	m3	623
<u>Testing of material and filling</u>			
Descriptions of earth filling, compaction, etc shall be deemed to include for all necessary testing required in accordance with the SABS 1200 series			
The items of testing given below are for additional testing which may be required by the Engineer over and above those required in accordance with the SABS 1200 series			
<u>Additional tests required by Engineer</u>			
250	Maximum dry density and optimum moisture content test in accordance with Method A7 of TMH 1	No	160
251	Atterberg limits test in accordance with methods A2 to A4 of TMH 1	No	107
252	In-situ dry density test in accordance with method A10(b) of TMH 1	Item	
<u>Weedkiller mixed with water and applied at a rate of 100grams/m2</u>			
253	Under parking area, etc. (LI)	m2	4 718
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Bituminous premix road surfacing</u>			
254	Prime and lay 30mm thick. Bitumen 9.5mm Stone, laid compacted, to falls	m2	4 718
<u>Precast concrete finished smooth on exposed surfaces including bedding, jointing and pointing</u>			
255	Kerb (SABS 927 fig 6) 125 x 260mm high with 150 x 150 x 300mm unreinforced concrete haunching at back of each joint including excavation, backfilling, etc	m	635
256	Kerb (SABS 927 fig 6) 125 x 260mm high with 150 x 150 x 300mm unreinforced concrete haunching at back of each joint circular on plan not exceeding 4m radius formed with short lengths of straight kerb including excavation, backfilling, etc	m	47
<u>Paintwork</u>			
<u>Prepare and apply one coat non reflective road marking paint at a nominal rate of 0.42l/m² on bituminous road surfacing, pre-cast concrete paving blocks, etc.</u>			
257	100mm Wide solid lines to parking demarcation bays, etc.	m	1 088
258	1,0m Long directional arrows	No	20
259	1,3m Long letters to 'STOP' sign, etc.	No	3
260	11 x 3,4m Wide pedestrian walkway	No	1
261	Disabled parking bay sign approximately 1,2m high	No	6
262	Painted white parking numbers	No	145
<u>DOMESTIC AND FIRE WATER STORAGE TANKS AND PUMPS</u>			
<u>Metalwork (CPAP Work Group No. 136)</u>			
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
<u>Hot Dipped Galvanised Sundry Steelwork</u>				
263	Supply, delivery, installation, connection, testing & commissioning of sectional steel 60kL effective capacity dedicated water storage tank for adequate supply of domestic water system including flanges, connections, fittings, hangers, brackets, vortex inhibitor, water level indicator, water inlets, water outlets to domestic pumps, catladder, access hatches, valves, drains, etc. complete. Reference to be made to Wet Services Drawing D3925-DW-A0-02 and technical specification when pricing, annexed to these bills of quantities.	No	1	
264	Supply, delivery, installation, connection, testing & commissioning of Cylindrical 144KL effective capacity dedicated fire storage tank for adequate supply of fire system including flanges, connections, fittings, hangers, brackets, vortex inhibitor, water level indicator, water inlets, water outlets to fire pumps, catladder, access hatches, valves, drains, etc complete. Reference to be made to DWG D0000-MF-A1-04 and technical specification when pricing, annexed to these bills of quantities.	No	1	
<u>Mechanical (CPAP Work Group No. 170)</u>				
<u>Supply and deliver the following booster pumps (KSB or other equally approved), complete with all with electrical connection to isolator, internal pump house reticulation piping- and drain piping, electrical control wiring, brackets, supports, steel bases, control panel and all necessary accessories, as per the specification and manufacturer's recommendation.</u>				
265	Supply, delivery, installation, connection, testing & commissioning of complete domestic water Bi-Plex Electric pump set including valves, vacuum breaks, auto air vents, etc. Pumps to operate Duty and Standby. Each Pump sized for 270 L/m @2.18bar	No	1	
266	Supply, delivery, installation, connection, testing & commissioning of complete fire water (Electric) pump set including valves, vacuum breaks, auto air vents, etc. Electric pump sized for 2400 L/m @17.53bar, Electrical Jockey pump sized for 60 L/min @17.53bar)	No	1	
Carried Forward				R
Bill No. 18 External Works				

Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4

Brought Forward			R
267	Supply, delivery, installation, connection, testing & commissioning of pump control panels	Item	
268	Supply, delivery, installation, connection, testing & commissioning of all electrical work in the pump house	Item	
269	Allow for the production and fixing of all statutory signs on chromadek or other equally approved material	Item	
270	Allow for all auxiliary equipment as specified in this document as well as the SANS 10287 code of practice, incl. valves, fittings supports, fire detection, ventilation, sprinkler protection to pump house, etc.	Item	
271	Supply, delivery, installation, connection, testing & commissioning of trunk mains from pump house to building	Item	
272	Supply, delivery, installation, connection, testing & commissioning of trunk mains from pump house to installation of control valves	Item	
<u>Pipework, valves, fittings, etc.</u>			
273	150mm Butterfly valves	No 6	
274	2500kPa Pressure gauge	No 16	
275	Domestic water pump test meter	No 1	
276	Fire water pump test meter	No 1	
277	100mm Butterfly valve	No 4	
278	150mm Non-return valve	No 4	
279	150mm Expansion joints	No 8	
280	150mm Strainer	No 2	
281	150mm Gate valve	No 6	
282	250mm Gate valve	No 4	
283	Vortex impellers	No 4	
284	Pressure switch	No 10	
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
285	20mm Ball valve	No	10	
286	20mm Check valve	No	8	
287	50mm Rubber expansion joints	No	4	
288	50mm Check valve	No	2	
289	50mm Ball valve	No	2	
290	Membrane vessel	No	2	
291	250mm Brass elbows	No	3	
292	150mm Brass elbows	No	4	
293	100mm Brass elbows	No	5	
294	250mm Brass tee-pieces	No	1	
295	150mm Brass tee-pieces	No	2	
296	250mm Brass straight piping	No	18	
297	150mm Brass straight piping	No	30	
298	100mm Brass straight piping	No	8	
299	250mm Black mild steel elbows	No	3	
300	150mm Black mild steel elbows	No	4	
301	100mm Black mild steel elbows	No	5	
302	250mm Black mild steel tee-pieces	No	1	
303	150mm Black mild steel tee-pieces	No	2	
304	250mm Black mild steel straight piping	No	18	
305	150mm Black mild steel straight piping	No	30	
306	100mm Black mild steel straight piping	No	8	
<u>WATER TANK BASE AND PLINTH</u>				
Carried Forward				R
Bill No. 18 External Works				

Brought Forward			R
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation in earth not exceeding 2m deep</u>			
307	Reduced levels under floors (LI)	m3	22
<u>Extra over all excavations for carting away</u>			
308	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	22
<u>Risk of collapse of excavations</u>			
309	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	16
<u>Compaction of surfaces</u>			
310	Compaction of ground surface under floors, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	54
<u>Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers</u>			
311	Under floors, steps, pavings, etc. (LI)	m3	8
<u>Prescribed density tests on filling</u>			
312	Modified AASHTO Density tests	No	4
<u>Approved brand of anti-termite soil poison applied by a Registered Pest Control company and guaranteed against termite infestation for ten years</u>			
313	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	64
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Reinforced concrete cast against excavated surfaces</u>			
Carried Forward			R
Bill No. 18 External Works			

**Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4**

	Brought Forward			R
	<u>30MPa/19mm concrete</u>			
314	Surface base (LI)	m3	14	
	<u>Reinforced concrete cast against on/in formwork</u>			
	<u>30MPa/19mm concrete</u>			
315	Upstand beams (Plinth) (LI)	m3	8	
	<u>Test cubes</u>			
316	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	4	
	<u>Concrete sundries</u>			
	<u>Finishing top surfaces of concrete smooth with a wood float</u>			
317	Surface beds, slabs, etc. (LI)	m2	54	
	<u>40MPa Non-shrink grout:</u>			
318	Bedding approximately 300 x 40mm thick	m	52	
	<u>Formwork (CPAP Work Group No. 111)</u>			
	<u>Smooth formwork to sides</u>			
319	Upstand beams (Plinth) (LI)	m2	46	
320	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	42	
	<u>Reinforcement (CPAP Work Group No. 114)</u>			
	<u>High tensile steel reinforcement to structural concrete work</u>			
321	Bars of various diameters (LI)	t	2,16	
	<u>Waterproofing (CPAP Work Group No. 120)</u>			
	<u>One layer of 375 micron waterproof sheeting sealed at laps as per approval</u>			
322	Under surface beds including sides (LI)	m2	64	
	Carried Forward			R
	Bill No. 18			
	External Works			

Brought Forward			R
<u>Metalwork (CPAP Work Group No. 136)</u>			
<u>80 x 8mm Thick heavy duty GMS plate fixed on to reinforced concrete plinth</u>			
323	4980mm long flat plate	No	10
<u>SAND, OIL AND GREASE TRAP</u>			
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation In earth not exceeding 2m deep</u>			
324	Holes (LI)	m3	9
<u>Extra over all excavations for carting away</u>			
325	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	8
<u>Risk of collapse of excavations</u>			
326	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	17
<u>Compaction of surfaces</u>			
327	Compaction of ground surface under floors, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	7
<u>Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density</u>			
328	Backfilling to trenches, holes, etc. (LI)	m3	1
<u>Prescribed density tests on filling</u>			
329	Modified AASHTO Density tests	No	2
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
<u>Approved anti-termite soil insecticide applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years including forming and poisoning shallow furrows along sides of foundation walls, etc., filling in and ramming:</u>				
330	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	24	
<u>Concrete (CPAP Work Group No. 110)</u>				
<u>Reinforced concrete cast against excavated surfaces</u>				
<u>30MPa/19mm concrete</u>				
331	Surface base (LI)	m3	2	
<u>Reinforced concrete cast against on/in formwork</u>				
<u>30MPa/19mm concrete</u>				
332	Slabs (LI)	m3	1	
<u>Test cubes</u>				
333	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	2	
<u>Concrete sundries</u>				
<u>Finishing top surfaces of concrete smooth with a wood float</u>				
334	Surface beds, slabs, etc. (LI)	m2	13	
<u>Formwork (CPAP Work Group No. 111)</u>				
<u>Smooth formwork to soffits</u>				
335	Slabs, propped up not exceeding 3.5m high (LI)	m2	6	
<u>Smooth formwork to sides</u>				
336	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m	39	
Carried Forward				R
Bill No. 18 External Works				

Brought Forward				R
<u>Boxing in smooth formwork to form</u>				
337	Extra over formwork to form opening size 225 x 225mm through 180mm thick slab (LI)	No	2	
338	Extra over formwork to form opening size 550mm diameter through 180mm thick slab (LI)	No	3	
<u>Movement Joints, Etc.</u>				
<u>Two sheets of tempered hardboard (smooth sides together) to form slip joint between abutting horizontal concrete and brickwork surfaces</u>				
339	Not exceeding 300mm wide (LI)	m	14	
<u>Reinforcement (CPAP Work Group No. 114)</u>				
<u>High tensile steel reinforcement to structural concrete work</u>				
340	Bars of various diameters (LI)	t	0,15	
<u>Fabric reinforcement</u>				
341	Type Ref. 193 fabric reinforcement in concrete surface beds, slabs, etc. (LI)	m2	7	
<u>Masonry (CPAP Work Group No. 116)</u>				
<u>Brickwork of NFX bricks in class II mortar</u>				
342	Half brick walls (LI)	m2	3	
343	One brick walls (LI)	m2	9	
<u>Brickwork sundries</u>				
<u>2.5mm Galvanised brickwork reinforcement</u>				
344	75mm Wide reinforcement built in horizontally (LI)	m	12	
345	155mm Wide reinforcement built in horizontally (LI)	m	35	
<u>Waterproofing (CPAP Work Group No. 120)</u>				
Carried Forward				R
Bill No. 18 External Works				

Ikageng New Police Station
Portion 4 of ERF 6934 Ikageng Ext. 4

Brought Forward			R
<u>One layer of 375 micron Brikrip DPC embossed damp proof course as per approval</u>			
346	In walls (LI)	m2	3
<u>One layer of 375 micron waterproof sheeting sealed at laps as per approval</u>			
347	Under surface beds (LI)	m2	7
<u>Drainage (CPAP Work Group No. 146 Unless Otherwise Stated)</u>			
<u>uPVC pipes cast into concrete slabs, fixed to soffit and walls, or chased into walls, chased into concrete, etc. in accordance with manufacturers specifications</u>			
348	110mm Pipes (LI)	m	9
<u>Extra over uPVC pipes for:</u>			
349	110mm Bend (LI)	No	5
350	110mm Junction (LI)	No	2
<u>Gratings, covers, etc.</u>			
351	225 x 255mm, cast iron cover and frame including	No	2
352	550mm Diameter x 176kg, type 2A cast iron cover and frame including	No	3
<u>COVERED WALKWAY</u>			
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation in earth not exceeding 2m deep</u>			
353	Bases (LI)	m3	213
<u>Extra over all excavations for carting away</u>			
354	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	110
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Risk of collapse of excavations</u>			
355	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	710
<u>Compaction of surfaces</u>			
356	Compaction of ground surface under bases, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	213
<u>Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density</u>			
357	Backfilling to trenches, holes, etc. (LI)	m3	103
<u>Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers</u>			
358	Under bases, etc. (LI)	m3	32
<u>Prescribed density tests on filling</u>			
359	Modified AASHTO Density tests	No	23
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Unreinforced concrete cast against excavated surfaces</u>			
<u>15MPa/19mm concrete</u>			
360	Surface blinding under bases (LI)	m3	11
<u>Reinforced concrete cast against excavated surfaces</u>			
<u>30MPa/19mm concrete</u>			
361	Base (LI)	m3	64
<u>Reinforced concrete cast against on/in formwork</u>			
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>30MPa/19mm concrete</u>			
362	Stub columns (LI)	m3	4
<u>Test cubes</u>			
363	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	11
<u>40Mpa Non-shrink grout</u>			
364	Bedding approximately 25mm thick under base plate including chamfered edges all round	m2	6
<u>Holding down bolts, etc</u>			
365	Set out and embed 100mm long M12 holding down bolts with 30 x 30 end plates in top of concrete in exact position	No	148
<u>Formwork (CPAP Work Group No. 111)</u>			
<u>Smooth formwork to sides</u>			
366	Stub columns (LI)	m2	71
<u>Reinforcement (CPAP Work Group No. 114)</u>			
367	Various diameter bars in high tensile steel reinforcement (LI)	t	8,50
<u>Roof Coverings, Etc. (CPAP Work Group No. 124)</u>			
<u>0.6mm thick colour coated galvanised sheet metal double-interlocking concealed fix profiled roofing fixed to timber purlins (timber purlins elsewhere measured)</u>			
368	Roof covering with pitches not exceeding 25 degrees fixed at walkways.	m2	508
<u>Sundries</u>			
369	Ridge capping 550mm girth 3 times bent and notched on site to suit roof profile	m	200
Carried Forward			R
Bill No. 18 External Works			

Brought Forward		R
370	Hip capping 550mm girth 3 times bent and notched on site to suit roof profile <u>0.6mm aluminium sheet</u>	m 16
371	Lining to valleys with riveted and sealed joints, with girth not exceeding 600mm. <u>Carpentry and Joinery (CPAP Work Group No. 126)</u> <u>Pre-treatment of timber</u> This service falls within the areas defined in the National Building Regulations for treatment of timber against insect infestation / insect pest affecting softwood fixed permanently in all buildings. The regulations require that the timber be treated in terms of SABS 05 and to comply with SABS 457, 753, 754 or 1288 as relevant. Tenderer's are to make allowance in there rates. <u>Sawn softwood:</u>	m 8
372	50 x 75mm Purlins	m 652
373	50 x 228mm Rafter	m 464
	<u>Laminated Wrot Saligna</u>	
374	76 x 222mm Beams	m 434
	<u>"Everite Nutec" or other equally approved medium density pressed fibre-cement</u>	
375	15 x 255mm Fascias, including galvanised steel H-profile joiners	m 217
376	80 x 275mm Angle section barge board, including galvanised steel H-profile joiners	m 247
	<u>Metalwork (CPAP Work Group No. 136)</u> <u>Hot Dipped Galvanised Sundry Steelwork</u>	
Carried Forward		R
Bill No. 18 External Works		

Brought Forward			R
<u>Brackets, posts, etc. to roof timbers, etc.</u>			
377	100 x 100 x 3mm Hollow section post 2750mm high with 200 x 200 x 10mm thick base plate welded to one end and the other end welded to and including purpose made U-shaped bracket to suit 76 x 222mm high timber beam (Timber beam elsewhere measured) with 6 No. M8 pre-drilled holes on bracket and 4 No. M10 pre-drilled holes on base plate to suit site conditions.	No	148
<u>Plumbing an Drainage (CPAP Work Group No. 148)</u>			
<u>0.9mm Pre-coated aluminium seamless gutter colour brown with baked enamel finish, including hanger brackets, etc.</u>			
378	Purpose made 150 x 125mm Eaves gutters	m	217
379	Extra over gutter for stop end	No	16
380	Extra over gutter for corner	No	15
381	Extra over gutter for outlet	No	36
<u>0.9mm Pre-coated aluminium seamless rainwater downpipes colour brown with baked enamel finish, including holder butts, etc.</u>			
382	100 x 100mm Rainwater downpipes	m	126
383	Extra on rainwater pipe for bend	No	72
384	Extra on rainwater pipe for shoe	No	36
<u>Paintwork (CPAP Work Group No. 152)</u>			
<u>Two coats Carbolineum</u>			
385	On exposed trusses (LI)	m2	690
<u>One coat primer, one coat universal undercoat and two coats "Velvagio Polyurethane Enamel" or equal and approved paint</u>			
386	On fascia and barge boards (LI)	m	464
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
	<u>Prepare and apply one coat of zinc chromate primer one coat universal undercoat and two coats of universal SABS approved gloss enamel paint. Colour to be chosen by Architect.</u>		
387	On steel posts (LI)	m2	163
	<u>COVERED CARPORTS</u>		
	<u>Earthworks (CPAP Work Group No. 104)</u>		
	<u>Excavation in earth not exceeding 2m deep</u>		
388	Bases (LI)	m3	106
	<u>Extra over all excavations for carting away</u>		
389	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	54
	<u>Risk of collapse of excavations</u>		
390	Sides of trench and hole excavations exceeding 1,5m and not exceeding 3m deep	m2	302
	<u>Compaction of surfaces</u>		
391	Compaction of ground surface under bases, etc. including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 93% mod AASHTO density	m2	106
	<u>Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density</u>		
392	Backfilling to trenches, holes, etc. (LI)	m3	52
	<u>Earth filling of G5 material supplied by contractor from commercial sources in accordance with SABS 1200 DM compacted to 98% Mod AASHTO density in 150mm thick layers</u>		
393	Under bases, etc. (LI)	m3	16

Carried Forward

Bill No. 18
External Works

R

R.

41

Handwritten signature

Brought Forward		R	
<u>Prescribed density tests on filling</u>			
394	Modified AASHTO Density tests	No	11
<u>Concrete (CPAP Work Group No. 110)</u>			
<u>Unreinforced concrete cast against excavated surfaces</u>			
<u>15MPa/19mm concrete</u>			
395	Surface blinding under bases (LI)	m3	5
<u>Reinforced concrete cast against excavated surfaces</u>			
<u>30MPa/19mm concrete</u>			
396	Base (LI)	m3	32
<u>Reinforced concrete cast against on/in formwork</u>			
<u>30MPa/19mm concrete</u>			
397	Stub columns (LI)	m3	3
<u>Test cubes</u>			
398	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	6
<u>40Mpa Non-shrink grout</u>			
399	Bedding approximately 25mm thick under base plate including chamfered edges all round	m2	2
<u>Holding down bolts, etc</u>			
400	Set out and embed 100mm long M12 holding down bolts with 30 x 30 end plates in top of concrete in exact position	No	54
<u>Formwork (CPAP Work Group No. 111)</u>			
<u>Smooth formwork to sides</u>			
401	Stub columns (LI)	m2	65
Carried Forward		R	
Bill No. 18 External Works			

Brought Forward				R
<u>Reinforcement (CPAP Work Group No. 114)</u>				
402	Various diameter bars in high tensile steel reinforcement (LI)	t	4,38	
<u>Structural Steel (CPAP Work Group No. 134)</u>				
<u>Welded columns in single lengths with flat section base, top, bearer and connection plates bolted to reinforced concrete at bottom and parallel flanged channel at top</u>				
403	100 x 100 x 4 SHS Column	t	1,05	
<u>Welded beams in single lengths with flat section bearer and connection plates bolted to columns</u>				
404	200 IPE Main Beam	t	3,55	
<u>Welded purlins, bracing, trimmers, eaves runner, etc. with flat section connection plates bolted to steel</u>				
405	175 x 50 x 20 x 3 CFLC purlins	t	4,31	
406	40 x 40 x 3 Angle purlins (sag bar)	t	0,27	
407	40 x 40 x 4 Angle bracing	t	1,75	
<u>Sundry Steelwork</u>				
408	Cleats, plates, gussets, connectors, etc.	t	3,04	
<u>Paintwork</u>				
<u>Remove all grease and oil by washing with a water emulsifiable solvent degreaser and rinsing with potable water, dry abrasive blast to rear white metal in accordance with Sa 2.5 of the International Standard ISO 850-1 to obtain a surface profile of 25 - 75 microns and apply one coat Inter guard 269 galvanizing primer and two coats Interthane 990 re-coatable polyurethane</u>				
409	On columns, beams, purlins, angles, etc.	t	10,93	
410	On cleats, plates, gussets, connectors, etc.	t	2,86	
Carried Forward				R
Bill No. 18 External Works				

Brought Forward			R
<u>Roof Coverings, Etc. (CPAP Work Group No. 124)</u>			
<u>Profiled Metal Sheetting and Accessories</u>			
<u>0.6mm thick colour coated galvanised sheet metal double-interlocking concealed fix profiled roofing fixed to steel purlins (steel purlins elsewhere measured)</u>			
411	Roof covering with pitch not exceeding 25 degrees	m2	738
<u>Sundries</u>			
412	Barge flashing, 550mm girths	m	149
413	Fascia flashing, 550mm girths	m	125
<u>Plumbing an Drainage (CPAP Work Group No. 148)</u>			
<u>0.9mm Pre-coated aluminium seamless gutter colour brown with baked enamel finish, including hanger brackets, etc.</u>			
414	Purpose made 150 x 125mm Eaves gutters	m	125
415	Extra over gutter for stop end	No	4
416	Extra over gutter for outlet	No	14
<u>0.9mm Pre-coated aluminium seamless rainwater downpipes colour brown with baked enamel finish, including holder butts, etc.</u>			
417	100 x 100mm Rainwater downpipes	m	42
418	Extra on rainwater pipe for bend	No	28
419	Extra on rainwater pipe for shoe	No	14
<u>RAINWATER TANKS AND BASES</u>			
<u>Earthworks (CPAP Work Group No. 104)</u>			
<u>Excavation in earth not exceeding 2m deep</u>			
420	Holes (LI)	m3	88
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Extra over all excavations for carting away</u>			
421	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor	m3	10
<u>Risk of collapse of excavations</u>			
422	Risk of collapse of sides of trench excavations exceeding 1.5m deep	m2	118
<u>Compaction of surfaces</u>			
423	Compaction of ground surface under floors compacted to 95% Mod. AASHTO density	m2	90
<u>Earth filling obtained from excavations and/or prescribed stock piles on site, compacted to 95% Mod AASHTO density</u>			
424	Earthfilling from the excavations as backfilling to trenches compacted to 95% Mod. AASHTO density (LI)	m3	78
<u>Prescribed density tests on filling</u>			
425	Modified AASHTO Density tests	No	13
<u>Approved anti-termite soil insecticide applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years including forming and poisoning shallow furrows along sides of foundation walls, etc., filling in and ramming:</u>			
426	Under floors, sides, etc. including forming and poisoning shallow furrows against foundation walls etc., filling in furrows and ramming (LI)	m2	208
<u>Concrete (CPAP Work Group No.110)</u>			
<u>Reinforced concrete cast against excavated surfaces</u>			
<u>30MPa/19mm concrete</u>			
427	Surface bases (LI)	m3	23
428	Surface bed (LI)	m3	7
<u>Reinforced concrete cast against on/in formwork</u>			
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>30Mpa/19mm Reinforced concrete</u>			
429	Filling to cavities of hollow walls (LI)	m3	12
<u>Test Cubes</u>			
430	Making and testing set of three 150 x 150 x 150mm concrete strength test cube (Provisional)	No	7
<u>Concrete Sundries</u>			
<u>Finishing top surfaces of concrete smooth with a wood float</u>			
431	Surface beds, slabs, etc. (LI)	m2	155
<u>Rough Formwork (CPAP Work Group No. 111)</u>			
432	Strip footings (Provisional) (LI)	m2	60
<u>Reinforcement (CPAP Work Group No. 114)</u>			
<u>Mild and high tensile steel reinforcement to structural concrete work</u>			
433	Various diameter bars (LI)	t	3,33
<u>Fabric reinforcement</u>			
434	Type ref. 193 fabric reinforcement in concrete surface beds, slabs, etc. (LI)	m2	65
<u>Masonry (CPAP Work Group No. 116)</u>			
<u>Brickwork of NFP bricks in class II mortar</u>			
435	One brick walls (LI)	m2	42
436	330mm Hollow walls of two half brick skins, including wire ties, to receive concrete infill (Concrete infill elsewhere measured) (LI)	m2	100
<u>Brickwork sundries</u>			
<u>2.5mm Galvanised brickwork reinforcement</u>			
437	155mm Wide reinforcement built in horizontally (LI)	m	949
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>Brickwork sundries</u>			
<u>Bagging of 1:3 cement and sand mixture</u>			
438	On brick walls, piers, etc. (LI)	m2	110
<u>Face brickwork</u>			
<u>"Agate" travertine FBX or other equally approved face bricks pointed with tinted recessed horizontal and vertical joints</u>			
439	Extra over brickwork for face brickwork wall (LI)	m2	110
440	Extra over brickwork for brick-on-edge header course bands one course high (LI)	m	110
<u>Waterproofing (CPAP Work Group No. 120)</u>			
<u>Two coats emulsion bitumen emulsion waterproof coating as per approval</u>			
441	On bagged brick walls, piers, etc. (LI)	m2	110
<u>Plumbing (CPAP Work Group No. 148)</u>			
<u>Polyethylene rainwater tanks, etc.</u>			
442	5000 Litres "JoJo" rainwater tank or other equally approved, with 100 x 100mm opening for downpipe from gutter including 50mm diameter overflow opening and outlet union for 20mm tap (tap elsewhere measured) and place in position on plinth and secure with twisted double strand 4mm galvanised wire.	No	10
<u>Taps, valves, etc.</u>			
443	Hose bib tap, brass including 3/4 hose union, etc. (Code: COB-208-20)	No	10
<u>Plastering (CPAP Work Group No. 142)</u>			
<u>Screeds wood floated, on concrete</u>			
444	Average 170mm thick on floors to falls (LI)	m2	27
<u>LANDSCAPING</u>			
Carried Forward			R
Bill No. 18 External Works			

Brought Forward			R
<u>(CPAP WORK GROUP NO. 104 UNLESS OTHERWISE STATED)</u>			
<u>Ground preparation</u>			
445	Site clearance	m2	4 543
446	Rip and prepare areas to receive planting/lawn/seeding	m2	4 543
<u>Topsoil, compost, lime and fertilizer</u>			
447	Import topsoil for planting/lawn/seeding areas (100mm) (LI)	m3	454
448	Final shaping of planting/lawn/seeding areas (LI)	m2	4 543
449	Compost to planting areas (50mm) (LI)	m3	227
450	Fertilizer to planting/lawn beds (50g/m ²) (LI)	kg	227
<u>Grassing, Trees, etc</u>			
<u>Supply and plant the following plants</u>			
451	Lampranthus at the rate of five per square metre (LI)	m2	118
452	Chondropetalum at the rate of three per square metre (LI)	m2	97
453	Heteropyxis Natalensis 200mm high (LI)	No	37
454	Podocarpus Henkel 200mm high (LI)	No	33
<u>Supply and plant the following grass</u>			
455	Grass planting to level areas with Cynadon Dactylon continuous root planting described including all necessary fertiliser, weed killer, watering and rolling, mowing, etc. (LI)	m2	4 543
<u>Maintenance</u>			
456	Maintenance of grassed areas for a period of 4 months (total area approximately 4543m ²) including regularly cutting, weeding and irrigating as necessary (LI)	Item	
Carried Forward			R
Bill No. 18 External Works			

Brought Forward				R
<u>Outdoor furniture</u>				
457	"Builders Merchant" or other equally approved quality garden concrete benches (two number) and table (one number), fixed to ground surfaces with approved epoxy glue (LI)	No	25	
458	"SA Bins" or other equally approved 500mm Diameter x 740mm high concrete ribbed round litter bin (grey colour finish), fixed to ground surfaces with approved epoxy glue (LI)	No	17	
Carried to Summary				
Bill No. 18 External Works				