

C2.2. PRICING SCHEDULES / BILLS OF QUANTITIES (BoQ)

Item No	Description	Minimum threshold for Local content	Unit of measure	Quantity	Total cost
1	Submission of SHE file for induction		Item	Item	
2	Install a low voltage feeder cable (estimated size 95mm2x4core PVCPCSWAPVC copper) of approximately 272 metres from the Zwartkopjes Chlorine Plant mini substation to the distribution board in the Pipe Fabrication Plant	90%	Item	Item	
3	Install a suitably rated circuit breaker and low voltage feeder cable (estimated size 35mm2x4core PVCPCSWAPVC copper) of approximately 144 metres from the distribution board in the Fabrication Plant to the distribution board in the Paint Store	90%	Item	Item	
4	Install a suitably rated circuit breaker and low voltage feeder cable (estimated size 25mm2x4core PVCPCSWAPVC copper) of approximately 100 metres from the distribution board in the Paint Store to the distribution board in the Green Area room	90%	Item	Item	
5	Install earth cables with all low voltage cables mentioned above		Item	Item	
6	Allow for approximately 300 metres length of 1-metre-deep trenching and protection of cable with concrete		Item	Item	

7	Site Clearence		Item	Item	
SUB TOTAL					
VAT					
TOTAL					