

	<b>REFURBISHMENT OF ROODEPOORT STATION- SOUTH GAUTENG REGION: RFQ NO:</b>	<b>Unit</b>	<b>Quantity</b>	<b>Rate</b>	<b>Amount</b>
<b>ITEM NO</b>	<p><b><u>SECTION 1</u></b></p> <p>BILL NO. 1 PRELIMINARIES <b><u>BUILDING AGREEMENT AND PRELIMINARIES</u></b></p> <p>The JBCC Series 2000 Principal Building Agreement (July 2007 edition 5.0) prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter</p> <p>The Preliminaries for use with the JBCC Series 2000 Principal <b>Building Agreement (May 2005 edition) prepared by the Joint Building Contracts Committee, shall be deemed to be</b> incorporated in these bills of quantities Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof These clauses are hereinafter referred to by clause number <b>and heading only. Where standard clauses or alternatives are <u>not entirely applicable to this contract such modifications,</u></b> corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents</p> <p>SECTION A: PRINCIPAL BUILDING AGREEMENT 1 Clause 1.0 - Definitions and interpretation Interpretation (A1-A7)</p>				
<b>1</b>	<b>SECTION B: GENERAL PRELIMINARIES</b>				

	1. General Preliminaries to Include Appointment of Local CLO, site clearance of trees, shrubs, access vegetation and make good	Item	1		
2	<b><u>DEMOLITIONS,ALTERATIONS ETC</u></b>  Allow a sum to include 7.5% attendance and handling fee for demolishing of existing structures and take off site, then make good at platforms, Ticket office, existing ablutions, existing retail area, unused stalls, Structural Steel, Old Steel Poles along the rails.	sum	85000		
	Attendance		7,5%		
	Profit		7,5%		
2	<b><u>TICKET OFFICE, ABLUTIONS</u></b>  Allow a sum to include 7.5% of attendance and handling fee to design, supply and full fitout of ticket office proposed for functionality. The proposal as per brief to have selling counter, Bullet Proof Window, Turnstiles, tiling, ceiling, etc.	sum	800000		
	Attendance		7,5%		
	Profit		7,5%		
3	<b><u>SIGNAGE</u></b>  External signage  500 x 150mm High double-sided ceiling mounted directional sign anodized aluminium female and male ablutions pictogram door sign, suspended from ceiling grids with brass chains. Minimum of 2,1m above finished floor level.  Allow to supply and fit station signage  Station name, to match the existing	No.	2		
		No	2		
4	<b><u>PROFILED METAL SHEETING AND</u></b>				

	<b><u>ACCESSORIES</u></b>				
	ABLUTIONS AND PLATFORM AREAS (Re-measure)				
	Roof covering with pitch not exceeding 25 degrees				
	0.58mm "Klip Lok 700" Z275 spelter galvanised				
	ribbed sheet steel with "Chromadek" finish on	m2	150		
	side in single lengths and accessories, fixed to				
	timber purlins using SL 700 approved clips and				
	fasteners all in accordance with manufacturer's				
	recommendations and specifications.				
4	<b><u>PLUMBING AND DRAINAGE</u></b>				
	Drainage and Water Connection				
	Allow a sum on all UPVC Pipes for drainage at				
	Ablutions and Kitchen on existing buildings and				
	Sewer connection as per below				
	<b><u>Sanitary plumbing and Manhole covers</u></b>				
	Allow a sum to include 7.5% attendance and				
	handling fee for all sanitary Plumbing work on the				
	public ablutions, Ticket office and the at the				
	Platform				
		sum	130000		
	Attendance		7,5%		
	Profit		7,5%		
	Sewer connection				
	Cutting into sides of existing manhole chamber for				
	and connecting 110mm pipe including inserting				
	110mm channel junction and making good				
	concrete benching	Item	1		
5	<b><u>SECURITY GATES</u></b>				
	<b>Supply and install Burglar door</b>				
	815 x 2100mm high Heavy duty Burglar door and				
	frame with 16mm steel round bar and 40 x 40 x				
	2.5mm square tubing as per attached drawing for	no	4		
	single door				
8	<b><u>STEEL ROLLER SHUTTERS</u></b>				

	Roll-Up solid galvanised, SABS 1461, & epoxy coated M/S manually hand chain operated push-up roller shutter for maximum opening 3000 x 3000mm high with standard bottom rail, 75 x 0.8mm thick end-locked slats, 120mm extra-wide tamper proof guides, 4.5mm end plates, closed shaft and 2 x slidebolts, extruded with Aluminium Tbar & Astragal rubber weather seal. Including galv. cover box and powder coated components incl. door curtain, end plates, cover box, guides & T-bar. Door fixed to brick, concrete or structural steel jambs and concrete or steel lintel over. Contractor to provide cavity of 160mm x 120mm for recessing guides				
	Manual <b>hand chain</b> Push-up Roller Shutters, for openings not exceeding 3000mm x 2500mm high.	no	2		
	<b>Supply and install Burglar windows</b> 600mm W x 600mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles.	No	8		
	1200mm W x 600mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles.	No	2		
	300mm W x 900mm H Box windows guard constructed with 5mm of expanded metal and 50 x 50 x 6mm equal angles.	No	2		
9	<b><u>FENCE AND GATES</u></b>				
	Supply and Install Steel Pallisade fence	m	200		
	Supply and fit – replace heavy duty gate , with heavy duty industrial motor which allows to be operated manually also., allow all necessary fittings to be installed to the total completion of the job.	no	1		
10	<b><u>PAINTWORK</u></b>				

	Allow a sum for All paintwork internal and external walls , steel work, doors, etc etc.	walls	m2	900			
		steel	m2	600			
11	<b><u>ELECTRICAL WORK</u></b>						
	Allow a sum on Electrical Works and reticulation to include all power supply to the station and connection from municipal supply to iclude but not limited to High mast pole street light fitting, The luminaire to consists of a separate lamp, control gear and spigot compartment. The control gear housing to be separated from the lamp housing for thermal reasons. To be designed to operate 70/400W mercury vapour and 70/400W high-pressure sodium/metal halide lamp.						
			sum	215000			
		Attendance		7,5%			
		Profit		7,5%			
	Supply and install 100KV a backup generator		No	1			
12	<b><u>MECHANICAL WORK</u></b>						
	Allow a sum on Mechanical Works,Inclusive of Air conditioning and Fire water reticulation around the station to include Fire hydrants and signage.						
			sum	175000			
		Attendance		7,5%			
		Profit		7,5%			
13	<b><u>ASPHALT TO PLATFORMS</u></b>						
	Prepare platforms to receive Asphalt(Resurfacing) to include all Yellow Markings		m2	700			
14	<b><u>PAVING</u></b>						
	60mm interlocking paver blocks as per PRASA spec		m2	200			

15	<b><u>STEEL WORK</u></b>				
	Allow a sum for bullustrade and handrails to staircases and Platform furniture and dustbins, include 7.5% handling and managent fee, all works to remeasured				
		Sum	130000		
	Attendance		7,5%		
	Profit		7,5%		
	<b>CONSTRUCTION COST</b>				
	<b>FINAL SUMMARY</b>				
	10 % Contingency fund				
	<b>SUB TOTAL</b>				
	ADD VAT @ 15%				
	<b>TOTAL AMOUNT</b>				