


TRANSNET LIMITED
5. ACTIVITY SCHEDULE:

All prices **exclude Vat** and additional items listed (with prices) shall be clearly labelled as optional or essential.

Item no.	Item	Quantity	Price
5.1	Health, safety and Environmental Management compliance	1	
5.2	Passage (Room 2)		
5.2.1	Supply and install tiles 600x600, area 1,56mX1,31m by the passage entrance. use first grade decorative tiles to enhance good looks for the area.	1	
5.2.2	Prepare and paint the wall 8,9mX2.8m	1	
5.3	Room 1.		
5.3.1	Prepare and paint the walls of the office dimensions 4mx3mx2.8m(h).	1	
5.3.2	Repair by removing the existing, fit new skirting board.	1	
5.4	Kitchen area (Room4)		
5.4.1	Clean ceiling panels 6mX5m	1	
5.4.2	Clean floor and wall using tile cleaner 6mX5mX2.8(h)	1	
5.5	Counter Area (Room 2)		
5.5.1	Use M150 concrete blocks to brickup the kitchen counter (5.1m long x 0.9m high). Plaster, prime and paint with 2 coats. Build the counter base support after every 1m length of the wall	1	
5.5.2	Install a granite top, bullnose edges on both ends, 5.1m (l) x 1m (w) x 0.03m (thickness).	1	
5.5.3	Repair cladding 9m x 3m.	1	
5.5.4	Repair cladding 3m x 4,6m x 2	2	
5.5.5	Clean the tiles with the tile cleaner 4mX2.8m	1	
5.5.6	Prepare walls and paint 3.3m X 2.8m	1	
5.5.7	Replace dry wall prime and paint 1.72mX260mmX2.8m(h) using 2 coats of WAA8.	2	
5.5.8	Paint ceiling board in the counter area 8.30mX8.2m	1	
5.6	Dinning area(Room 5)		
5.6.1	Scrape, skim, prime and paint wall with 2 coats of WAA8. The dimensions are 27m (l) x 9m (w) x 4m (h).	1	

5.6.2	Remove all damaged floor tiles and supply, install new floor tiles and skirting, area 9m x 27m (used first grade 600mmX600mm)	1	
5.6.3	Prepare and paint ceiling in dining area 27mX15m use 2 coats of 110-10-020	1	
5.7	Veranda		
5.7.1	Repair 5 steel poles with 110mm (diameter, 3mm thick) poles. See figure 3 for suitable kind of poles. Poles shall be hot dip galvanized, in accordance with SANS 121. Paint all poles in black paint Duram 52-90-001.	5	
5.7.2	Remove all damaged tiles and supply, install new tiles area 4m x 38m (used first grade 600mmX600mm)	1	
5.7.3	Repair (3,6 x 1200X15qty) damaged ceiling rhino boards and secure. Use rhinolite to skim and level. Paint the ceiling (4m x 38m) with 2 coats of white paint (use Duram 110-10-020 Wall & Ceiling Paint).	15	
5.8	Roof		
5.8.1	Replace 120m of gutters. Use bronze aluminum seamless gutter	1	
5.8.2	Replace 7 aluminum down pipe 7 meters long	1	
5.8.3	Repair, scrape and paint Facia board 120meters long	1	
5.8.4	Seal the entire region 50meters long using membrane.	1	
5.8.5	Seal between building and Veranda 50meters long using membrane	1	
5.8.6	Repair leaks in the veranda between pillar 1 and pillar 2 using a membrane.	3	

5.8.7	Repair roof leaks in the veranda between pillar 4 and pillar 6 using a membrane.	4	
5.8.8	Repair roof leak in the veranda between pillar 8 and pillar 9 using a membrane.	2	
5.9	Walls		
5.9.1	High pressure clean external face brick walls using mild detergent area 10mX50m	1	

Name: Khethu Nzuz Designation: Engineering Technician Signature and date:  20/07/2026

Name: Lindo Ngcobo Designation: Maintenance Manager Signature and date:  22/07/2026

Name: Mhlonipheni Nxumalo Designation: Executive Manager Signature and date:  23/07/2026