



**CD49/2023**

**THE MANUFACTURE, SUPPLY, DELIVERY OF NEW 12 kV INDOOR METAL CLAD SWITCHGEAR, 12kV FIXED PATTERN NON-EXTENDABLE (RMU) SWITCHGEAR AND ASSOCIATED EQUIPMENT. THE REPAIR OF EXISTING SWITCHGEAR AND THE RETROFIT OF EXISTING SWITCHGEAR.**

## Table of Contents

1. STATEMENT OF INVITATION .....	3
2. MINIMUM REQUIREMENTS .....	3
3. DEFINITIONS AND ABBREVIATIONS .....	6
5. TECHNICAL SPECIFICATION .....	7
6. HEALTH AND SAFETY REQUIREMENTS.....	84
7. SPECIAL CONDITIONS OF THE CONTRACT.....	4
8. EVALUATION CRITERIA.....	85
9. PRICING .....	88
10. CONTACT INFORMATION.....	111
11. ANNEXURES.....	129

## 1. STATEMENT OF INVITATION

CENTLEC (SOC) Ltd (Here after referred to as CENTLEC) a Municipal Entity distributing electricity in Mangaung and other Municipalities invites suitable bidders to bid for the manufacture, supply, delivery of new 12 kV indoor metal clad switchgear, 12kV fixed pattern non-extendable (RMU) switchgear and associated equipment. The repair of existing switchgear and the retrofit of existing switchgear as per specifications detailed below for a period of thirty-six (36) months.

### 1.2 Specified Goals for Preferential Point System

Specified Goals	Points Allocation
50% Black owned	6
50% Women owned	2
50% Youth owned <35 years	2
<b>Total Points</b>	<b>10</b>

Table 1: Specified Goals

## 2. MINIMUM REQUIREMENTS

- 2.1. Supply unique security personal identification number (PIN) from SARS for TAX compliant status.
- 2.2. Supply municipal services (water, sanitation, rates and electricity) clearance certificate or Lease Agreement with a current Bill and rates clearances, or Current Bill of Account not owing more than 90 days. In a case where the services are paid by the Landlord, the signed lease agreement and statement of account must be submitted by the bidder.
  - 2.1.1 In an event, that the Bidder utilizes prepaid services (e.g. Water or electricity) a valid municipal clearance certificate(s) must still be provided.
- 2.2 CIDB grading – Level 6 EP/EB/CE and above.
- 2.3 The service provider must supply valid letter of good standing with the Compensation Commissioner.
- 2.4 The bidder must be registered with National Treasury Data Base of suppliers and proof thereof must be submitted.
- 2.5 Proof of ISO 9001 quality accreditation from the manufacturer of the goods (a certified copy of the accreditation will suffice).
- 2.6 Please note that the Special Conditions table as per point 3 below, needs to be met. All supporting documents needs to be submitted where applicable.

### 3. SPECIAL CONDITIONS

**Take Note that it is compulsory for Bidders to complete the table in full.**

Description	Yes	No	Submit documentation
The successful bidder will be expected to enter into a Service Level Agreement with CENTLEC			<b>Upon appointment</b>
Please note that CENTLEC reserves the right to appoint more than one bidder.			N/A
Any work outside of the current scope of work, identified by CENTLEC duly authorized persons can be quoted on by the approved bidder.			N/A
The quotation can be considered by CENTLEC, and a work instruction generated for the quoted Adhoc work.			N/A
Factory Acceptance Test for four CENTLEC persons must include transport (flight arrangements), accommodation and transport. The cost will be for the successful bidder account.			N/A
All the equipment delivered must be accompanied with protection wiring diagrams, panel layout drawings, factory test results, special keys, 200ml touch up paint, and maintenance manuals.			N/A
All the current transformer information will be indicated in the panel kiosk.			N/A
All the panels must be labeled according to the specification, A1 to A10, in the middle and on top of the panel kiosk.			N/A
The services provider will train CENTLEC personnel on all relays, circuit breaker and panel operations for the duration of this contract.			N/A
The service provider will submit, with his tender a fully breakdown like the spares list, a list of spares that will be applicable to the switchgears tendered for.			Spares list
The service provider must ensure that			Submit letter of con-

all circuit breakers are functional in all panels so that it can be utilized in any panel. CB wiring and panel wiring must be standard.			formation.
---	--	--	------------

**Table 2. Special Conditions**

## 4. DEFINITIONS AND ABBREVIATIONS

- 4.1 A - Ampere
- 4.2 V - Voltage
- 4.3 kVA - Kilo Volt Ampere
- 4.4 LV - Low Voltage
- 4.5 Hz - Hertz
- 4.6 ISO - International Organization for Standardization
- 4.7 IEC - International Electro Technical Commission Standards
- 4.8 SANS - South Africa Nasional Standard
- 4.9 Ue – Operational voltage
- 4.10 Ui - Isolation voltage
- 4.11 VA - Volt Ampere
- 4.12 kA - Kilo Ampere
- 4.13 Ct - Current transformer
- 4.14 Pt - Potential transformer
- 4.15 NER - Neutral Earth Resistor
- 4.16 NERCT – Neutral Earth Compensator Resistor

## 5. SCOPE OF WORK

5.1 The bidder will be required to manufacture, supply and deliver the following:

- 5.1.1 Part A: 12 kV vacuum indoor metal clad switchgear.
- 5.1.2 Part B: 12 kV fixed pattern metal clad ring main unit and associated accessories according to the applicable standards.
- 5.1.3 Part C: Vacuum circuit breakers to replace AG16 oil type circuit breakers and the repairs of 12kV switchgear on adhoc quotation basis. Retrofit Reyrolle circuit breakers.

5.2 The bidder will be required to (existing 11kV switchgear):

- 5.2.1 Repair existing 11kV circuit breakers and related equipment in CENTLEC's network.
- 5.2.2 Strip and quote quotations on repairs of existing 11kV switchgear, related equipment and the transporting from Bloemfontein to their premises and back to CENTLEC.
- 5.2.3 To supply the related Protective Relays and other listed items in the Pricing Schedule.

## 6. TECHNICAL SPECIFICATION

### 6.1 METEOROLOGICAL CONDITIONS AT CENTLEC SUPPLY AREA

1. Outdoor temperatures in degrees Celsius	Annual mean – 24.4; Maximum = 40; Minimum = -10
2. Average relative humidity	At 8h00 = 76%; at 14h00 = 33%; at 20h00 = 48%  Minimum = 7% and Maximum = 98%
3. Thunderstorm activity	Severe Thunderstorms

**Table 2 – Climatological Data**

### 6.2 ELECTRICAL SYSTEM IN BLOEMFONTEIN

- 6.2.1 Voltage: 11 000 /400 Volt
- 6.2.2 Phase: 3 (A-Red, B-Yellow and C-Blue)
- 6.2.3 Frequency: 50 Hz
- 6.2.4 On the 11 kV side at the transformers 33/11 kV and 132kV/11kV in distribution centres in Bloemfontein; the neutral is earthed through a resistor to limit the maximum current to 300 A, 20Ω or 600 A, 10Ω. Please note that the circuit breakers must still be designed to fault level capacity of 350 MVA.
- 6.2.5 Phase rotation is non-standard. (Red, Yellow, Blue) Must be label on switchgear.
- 6.2.6 The load on the system consists mainly of lighting, heating and inductive loads.
- 6.2.7 The three types of cable mainly used on the 11 kV network are 240 mm<sup>2</sup> Cu paper insulated lead, 185mm<sup>2</sup> Al paper insulated lead and 70 mm<sup>2</sup> Cu paper insulated lead, cable.
- 6.2.8 The insulation level for the voltage transformers must be according to SANS 780: 2009.

### 6.3 SPECIFICATIONS ON SWITCHGEAR:

- 6.3.1 Busbar insulation: -

Busbars, cable termination points and all live metal shall be fully and suitably insulated. Busbars which use air only as insulating medium is not acceptable. Switchgear and busbar insulation shall be designed to prevent the risk of accidental short circuit due to animals and vermin. Busbar connections must be tinned (Silver plate).

The degree of Ingress-Protection for the metal-clad switchgear shall conform to IP4X

6.3.2 Rated insulation level: -

Switchgear must have a basic impulse insulation withstand level of 95 kV.

6.3.3 Voltage transformers: -

- a. Voltage transformer shall comply with the requirements of SANS (SANS) IEC 60044-2, 3 phase, 100VA, Class 0.5 and shall be the encapsulated type that is fully encapsulated in epoxy resin and must be fitted with an earthed metal screen. Only the LIMB /swivel type with interlocking busbar shutters will be considered on switchgear type A2, A3 and A10. The phasing must be labeled clearly.
- b. **Take note of the primary connection position of all 11000/110 Volt voltage transformers on the switchgear** The position of voltage transformer shall be Cable side mounted as specified in the schedule unless specifically specified otherwise on an order.
- c. The 110-volt DC (secondary side) fuses must be accessible and easy to be replace without isolation of the voltage transformer or removing of covers.
- d. Installation of a panel mounted voltmeter is only necessary if the protection relay is unable to display the primary voltage.

6.3.4 Metering: -

- a. Circuit breaker panels, schedule A2, A3 and A10, metering CT's must be installed as specification unless otherwise specified on order, according to schedule A11.6.
- b. Connection points (HV side) on current transformers base must be such that it can be easily taped close.

6.3.5 Protection and auxiliary equipment: -

All Protection Relays offered in the main offer must be consistent with the technical specifications as listed and described in the schedules under item 6.4 below including the dimensions. All Current transformers will be studded type where all small wiring will be terminated labeled and numbered.

***All relays must carry a minimum of Ten Year (10) warranty, for repair(s) or replacement(s).***

6.3.6 Protection Relay and Bus Wiring must be as follows: -

The auxiliary DC supply (protection relay auxiliary supply) and the tripping/closing DC supply must be separated and individually supplied (Moulded Case Circuit Breakers). Both DC supply circuits must be wired to the rear terminal box.

- 6.3.7 Install arc flash protection in cable termination chamber and busbar chamber to trip each individual circuit breaker. Light sensors must be installed at the specific points that have the greatest risk of arc flash. Light sensors must be linked to the protective relay. The protective relay must be easily integrated with the supervisory and control system, enabling remote settings and configuration, and must have a high-speed pickup. Light sensors must be interconnected to the protective relay by fiber optic cables to eliminate the need for other components inside the cubicles.
- 6.3.8 Hand-held remote control (Pendant control), for closing and tripping the circuit breaker, must be standard on all panels. This can be accomplished by a plug-in type of extension lead with trip / close control (minimum 10m in length). Quantity of leads will be specified when ordered.
- 6.3.9 Auxiliary wiring between the switchgear panel and the withdrawable circuit breaker shall be by means of a wire harness with a detachable socket. Interlocking to prevent operation of the switchgear is required if the detachable socket is not firmly in position.
- 6.3.10 Provision must be made for the circuit breaker status ("open" or "closed") to be indicated on the panel, using a LED type lamp indicator.
- 6.3.11 All spare circuit breaker auxiliary contacts ("a" and "b") must be wired to rear terminal box.
- 6.3.12 Auto-reclose status and sensitive earth fault status must be flagged on the protection relay display.
- 6.3.13 Auto-reclose on sensitive earth fault must be selectable via a front panel selector switch. This must be duplicated on the protective relay.
- 6.3.14 Auto-reclose, "On" and "Off" must be selectable via a front panel selector switch. This may be duplicated on the relay.
- 6.3.15 Ammeters are only to be installed if the protection relays are incapable of displaying instantaneous current values. In this case, only a single meter must be installed on the yellow phase, with the appropriate interposing CT.

6.3.16 Cable termination boxes: -

- a. Surge Arresters must be installed on all type A7 panels and be situated in the power cable termination box as close as possible to the terminal fixing point of the cable. Surge arresters installed must not have an integral disconnecting device.
- b. All power cable termination boxes must cater for split gland plates and include a PVC wedge type non-ferrous, cable retaining cleat to accommodate from 70mm<sup>2</sup> Cu PILC cable, 185 mm<sup>2</sup> Al PILC cable and 240mm<sup>2</sup> Cu PILC cable.

6.3.17 Labels (All labels shall conform to SANS 1885: 2001 clause 4.17).

6.3.18 All panels with manual spring charge circuit breakers (non-motorized circuit breaker mechanisms) a label must be provided on the circuit breaker, red text on white background that reads: "Hand charge - Closing and Tripping must be done with using Pendant Control or standoff push button cable".

**6.4 PART A: -**

**METAL-CLAD SWITCHGEAR 12kV (SBV4-E, SBV3-E types) or equivalent, Complete Colom, PARTICULARS OFFERED AND GURANTEED, from schedule A1 to A11.**

**6.4.1 A1 SWITCH-DISCONNECTOR**

SCHEDULE A1: SWITCH-DISCONNECTOR PANEL – COMPATIBLE WITH ALL SWITCHGEAR PANELS		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A1	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GURANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Switch Disconnectors		
Insulation Medium		Oil, Vacuum or Sf6 gas.	4.3.1.1.3	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Manual	4.3.1.9	
Trip Coil	V	Hand Operated	4.3.1.10	
Spring Release Coil	V	N/A	4.3.1.10	
Indication for Trip/Close		YES	4.3.1.2	
Status Indication Lamps (open/close)	LED	N/A	4.3.2.2	

			a)	
Circuit Earthing Facilities		Bottom Entry	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Ca- ble.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		N/A (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
Install CT's		N/A	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		N/A	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

<b>SCHEDULE A1: SWITCH-DISCONNECTOR PANEL – COMPATIBLE WITH ALL SWITCHGEAR PANELS</b>		<b>PART A – METAL-CLAD SWITCHGEAR</b>			
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A1</b>	<b>UNITS</b>	<b>SPECIFIED RE- QUIREMENT</b>	<b>SANS CLAU SE</b>	<b>PARTICILARS OFFERED AND GU- RANTEED</b>	
<b>VOLTAGE TRANSFORMER</b>					
Install VT		No	4.9		
Ratio		N/A			
Burden and Accuracy		N/A			
Voltage Factor		N/A			
Limbs		N/A			
<b>AMMETER:</b>					
Scale		No	4.14.4		
Interposing CT		N/A			
Maximum Demand Indicator		N/A			
<b>VOLTMETER:</b>					
Voltmeter		No	4.14.4		
Phase Selector Switch		N/A			
<b>GENERAL:</b>					
Configuration of Switchgear		TS-9-7			
Spare auxiliary Contacts required		N/A	4.14		
		N/A			

Marking/Labeling/Documentation		N/A	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		N/A	4.10	
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag		N/A	4.10	
D.C Circuit Protection		N/A	4.14.3	
Location of Fuses inside RC		N/A		
Location of Test Terminal Blocks RC Door		N/A	4.14.7	
Battery Charger with Batteries – 30 Volt		No		
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.2 A2 CIRCUIT BREAKER

SCHEDULE A2: CIRCUIT BREAKER - MV CONNECTION < 1MVA		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A2	UNITS	SPECIFIED REQUIREMENT	RE-CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		MV Connection < 1MVA		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		

Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		100/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		60/30/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 12/28/95 KV		

<b>SCHEDULE A2: CIRCUIT BREAKER - MV CONNECTION &lt; 1MVA</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A2</b>	<b>UNITS</b>	<b>SPECIFIED REQUIREMENT</b>	<b>RE-CLAUSE</b>	<b>PARTICILARS OFFERED AND GU-RANTEED</b>
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		11000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 7		
Spare auxiliary Contacts required		"a"-2 :b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:	4.10	

		<ul style="list-style-type: none"> <li>i. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</li> <li>ii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>iv. <b>Configurable labels:</b> Yes</li> <li>v. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</li> <li>vi. <b>Communications Protocol:</b> DNP3_level 2 minimum</li> <li>vii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>ix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>x. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</li> <li>xi. <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</li> </ul>		
<p>Pilot Wire Current Differential Protection Seepricing schedule onpage 94</p>		<p>N/A</p>	<p>4.10</p>	
<p>Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state</p>		<p>N/A</p>	<p>4.10</p>	

3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		Yes	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber		
D.C Circuit Protection		MCB's	4.14.3	
Location of MCB inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

### 6.4.3 A3 CIRCUIT BREAKER

SCHEDULE A3: CIRCUIT BREAKER - MV CONNECTION > 1MVA		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A3	UNITS	SPECIFIED REQUIREMENT	RE- SANS CLAUSE	PAR-TICILARS OFFERED AND GU-RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		MV Connection > 1MVA		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		

Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 12/28/95 KV		

<b>SCHEDULE A3: CIRCUIT BREAKER - MV CONNECTION &gt;1MVA</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS</b> NOTE: PANEL MUST BE MARKED ON TOP A3	<b>UNITS</b>	<b>SPECIFIED REQUIREMENT</b>	<b>SANS CLAUSE</b>	<b>PARTICULARS OFFERED AND GURANTEED</b>
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		11000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-8		
Spare auxiliary Contacts required		"a"-2 :b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:  i. <b>Power Supply:</b> Universal – 24 to 120V DC/AC. ii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input. iii. <b>Voltage Input:</b> 110V phase to phase AC	4.10	

		<p>Voltage.</p> <p>iv. <b>Configurable labels:</b> Yes</p> <p>v. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</p> <p>vi. <b>Communications Protocol:</b>  DNP3_level 2 minimum</p> <p>vii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</p> <p>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>ix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>x. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b>  Must be able to fit onto the control panel portion of the switchgear.</p>		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		Yes	4.10	
Arc Flash sensors		Cable, Circuit Break-		

		er and Busbar chamber		
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.4 A4 CIRCUIT BREAKER SECONDARY FEEDER

SCHEDULE A4: CIRCUIT BREAKER - SECONDARY FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A4	UNITS	SPECIFIED REQUIREMENT	RE-SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Secondary Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
Install CT's		Studded 6mm Brass S connections.		
Purpose		Yes	4.8	
Ratio		OC/EF Protection		
Burden		600/1		
Class		10VA		
		10P10		

Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		No	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

SCHEDULE A4: CIRCUIT BREAKER - SECONDARY FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A4	UNIT S	SPECIFIED REQUIREMENT	RE- SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		NO	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-8		
Spare auxiliary Contacts required		"a"-2 "b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:  i. <b>Power Supply:</b> Universal – 24 to 120V DC/AC. ii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input. iii. <b>Voltage Input:</b> 110V phase to phase AC Voltage. iv. <b>Configurable labels:</b> Yes v. <b>Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.	4.10	

		<p><b>Front:</b> 1 x Serial Port</p> <p>vi. <b>Communications Protocol:</b> DNP3_level 2 minimum</p> <p>vii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</p> <p>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>ix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>x. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>		
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC		Yes	4.14.7	

Door				
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.5 A5 CIRCUIT BREAKER PRIMARY OUT GOING FEEDER

SCHEDULE A5: CIRCUIT BREAKER – PRIMARY OUT-GOING FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A5	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Primary Out-Going Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)		Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		

<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Pilot wire protection		
Burden				
Ratio		600/1		
Class		X or TPS or PX		
Quantity		3		
Insulation Level		IL 12/28/95 KV		

<b>SCHEDULE A5: CIRCUIT BREAKER – PRIMARY OUT-GOING FEEDER</b>		<b>PART A – METAL-CLAD SWITCHGEAR</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A5</b>	<b>UNITS</b>	<b>SPECIFIED REQUIREMENT</b>	<b>SANS CLAUSE</b>	<b>PARTICULARS OFFERED AND GUARANTEED</b>
<b>VOLTAGE TRANSFORMER</b>				
Install VT		NO	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 8		
Spare auxiliary Contacts required		"a"-2 :b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:  i. <b>Power Supply:</b> Universal – 24 to 120V DC/AC. ii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A	4.10	

		<p>Neutral Input.</p> <p>iii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</p> <p>iv. <b>Configurable labels:</b> Yes</p> <p>v. <b>Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port</p> <p>vi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</p> <p>vii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</p> <p>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>ix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>x. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>		
High Speed Pilot wire protection- “ Solkor RF” or compatible		Yes	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with coun-		N/A	4.10	

ter-solid state				
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.6 A6 CIRCUIT BREAKER TRANSFORMER FEEDER.

SCHEDULE A6: CIRCUIT BREAKER TRANSFORMER FEEDER.		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A6	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Transformer Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	

Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS AND FINISH</b>	Paint	Light Grey G29		
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		60/30/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		N/A	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

SCHEDULE A6: CIRCUIT BREAKER TRANSFORMER FEEDER.		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A6	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-9		
Spare auxiliary Contacts required		"a"-2	4.14	
		"b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:  i. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.	4.10	

		<ul style="list-style-type: none"> <li>ii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>iv. <b>Configurable labels:</b> Yes</li> <li>v. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</li> <li>vi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</li> <li>vii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>ix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>x. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).  <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</li> </ul>		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	

Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.7 A7 CIRCUIT BREAKER OVERHEAD LINE FEEDER

SCHEDULE A7: CIRCUIT BREAKER OVERHEAD LINE FEEDER		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A7	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Overhead line feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Auto Spring Charge	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		

Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		Yes, Cable side 12kV	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connec- tions.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10 VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 12/28/95 KV		

<b>SCHEDULE A7: CIRCUIT BREAKER OVERHEADLINE FEEDER.</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A7</b>	<b>UNIT S</b>	<b>SPECIFIED RE-QUIREMENT</b>	<b>SANS CLAUS E</b>	<b>PARTICILARS OFFERED AND GU-RANTEED</b>
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		11000/110		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		Yes	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-9		
Spare auxiliary Contacts required		"a"-2 :b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		Yes: The Relay must have these capabilities:  i. <b>Power Supply:</b>	4.10	

		<p>Universal – 24 to 48VDC</p> <p>ii. <b>Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input.</p> <p>iii. <b>Voltage Input:</b> <math>V_{NOM(L-L)}</math> should have the following specifications; 20 to 440V for DELTA_Y for DELTA and WYE</p> <p>iv. <b>Configurable labels:</b> Yes</p> <p>v. <b>Programmable pushbuttons:</b> Minimum of four programmable pushbuttons, each with programmable LEDs</p> <p>vi. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</p> <p>vii. <b>Communications Protocol:</b> DNP3 level 2 minimum.</p> <p>viii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24VDC (External wetting); Inputs should be individually user-configured to operate.</p> <p>ix. <b>High Speed, High current Interruption (Outputs):</b> Minimum of 6A continuous current – Minimum of 8 Universal – 19.2 to 60 VDC for the 24 to 48 power supply.</p> <p>x. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xi. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control</p>		
--	--	--	--	--

		panel portion of the switchgear.		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		Yes	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		Yes	4.10	
Auto-reclose facility.		Yes: 30V DC electrical closing via ARC relay.	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.8 A8 CIRCUIT BREAKER PRIMARY INCOMER FEEDER

SCHEDULE A8: CIRCUIT BREAKER PRIMARY INCOMER FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A8	UNITS	SPECIFIED REQUIREMENT	RE-SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Primary Incomer feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	

Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		No	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
Install CT's		Studded 6mm Brass S connections.		
Purpose		Yes Differential	4.8	
Ratio		Pilot wire protection		
Burden		600/1		
Class		10VA		
Quantity		X or TPS or PX		
Insulation Level		3		
Install Ct's (Metering/Differential)		IL 12/28/95 KV		
Purpose		Yes	4.8	
Burden		Metering		
Ratio		10VA		
Class		300/5		
Quantity		0.5		
Insulation Level		2		
		IL 12/28/95 KV		

SCHEDULE A8: CIRCUIT BREAKER PRIMARY INCOMER FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A8	UNITS	SPECIFIED REQUIREMENT	RE- SANS CLAUSE	PAR- TICULARS OFFERED AND GU- RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		Yes	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-10		
Spare auxiliary Contacts required		"a"-2 :b"-2	4.14	
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	

<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		No	4.10	
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		Yes	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		No	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		No	4.10	
Auto-reclose facility.		No	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.9 A9 CIRCUIT BREAKER BUS- SECTION SWITCH

<b>SCHEDULE A9: CIRCUIT BREAKER BUS- SECTION SWITCH</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A9</b>	<b>UNIT S</b>	<b>SPECIFIED REQUIREMENT</b>	<b>SANS CLAUSE</b>	<b>PARTICULARS OFFERED AND GUARANTEED</b>
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Bus-Section Switch		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		N/A	4.3.1.9	

Main Cable Detail		Busbars to Link busbars through Circuit breaker.		
Main Cable Termination		N/A		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		No	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		No	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 12/28/95 KV		

SCHEDULE A9: CIRCUIT BREAKER BUS- SECTION SWITCH		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A9	UNITS	SPECIFIED REQUIREMENT	RE-SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 10		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		

Mark- ing/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <ul style="list-style-type: none"> <li>xi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</li> <li>xii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>xiv. <b>Configurable labels:</b> Yes</li> <li>xv. <b>Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port</li> <li>xvi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</li> <li>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user configured to operate.</li> <li>xviii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>xx. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</li> </ul> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>	4.10	
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		No	4.10	
Sensitive Earth Fault – Time delay range		No	4.10	

0.01-25 sec – solid state				
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		No	4.10	
Auto-reclose facility; 1A Phase and 50mA neutral.		No	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.10 A10 FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS

SCHEDULE A10: FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS. NOTE: PANEL MUST BE MARKED ON TOP A10	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Fused-Switch Disconnecter with metering.		
Insulation Medium		Oil, vacuum or SF6 gas	4.3.2.1.6	
System Voltage	kV	11	4.1.1.1	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	

Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	No	4.3.1.10	
Spring Release Coil	V	No	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		PVC Wedge cleat 70 to 185 mm Ca- ble		
Main Cable Termination		1x 185mm x 3 core PILC.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		No	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
		<b>Studded 6mm Brass S connec- tions.</b>		
Install CT's		No	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		60/30/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 12/28/95 KV		

SCHEDULE A10: FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS. NOTE: PANEL MUST BE MARKED ON TOP A10	UNIT S	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio	V	11000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		

<b>VOLTMETER:</b>			
Voltmeter	No	4.14.4	
Phase Selector Switch	N/A		
<b>GENERAL:</b>			
Configuration of Switchgear	TS -9- 10		
Spare auxiliary Contacts required	"a"-2	4.14	
	:b"-2		
Marking/Labeling/Documentation	Yes	4.17	
Main Circuit Designation Label	Blank	4.17	
<b>PROTECTION:</b>			
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)	No	4.10	
Pilot Wire Current Differential Protection Seepricing schedule on-page 94	No	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state	No	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state	No	4.10	
Auto-reclose facility	No	4.10	
Arc Flash Sensors	No	4.10	
D.C Circuit Protection	MCB's	4.14.3	
Location of Fuses inside RC	Yes		
Location of Test Terminal Blocks RC Door	Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery	2	7.3	
Number of copies of Routine Test Report Certificates on delivery	2	7.4	

**METAL-CLAD SWITCHGEAR 22kV (SBV4-E, types) or equivalent, Complete Colom, PARTICILARS OFFERED AND GURANTEED, from schedule 22A1 to 22A11.**

#### 6.4.11 22A1 SWITCH-DISCONNECTOR

SCHEDULE 22A1: SWITCH-DISCONNECTOR PANEL – COMPATIBLE WITH ALL SWITCHGEAR PANELS		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A1	UNIT S	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GU-RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Switch Disconnectors		
Insulation Medium		Oil, Vacuum or Sf6 gas.	4.3.1.1.3	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	

Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Manual	4.3.1.9	
Trip Coil	V	Hand Operated	4.3.1.10	
Spring Release Coil	V	N/A	4.3.1.10	
Indication for Trip/Close		YES	4.3.1.2	
Status Indication Lamps (open/close)	LED	N/A	4.3.2.2 a)	
Circuit Earthing Facilities		Bottom Entry	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Ca- ble.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		N/A (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
Install CT's		N/A	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		N/A	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

<b>SCHEDULE 22A1: SWITCH-DISCONNECTOR PANEL – COMPATIBLE WITH ALL SWITCHGEAR PANELS</b>		<b>PART A – METAL-CLAD SWITCHGEAR</b>		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP A1	UNIT S	SPECIFIED REQUIREMENT	RE-SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	

Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-7		
Spare auxiliary Contacts required		N/A	4.14	
		N/A		
Marking/Labeling/Documentation		N/A	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		N/A	4.10	
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag		N/A	4.10	
D.C Circuit Protection		N/A	4.14.3	
Location of Fuses inside RC		N/A		
Location of Test Terminal Blocks RC Door		N/A	4.14.7	
Battery Charger with Batteries – 30 Volt		No		
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.12 22A2 CIRCUIT BREAKER

SCHEDULE 22A2: CIRCUIT BREAKER - MV CONNECTION < 1MVA		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22 A2	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		MV Connection < 1MVA		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	

Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		100/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		60/30/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 24/40/95 KV		

<b>SCHEDULE 22A2: CIRCUIT BREAKER - MV CONNECTION &lt; 1MVA</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A2</b>	<b>UNITS</b>	<b>SPECIFIED REQUIREMENT</b>	<b>RE-CLAUSE</b>	<b>PARTICILARS OFFERED AND GU-RANTEED</b>
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		22000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		

<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 7		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <p>xii. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</p> <p>xiii. <b>Secondary Input Current:</b>3 x AC 5A/1A plus a 1A/5A Neutral Input.</p> <p>xiv. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</p> <p>xv. <b>Configurable labels:</b> Yes</p> <p>xvi. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</p> <p>xvii. <b>Communications Protocol:</b> DNP3_level 2 minimum</p> <p>xviii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</p> <p>xix. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>xx. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xxi. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p>	4.10	

		xxii. <b>Relay dimensions:</b> Must be able to fit on-to the control panel portion of the switch-gear.		
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		Yes	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber		
D.C Circuit Protection		MCB's	4.14.3	
Location of MCB inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

### 6.4.13 22A3 CIRCUIT BREAKER

SCHEDULE 22A3: CIRCUIT BREAKER - MV CONNECTION > 1MVA		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A3	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		MV Connection > 1MVA		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	

Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 24/40/95 KV		

SCHEDULE 22A3: CIRCUIT BREAKER - MV CONNECTION >1MVA		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A3	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GURANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		22000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	

Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-8		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <ul style="list-style-type: none"> <li>xi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</li> <li>xii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>xiv. <b>Configurable labels:</b> Yes</li> <li>xv. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</li> <li>xvi. <b>Communications Protocol:</b> DNP3_level 2 minimum</li> <li>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>xviii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>xx. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At</li> </ul>	4.10	

		no additional costs (free issue with the relay). <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		Yes	4.10	
Arc Flash sensors		Cable, Circuit Breaker and Busbar chamber		
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.14 22A4 CIRCUIT BREAKER SECONDARY FEEDER

SCHEDULE 22A4: CIRCUIT BREAKER - SECONDARY FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A4	UNIT S	SPECIFIED REQUIREMENT	RE-SANS CLAUSE	PARTICULARS OFFERED AND GU-RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Secondary Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	

Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		No	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

SCHEDULE 22A4: CIRCUIT BREAKER - SECONDARY FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A4	UNIT S	SPECIFIED REQUIREMENT	RE- SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		N0	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				

Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-8		
Spare auxiliary Contacts required		"a"-2	4.14	
		"b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <ul style="list-style-type: none"> <li>xi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</li> <li>xii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>xiv. <b>Configurable labels:</b> Yes</li> <li>xv. <b>Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port</li> <li>xvi. <b>Communications Protocol:</b> DNP3_level 2 minimum</li> <li>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>xviii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be</li> </ul>	4.10	

		provided with the relay. xx. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay). <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.		
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.15 22A5 CIRCUIT BREAKER PRIMARY OUT GOING FEEDER

SCHEDULE 22A5: CIRCUIT BREAKER – PRIMARY OUT-GOING FEEDER		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A5	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Primary Out-Going		

		Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)		Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
		<b>Studded 6mm Brass S connec- tions.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Pilot wire protection		
Burden				
Ratio		600/1		
Class		X or TPS or PX		
Quantity		3		
Insulation Level		IL 24/40/95 KV		

<b>SCHEDULE 22A5: CIRCUIT BREAKER – PRIMARY OUT-GOING FEEDER</b>		<b>PART A – METAL-CLAD SWITCHGEAR</b>		
<b>DESCRIPTION OF PARTICU- LARS NOTE: PANEL MUST BE MARKED ON TOP 22A5</b>	<b>UNITS</b>	<b>SPECIFIED RE- QUIREMENT</b>	<b>SANS CLAUSE</b>	<b>PAR- TICILARS OFFERED AND GU-</b>

				RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		NO	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 8		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <ul style="list-style-type: none"> <li>xi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</li> <li>xii. <b>Secondary Input Current:</b>3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</li> <li>xiv. <b>Configurable labels:</b> Yes</li> <li>xv. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</li> <li>xvi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</li> <li>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>viii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous –</li> </ul>	4.10	

		<p>Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xx. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>		
High Speed Pilot wire protection- “Solkor RF” or compatible		Yes	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
D.C Circuit Protection		MCB’s	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

**6.4.16 22A6 CIRCUIT BREAKER TRANSFORMER FEEDER.**

SCHEDULE 22A6: CIRCUIT BREAKER TRANSFORMER FEEDER.		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A6	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Transformer Feeder		
Insulation Medium		Vacuum	4.3.2.1.6	

System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PLIC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		N/A	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS AND FINISH</b>	Paint	Light Grey G29		
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		60/30/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		N/A	4.8	
Purpose		N/A		
Burden		N/A		
Ratio		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		

SCHEDULE 22A6: CIRCUIT BREAKER TRANSFORMER FEEDER.		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A6	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	

Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-9		
Spare auxiliary Contacts required		"a"-2	4.14	
		"b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <p>xxi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</p> <p>xxii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</p> <p>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</p> <p>xiv. <b>Configurable labels:</b> Yes</p> <p>xv. <b>Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port</p> <p>xvi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</p> <p>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</p> <p>xviii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V</p>	4.10	

		<p>DC/AC voltage application.</p> <p>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xxx. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		N/A	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		N/A	4.10	
Transformer Over Temperature tripping relay Hand reset Flag or LEDs		N/A	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Arc Flash Sensors		Cable, Circuit Breaker and Bus-bar chamber	4.10	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.17 22A7 CIRCUIT BREAKER OVERHEAD LINE FEEDER

SCHEDULE 22A7: CIRCUIT BREAKER OVERHEAD LINE FEEDER		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A7	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GU-

				RANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Overhead line feeder		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Auto Spring Charge	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		70 to 185mm x 3core XLPE/PILC	4.3.1.2	
Main Cable Termination		PVC wedge cleat 70 to 185 mm Cable.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		Yes, Cable side 12kV	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes	4.8	
Purpose		OC/EF Protection		
Ratio		600/1		
Burden		10VA		
Class		10P10		
Quantity		3		
Insulation Level		IL 24/40/95 KV		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10 VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 24/40/95 KV		

SCHEDULE 22A7: CIRCUIT BREAKER OVERHEADLINE FEEDER.		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A7	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED

<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		22000/110		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		Yes	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-9		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <p>xii. <b>Power Supply:</b> Universal – 24 to 48VDC</p> <p>xiii. <b>Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input.</p> <p>xiv. <b>Voltage Input:</b> <math>V_{NOM}</math> (L-L) should have the following specifications: 20 to 440V for DELTA_Y for DELTA and WYE</p> <p>xv. <b>Configurable labels:</b> Yes</p> <p>xvi. <b>Programmable pushbuttons:</b> Minimum of four programmable pushbuttons, each with programmable LEDs</p> <p>xvii. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</p> <p>xviii. <b>Communications Protocol:</b> DNP3 level 2 minimum.</p> <p>xix. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24VDC (External wetting); Inputs should be individually user-configured to operate.</p>	4.10	

		<p>xx. <b>High Speed, High current Interruption (Outputs):</b> Minimum of 6A continuous current – Minimum of 8 Universal – 19.2 to 60 VDC for the 24 to 48 power supply.</p> <p>xxi. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xxii. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>		
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		N/A	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		Yes	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		Yes	4.10	
Auto-reclose facility.		Yes: 30V DC electrical closing via ARC relay.	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.18 22A8 CIRCUIT BREAKER PRIMARY INCOMER FEEDER

SCHEDULE 22A8: CIRCUIT BREAKER PRIMARY INCOMER FEEDER		PART A – METAL-CLAD SWITCHGEAR			
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A8	UNITS	SPECIFIED REQUIREMENT	RE-	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED

<b>SWITCHGEAR GENERAL</b>				
Panel Function			Primary Incomer feeder	
Insulation Medium			Vacuum	4.3.2.1.6
System Voltage	kV		22	4.1.1.1
Rated Voltage	kV		24	4.1.1.1
Circuit Normal Rated Current	Amp		800	4.1.1.3
Busbar Normal Rated Current	Amp		800	4.1.1.3
Fault Level Capacity	MV A		350	4.1.1.3
Impulse Withstand Voltage	kV		95	4.1.1.4.2
Short Circuit Breaking Capacity	kA		20	4.1.1.5
Duration of Short Circuit	s		3	4.1.1.5
Peak Withstand Current	kA		63	4.1.1.5
Mechanism Type			Handspring	4.3.1.9
Trip Coil	V		30 V D.C	4.3.1.10
Spring Release Coil	V		30 V D.C	4.3.1.10
Indication for Trip/Close			Yes	4.3.1.2
Status Indication Lamps (open/close)	LED		Yes	4.3.2.2 a)
Circuit Earthing Facilities			Yes	4.2.8.2
System Earthing			NER 300 A Max	4.3.1.1.3
Cable Entry			Bottom Entry	4.3.1.9
Main Cable Detail			70 to 185mm x 3core XLPE/PILC	4.3.1.2
Main Cable Termination			PVC wedge cleat 70 to 185 mm Cable.	
Circuit Earthing Facility			Yes	4.2.8.1
Interlocks			Yes	
Surge Arrestors (suppressors)			No	4.2.7
Remote Control Unit			Yes (open and close)	4.3.1.7
<b>DIMENSIONS</b>				
Height	mm		Max 1800	
Depth	mm		Max 1500	
Width	mm		Max 600	
<b>CURRENT TRANSFORMERS:</b>			<b>Studded 6mm Brass S connections.</b>	
Install CT's			Yes Differential	4.8
Purpose			Pilot wire protection	
Ratio			600/1	
Burden			10VA	
Class			X or TPS or PX	
Quantity			3	
Insulation Level			IL 24/40/95 KV	
Install Ct's (Metering/Differential)			Yes	4.8
Purpose			Metering	
Burden			10VA	
Ratio			300/5	
Class			0.5	
Quantity			2	
Insulation Level			IL 24/40/95 KV	

<b>SCHEDULE 22A8: CIRCUIT BREAKER PRIMARY INCOMER FEEDER</b>		<b>PART A – METAL-CLAD SWITCHGEAR</b>			
<b>DESCRIPTION OF PARTICU- LARS NOTE: PANEL MUST BE MARKED ON TOP 22A8</b>	<b>UNIT S</b>	<b>SPECIFIED RE- QUIREMENT</b>	<b>SANS CLAUS E</b>	<b>PAR- TICILARS OFFERED AND GU- RANTEED</b>	

<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		Yes	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		Yes	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS-9-10		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		No	4.10	
Pilot Wire Current Differential Protection Seepricing schedule on-page 94		Yes	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		No	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		No	4.10	
Auto-reclose facility.		No	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.19 22A9 CIRCUIT BREAKER BUS- SECTION SWITCH

<b>SCHEDULE 22A9: CIRCUIT BREAKER BUS- SECTION SWITCH</b>		<b>PART A – METAL-CLAD SWITCHGEAR (WITH METERING)</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A9</b>	<b>UNIT S</b>	<b>SPECIFIED REQUIREMENT</b>	<b>RE- SANS CLAUSE</b>	<b>PARTICILARS OFFERED AND GU-RANTEED</b>
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Bus-Section Switch		
Insulation Medium		Vacuum	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	

Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Hand Spring	4.3.1.9	
Trip Coil	V	30 V D.C	4.3.1.10	
Spring Release Coil	V	30 V D.C	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	
Cable Entry		N/A	4.3.1.9	
Main Cable Detail		Busbars to Link bus-bars through Circuit breaker.		
Main Cable Termination		N/A		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		No	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		No	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		300/200/100/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 24/40/95 KV		

SCHEDULE 22A9: CIRCUIT BREAKER BUS- SECTION SWITCH		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED ON TOP 22A9	UNITS	SPECIFIED REQUIREMENT	RE- SANS CLAUSE	PARTICILARS OFFERED AND GU-RANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	

Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 10		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		<p>Yes: The Relay must have these capabilities:</p> <p>xxi. <b>Power Supply:</b> Universal – 24 to 120V DC/AC.</p> <p>xxii. <b>Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</p> <p>xiii. <b>Voltage Input:</b> 110V phase to phase AC Voltage.</p> <p>xiv. <b>Configurable labels:</b> Yes</p> <p>xv. <b>Communication Ports:</b>  <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port.  <b>Front:</b> 1 x Serial Port</p> <p>xvi. <b>Communications Protocol:</b> DNP3 level 2 minimum.</p> <p>xvii. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user configured to operate.</p> <p>xviii. <b>Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>xix. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xl. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with</p>	4.10	

		the relay). <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.		
Pilot Wire Current Differential Protection Seepricing schedule onpage 94		No	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		No	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		No	4.10	
Auto-reclose facility; 1A Phase and 50mA neutral.		No	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

#### 6.4.20 22A10 FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS

SCHEDULE 22A10: FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS		PART A – METAL-CLAD SWITCHGEAR (WITH METERING)		
DESCRIPTION OF PARTICULARS. NOTE: PANEL MUST BE MARKED ON TOP 22A10	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>SWITCHGEAR GENERAL</b>				
Panel Function		Fused-Switch Disconnecter with metering.		
Insulation Medium		Oil, vacuum or SF6 gas	4.3.2.1.6	
System Voltage	kV	22	4.1.1.1	
Rated Voltage	kV	24	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.3	
Busbar Normal Rated Current	Amp	800	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.4.2	
Short Circuit Breaking Capacity	kA	20	4.1.1.5	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type		Handspring	4.3.1.9	
Trip Coil	V	No	4.3.1.10	
Spring Release Coil	V	No	4.3.1.10	
Indication for Trip/Close		Yes	4.3.1.2	
Status Indication Lamps (open/close)	LED	Yes	4.3.2.2 a)	
Circuit Earthing Facilities		Yes	4.2.8.2	
System Earthing		NER 300 A Max	4.3.1.1.3	

Cable Entry		Bottom Entry	4.3.1.9	
Main Cable Detail		PVC Wedge cleat 70 to 185 mm Ca- ble		
Main Cable Termination		1x 185mm x 3 core PILC.		
Circuit Earthing Facility		Yes	4.2.8.1	
Interlocks		Yes		
Surge Arrestors (suppressors)		No	4.2.7	
Remote Control Unit		Yes (open and close)	4.3.1.7	
<b>DIMENSIONS</b>				
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>				
Install CT's		No	4.8	
Purpose		N/A		
Ratio		N/A		
Burden		N/A		
Class		N/A		
Quantity		N/A		
Insulation Level		N/A		
Install Ct's (Metering/Differential)		Yes	4.8	
Purpose		Metering		
Burden		10VA		
Ratio		60/30/5		
Class		0.5		
Quantity		2		
Insulation Level		IL 24/40/95 KV		

SCHEDULE 22A10: FUSED SWITCH DISCONNECTOR COMPATIBLE TO ALL PANELS		PART A – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICULARS. NOTE: PANEL MUST BE MARKED ON TOP 22A10	UNITS	SPECIFIED REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio	V	22000/110 V		
Burden and Accuracy		0.5		
Voltage Factor		1.9		
Limbs		3		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		No	4.14.4	
Phase Selector Switch		N/A		
<b>GENERAL:</b>				
Configuration of Switchgear		TS -9- 10		
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		

Marking/Labeling/Documentation		Yes	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Overcurrent and Earth fault- 3 Pole Phase plus Earth Fault (IDMT)		No	4.10	
Pilot Wire Current Differential Protection See pricing schedule on page 94		No	4.10	
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state		No	4.10	
3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		No	4.10	
Auto-reclose facility		No	4.10	
Arc Flash Sensors		No	4.10	
D.C Circuit Protection		MCB's	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

**6.4.21 (A) Feeder 110VDCpanel:**

**Tender must be for single and double busbars. (Upper bar/Lower Bar and Front / back bar) with complete busbars for SBV3 and SBV4.**

SCHEDULE 12: SBV 3 E FEEDER PANEL COMPATIBLE WITH ALL SWITCHGEAR PANELS (110VDC)		PART C – METAL-CLAD SWITCHGEAR			
DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED	UNITS	SPECIFIED MENT	REQUIRE- MENT	SANS CLAUSE	PAR- TICULARS OFFERED AND GU- RANTEED
Panel Function		Feeder			
Insulation Medium		Vacuum			
System Voltage	kV	11		4.3.2 .1.6	
Rated Voltage	kV	12		4.1.1 .1	
Circuit Normal Rated Current	Amp	800		4.1.1 .1	
Busbar Normal Rated Current	Amp	2500		4.1.1 .3	
Fault Level Capacity	MVA	350		4.1.1 .3	
Impulse Withstand Voltage	kV	95		4.1.1 .3	
Short Circuit Breaking Capacity	kA	20		4.1.1 .4.2	
Duration of Short Circuit	s	3		4.1.1 .5	
Peak Withstand Current	kA	63		4.1.1 .5	

Mechanism Type	M.W .S	Auto spring charges	4.1.1 .5	
Trip Coil 120VDC	V	YES	4.3.1 .9	
Spring Release Coil 110VDC	V	YES	4.3.1 .10	
Indication for Trip/Close 110VDC		YES	4.3.1 .10	
Status Indication Lamps (open/close) VCB open; Green LED indication. VCB Close: Red LED indication VCB Earthed: White LED indication VCB In Service Position Amber in- dication.	LED	YES	4.3.1 .2	
Local Remote selector switch		YES		
Circuit Earthing Facilities		Bottom Entry	4.3.2 .2 a)	
System Earthing		NER 300 A,20Ω Max	4.2.8 .2	
Cable Entry		Bottom Entry	4.3.1 .1.3	
Main Cable Detail		70 to 240mm <sup>2</sup> x 3core XLPE/PILC 300 to 500mm <sup>2</sup> Single Core Cable	4.3.1 .9	
Main Cable Termination		PVC wedge cleat 70 to 240 mm <sup>2</sup> Cable. PVC wedge cleat 300 to 500 mm <sup>2</sup>		
Circuit Earthing Facility		Yes		
Interlocks		Yes	4.2.8 .1	
Surge Arrestors (suppressors)		Yes		
Remote Control Unit. Panel fitted with cannon standoff trip/close socket.		Open and Close	4.2.7	
Panel heater (220V)		YES		
VCB Chamber light (110VDC)		YES		
<b>DIMENSIONS</b>			4.3.1 .7	
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes		
Purpose		OC / EF	4.8	
Ratio		600/1		
Burden		10VA		
Class		5P20		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Differential)		YES		
Purpose		FEEDER	4.8	

Burden		kPV = 300V		
Ratio		600/1		
Class		X/TPS/PX		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (OC/EF)		
Install Ct's (Metering)		YES		
Purpose		Metering	4.8	
Burden		600/300/200/1		
Ratio		10VA		
Class		0.5		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (Diff / Metering)		
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14. 4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		YES	4.14. 4	
Phase Selector Switch		YES		
<b>GENERAL:</b>				
Configuration of Switchgear				
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes (Blank)	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state. Auto Re-Close: 3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		Yes: The Relay must have these capabilities:  <b>i Power Supply:</b> Universal – 110 to 240 Vac/VDC. <b>ii Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input. <b>iii Voltage Input:</b> VNOM (L-L) should have the following specifications: 20 to 440V for DELTA_Y for DELTA and WYE <b>iv Configurable labels:</b> Yes <b>v Programmable pushbuttons:</b> Minimum of four programmable	4.10	

		<p>pushbuttons, each with programmable LEDs</p> <p><b>vi Front panel LEDs:</b> Status and Trip Target LEDs</p> <p><b>vii Communication</b></p> <p><b>Ports:</b> Rear: 1 x 10/100 base-T plus 1 x 1 RS 232 port. Front: 1 x Serial Port</p> <p><b>viii Communications Protocol:</b> Should have the following protocols: DNP3 level 2 minimum, standard plus IEC 61850, Modbus RTU, Modbus TCU,</p> <p><b>ix Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 110 Vac/VDC digital inputs with an operating range of 88 to 137,5 VDC (External wetting); Inputs should be individually user-configured to operate.</p> <p><b>x High Speed, High current Interruption (Outputs):</b> Minimum of 6A continuous current – Minimum of 8 Universal – with a rated operating voltage of 264 VDC and a rated voltage range of 19.2 to 275 VDC. Should have a mechanical durability with a minimum of 100 000 no load operations."</p> <p><b>xi Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p><b>xii Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>xiii Protection elements:</b> Relay should have the following elements: Phase, neutral, residual, and negative-sequence overcurrent elements; Phase, neutral, residual, and negative-sequence time-overcurrent elements; Current-based over- and under frequency; Arc-</p>		
--	--	---	--	--

		flash detection and arc-flash overcurrent; Over- and under voltage; Power elements; Voltage-based over- and under frequency; Rate-of-change of frequency; Measured residual overcurrent		
High Speed Pilot wire protection- "Solkor R or RF" or compatible. Differential protection.		Pilot wire Protection Relay, 1A or 5A and must be compatible with Solkor R/RF Relay.	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's 110VDC	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

**6.4.22 (B) Incomer 110VDC panel: Tender must be for single and double busbars. (Upper bar / Lower bar and Front / back bar) with complete busbars.**

<b>SCHEDULE 12: SBV 3 E FEEDER PANEL COMPATIBLE WITH ALL SWITCHGEAR PANELS (110VDC)</b>		<b>PART C – METAL-CLAD SWITCHGEAR</b>		
<b>DESCRIPTION OF PARTICULARS NOTE: PANEL MUST BE MARKED</b>	<b>UNITS</b>	<b>SPECIFIED REQUIREMENT</b>	<b>SANS CLAUSE</b>	<b>PARTICULARS OFFERED AND GUARANTEED</b>
Panel Function		Feeder		
Insulation Medium		Vacuum		
System Voltage	kV	11	4.3.2.1.6	
Rated Voltage	kV	12	4.1.1.1	
Circuit Normal Rated Current	Amp	800	4.1.1.1	
Busbar Normal Rated Current	Amp	2500	4.1.1.3	
Fault Level Capacity	MVA	350	4.1.1.3	
Impulse Withstand Voltage	kV	95	4.1.1.3	
Short Circuit Breaking Capacity	kA	20	4.1.1.4.2	
Duration of Short Circuit	s	3	4.1.1.5	
Peak Withstand Current	kA	63	4.1.1.5	
Mechanism Type	M.W.S	Auto spring charges	4.1.1.5	
Trip Coil 120VDC	V	YES	4.3.1.9	
Spring Release Coil 110VDC	V	YES	4.3.1.10	
Indication for Trip/Close 110VDC		YES	4.3.1.10	
Status Indication Lamps (open/close)	LED	YES	4.3.1.2	

VCB open; Green LED indication. VCB Close: Red LED indication VCB Earthed: White LED indication VCB In Service Position Amber indication.				
Local Remote selector switch		YES		
Circuit Earthing Facilities		Bottom Entry	4.3.2.2 a)	
System Earthing		NER 300 A, 20Ω Max	4.2.8.2	
Cable Entry		Bottom Entry	4.3.1.1.3	
Main Cable Detail		70 to 240mm <sup>2</sup> x 3core XLPE/PILC 300 to 500mm <sup>2</sup> Single Core Cable	4.3.1.9	
Main Cable Termination		PVC wedge cleat 70 to 240 mm <sup>2</sup> Cable. PVC wedge cleat 300 to 500 mm <sup>2</sup>		
Circuit Earthing Facility		Yes		
Interlocks		Yes	4.2.8.1	
Surge Arrestors (suppressors)		Yes		
Remote Control Unit. Panel fitted with cannon standoff trip/close socket.		Open and Close	4.2.7	
Panel heater (220V)		YES		
VCB Chamber light (110VDC)		YES		
<b>DIMENSIONS</b>			4.3.1.7	
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes		
Purpose		OC / EF	4.8	
Ratio		600/1		
Burden		10VA		
Class		5P20		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Differential)		YES		
Purpose		FEEDER	4.8	
Burden		kPV = 300V		
Ratio		600/1		
Class		X/TPS/PX		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (OC/EF)		
Install Ct's (Metering)		YES		
Purpose		Metering	4.8	
Burden		600/300/200/1		
Ratio		10VA		
Class		0.5		
Quantity		3		
Insulation Level		IL 12/28/95 KV		

Install test block PK2-4way		YES (Diff / Metering)		
<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		11000/110/63.5 Volts		
Burden and Accuracy		100 VA Class 0.5		
Voltage Factor		1.9		
Limbs		3 or 5		
Primary Connection		Cable side		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		YES	4.14.4	
Phase Selector Switch		YES		
<b>GENERAL:</b>				
Configuration of Switchgear				
Spare auxiliary Contacts required		"a"-2	4.14	
		:b"-2		
Marking/Labeling/Documentation		Yes (Blank)	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state. Auto Re-Close: 3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		Yes: The Relay must have these capabilities:  <b>i Power Supply:</b> Universal – 110 to 240 Vac/VDC. <b>ii Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input. <b>iii Voltage Input:</b> VNOM (L-L) should have the following specifications: 20 to 440V for DELTA_Y for DELTA and WYE <b>iv Configurable labels:</b> Yes <b>v Programmable pushbuttons:</b> Minimum of four programmable pushbuttons, each with programmable LEDs <b>vi Front panel LEDs :</b> Status and Trip Target LEDs <b>vii Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port	4.10	

	<p><b>viii Communications Protocol:</b> Should have the following protocols: DNP3 level 2 minimum, standard plus IEC 61850, Modbus RTU, Modbus TCU,</p> <p><b>ix Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 110 Vac/VDC digital inputs with an operating range of 88 to 137,5 VDC (External wetting); Inputs should be individually user-configured to operate.</p> <p><b>x High Speed, High current Interruption (Outputs):</b> Minimum of 6A continuous current – Minimum of 8 Universal – with a rated operating voltage of 264 VDC and a rated voltage range of 19.2 to 275 VDC. Should have a mechanical durability with a minimum of 100 000 no load operations."</p> <p><b>xi Arc Flash capability:</b> 4 x Arc Flash detection inputs. <b>Four Fiber-optic point sensors for ARC flash must be provided with the relay.</b></p> <p><b>xii Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>xiii Protection elements:</b> Relay should have the following elements: Phase, neutral, residual, and negative-sequence overcurrent elements; Phase, neutral, residual, and negative-sequence time-overcurrent elements; Current-based over and under frequency; Arc-flash detection and</p>	
--	---	--

		arc-flash overcurrent; Over-and under volt- age; Power elements; Voltage-based over- and under frequency; Rate-of-change of fre- quency; Measured re- sidual overcurrent		
High Speed Pilot wire protection- “Solkor R or RF” or compatible. Differential protection.		NO	4.10	
Arc Flash Sensors		Cable, Circuit Break- er and Busbar chamber	4.10	
D.C Circuit Protection		MCB’s 110VDC	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

**6.4.23 (C) Bus Coupler 110VDC panel: Tender must be for single and double busbars.  
(Upper / Lower bar and Front / back bar) with complete busbars and boxes.**

SCHEDULE 12: SBV 3 E FEEDER PANEL COMPATIBLE WITH ALL SWITCHGEAR PANELS (110VDC)			PART C – METAL-CLAD SWITCHGEAR		
DESCRIPTION OF PARTICU- LARS NOTE: PANEL MUST BE MARKED	UNI TS	SPECIFIED RE- QUIREMENT	SANS CLAUSE	PAR- TICILARS OFFERED AND GU- RANTEED	
Panel Function		Feeder			
Insulation Medium		Vacuum			
System Voltage	kV	11	4.3.2.1.6		
Rated Voltage	kV	12	4.1.1.1		
Circuit Normal Rated Current	Amp	800	4.1.1.1		
Busbar Normal Rated Current	Amp	2500	4.1.1.3		
Fault Level Capacity	MVA	350	4.1.1.3		
Impulse Withstand Voltage	kV	95	4.1.1.3		
Short Circuit Breaking Capacity	kA	20	4.1.1.4.2		
Duration of Short Circuit	s	3	4.1.1.5		
Peak Withstand Current	kA	63	4.1.1.5		
Mechanism Type	M.W .S	Auto spring charges	4.1.1.5		
Trip Coil 120VDC	V	YES	4.3.1.9		
Spring Release Coil 110VDC	V	YES	4.3.1.10		
Indication for Trip/Close 110VDC		YES	4.3.1.10		
Status Indication Lamps	LED	YES	4.3.1.2		

(open/close) VCB open; Green LED indication. VCB Close: Red LED indication VCB Earthed: White LED indication VCB In Service Position Amber indication.				
Local Remote selector switch		YES		
Circuit Earthing Facilities		Bottom Entry	4.3.2.2 a)	
System Earthing		NER 300 A, 20Ω Max	4.2.8.2	
Cable Entry		Bottom Entry	4.3.1.1.3	
Main Cable Detail		70 to 240mm <sup>2</sup> x 3core XLPE/PILC 300 to 500mm <sup>2</sup> Single Core Cable	4.3.1.9	
Main Cable Termination		PVC wedge cleat 70 to 240 mm <sup>2</sup> Cable. PVC wedge cleat 300 to 500 mm <sup>2</sup>		
Circuit Earthing Facility		Yes		
Interlocks		Yes	4.2.8.1	
Surge Arrestors (suppressors)		Yes		
Remote Control Unit. Panel fitted with cannon standoff trip/close socket.		Open and Close	4.2.7	
Panel heater (220V)		YES		
VCB Chamber light (110VDC)		YES		
<b>DIMENSIONS</b>			4.3.1.7	
Height	mm	Max 1800		
Depth	mm	Max 1500		
Width	mm	Max 600		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes		
Purpose		OC / EF	4.8	
Ratio		600/1		
Burden		10VA		
Class		5P20		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Differential)		YES		
Purpose		FEEDER	4.8	
Burden		kPV = 300V		
Ratio		600/1		
Class		X/TPS/PX		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (OC/EF)		
Install Ct's (Metering)		YES		
Purpose		Metering	4.8	
Burden		600/300/200/1		
Ratio		10VA		
Class		0.5		
Quantity		3		

Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (Diff / Metering)		
<b>VOLTAGE TRANSFORMER</b>				
Install VT		No	4.9	
Ratio		N/A		
Burden and Accuracy		N/A		
Voltage Factor		N/A		
Limbs		N/A		
Primary Connection		N/A		
<b>AMMETER:</b>				
Scale		No	4.14.4	
Interposing CT		N/A		
Maximum Demand Indicator		N/A		
<b>VOLTMETER:</b>				
Voltmeter		YES	4.14.4	
Phase Selector Switch		YES		
<b>GENERAL:</b>				
Configuration of Switchgear				
Spare auxiliary Contacts required		“a”-2	4.14	
		:b”-2		
Marking/Labeling/Documentation		Yes (Blank)	4.17	
Main Circuit Designation Label		Blank	4.17	
<b>PROTECTION:</b>				
Sensitive Earth Fault – Time delay range 0.01-25 sec – solid state. Auto Re-Close: 3Pole Multi Shot Auto-Reclose Relay – min. 4 Shot Programmable with counter-solid state		Yes: The Relay must have these capabilities:  <b>i Power Supply:</b> Universal – 110 to 240 Vac/VDC. <b>ii Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input. <b>iii Voltage Input:</b> VNOM (L-L) should have the following specifications: 20 to 440V for DELTA_Y for DELTA and WYE <b>iv Configurable labels:</b> Yes <b>v Programmable pushbuttons:</b> Minimum of four programmable pushbuttons, each with programmable LEDs <b>vi Front panel LEDs:</b> Status and Trip Target LEDs <b>vii Communication Ports:</b> <b>Rear:</b> 1 x 10/100 base-T plus 1 x 1 RS 232 port. <b>Front:</b> 1 x Serial Port <b>viii Communications Protocol:</b> Should have	4.10	

the following protocols:  
DNP3 level 2 minimum,  
standard plus IEC  
61850, Modbus RTU,  
Modbus TCU,  
**ix Digital Optoisolated  
Inputs:** Minimum of 8.  
Universal – 110  
Vac/VDC digital inputs  
with an operating range  
of 88 to 137,5 VDC (Ex-  
ternal wetting); Inputs  
should be individually  
user-configured to op-  
erate.

**x High Speed, High  
current Interruption  
(Outputs):** Minimum of  
6A continuous current –  
Minimum of 8 Universal  
– with a rated operating  
voltage of 264 VDC and  
a rated voltage range of  
19.2 to 275 VDC.  
Should have a mechan-  
ical durability with a  
minimum of 100 000 no  
load operations."

**xi Arc Flash capabil-  
ity:** 4 x Arc Flash detec-  
tion inputs. Four Fiber-  
optic point sensors for  
ARC flash must be pro-  
vided with the relay.

**xii Software:** Windows-  
based PC software for  
setting, report retrieval,  
metering, HMI, and  
control; At no additional  
costs (free issue with  
the relay).

**xiii Protection ele-  
ments:** Relay should  
have the following ele-  
ments: Phase, neutral,  
residual, and negative-  
sequence overcurrent  
elements; Phase, neu-  
tral, residual, and nega-  
tive-sequence time-  
overcurrent elements;  
Current-based over-  
and under frequency;  
Arc-flash detection and  
arc-flash overcurrent;  
Over-and under volt-  
age; Power elements;  
Voltage-based over-  
and under frequency;

		Rate-of-change of frequency; Measured residual overcurrent.		
High Speed Pilot wire protection- "Solkor R or RF" or compatible. Differential protection.		NO	4.10	
Arc Flash Sensors		Cable, Circuit Breaker and Busbar chamber	4.10	
D.C Circuit Protection		MCB's 110VDC	4.14.3	
Location of Fuses inside RC		Yes		
Location of Test Terminal Blocks RC Door		Yes	4.14.7	
Number of copies of Drawings supplied with Panel on delivery		2	7.3	
Number of copies of Routine Test Report Certificates on delivery		2	7.4	

**6.4.24 Description of the 12kV and 22kV Joint (J)-, Switch (S)-, Test (T) - AND Panel (P)-packs according, to SANS 1885: 2001 and latest amendments, for 400A, 800A and 2000A specifications.**

Detail breakdown of "P, J, T and S-Packs"			
DESCRIPTION	QTY	Part No.	COMMENTS
<b>"P-pack" (A12.1)</b>			
38w scotch fill putty	18		1 set per panel. Packed in one box and labeled "P-pack".
Electrical scotch no 23 tapes	9		
18w no 33 tapes	18		
250 ml tin panel touch-up paint	1		
All bolts to bolt panels together (sink coated)	Box		
Busbar end covers (Painted red)	2		
100mm x 10 mm anchor bolts and nuts	6		
<b>"J-pack" (A12.2)</b>			
6x25mm inter panel earth bar	1		1 set per panel. Packed in one box labeled "J-pack".
800 Amp insulated, tinted busbars	3		
800 Amp lh/half joint shroud	3		
800 Amp rh/half joint shroud	3		
M12 washers for busbars	12		
M12 x 55 high tension busbar bolts (sink coated)	6		
M12 nuts	6		
M12 spring washers	6		
Insulated-lock cable ties	6		
<b>"S-pack" (A12.3)</b>			
Circuit breaker ramp plate	1		1 set as per order. Packed in one box labeled "S-pack".
Circuit breaker spring charge handle	1		
Circuit breaker racking handle	1		
Hand-held remote control (pendant control 15m extension lead)	1		

Wall mounted bracket for all items in "S-pack"	1		
<b>"T-pack" (A12.4)</b>			
Tests spouts	1		1 set as per order. Packed in one box labeled "T-pack".
Circuit breaker wear gauge	1		
Trolleys (if applicable)	1		
Set of special tools (if applicable)	1		

### 6.4.25 Schedule Packs

ITEM	DESCRIPTION	SPECIFIC REQUIREMENT	SANS CLAUSE	PARTICULARS OFFERED AND GUARANTEED
A12.1	Panel Packs as specify in description 5.4.12 above	As per SANS	4.15.1	
A12.2	Jointing Packs as specify in description 5.4.12 above	As per SANS	4.15.2	
A12.3	Switchboard Accessories Packs as specify in description 5.4.12 above	Yes – Wall mounted	4.15.3	
A12.4	Test Packs as specify in description 5.4.12 above	As per NRS	4.15	

**Part B:** Fixed pattern metal clad ring main unit and associated accessories according to the applicable standards, non-extendable.

### 6.5.1 Ring Main Units

SCHEDULE B1; B2, B3: - METAL ENCLOSED RING MAIN UNITS				
DESCRIPTION OF PARTICULARS:	UNITS	SPECIFIED REQUIREMENTS	SANS 1874 CLAUSE S	PARTICULARS OFFERED AND GUARANTEED (SCHEDULE B)
Manufacturer				
Country of origin				
Catalogue/Type designation				
Total switchgear mass	kg	Total mass with kiosk		
Nominal voltage	kV	12		
Rated voltage	kV	12	4.1.1	
Circuit rated normal current	A	200 to 630 (LV fuse Units)	4.3.1.2	
Busbar rated normal current	A	630		
System earthing method	A	NER - 300 A maximum, 20Ω		
Fault breaking capacity	MVA	350		
Fault making capacity	kA	33,4		
Through fault rating for 3 seconds	kA	20		
Standard 1/50 microsecond impulse rating at sea level	kV	95		
Is an indoor or outdoor unit required?		Indoor/outdoor	4.2.1.5	
Is an extensible or non-extensible unit required?		Non- extensible	4.2.2.1	
Degree of protection of unit offered			4.2.3.2	

Specify the configuration		<p><b>B1.</b> Ring main unit with fused transformer t-off feeder – without metering, fitted inside metal clad outdoor kiosk. (Preferably SF6 gas)</p> <p><b>B2.</b> Ring main unit with fused Medium Voltage connection feeder – with metering unit, fitted inside metal clad outdoor kiosk. The CT's must be fitted in the cable connection box, easily accessible when test or replaced. The CT, s must be studded for secondary wiring and numbering. The Power transformer fuses on the secondary side must be easily accessible for testing.</p> <p><b>B3.</b> Ring main unit with two fused t-off feeders- One with metering for medium voltage connection feeder and the other one without metering for a transformer, fitted inside metal clad outdoor kiosk. The CT's must be fitted in the cable connection box of the medium voltage connection, easily accessible when test or replaced. The CT's must be studded for secondary wiring and numbering. The Power transformer fuses on the secondary side must be easily accessible for testing or replacement.</p>	4.2.4	
Integral cable earth facility with lock-out mechanism required		Yes	4.2.5.1	
Type of cable testing facility offered		1	4.2.5.2	
The insulation medium, or the interruption medium (or both) of switch disconnectors, if there is a preference		SF6 Gas and oil is preferred as insulation medium. Price on both.	4.3.2.1	
The insulating medium, or the interrupting medium (or both) of switch disconnectors offered			4.3.2.2	
Maximum transformer load to be protected	kVA	1000	4.4.2.1	
Rated current of fuse link	A	35.5 to 63 (Max)	4.2.1.5	
Type of fuse link offered		Fuse – Striker pin type HRC HT	4.2.2.1	
Dimensions of fuse link offered			4.2.3.2	
Metering CT/PT unit to fit fused isolator		60-30/5 10 VA Class 0.5	4.4.3.2	
Metering Potential Transformer		11kV/110V Star/Star 100VA Class 0.5 Dry type with remote secondary terminals. Low voltage PT fuses must be outside.	4.4.3.3	
Type of protection required on transformer feeder		Fuse– striker pin type HRC HT	4.5.2.1	
What is the insulation medium of the busbar chamber?			4.6.5	

Is a cable boxes required?		Yes	4.7.1.1	
Compound-filled or air-filled cable box required?		Air filled	4.7.1.2	
Cable type		PILC or XLPE	4.7.1.3	
Maximum size(s)		35mm to 185 mm		
Dimensions of cable trench: aa) depth bb) width	mm mm	400 600	4.7.1.4	
Termination type		Heat Shrink	4.7.2.2	
Are only type C bushings required?		Yes	4.7.4.2	
Are the accessories for cable terminations to be supplied		No	4.7.5.1	
Are cable glands to be insulated and fitted with an earth strap?		No	4.7.5.2	
Required method of clamping the cables		PVC wedge cleats	4.7.5.4	
Is a pressure-checking device required?		Yes, If it is SF6 gas and Oil level glass if it is oil filled.	4.9.3	
Quantity of SF <sub>6</sub>	l	Indicate the unit gas pressure.	4.9.5	
Recommended types of tools to install and maintain unit		All special tools must be supplied on order if specified. SF6 gauges and fitting must be supplied with switchgear.	4.14.2	
Method used to attach rating plates		Screwed on	4.15.1	
Method used to attach labels		Screwed on	4.16.1.1	
Is engraving of main circuit designation labels required?		No	4.16.2.5	
If yes, state details		Leave it blank		
Colour of unit		Light - grey	4.17.4	
Is the ring main unit required for a corrosive or a non-corrosive environment?		Non-corrosive	4.17.7	
Details of internal arc tests		Supply test certificates	5.1.3	
Documentation required		Supply all factory tests	5.2(k)	
Number of sets of manuals required, if more than one set		One per each unit delivered.	6.1	
All mounting material necessary to mount the unit is to be supplied with every unit				

### 6.5.2 Supply and/or repairs of NULEC N-series ACR N12 Pole mounted Automatic Circuit Reclosing Breakers (12 kV).

The N-Series three phase pole/structure mounted auto recloser circuit breaker, must be Sf6 gas filled with vacuum arc interrupters. Supply with integrated CT's and Vt's and with remote control complete with all the brackets and small cabling. Complete with pole top and communication cubicle. **The replacement of the existing Switchgear and Control Panels, with equivalent and compatible equipment, is required should the existing equipment be discontinued or obsolete.**

1.	Rated Voltage	15 kV
2.	Rated Short circuit current	16kA
3.	Rated Load Current	800Amp
4.	Stainless Steel Tank	316 grades, Sf6 gas filled
5.	Arc Interruption	Vacuum
6.	Battery back up	24 VDC (2X12VDC, 7Ah)
7.	Battery charger	24VDC
8.	Sf6 gas refill kit Nulec	Connecting fittings, pipes and gauges. Complete set.
9.	SCADA	Supporting DNP3 Protocol – Level 2

### 6.5.3 Supply and/or repairs of NULEC N-series ACR N12 Pole mounted Automatic Circuit Reclosing Breakers (36 kV).

1.	Rated Voltage	36 kV
2.	Rated Short circuit current	40 kA
3.	Rated Load Current	800Amp
4.	Stainless Steel Tank	316 grades, Sf6 gas filled
5.	Arc Interruption	Vacuum
6.	Battery back up	24 VDC (2 x 12VDC, 7Ah)
7.	Battery charger	24VDC
8.	Sf6 gas refill kit Nulec	Connecting fittings, pipes and gauges. Complete set.
9.	SCADA	Supporting DNP3 Protocol – Level 2


### 6.5.4 Magnefix Type MF disconnecter switch

The Magnefix MF disconnecter switches must be supplied complete with brackets and fuses to fit in a miniature substation HT kiosk.

<b>MAGNEFIX TYPE MF</b>		
1.	Cable unit	105 mm
2.	Busbar connection unit	105 mm
3.	Cable unit for top connection	210 mm
4.	Busbar Sectionalizer	210 mm
5.	Fuse protection tee-off	244 mm (30.5 Amp fuses)
6.	Circuit-breaker protection tee-off	-
7.	Total width calculations	$B = C \times 105 + T \times 244 + 72$
(C= number of cable units, T = number of protected tee-offs)		

<b>Magnefix type MF</b>						
1.	Normal current	A	450	450	450	450
2.	Mainly active load breaking current	A	450	450	450	450

3.	Short-circuit making current peak value	kA	50	50	50	50
4.	Short time withstand current	kV - 1s	20	20	20	20
5.	Earth fault breaking current	A	240	240	240	240
6.	Cable charging breaking current	A	25	25	25	25
7.	Normal current	A	450	450	450	450



Picture on the right Magnefix MF

**Part C:** Vacuum circuit breakers to replace AG16 oil type circuit breakers and the repairs of 12kV switchgear on adhoc quotation bases. **(Retrofit)**The service provider will be responsible for strip and quote quotations on repairs of 11kV switchgear and related equipment and the transport from Bloemfontein to their premises and back.

**SCHEDULE C1: VACUUM CIRCUIT BREAKER REPAIR AND RETROFIT (NOTE: No alternations to panel will be allowed, the new vacuum breaker must fit in existing panel)**

**6.5.5 A. Existing Switch Gear GEC, AG16, to vacuum.**

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	RE-	SANS 1874 CLAUSE	PARTICULARS OFFERED AND GUARANTEED SCHEDULE C
Manufacturer					
Country of origin					
Catalogue/Type designation					
Total switchgear mass	kg				

Nominal voltage	kV	11		
Rated voltage	kV	12	4.1.1	
Circuit rated normal current	A	800	4.3.1.2	
Busbar rated normal current	A	800		
Fault breaking capacity	MVA	350		
Fault making capacity	kA	33,4		
Through fault rating for 3 seconds	kA	20 kA		
Standard 1/50 micro-second impulse rating at sea level	kV	95		
Circuit Breaker to fit Panel		GEC type AG16 (without any alternations to the existing panel)		

**B. Existing Switchgear Reyrolle LMS, LMR, LMT to VD4-LMT ABB-Reyrolle CB. (Vacuum)**

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	SANS 1874 CLAUSE	PARTICULARS OFFERED AND GUARANTEED SCHEDULE C
Manufacturer				
Country of origin				
Catalogue/Type designation				
Total switchgear mass	kg			
Nominal voltage	kV	11		
Rated voltage	kV	12	4.1.1	
Circuit rated normal current	A	1250	4.3.1.2	
Busbar rated normal current	A	1250		
Fault breaking capacity	MVA	350		
Fault making capacity	kA	31.5		
Through fault rating for 3 seconds	kA	20 kA		
Standard 1/50 micro-second impulse rating at sea level	kV	95		
Circuit Breaker to fit Panel		Circuit Breaker to fit in existing panel without alternations to panel.		
<b>Replacement of Reyrolle Panel, Current transformers and Voltage Transformers.</b>				
Reyrolle Panel complete with busbars and shutters.	A	1250		

<b>VOLTAGE TRANSFORMER</b>				
Install VT		Yes	4.9	
Ratio		11000/110/63.5 Volts		
Burden and Accuracy		100 VA Class 0.5		
Voltage Factor		1.9		
<b>CURRENT TRANSFORMERS:</b>		<b>Studded 6mm Brass S connections.</b>		
Install CT's		Yes		
Purpose		OC / EF	4.8	
Ratio		600/1		
Burden		10VA		
Class		5P20		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install Ct's (Differential)		Yes		
Purpose		Diff	4.8	
Burden				
Ratio		600/1		
Class		X or TPS or PX		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (OC/EF)		
Install Ct's (Metering)		YES		
Purpose		Metering	4.8	
Burden		600/300/200/1		
Ratio		10VA		
Class		0.5		
Quantity		3		
Insulation Level		IL 12/28/95 KV		
Install test block PK2-4way		YES (Diff / Metering)		
Required method of clamping the cables		PVC wedge cleats	4.7.5.4	

**6.5.6 Existing Switch Gear. The following Existing Circuit breakers must be repaired: (Strip & Quote)**

<b>Make</b>	<b>Type</b>
Reyrolle LMS	LMS/X1/QMRO
Reyrolle LMR	LMR/X2/QMRO
Reyrolle LMT	LMT2/X31/QM
Actom	SBV4E/2000/25/SI
Johnson & Phillips	PDB/A/2Z and TSB16
GEC	PDB/A/400
HAWKER SIDDELEY	VIL-6 and R4/1 and V4/1 and D6XD
FIRST ELECTRIC	JB621
BRUSH	W4/11 and S4

LONG & CRAWFORD	AVS2
ALSTOM	AGVB-800/20/S and SBV4/800/20-S1
SACE BERGAMO	RM1235
BRITISH THOMPSON	BTH/JB621 and LC/B3
BRUSH	W4/11
NULEC	N24S-ACR-SF6-24-12-150
JG STATTER	VTGR150
YORKSHIRE	YSF6
RMU Actom	K3 oil and gas
RMU Magenefix	Dry Type Air
RMU GEC	T3 oil
RMU ABB	Gas
RMU Schneider	Gas
RMU Tiger	oil
Nulec switchgear outdoor pole mounted.	Sf6 Gas

**6.5.7 Supply of switching- and spring charges handles on the following types of existing switchgear.**

<b>Make</b>	<b>Type</b>
Reyrolle LMS	LMS/X1/QMRO
Reyrolle LMR	LMR/X2/QMRO
Reyrolle LMT	LMT2/X31/QM
Actom	SBV4E/2000/25/SI
Johnson & Phillips	PDB/A/2Z and TSB16
GEC	PDB/A/400
HAWKER SIDDELEY	VIL-6 and R4/1 and V4/1 and D6XD
FIRST ELECTRIC	JB621
BRUSH	W4/11 and S4
LONG & CRAWFORD	AVS2
ALSTOM	AGVB-800/20/S and SBV4/800/20-S1
SACE BERGAMO	RM1235
BRITISH THOMPSON	BTH/JB621 and LC/B3
BRUSH	W4/11
NULEC	N24S-ACR-SF6-24-12-150
JG STATTER	VTGR150
YORKSHIRE	YSF6
RMU Actom	K3 oil and gas
RMU Magenefix	Dry Type Air
RMU GEC	T3 oil
RMU ABB	Gas
RMU Schneider	Gas
RMU Tiger	oil
Nulec switchgear outdoor pole mounted.	Sf6 Gas

## 7. HEALTH AND SAFETY REQUIREMENTS

- 7.1 All the equipment must be plastic wrapped and secure when transport.
- 7.2 All the Items must be properly labeled with sticker, after wrapping, to identify the offloading without unwrapping the plastic rapping.
- 7.3 The offloading of equipment on CENTLEC premises must be done safely.
- 7.4 All chemical data sheets must be delivered with equipment.
- 7.5 Maintenance manuals must be delivered with equipment.

## 8. EVALUATION CRITERIA

All proposals submitted will be evaluated in accordance with the criteria set out in the policy of Supply Chain Management of the Entity.

The most suitable candidate will then be selected. Please take note that CENTLEC is not bound to select any of the bidders' submitting proposals.

Furthermore, technical competence is the principal selection criteria, CENTLEC will evaluate the technical criteria first, and will only look at the price and BBEE level of contribution if it is satisfied with the technical evaluation. As a result of this, CENTLEC does not bind itself in any way to select the bidder offering the lowest price.

The relative specific goal criteria are as follows:

No.	Criteria	Description	Points
8.1	Track record and experience	Submit reference letter(s), signed off by an authorised official to confirm the successful completion of manufacturing, supplying, and delivering of similar equipment to a local authority.  Two (2) letters = <b>10 points</b> Three (3) or more letters = <b>20 points.</b>	20
8.2	Capability	The bidder(s) must provide proof of their ability to manufacture this equipment by submit prove of the following: (Submit contracts of agreements, on signed letter head, if outsourced, for the duration of contract.)  Manufacturer Licensed facility = <b>10 Points</b> Testing facilities (submit a valid accreditation certificate) = <b>10 Points</b> Field services for installation (Letter of commitment) = <b>10 Points</b>	30
8.3	Technical schedules	Did the Manufacturer complete all the Schedules and submit it? <b>Spare list must be completed = 30 Points</b>	30

No.	Criteria	Description	Points
8.4	Guarantee and Warranty	Submit Ten Year (10) warranty and guarantee that is signed by the manufacturer of the relays = <b>10 points</b>	10
8.5	Local (Mangaung) operational capability and economic investment	Does the bidder have a local office with operational capability? (a) Existing and established local office = <b>10 points</b> (b) If not, but within RSA = <b>5 points</b>	10
<b>TOTAL</b>			<b>100</b>

A bidder who gets a minimum of 85 points and above will qualify to the next stage. Individual tenders would have to be evaluated according to the preferential point system.

The bidder must score minimum points as follows:

Item 1 – 10 points

Item 2 – 30 points

Item 3 – 30 points

Item 4 – 10 points

Item 5 – 5 points in the Evaluation Criteria.

## 8.2. PRICE AND REFERENTIAL POINTS SCORING – STAGE 2 (Price and B-BBEE status)

All Bidders that have passed the technical evaluation threshold of 85 points would also be scored based the 90/10 principle where 90 Points is for the Price and 10 points for B-BBEE as per the detail given below.

### 8.3 Points awarded for price

A maximum of 90 Points is allocated for price on the following basis:

$$\text{Where } P_s = 90 \left[ 1 - \frac{P_t - P_{\min}}{P_{\min}} \right]$$

$P_s$  = Points Scored for comparative price of bid under consideration

$P_t$  = Comparative Price of bid under consideration

$P_{\min}$  = Comparative Price of lowest acceptable bid

## 8.4POINTS AWARDED FOR SPECIFIC GOALS

In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in table below as may be supported by proof/ documentation stated in the conditions of this tender:

### Specified Goals for Preferential Point System

<b>Specified Goals</b>	<b>Points Allocation</b>
50% Black owned	10
50% Women owned	5
50% Youth owned <35 years	5
<b>Total Points</b>	<b>20</b>

Table 3: Specified Goals

## 8. PRICING SCHEDULES

### 8.1 Quotation Price

8.1.1 The bid price(s) shall be SEIFSA based priced

8.1.2 The bid price(s) shall be subject to negotiated increase, if absolutely unavoidable, should the contract be extended for one or more further periods, each period not exceeding 12 months.

**PRICE SCHEDULE FOR SPARES, Current transformers on special order. (Ad-hoc purchase)** Prices must exclude VAT and include delivery to our CENTLEC stores.

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
1	100-50/5, 10 VA, Class 0.5 IL12/28/75 kV	Each			
2	100-50/10VA, 10P10 IL12/28/75 kV	Each			
3	Combined CT, 100-50/5, 10 VA Class 0.5, IL12/28/75 kV 100-50/5, 10VA, 10P10 IL12/28/75 kV	Each			
4	Combined CT 100-50/5, 10 VA Class 0.5, IL12/28/75 kV 600/1, 10VA, 10P10 IL12/28/75 kV	Each			
5	300-200-100/5, 10VA, Class 0.5 IL12/28/75 kV 600/1, 10VA, 10P10 IL12/28/75 kV	Each			
6.	60/30/5, 10VA, 10P10, Ring type IL12/28/75 kV	Each			
7.	600/5, 10VA, 10P10, Ring Type	Each			

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	IL12/28/75 kV				
8	60-30/5, 10 VA, Class 0.5, IL12/28/75 kV	Each			
9	100-50/5, 10 VA, Class 0.5, IL12/28/75 kV	Each			

**NOTE: PRICES OF SPARES, for existing infrastructure, on the SBV3, SBV4, GEC, J&P and English Electrical Switch gear. Please include circuit breaker list for spares. Prices must exclude VAT and include delivery to our CENTLEC stores.**

Item	Description	Unit of Measurement	Manufacturer	Unit Price in (R)	Delivery Time
1	32 Volt trip coil	Each			
2	32 Volt closing coil	Each			
3	110 Volt trip coil	Each			
4	110 Volt Closing coil	Each			
5	110 Volt DC Spring charges motor	Each			
6	Circuit Breaker Contacts 400 Amp	Set of Three			
7	Circuit Breaker Contacts 800 Amp	Set of Three			
8	Circuit Breaker contacts 1600 Amp	Set of Three			
9	Circuit Breaker contacts 2000 Amp	Set of Three			
10	Vacuum Bottle replacement per set 400 Amp	Set of Three			
11	Vacuum Bottle replacement per set 1600 Amp	Set of			

Item	Description	Unit of Measurement	Manufacturer	Unit Price in (R)	Delivery Time
		Three			
12	Vacuum Bottle replacement per set 2000 Amp	Set of Three			
13	SF6 gas gauges for refilling of Sf6 gas	Set of Three			
14	Auxiliary contacts rotor switch for 110 Volt breaker	Each			
15	Auxiliary contacts rotor switch for 32 Volt breaker	Each			
16	Set of limit switches per circuit breaker	Per/set			
17	Touch-up paint 1 litre tin for panels	500ml			
18	400Amp Copper Busbars silver plated per/set of 3 with all Bolts & nuts	Set of Three			
19	Set of Three (3) 400 Amp Cable side spouts (Mono blocks)	Set of Three			
20	Set of Three (3) 400amp Busbar side spouts (Mono blocks)	Set of Three			
21	Set of Three (3) 800 Amp Cable side spouts (Mono blocks)	Set of Three			
22	Set of Three (3) 800amp Busbar side spouts (Mono blocks)	Set of Three			
23	Set of Three (3) 2000amp Busbar side spouts (Mono blocks)	Set of Three			
24	Set of Three (3) 2000 Amp Cable side spouts (Mono blocks)	Set of Three			
25	LED type lamp indicator Red, Yellow, Clear and green.	Set of Three			
26	12 kV Surge arresters x Three (3)	Set of Three			

Item	Description	Unit of Measurement	Manufacturer	Unit Price in (R)	Delivery Time
27	Voltage Transformer, 11000/110 V, 100VA, 3 limb, Voltage factor 1.9, accuracy class 0.5. Complete with base.	Each			
28	Set of Three (3) Voltage transformer, Cu busbar raisers on the cable side.	Set of Three			
29	Set of Three (3) Voltage transformer, Cu busbar raisers on the busbar side.	Set of Three			
30	Current transformers 600/1,5P20, 10VA, IL 12/28/75 kV.	Each			
31	Current transformers 600/1, class X, IL 12/28/75 kV.	Each			
32	Current transformers 300/200/100/5, class 0.5, IL 12/28/75 kV.	Each			
33	Current transformers 60/30/5, class 0.5, IL 12/28/75 kV.	Each			
34	Dual Current transformers 600/1,10P10, 10VA, IL 12/28/75 kV. Current transformers 300/200/100/5, class 0.5, IL 12/28/75 kV.	Each			
35	Dual Current transformers 600/1,10P10, 10VA, IL 12/28/75 kV. Current transformers 60/30/5, class 0.5, IL 12/28/75 kV.	Each			
36	Plug sock for pendant control on panels, price per each.	Each			
37	All weather door for ring main K-3 type unit	Each			

Item	Description	Unit of Measurement	Manufacturer	Unit Price in (R)	Delivery Time
	three cable entries.				
38	Safety side wall for panels (Fire wall)	Each			
39	Hand-held remote control	Each			
40	J-packs for SBV3 2000Amp	Each			
41	J-packs for SBV3-E 2000Amp	Each			
42	J-packs for AG16 GEC Panel 800Amp	Each			
43	Nulec Battery charger 24VDC	Each			
44	Sf6 gas refill kit Nulec. Connecting fittings, pipes and gauges. Complete set.	Each			
45	GEC AG16 tank rubber packings	Each			
46	GEC AG16 inside tank insulation	Each			

**PRICE SCHEDULE FOR SPARES, for existing infrastructure, 30VDC RELAYS: (Ad-hoc purchase)** Prices must exclude VAT and include delivery to our CENTLEC stores.

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
1	<p><b>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</b></p> <ul style="list-style-type: none"> <li>i. <b>Power Supply:</b> 24 to 48VDC</li> <li>ii. <b>Secondary Input Current:</b> 3 x AC 1A plus a 50mA Neutral Input.</li> <li>iii. <b>Voltage Input:</b> VNOM (L-L) should have the following specifications: 20 to 440V for</li> </ul>	Each			

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>DELTA_Y for DELTA and WYE</p> <ul style="list-style-type: none"> <li>iv. <b>Configurable labels:</b> Yes</li> <li>v. <b>Programmable pushbuttons:</b> Minimum of four programmable push button, each with programmable LEDs</li> <li>vi. <b>Communication Ports:</b></li> <li>vii. <b>Rear:</b> 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>viii. <b>Front:</b> 1 x Serial Port</li> <li>ix. <b>Communications Protocol:</b> DNP3 level 2 minimum.</li> <li>x. <b>Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24VDC (External wetting); Inputs should be individually user-configured to operate.</li> <li>xi. <b>High Speed, High current Interruption (Outputs):</b> Minimum of 6A continuous current – Minimum of 8 Universal – 19.2 to 60 VDC for the 24 to 48 power supply.</li> <li>xii. <b>Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>xiii. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</li> </ul>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>xiv. <b>Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear</p>				
1.1	50mA neutral SEF Element as a replaceable card or component. 30VDC. (Only the card or component alone)	Each			
1.2	1Amp OC/EF Element as a replaceable card or component. 30VDC. (Only the card or component alone)	Each			
2	<p><b>Pilot Wire Current Differential Protection</b></p> <ul style="list-style-type: none"> <li>i. High transient stability</li> <li>ii. High speed operation</li> <li>iii. Low phase and earth fault settings</li> <li>iv. Little or no variation of settings with pilot length</li> <li>v. In zone bleed off up to 20% of rated load</li> <li>vi. 15kV pilot isolation option</li> <li>vii. Be connected as either Solkor Rf or SolkorR</li> <li>viii. <b>Rated Frequency: 50Hz/60Hz</b></li> <li>ix. <b>Operating Frequency range:47Hz to 52Hz</b></li> <li>x. <b>Max. Loop resistance:</b> <ul style="list-style-type: none"> <li><b>For R Mode:</b> 1000 ohm</li> <li><b>For Rf Mode:</b> 2000 ohm</li> </ul> </li> <li>xi. Peak Voltage applied to pilots under fault conditions: <ul style="list-style-type: none"> <li><b>For R Mode:</b> 300v</li> </ul> </li> </ul>	Each			

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p><b>For RF Mode:</b> 450v</p> <p>xii. Maximum current carried by pilots under fault conditions:</p> <p><b>For R Mode:</b> 200mA</p> <p><b>For Rf Mode:</b> 250mA</p> <p><b>NB! It is critical that it be noted that the existing Pilot Wire Protection relays are the Solkor R/RF make. The relays on Offer must be compatible with them.</b></p>				
3	<p><b>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</b></p> <p>i. <b>Power Supply:</b> 24–48 VDC nominal</p> <p>ii. <b>Secondary Input Current:</b> 1 Amp Phase, 1 Amp Neutral; 5Amp Phase, 5Amp Neutral; 1Amp Phase, 50mA Neutral (nondirectional Sensitive Earth fault [SEF]).</p> <p>iii. <b>Voltage Input:</b> Nominal range:</p> <p>iv. Line-to-Neutral: 67-120 Vrms</p> <p>v. Line-to-Line: 115-120 Vrms</p> <p>vi. <b>Configurable labels:</b> Yes</p> <p>vii. <b>Pushbuttons:</b> Minimum of eight operator control push buttons.</p> <p>viii. <b>Front panel LEDs:</b> Status and Trip Target LEDs.</p> <p>ix. <b>Communication Ports:</b></p> <p>x. <b>Rear:</b> 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</p> <p>xi. <b>Front:</b> 1 x Serial Port; EIA-485</p>	Each			

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>xii. <b>Firmware:</b> Standard</p> <p>xiii. <b>Communications Protocol:</b> Should have the following protocols: DNP 3.00 Level 2 Slave.</p> <p>xiv. <b>Digital Optoisolated Inputs:</b> Minimum of on for 15–30 VDC for VDC control inputs and 12.8–30.0 Vac for Vac control inputs; Inputs should be individually user-configured to operate.</p> <p>xv. <b>High Speed, High current Interruption (Outputs):</b> Minimum of 15 Universal outputs with the following criteria: Make: 30 A; Carry: 6 A continuous carry; MOV Protection: 270 Vac/360 VDC; 40 J;</p> <p>xvi. <b>Arc Flash capability:</b> No</p> <p>xvii. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p>xviii. <b>Protection elements:</b> Phase Fault Overcurrent Protection; Adaptive Phase Overcurrent Elements; Ground Fault Overcurrent Protection; Directional Ground Protection; Under- and Overvoltage Elements; Under- and Over Frequency Protection; Rate-of-Change-of-Frequency Protection; Harmonic Blocking; Sequence Voltage Elements; Fault Locator</p> <p>xix. <b>Relay Logic/Automation:</b> Relay should have: local control logic points; remote control logic points; latching logic points; counters; math variables; logic variables; timers</p>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p><b>xx. Monitoring and reporting:</b> Event Reporting and Sequential Events Recorder (SER)</p>				
4	<p><b>Bus Differential and Breaker failure protection Numerical Relay. Compliant to the Technical Specifications below:</b></p> <ul style="list-style-type: none"> <li><b>i. Power Supply:</b> 48/125 VDC or 110-120 VAC</li> <li><b>ii. Mainboard Input Voltage:</b>110 VDC</li> <li><b>iii. Secondary Input Current:</b> 1 Amp Phase, 1 Amp Neutral.</li> <li><b>iv. Voltage Input:</b> 3 AC Voltage, 21 AC Current</li> <li><b>v. Configurable labels:</b> Yes</li> <li><b>vi. Programmable pushbuttons:</b> Trip/Close Pushbuttons; 8 operator control pushbuttons</li> <li><b>vii. Front panel LEDs:</b> Status and Trip Target LEDs (minimum of 16)</li> <li><b>viii. Communication Ports:</b></li> <li><b>ix. Rear:</b> Ethernet Card with Two 10/100 Base-T plus 1 x 1 RS 232 port</li> <li><b>x. Front:</b> 1 x Serial Port; EIA-485</li> <li><b>xi. Firmware:</b> Includes Mirrored Bits and Load Profile.</li> <li><b>xii. Communications Protocol:</b> Should have the following protocols: DNP 3.00 Level 2 Slave, FTP, Telnet, and DNP3 LAN/WAN</li> <li><b>xiii. Digital Optoisolated Inputs:</b> Minimum of</li> </ul>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>16 – 110 Vac/VDC digital inputs with a pickup 88–132 VDC; Dropout 66 VDC (External wetting); Inputs should be individually user-configured to operate.</p> <p><b>xiv. High Speed, High current Interruption (Outputs):</b> Minimum of 15 Universal outputs with the following criteria: Make: 30 A; Carry: 6 A continuous carry; MOV Protection: 270 Vac/360 VDC; 40 J;</p> <p><b>xv. Arc Flash capability:</b> No</p> <p><b>xvi. Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>xvii. Protection elements:</b> Phase Fault Overcurrent Protection; Adaptive Phase Overcurrent Elements; Ground Fault Overcurrent Protection; Directional Ground Protection; Under- and Overvoltage Elements; Under- and Over Frequency Protection; Rate-of-Change-of-Frequency Protection; Harmonic Blocking; Sequence Voltage Elements; Fault Locator</p> <p><b>xviii. Relay Logic/Automation: Relay should have:</b> local control logic points; remote control logic points; 2 latching logic points; counters; math variables; logic variables; timers</p> <p><b>xix. Monitoring and reporting:</b> Event Reporting and Sequential Events Recorder (SER)</p>				
5	Transformer differential protection, Numeri-				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p><b>cal Relay. Compliant to the Technical Specifications below:</b></p> <ul style="list-style-type: none"> <li><b>i. Power Supply:</b> 125/250 VDC or VAC; 85–350 VDC or 85–264 Vac</li> <li><b>ii. AC Secondary Input Current:</b> Secondary Input Current 1 Amp Phase, 1 Amp Neutral, including 2xREF Element; 3 A continuous, 100 A for 1 s;</li> <li><b>iii. Voltage Input:</b> No</li> <li><b>iv. Configurable labels:</b> No</li> <li><b>v. Front panel LEDs:</b> Status and Trip Target LEDs</li> <li><b>vi. Programmable pushbuttons:</b> Minimum of eight operator control pushbuttons</li> <li><b>vii. Communication Ports:</b></li> <li><b>viii. Rear:</b> 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li><b>ix. Front:</b> 1 x Serial Port</li> <li><b>x. Communications Protocol:</b> Should have the following protocols: DNP 3.00 Level 2 Slave,</li> <li><b>xi. Digital Optoisolated Inputs:</b> Minimum of 16 – 110 Vac/VDC digital inputs with a pickup 88–132 VDC; Dropout 66 VDC (External wetting); Inputs should be individually user-configured to operate.</li> <li><b>xii. High Speed, High current Interruption (Outputs):</b> Minimum of 15 Universal outputs with the following criteria: Make: 30 A; Carry: 6 A continuous carry; MOV Protection:</li> </ul>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>270 Vac/360 VDC; 40 J;</p> <p><b>xiii. Arc Flash capability:</b> No</p> <p><b>xiv. Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>xv. Relay Logic/Automation:</b> Relay should have: local control logic points; remote control logic points; latching logic points; counters; math variables; logic variables; timers</p> <p><b>xvi. Monitoring and reporting:</b> Event Reporting and Sequential Events Recorder (SER)</p> <p><b>xvii. Protection elements:</b> Relay should have the following protection elements: Percentage Differential Protection; Harmonic and DC Elements; Unrestrained Differential Protection; Overcurrent Fault Protection; Restricted Earth Fault Protection; Through-Fault Event Monitor; CT Phase Angle Compensation</p>				
6	<p><b>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</b></p> <p><b>i. Power Supply:</b> 125VDC or 120 VAC</p> <p><b>ii. Secondary Input Current:</b> 1 Amp Phase, 1 Amp Neutral; 5Amp Phase, 5Amp Phase; 1Amp Phase, 0.05Amp Neutral (nondirectional Sensitive Earth fault [SEF]).</p> <p><b>iii. Voltage Input:</b> No</p> <p><b>iv. Configurable labels:</b> Yes</p>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<ul style="list-style-type: none"> <li>v. <b>Pushbuttons:</b> Minimum of eight operator control push buttons; Trip/Close Pushbuttons</li> <li>vi. <b>Front panel LEDs:</b> Status and Trip Target LEDs</li> <li>vii. <b>Communication Ports:</b></li> <li>viii. <b>Rear:</b> 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>ix. <b>Front:</b> 1 x Serial Port; EIA-485</li> <li>x. <b>Firmware:</b> Includes Mirrored Bits and Load Profile.</li> <li>xi. <b>Communications Protocol:</b> Should have the following protocols: DNP 3.00 Level 2 Slave, standard protocols; IEC 61850</li> <li>xii. <b>Digital Optoisolated Inputs:</b> Minimum of 16 – 110 Vac/VDC digital inputs with a pickup 88–132 VDC; Dropout 66 VDC (External wetting); Inputs should be individually user-configured to operate.</li> <li>xiii. <b>High Speed, High current Interruption (Outputs):</b> Minimum of 15 Universal outputs with the following criteria: Make: 30 A; Carry: 6 A continuous carry; MOV Protection: 270 Vac/360 VDC; 40 J;</li> <li>xiv. <b>Arc Flash capability:</b> No</li> <li>xv. <b>Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</li> <li>xvi. <b>Protection elements:</b> Phase Fault Overcurrent Protection; Adaptive Phase Overcurrent Elements; Ground Fault Overcurrent Protec-</li> </ul>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>tion; Directional Ground Protection; Under- and Overvoltage Elements; Under- and Over Frequency Protection; Rate-of-Change-of-Frequency Protection; Harmonic Blocking; Sequence Voltage Elements; Fault Locator</p> <p><b>xvii. Relay Logic/Automation:</b> Relay should have: local control logic points; remote control logic points; latching logic points; counters; math variables; logic variables; timers</p> <p><b>xviii. Monitoring and reporting:</b> Event Reporting and Sequential Events Recorder (SER)</p>				
7	<p><b>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</b></p> <p><b>i. Power Supply:</b> Universal – 24 to 120V DC/AC.</p> <p><b>ii. Secondary Input Current:</b> 3 x AC 5A/1A plus a 1A/5A Neutral Input.</p> <p><b>iii. Voltage Input:</b> 110V phase to phase AC Voltage.</p> <p><b>iv. Configurable labels:</b> Yes</p> <p><b>v. Communication Ports:</b></p> <p><b>vi. Rear:</b> 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</p> <p><b>vii. Front:</b> 1 x Serial Port</p> <p><b>viii. Communications Protocol:</b> DNP3_level 2 minimum</p> <p><b>ix. Digital Optoisolated Inputs:</b> Minimum of 8. Universal – 24 to 120V DC/AC voltage ap-</p>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>plication (External wetting); Inputs should be individually user-configured to operate.</p> <p><b>x. Digital Optoisolated high speed and high current Outputs:</b> Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p><b>xi. Arc Flash capability:</b> 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p><b>xii. Software:</b> Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p><b>xiii. Relay dimensions:</b> Must be able to fit onto the control panel portion of the switchgear.</p>				
8	<p><b>Arc fault monitor. Compliant to the Technical Specifications below:</b> 20 – 60 VDC</p> <ul style="list-style-type: none"> <li><b>i.</b> Should have a tri-colour LED.</li> <li><b>ii.</b> Front push button reset.</li> <li><b>iii.</b> Minimum of three arc sensor inputs</li> <li><b>iv.</b> Two high speed tripping duty arc sense output contacts: 2 N/O, 1 N/C for the power supply.</li> <li><b>v. Output contact ratings:</b> Continuous current carrying ability should be 5A AC or DC.</li> <li><b>vi. Transient overvoltage:</b> Between all termi-</li> </ul>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>nals and earth – 5kV 1.2/50 microseconds, 0,5 J. Between independent circuits without damage or flashover – 5kV 1.2/50 microseconds 0.5 J.</p> <p><b>vii. Case:</b> ZA12 flash or DIN rail mount type</p> <p><b>viii.</b> Must have a continuous arc sensor supervision.</p> <p><b>ix.</b> Should have Intergrated self-supervision.</p> <p><b>x.</b> Should have a fail alarm contact</p> <p><b>xi. Operating voltage:</b> 20 - 60Vdc</p> <p><b>xii.</b> Should provide three optical arc fault sensors that is applicable to the device. The sensor should have the following characteristics: Compact rugged design, three optical detectors, high speed arc detection, Optional 20m and screened cable, heavy duty 6m terminal cables, sealed unit for harsh environments.</p>				
9	<p><b>Arc fault monitor. Compliant to the Technical Specifications below:</b></p> <p>110 – 150 VDC</p> <p><b>i.</b> Should have a tri-colour LED.</p> <p><b>ii.</b> Front push button reset.</p> <p><b>iii.</b> minimum of three arc sensor inputs.</p> <p><b>iv.</b> Two high speed tripping duty arc sense output contacts: 2 N/O, 1 N/C for the power</p>				

Item	Description	Unit of measurement	Manufacturer	Price in (R)	Delivery Time
	<p>supply.</p> <ul style="list-style-type: none"> <li>v. <b>Output contact ratings:</b> Continuous current carrying ability should be 5A AC or DC.</li> <li>vi. <b>Transient overvoltage:</b> Between all terminals and earth – 5kV 1.2/50 microseconds, 0,5 J. Between independent circuits without damage or flashover – 5kV 1.2/50 microseconds 0.5 J.</li> <li>vii. <b>Case:</b> ZA12 flash or DIN rail mount type</li> <li>viii. Must have a continuous arc sensor supervision.</li> <li>ix. Should have Intergrated self-supervision.</li> <li>x. Should have a fail alarm contact.</li> <li>xi. Operating voltage: 110 -150Vdc</li> <li>xii. Optical ARC flash sensor: Should provide three optical arc fault sensors that is applicable to the device. <b>The sensor should have the following characteristics:</b> Compact rugged design, three optical detectors, high speed arc detection, Optional 20m and screened cable, heavy duty 6m terminal cables, sealed unit for harsh environments.</li> </ul>				
10	<p><b>Fiber optic Arc fault sensor.</b></p> <ul style="list-style-type: none"> <li>i. Fiber-optic point sensors that comply with relay specifications mentioned in previous sections.</li> </ul>				

**PRICES AND DELIVERY SCHEDULE** - Prices must exclude VAT and include delivery to our CENTLEC stores.

**PART A – PRICING FOR METAL-CLAD SWITCHGEAR:**

Item	Schedule	Description	Unit of measurement	Price per unit in (R) for vacuum VCB's	Manufacturer	Delivery period in weeks
1.	A1	Switch - Disconnect panel - diagram 1/10	Each			
2.	A2	Circuit breaker panel - diagram 2/10 MV Connection < 1 MVA	Each			
3.	A3	Circuit breaker panel - diagram 3/10 MV Connection > 1 MVA	Each			
4.	A4	Circuit breaker panel - diagram 4/10 Secondary feeder	Each			
5.	A5.	Circuit breaker panel - diagram 5/10 Primary feeder (out-going)	Each			
6.	A6	Circuit breaker panel - diagram 6/10 Transformer feeder	Each			
7.	A7	Circuit breaker panel - diagram 7/10 Overhead line feeder	Each			
8.	A.8	Circuit breaker panel - diagram 8/10 Primary feeder - (in-coming)	Each			
9.	A.9	Circuit breaker panel - diagram 9/10 Bus- Section switch (busbar coupler)	Each			

Item	Schedule	Description	Unit of measurement	Price per unit in (R) for vacuum VCB's	Manufacturer	Delivery period in weeks
10.	A.10	Fused switch disconnecter - diagram 10/10	Each			
11.	1	Complete Magnefix Disconnect or switch (5.5.2)	Each			
12.	2	Complete Nulec N-series ACR N12 recloser / circuit breaker. (5.5.3)	Each			

**5.4.11 PRICING FOR 110VDC PANELS:** Tender must be for single and double busbars. (Upper bar and back bar) Complete with busbars. (SBV3 and SBV3 E or compatible equivalent without juggle boxes)

Item	Schedule	Description	Unit	Price per unit in (R) for Single Bar	Price per unit in (R) for Front and Back Bar	Price per unit in (R) for Upper and Lower Bar	Manufacturer	Delivery period weeks
1.	5.4.11 A	Feeder panel	Each					
2.	5.4.11 B	Incomer panel with 3Limb VT	Each					
3.	5.4.11 B	Incomer panel with 5Limb VT	Each					

Item	Schedule	Description	Unit	Price per unit in (R) for Single Bar	Price per unit in (R) for Front and Back Bar	Price per unit in (R) for Upper and Lower Bar	Manufacturer	Delivery period weeks
4.	5.4.11.C	Bus Coupler panel	Each					
5.	5.4.12.D	Power transformer 11000/110 V, 100VA, 5 limb, Voltage factor 1.9, accuracy class 0.5. Complete with base and busbar raisers.	Each					
6.	5.4.13.E	Power transformer 11000/110 V, 100VA, 3 limb, Voltage factor 1.9, accuracy class 0.5. Complete with base and busbar raisers.	Each					

**5.4.12 PRICING FOR PACKS – 11kV VACUUM CIRCUIT BREAKERS:**

Item	Schedule	Description	Unit of measurement	Price per unit in (R) for vacuum VCB's	Manufacturer	Delivery period in weeks
1.	A12.1	Panel packs "P"-packs (all tapes, bolts and nuts for panels included)	Each			
2.	A12.2A	a) Jointing packs "J"-packs 400 Amp silver coated on the connection points. (Bolts and nuts included)	Each			
3.	A12.2B	b) Jointing packs "J"-packs 800 Amp silver coated on the connection points. (Bolts and nuts included)	Each			
4.	A12.2C	c) Jointing packs "J"-packs 2000 Amp silver coated on the connection points. (Bolts and nuts included)	Each			
5.	A12.3	Switchboard accessories "S"-packs.	Each			
6.	A12.4	Test packs "T"-packs	Each			
7.	A12.3	Hand-held remote control	Each			

**PART B – NON-EXTENSIBLE RING MAIN UNITS 11kV–**

Prices must exclude VAT and include delivery to our CENTLEC stores.

Item	Schedule	Description	Unit of measurement	Price per unit (R) for Oil (per litre)	Price per unit (R) for SF6 Gas (per kg)	Manufacturer	Delivery period in weeks
1.	B1	Ring main unit with fused transformer feeder without metering	Each				
2.	B2	Ring main unit with fused transformer feeder with metering unit, fitted inside metal clad outdoor kiosk	Each				
3.	B3	Ring main unit with two fused transformer feeders- One with metering and the other one without metering	Each				

**PART C – 1. A. Oil to Vacuum Circuit Breakers Retrofit and Repair of The Listed Circuit Breakers, 12kV.**

Prices must exclude VAT and include delivery to our CENTLEC Premises.

Item	Schedule	Description	Unit	Unit total price in (R)	Manufacturer and Service provider to be stated below.	Delivery period in weeks
1.	C1 a)	Vacuum circuit breaker to retrofit type PDB oil circuit breaker to fit the panel without any alternations to the panel. This must be for GEC, English-Electric and Johnson & Phillips. Type AG 16.11kV switchgear.	Each			
2.	C1 b)	Transport of circuit breaker	p/km			

Item	Schedule	Description	Unit	Unit total price in (R)	Manufacturer and Service provider to be stated below.	Delivery period in weeks
3.	C1 c)	Labour	p/hour			
4.	C1 d)	Repair CB on existing switchgear list below.  <b>NB! "Strip &amp; Quote" will be applicable.</b>	Each			
5.	C1 e)	Retrofit the Reyrolle breakers spring charge mechanism with new spring charges motors.	Each			

**PART D - Retrofit existing switchgear, SF6 circuit breakers in particular - Reyrolle LMS, LMR, LMT to the replacement and equivalent vacuum or SF6 circuit breaker that will fit into the existing panel. The 110V circuit breaker panels)**

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit total price in (R)	Delivery period in weeks
Manufacturer			Each		
Country of origin					
Insulation (Arc extinguishing) medium					
Circuit breaker type					
Total switchgear (circuit breaker) mass	kg				
Nominal voltage	kV	11			
Rated voltage	kV	12			
Circuit rated normal current	A	1250			
Busbar rated normal current	A	1250			
Fault breaking capacity	MVA	350			
Fault making capacity	kA	31.5			
Through fault rating for 3 seconds	kA	20 kA			

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit total price in (R)	Delivery period in weeks
Standard 1/50 microsecond impulse rating at sea level	kV	95			
Spring charge motor (110V DC)					
Closing coil (110V DC)					
Trip coil (110V DC)					
Circuit Breaker to fit Panel		Circuit Breaker to fit in existing panel without alternations to panel.			

**PART E - Retrofit existing switchgear, SF6 circuit breakers in particular - Reyrolle LMS, LMR, LMT to the replacement and equivalent vacuum or SF6 circuit breaker that will fit into the existing panel. The 32V circuit breaker panels)**

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit total price in (R)	Delivery period in weeks
Manufacturer			Each		
Country of origin					
Insulation (Arc extinguishing) medium					
Circuit breaker type					
Total switchgear (circuit breaker) mass	kg				
Nominal voltage	kV	11			
Rated voltage	kV	12			
Circuit rated normal current	A	1250			
Busbar rated normal current	A	1250			

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit total price in (R)	Delivery period in weeks
Fault breaking capacity	MVA	350			
Fault making capacity	kA	31.5			
Through fault rating for 3 seconds	kA	20 kA			
Standard 1/50 microsecond impulse rating at sea level	kV	95			
Spring charge motor (32V DC)					
Closing coil (32V DC)					
Trip coil (32V DC)					
Circuit Breaker to fit Panel		Circuit Breaker to fit in existing panel without alternations to panel.			

**PART F: Replacement of Reyrolle Panel - Feeder Protection Panel without Pilot Wire Protection.**

**NB: Panel can be ordered either with 600/5 or 600/1 Current Transformers as well as a 1A or 5A Nominal Current, Numerical Protective Relay as described in the table below.**

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit total price in (R)	Delivery period in weeks
Reyrolle Panel complete with bus-bars and shutters.	A	1250	Each		
<b>VOLTAGE TRANSFORMER</b>					
Install VT		NA	Each		
Ratio					
Burden and Accuracy					

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Voltage Factor						
<b>CURRENT TRANSFORMERS: Studded 6mm Brass "S" connections.</b>						
Manufacturer						
Install CT's		Yes	<b>Each</b>			
Purpose		OC / EF				
Ratio		600/1				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
ALTERNATIVE CTs TO BE INSTALLED						
Purpose		OC / EF	<b>Each</b>			
Ratio		600/5				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
Install Ct's (Differential)		N/A	<b>Each</b>			
Purpose						
Burden						
Ratio						
Class						
Quantity						
Insulation Level			<b>Each</b>			
Install test block PK2-4way		YES (OC/EF)				
Install Ct's (Metering)		N/A	<b>Each</b>			
Purpose						
Burden						
Ratio						
Class						

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Quantity						
Insulation Level						
Install test block PK2-4way		N/A				
<b>PROTECTIVE RELAY</b>						
Manufacturer						
Protective Relay: Time Overcurrent and Earth Fault Protection		<p>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</p> <ul style="list-style-type: none"> <li>i. Power Supply: Universal – 24 to 120V DC/AC.</li> <li>ii. Secondary Input Current: 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. Voltage Input: 110V phase to phase AC Voltage.</li> <li>iv. Configurable labels: Yes</li> <li>v. Communication Ports:</li> <li>vi. Rear: 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>vii. Front: 1 x Serial Port</li> <li>viii. Communications Protocol: DNP3_level 2 minimum</li> <li>ix. Digital Optoisolated Inputs: Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>x. Digital Optoisolated high speed and high current Outputs: Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xi. Arc Flash capability: 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> </ul>				

DESCRIPTION OF PARTICULARS	UNITS	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
		xii. Software: Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay). xiii. Relay dimensions: Must be able to fit onto the control panel portion of the switchgear.				

**PART G: Replacement of Reyrolle Panel - Feeder Protection Panel with Pilot Wire Protection.**

**NB: Panel can be ordered either with 600/5 or 600/1 Current Transformers as well as a 1A or 5A Nominal Current, Numerical Protective Relay as described in the table below. The Pilot Wire Protection Relay is also to be added to this panel.**

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Reyrolle Panel complete with bus-bars and shutters.	A	1250	Each			
<b>VOLTAGE TRANSFORMER</b>						
Install VT		NA	Each			
Ratio						
Burden and Accuracy						
Voltage Factor						
<b>CURRENT TRANSFORMERS: Studded 6mm Brass "S" connections.</b>						
Install CT's		Yes	Each			
Purpose		OC / EF				
Ratio		600/1				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
ALTERNATIVE CTs TO BE INSTALLED						
Purpose		OC / EF	Each			
Ratio		600/5				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
Install Ct's (Differential)		Yes	Each			
Purpose		Differential				
Burden						
Ratio		600/1				
Class		X or TPS or PX				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
ALTERNATIVE CTs TO BE INSTALLED						
Install Ct's (Differential)		Yes	Each			
Purpose		Differential				
Burden						
Ratio		600/e				
Class		X or TPS or PX				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
Install test block PK2-4way		YES (OC/EF) and Differential	Each			
Install Ct's (Metering)		N/A	Each			
Purpose						
Burden						
Ratio						
Class						
Quantity						

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Insulation Level						
Install test block PK2-4way		N/A				
<b>PROTECTIVE RELAY</b>						
Manufacturer						
Protective Relay: Time Overcurrent and Earth Fault Protection		<p>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</p> <ul style="list-style-type: none"> <li>i. Power Supply: Universal – 24 to 120V DC/AC.</li> <li>ii. Secondary Input Current: 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. Voltage Input: 110V phase to phase AC Voltage.</li> <li>iv. Configurable labels: Yes</li> <li>v. Communication Ports:</li> <li>vi. Rear: 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>vii. Front: 1 x Serial Port</li> <li>viii. Communications Protocol: DNP3_level 2 minimum</li> <li>ix. Digital Optoisolated Inputs: Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>x. Digital Optoisolated high speed and high current Outputs: Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xi. Arc Flash capability: 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> </ul>				

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in weeks
		xii. Software: Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay). xiii. Relay dimensions: Must be able to fit onto the control panel portion of the switchgear.			
HIGH SPEED PILOT WIRE DIFFERENTIAL PROTECTION					
Manufacturer					
		<p><b>Pilot Wire Current Differential Protection</b></p> <ul style="list-style-type: none"> <li>i. High transient stability</li> <li>ii. High speed operation</li> <li>iii. Low phase and earth fault settings</li> <li>iv. Little or no variation of settings with pilot length</li> <li>v. In zone bleed off up to 20% of rated load</li> <li>vi. 15kV pilot isolation option</li> <li>vii. Be connected as either Solkor Rf or SolkorR</li> <li>viii. <b>Rated Frequency: 50Hz/60Hz</b></li> <li>ix. <b>Operating Frequency range:47Hz to 52Hz</b></li> <li>x. <b>Max. Loop resistance:</b> <ul style="list-style-type: none"> <li>a. <b>For R Mode:</b> 1000 ohm</li> <li>b. <b>For Rf Mode:</b> 2000 ohm</li> </ul> </li> <li>xi. Peak Voltage applied to pilots un-</li> </ul>			

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
		der fault conditions: xii. <b>For R Mode:</b> 300V xiii. <b>For RF Mode:</b> 450V xiv. Maximum current carried by pilots under fault conditions: xv. <b>For R Mode:</b> 200mA xvi. <b>For Rf Mode:</b> 250mA  <b>NB! It is critical that it be noted that the existing Pilot Wire Protection relays are the Solkor R/RF make. The relays on Offer must be compatible with them.</b>				

**PART H: Replacement of Reyrolle Panel - Feeder Protection Panel for local transformer use.**

**NB: Panel can be ordered either with 100/1 OR 100/5 Current Transformers as well as a 1A or 5A Nominal Current, Numerical**

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Reyrolle Panel complete with bus-bars and shutters.	A	1250	Each			
<b>VOLTAGE TRANSFORMER</b>						
Install VT		N/A	Each			
Ratio						
Burden and Accuracy						
Voltage Factor						
<b>CURRENT TRANSFORMERS: Studded 6mm Brass "S" connections.</b>						
Manufacturer						

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price in (R)	total in	Delivery period in weeks
Install CT's		Yes	Each			
Purpose		OC / EF				
Ratio		100/1				
Burden		10VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
<b>ALTERNATIVE CTs TO BE INSTALLED</b>						
Install Ct's (Differential)		Yes	Each			
Purpose		OC / EF				
Ratio		100/5				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
Install test block PK2-4way		YES (OC/EF)	Each			
Install Ct's (Metering)		N/A	Each			
Purpose						
Burden						
Ratio						
Class						
Quantity						
Insulation Level						
Install test block PK2-4way		YES (Diff / Metering)				
<b>PROTECTIVE RELAY</b>						
Manufacturer						
Protective Relay: Time Overcurrent and Earth Fault Protection		Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:				

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price in (R)	total in weeks
		<ul style="list-style-type: none"> <li>i. Power Supply: Universal – 24 to 120V DC/AC.</li> <li>ii. Secondary Input Current: 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. Voltage Input: 110V phase to phase AC Voltage.</li> <li>iv. Configurable labels: Yes</li> <li>v. Communication Ports:</li> <li>vi. Rear: 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>vii. Front: 1 x Serial Port</li> <li>viii. Communications Protocol: DNP3_level 2 minimum</li> <li>ix. Digital Optoisolated Inputs: Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); Inputs should be individually user-configured to operate.</li> <li>x. Digital Optoisolated high speed and high current Outputs: Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</li> <li>xi. Arc Flash capability: 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</li> <li>xii. Software: Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</li> <li>xiii. Relay dimensions: Must be able to fit onto the control panel portion of the switchgear.</li> </ul>			

**PART I: Replacement of Reyrolle Panel - Feeder Protection Panel for Medium Voltage Connection.**

**NB: Panel can be ordered either with 600/1 OR 100/1 Current Transformers as well as a 1A or 5A Nominal Current, Numerical**

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price (R)	total in	Delivery period in weeks
Reyrolle Panel complete with bus-bars and shutters.	A	1250	Each			
<b>VOLTAGE TRANSFORMER</b>						
Manufacturer						
Install VT		Yes	Each			
Ratio		11000/110/63.5 Volts				
Burden and Accuracy		100 VA Class 0.5				
Voltage Factor		1.9				
<b>CURRENT TRANSFORMERS: Studded 6mm Brass "S" connections.</b>						
Manufacturer						
Install CT's		Yes	Each			
Purpose		OC / EF				
Ratio		600/1				
Burden		15VA				
Class		10P10				
Quantity		3				
Insulation Level		IL 12/28/95 KV				
ALTERNATIVE CTs TO BE INSTALLED			Each			
Purpose		OC / EF				
Ratio		100/1				
Burden		15VA				
Class		10P10				
Quantity		3				

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price total in (R)	Delivery period in weeks
Insulation Level		IL 12/28/95 KV			
Install Ct's (Differential)		N/A			
Install test block PK2-4way		YES (OC/EF)	Each		
Install Ct's (Metering)		YES	Each		
Purpose		Metering			
Burden		600/300/200/1			
Ratio		10VA			
Class		0.5			
Quantity		3			
Insulation Level		IL 12/28/95 KV			
Install test block PK2-4way		YES (Diff / Metering)			
<b>PROTECTIVE RELAY</b>					
Manufacturer					
Protective Relay: Time Overcurrent and Earth Fault Protection		<p>Overcurrent, Earth Fault and Sensitive Earth Fault Numerical Relay. Compliant to the Technical Specifications below:</p> <ul style="list-style-type: none"> <li>i. Power Supply: Universal – 24 to 120V DC/AC.</li> <li>ii. Secondary Input Current: 3 x AC 5A/1A plus a 1A/5A Neutral Input.</li> <li>iii. Voltage Input: 110V phase to phase AC Voltage.</li> <li>iv. Configurable labels: Yes</li> <li>v. Communication Ports:</li> <li>vi. Rear: 1 x 10/100 Base-T plus 1 x 1 RS 232 port.</li> <li>vii. Front: 1 x Serial Port</li> <li>viii. Communications Protocol: DNP3_level 2 minimum</li> <li>ix. Digital Optoisolated Inputs: Minimum of 8. Universal – 24 to 120V DC/AC voltage application (External wetting); In-</li> </ul>			

DESCRIPTION OF PARTICULARS	UNIT S	SPECIFIED REQUIREMENT	Unit	Unit price in (R)	total in weeks
		<p>puts should be individually user-configured to operate.</p> <p>x. Digital Optoisolated high speed and high current Outputs: Minimum of 6A continuous – Minimum of 8. Universal – 24 to 120V DC/AC voltage application.</p> <p>xi. Arc Flash capability: 4 x Arc Flash detection inputs. Four Fiber-optic point sensors for ARC flash must be provided with the relay.</p> <p>xii. Software: Windows-based PC software for setting, report retrieval, metering, HMI, and control; At no additional costs (free issue with the relay).</p> <p>xiii. Relay dimensions: Must be able to fit onto the control panel portion of the switchgear.</p>			

The following Existing Circuit breakers must be repaired: (Strip &Quote)

**Repair, Strip & Quote** means that the Service provider must submit a quotation for the repairs and then invoice after repairs.

<b>Make</b>	<b>Type</b>
Reyrolle LMS	LMS/X1/QMRO
Reyrolle LMR	LMR/X2/QMRO
Reyrolle LMT	LMT2/X31/QM
Actom	SBV4E/2000/25/SI and SBV4/80/20/S1
Actom	SBV3E/2000/25/SI
Johnson & Phillips	PDB/A/2Z and TSB16
GEC	PDB/A/400
HAWKER SIDDELEY	VIL-6 and R4/1 and V4/1 and D6XD
FIRST ELECTRIC	JB621
BRUSH	W4/11 and S4
LONG & CRAWFORD	AVS2
ALSTOM	AGVB-800/20/S and SBV4/800/20-S1
SACE BERGAMO	RM1235
BRITISH THOMPSON	BTH/JB621 and LC/B3
BRUSH	W4/11
NULEC	N24S-ACR-SF6-24-12-150
JG STATTER	VTGR150
YORKSHIRE	YSF6
RMU Actom	K3 oil and gas
RMU Magenefix	Dry Type Air
RMU GEC	T3 oil
RMU ABB	Gas
RMU Schneider	Gas
RMU Tiger	oil
NULEC switchgear outdoor pole mounted.	Sf6 Gas

**8.5.4 Price for switching and spring charges handles (set) on the following types of existing switchgear.**

Item	Make	Type	Delivery period in weeks	Price per set
1.	Reyrolle LMS	LMS/X1/QMRO		
2.	Reyrolle LMR	LMR/X2/QMRO		
3.	Reyrolle LMT	LMT2/X31/QM		
4.	Actom	SBV4E/2000/25/SI		
5.	Johnson & Phillips	PDB/A/2Z and TSB16		
6.	GEC	PDB/A/400		
7.	HAWKER SID-DELEY	VIL-6 and R4/1 and V4/1 and D6XD		
8.	FIRST ELECTRIC	JB621		
9.	BRUSH	W4/11 and S4		
10.	LONG & CRAW-FORD	AVS2		
11.	ALSTOM	AGVB-800/20/S and SBV4/800/20-S1		
12.	SACE BERGAMO	RM1235		
13.	BRITISH THOMP-SON	BTH/JB621 and LC/B3		
14.	BRUSH	W4/11		
15.	NULEC	N24S-ACR-SF6-24-12-150		
16.	JG STATTER	VTGR150		
17.	YORKSHIRE	YSF6 (Sf6gas)		
18.	RMU Actom	K3 oil and gas		
19.	RMU Magenefix	Dry Type Air		

20.	RMU GEC	T3 oil		
21.	RMU ABB	Gas		
22.	RMU Schneider	Gas		
23.	RMU Tiger	oil		
24.	Nulec switchgear outdoor pole mounted.	Sf6 Gas		
25.	Transport costs	Transport for <b>strip and quote only</b>		AA rates basis

## 11 CONTACT INFORMATION

- 11.1 For any further technical information regarding the document contents please contact Mr P.J. Niemann at [Piet.Niemann@centlec.co.za](mailto:Piet.Niemann@centlec.co.za) or [Lindiwe.Kalane@centlec.co.za](mailto:Lindiwe.Kalane@centlec.co.za) and all queries must be done in writing, the email address provided serves this purpose. The answer to one question will be sent to all the other prospective bidders that have bought the bid documents.
- 11.2 For Supply Chain Related questions, please contact Me. Palesa Makhele at [Palesa.makhele@centlec.co.za](mailto:Palesa.makhele@centlec.co.za)

## 12 ANNEXURES




DIAGRAM 2 /10  
SCHEDULE A2  
MV CONNECTION <1 MVA

NOTE 2.5.2  
THE CONNECTION OF THE HT SIDE OF VT SHALL BE CONNECTED ON THE CABLE SIDE UNLESS OTHERWISE INDICATED.

	WITHDRAWABLE METAL CLAD C / B
	SWITCH DISCONNECTOR
	CURRENT TRANSFORMER
	INVERSE DEFINITE MINIMUM TIME OC & EF RELAY (SEL 5SIC)
	MVA / kWh COMBINATION ENERGY METER
	VOLTAGE TRANSFORMER
	VOLT METER
	TERMINAL TESTBLOCK ON FRONT PANEL
	TERMINAL BLOCK IN FRONT PANEL
	TERMINAL BLOCK IN REAR PANEL
	FUSE
	CABLE TERMINATION


<b>CENTLEC (S.O.C.) LTD</b>		DESIGNED	SCALE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & SFS	SYSTEMS DESIGN & PROCESS ENG.	FIELD ENGINEERING & M&S	OPERATIONS ENGINEERING	
14-08-2023 14-08-2023		T. NAKALA	M13	1st Draft 0.0 & 0.1 Mchfy	K BOOSEN Chief Eng. Ass. (EVL)	X MBALI MANAGER DEVELOPMENT (EVL NUMBER 1)	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	L KORTZWEBER (EVL ENG.) TECHNICAL ADVISOR ACT. (EVL)	
PRINTING DATE: 14-08-2023		DATE	DATE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	
REV. NO. - 000000		REV. NO. - 000000	REV. NO. - 000000	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	
A.C. DE WET		1997 - 11 - 20	1997 - 11 - 20	W DE JAGER (Chief Eng. Ass. (EVL))	M PLOERIE MANAGER DESIGN (ACT)	B MOTSWAGWE (EVL NUMBER 0 & 0.1 ACT) (EVL NUMBER 2)	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	SECTION 09.1.1.1 W/INTENANCE	
TITLE		TITLE		TITLE		TITLE		TITLE		TITLE	
SCHEMATIC DIAGRAM FOR MV SWITCHGEAR		SCHEMATIC DIAGRAM FOR MV SWITCHGEAR		SCHEMATIC DIAGRAM FOR MV SWITCHGEAR		SCHEMATIC DIAGRAM FOR MV SWITCHGEAR		SCHEMATIC DIAGRAM FOR MV SWITCHGEAR		SCHEMATIC DIAGRAM FOR MV SWITCHGEAR	
DRAWING No. TS - 9 - 7		DRAWING No. TS - 9 - 7		DRAWING No. TS - 9 - 7		DRAWING No. TS - 9 - 7		DRAWING No. TS - 9 - 7		DRAWING No. TS - 9 - 7	
REV. NO. - 000000		REV. NO. - 000000		REV. NO. - 000000		REV. NO. - 000000		REV. NO. - 000000		REV. NO. - 000000	







**CENTLEC (S.O.C.) Ltd**



**NOTE 2.52**  
THE CONNECTION OF THE HT SIDE OF V.T. SHALL BE CONNECTED ON THE CABLE SIDE, UNLESS OTHERWISE INDICATED.

**DIAGRAM 7 /10 - SCHEDULE A7  
OVER-HEAD LINE FEEDER**

- WITHDRAWABLE METAL CLAD C/B
- CURRENT TRANSFORMER
- INVERSE DEFINITE MINIMUM TIME OC & EF RELAY (SEL-550)
- KVA /KWH COMBINATION ENERGY METER
- SENSITIVE EARTH FAULT RELAY SEL751A
- MULTI SHOT AUTO-RECLOSE RELAY
- VOLTAGE TRANSFORMER
- VOLT METER
- TERMINAL TESTBLOCK ON FRONT PANEL
- TERMINAL BLOCK IN FRONT PANEL
- TERMINAL BLOCK IN REAR PANEL
- FUSE
- CABLE TERMINATION

REVISION DATE: 28 AUGUST 2018

<b>CENTLEC (S.O.C.) Ltd</b> Reg No 2021/06/03 PHONE 060 14 89000 FAX 060 14 89000	DESIGNED	SCALE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & ST	INSTALLATION & PROCESS ENG. DEPT. (ENGINEERING - MESS)	ISSUED (ENGINEERING)	TITLE
	D. SCHULTZ	NOT TO SCALE	W. DE JAGER	K. BOONSEN	X. MABU	SECTION 972 & MAINTENANCE	SEC. MANAGER (ENG.)	A. MASON (P. TECH. ENG.)	SCHEMATIC DIAGRAM FOR MV SWITCHGEAR
DATE	DATE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES	TECHNICAL DIVISION (E.T.)	DESIGNED BY	REVISION
20 - 11 - 1997	20 - 11 - 1997	W. DE JAGER (Chief Eng. Ass. REGION 1)	M. RUDOLF (MANAGER REGION 1, E.T.)	B. WITSCHORE (MANAGER REGION 1, E.T.)	SECTION 972 & MAINTENANCE	REGIONAL SERVICES	TECHNICAL DIVISION (E.T.)	TS - 9 - 9	A




DIAGRAM 8/10 - SCHEDULE A8  
PRIMARY FEEDER (IN-COMING)




DIAGRAM 9/10 - SCHEDULE A9  
BUS-SECTION SWITCH

NOTE 2.32  
THE CONNECTION OF THE HT SIDE OF VT SHALL BE CONNECTED ON THE CABLE SIDE UNLESS OTHERWISE INDICATED.




DIAGRAM 10/10 SCHEDULE A10  
FUSED SWITCH DISCONNECTOR  
WITH METERING

- WITHDRAWABLE METAL CLAD C/B
- CURRENT TRANSFORMER
- PILOT WIRE PROTECTION RELAY (SOLKOR R+H)
- kWh COMBINATION ENERGY METER
- VOLTAGE TRANSFORMER
- VOLT METER
- TERMINAL TESTBLOCK ON FRONT PANEL
- TERMINAL BLOCK IN FRONT PANEL
- TERMINAL BLOCK IN REAR PANEL
- FUSE
- CABLE TERMINATION

REVISION No.	REVISION DATE	TITLE
D	28 AUGUST 2018	SCHEMATIC DIAGRAM FOR MV SWITCHGEAR
C	08 DECEMBER 2010	
B	11 AUGUST 2010	
A	05 AUGUST 2009	

<b>CENTLEC (S.O.C.) LTD</b>		DESIGNED	SCALE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		D. SPOULTZ	NOT TO SCALE	PLANNING DIVISION	K. BOONSEN	X. MEAU	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		DATE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		20 - 11 - 1997	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		W. DE JAGER	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		M. ROOSE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		B. MOUTSMAE	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		L. VINTZEN (P+H) (C.A.)	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		A. MOOL (P+H) (C.A.)	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		TS - 9 - 10	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009
By: 2023/08/23 PWS: 26, 24, 20/2023-2024		REV. 0	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	PLANNING DIVISION	REGIONAL SERVICES & STS	SYSTEMATION & PROCESS ENG. ENGINEERING - PWS	DATE: 05 AUGUST 2009