



CONTRACT NO: RLM/RWST/OMM/0103/2024/25 – RE-ADVERT:
UPGRADING AND EXTENSION OF BOSPOORT WATER TREATMENT WORKS - MECHANICAL AND ELECTRICAL WORKS

CONTRACT NO: RLM/RWST/OMM/0103/2024/25

RE-ADVERT: APPOINTMENT OF A CONTRACTOR FOR THE UPGRADING AND EXTENSION OF BOSPOORT WATER TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS

VOLUME 1B: PRICING DATA

JULY 2025

NAME OF BIDDER:

BID PRICE: (VAT Incl.)

Prepared by:

**RUSTENBURG WATER SERVICES TRUST
1A KOCK STREET
RUSTENBURG
0300**

BID CLOSING: 01 August 2025 at 10:00

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS

CONTENTS LIST

DESCRIPTION	VOLUME	COLOUR
LOCALITY PLAN		
<u>PORTION 1</u>	<u>TENDER</u>	
Part T1	Tendering procedures	Volume 1A
Section T1.1	Tender Notice and Invitation to Tender	White
Section T1.2	Tender Data	Pink
Section T1.3	Standard Conditions of Tender	Pink
Part T2	Returnable documents	Volume 1A
Section T2.0	Checklist of Returnable Documents and Schedules	Yellow
Section T2.1	Municipal Bidding Documents	
Section T2.2	Returnable Documents	
Section T2.3	Returnable Schedules	
Section T2.4	Technical Schedules	Volume 1B
Volume 1B		Yellow
<u>PORTION 2</u>	<u>CONTRACT</u>	
Part C1	Agreements and Contract Data	Volume 1A
Section C1.1	Forms of Offer and Acceptance	Yellow
Section C1.2	Contract Data	
Section C1.3	Form of Guarantee	
Section C1.4	Health and Safety Agreement	
Part C2	Pricing Data	Volume 1B
Section C2.1	Pricing Instructions	Yellow
Section C2.2	Schedule of Quantities	
Section C2.3	Summary of Schedules	
Part C3	Scope of Work	Volume 1A
Section C3.1	Description of the Works	Blue
Section C3.2	Engineering	
Section C3.3	Procurement	
Section C3.4	Construction (Specifications)	
Section C3.4.1	General Clauses and Requirements	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2
June 2025

Section 3.4.2	Construction of Mechanical Works	Volume 2	
Section C3.4.2.1	Variations and Additions to Particular Specifications for Mechanical Works	Volume 2	
Section C3.4.2.2	Particular Specifications for Mechanical Works	Volume 3	
Section 3.4.3	Construction of Electrical and Electronic Works	Volume 2	
Section C3.4.3.1	Variations and Additions to Particular Specifications for Electrical Works	Volume 2	
Section C3.4.3.2	Standard and Particular Specifications for Electrical and Electronic Works	Volume 3	
Section 3.4.4	Construction of Civil Works	Volume 2	
Section C3.4.4.1	Standard Specifications for Civil Works	Volume 3	
Section C3.4.4.2	Variations and Additions to Particular Specifications for Civil Works	Volume 2	
Section C3.4.4.3	Particular Specifications for Civil Works	Volume 3	
Section C3.5	Management	Volume 1A	Blue
Section C3.5.1	Management of the Works	Volume 1A	
Section C3.5.2	Quality Management	Volume 1A	
Section C3.5.3	Occupational Health and Safety Management	Volume 1A	
Section C3.5.4	Environmental Management Plan	Volume 1A	
<u>PORTION 3 BOOK OF DRAWINGS</u>		Volume 4	White

END OF SECTION

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS

PORTION 2: CONTRACT

PART C2 PRICING DATA

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2
June 2025

C2 PRICING DATA

INDEX		
Section	Description	Page No
C2.1	PRICING INSTRUCTIONS	C2.1-1
C2.2	BILL OF QUANTITIES	C2.2
C2.3	SUMMARY OF SCHEDULES	C2.3

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

**RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT
WORKS – MECHANICAL AND ELECTRICAL WORKS**

C2.1 PRICING INSTRUCTIONS

C2.1 PRICING INSTRUCTIONS

1. General

1.1 This section provides the tenderer with guidelines and requirements with regard to the completion of the Bill of Quantities. The Schedule has to be completed in black ink and the tenderer is referred to the Tender Specifications in regard to the correction of errors.

1.2 The Bill of Quantities shall be read with all the documents which form part of this Contract.

1.3 The following words shall have the meanings hereby assigned to them:

- Unit: The unit of measurement for each item of work in terms of the Specifications and the Project Specifications.
- Quantity: The number of units of work for each item.
- Rate: The payment per unit of work at which the tenderer tenders to do the work.
- Amount: The product of the quantity and the rate tendered for an item.
- Lump sum: An amount tendered for an item, the extent of which is described in the Bill of Quantities, the Specifications and the Project Specifications, but the quantity of work of which is not measured in any units.

1.4 Reference shall be made to the General and Special Conditions of Contract regarding Provisional and Prime Costs Sums.

1.5 The contractor shall determine the contract skills participation goals, expressed in Rand, which shall not be less than the sub-total multiplied by a percentage factor given in Table 2 in the Standard for the applicable class of construction works. This is indicated by the percentage factor in the Final Tender Summary section. Minimum Contract Skills Development Goal (CSDG) sum = Electrical Engineering(Infrastructure) EP and Mechanical Engineering (Infrastructure) ME of (0.25%) x Subtotal of the tender amount.

2. PRICING OF MECHANICAL AND ELECTRICAL WORKS

The prices quoted for the supply of plant and equipment shall include for all handling, loading, transporting and off-loading required for the delivery of the plant and equipment to the site, including in the case of off-site storage for double handling at the store.

The prices quoted for erection and/or installation shall include for all handling, loading, transporting and off-loading to take plant and equipment to place on site where required, erection, installation, painting, guaranteeing for a period of twelve (12) months and upholding for a period of twelve (12) months, all as specified.

The prices quoted for the commissioning of plant shall include for operating, mechanical and electrical testing, adjusting and handing over in a proper working order and for the provision of operating and maintenance manuals, all as specified.

<div data-bbox="159 2024 331 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Contractor</p>	<div data-bbox="387 2024 563 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Witness 1</p>	<div data-bbox="619 2024 794 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Witness 2</p>	<div data-bbox="850 2024 1026 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Employer</p>	<div data-bbox="1082 2024 1241 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Witness 1</p>	<div data-bbox="1313 2024 1473 2096" style="border: 1px solid black; width: 100px; height: 30px;"></div> <p>Witness 2</p>
--	---	---	---	---	---

02_Vol1B_ME_June25Part C2

June 2025

Any additional charges in connection with off-site storage which there may be over and above the prices quoted in the various sections of this Bill of prices, shall be set-out in detail by the Tenderer.

Amounts allowed for provisional sums and contingencies will be spent in part or as a whole at the sole discretion of the Engineer.

2. PAY ITEMS

For preliminary and general charges, the method of measurement and payment shall be as specified in Particular Specification PPG of the contract documents. Measurement and payment of mechanical and electrical equipment shall be as described in the Particular Specification, as amended, or as described in the Bill of Quantities.

Descriptions in the Bill of Quantities are abbreviated and comply generally with those in the Standard Specifications. The measurement and payment clause of each Standard Specification, read together with the relevant variations and amendments to the Standard Specification, set out what ancillary or associated activities must be included in the rates for the operations specified. Should any requirements of the measurement and payment clause of the applicable Standard Specification, or the variation thereof, conflict with the terms of the Bill of Quantities, the requirements of the Standard Specification or variation thereof, as applicable, shall prevail.

The units of measurement described in the Bill of Quantities are metric units. Abbreviations used in the Bill of Quantities are as follows:

mm	=	millimetre	h	=	hour
m	=	metre	kg	=	kilogram
km	=	kilometre	t	=	ton (1000kg)
m ²	=	square metre	no.	=	number
m ² .pass	=	square metre pass	sum	=	lump sum
ha	=	hectare	MN	=	meganewton
m ³	=	cubic metre	MN.m	=	meganewton-metre
m ³ .km	=	cubic metre-kilometre	PC sum	=	Prime Cost sum
l	=	litre	Prov sum	=	Provisional sum
kl	=	kilolitre	%	=	Percent
MPa	=	megaspascal	kW	=	kilowatt

4. RATES

4.1 The prices and rates to be inserted in the Bill of Quantities are to be full inclusive prices for the work described under the several items. Such prices and rates shall cover all costs and expenses that may be required in and for the execution of the work described, and shall cover the cost of all general risks, liabilities, and obligations set forth or implied in the documents on which the tender is based, as well as overhead charges and profit. Reasonable prices shall be inserted as these will be used as a basis for assessment of payment for additional work that may have to be carried out.

4.2 A price or rate is to be entered against each item in the Bill of Quantities, whether the quantities are stated or not. An item against which no price is entered or where a word or phrase such as "included" or

<div></div> <div>Contractor</div>	<div></div> <div>Witness 1</div>	<div></div> <div>Witness 2</div>	<div></div> <div>Employer</div>	<div></div> <div>Witness 1</div>	<div></div> <div>Witness 2</div>
-----------------------------------	----------------------------------	----------------------------------	---------------------------------	----------------------------------	----------------------------------

02_Vol1B_ME_June25Part C2

June 2025

“provided elsewhere” will be accepted as a rate of nil (R0,00) having been entered against such items and covered by the other prices or rates in the schedule.

Any work executed to which such a pay item applies, shall be measured under the appropriate items in the Bill of Quantities and valued at a rate of nil (R0,00). The rate of nil shall be valid irrespective of any change in the quantities during the execution of the Contract.


- 4.3 The Tenderer shall fill in a rate against all items where the words “rate only” appears in the amount column. The intention is that, although no work is foreseen under such item and no quantities are consequently given in the quantity column, the tendered rate shall apply should work under this item be actually required.
- 4.4 Except where rates only are required, the Tenderer shall insert all amounts to be included in his total tendered price in the “Amount” column and show the corresponding total tendered price.
- 4.5 All rates and sums of money quoted in the Bill of Quantities shall be in rands and whole cents. Fractions of a cent shall be discarded.
- 4.6 All prices and rates entered in the Bill of Quantities must be **excluding** Value Added Tax (VAT). VAT will be added last on the summary page of the Bill of Quantities.
- 4.7 Should excessively high unit prices be tendered, such prices may be of sufficient importance to warrant rejection of a tender by the Employer.
- 4.8 Where the Contractor is required to furnish detailed drawings and designs or other information in terms of the Contract Documents, all costs thereof shall be deemed to have been provided for and included in the unit rates and sum amounts tendered for the items scheduled in the Bill of Quantities, and separate additional payments will not be made.
- 4.9 For items in the bill of quantities where rates include the disposal of recyclable materials, the rebate for the value of the recyclable materials are to be included in the rate provided.

CORRECTION OF ENTRIES MADE BY TENDERER

Any entry made by the Tenderer in the Bill of Quantities, forms, etc, which the tenderer desires to change, shall not be erased or painted out. A line shall be drawn through the incorrect entry and the correct entry shall be written above in black ink and the full signature of the Tenderer shall be placed next to the correction.



Contractor



Witness 1




Witness 2



Employer



Witness 1



Witness 2

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

**RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT
WORKS – MECHANICAL AND ELECTRICAL WORKS**

C2.2 PRICING SCHEDULE

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
	PPG	<u>SCHEDULE NO. 1</u> <u>PRELIMINARY AND GENERAL</u>					
1.1		<u>SCHEDULE NO: 1.1 - FIXED-CHARGE ITEMS</u>					
1.1.1	PPG8.1.1	Contractual Requirements <u>Establishment of Facilities on Site</u>	G	sum	1		
1.1.2	PSPPG3	Facilities for the Engineer	G	sum	1		
1.1.3	PPG 8.1.2	Facilities for the Contractor	G	sum	1		
1.1.4	PPG 8.1.4	Other fixed-charge obligations					
1.1.4.1	 (contractor to specify)	G	sum	1		
1.1.5	PPG 8.1.5	Removal of Contractor's site establishment on completion	G	sum	1		
1.1.6	PPG 8.1.6	Compliance with Health and Safety Requirements	G	sum	1		
1.1.7	PSPPG8.1.7	Provision of LEP Plan, auditing and monthly reports	G	sum	1		
1.1.8	PPG 8.1.8	Compliance with record of decision and EMP	G	sum	1		
1.2		<u>SCHEDULE NO: 1.2 - TIME-RELATED ITEMS</u>					
1.2.1	PPG 8.2.1	Contractual Requirements <u>Operation and maintenance of facilities on the Site for the duration of construction</u>	G	sum	1		
1.1.2	PSPPG3	Facilities for the Engineer	G	sum	1		
1.1.3	PPG 8.2.2	Facilities for the Contractor	G	sum	1		
1.2.4	PPG 8.2.3	Supervision for duration of installation	G	sum	1		
1.2.5	PPG 8.2.4	Company and head office overhead costs for the duration of the contract	G	sum	1		
1.2.6	PPG 8.2.5	Other time-related obligations	G	sum	1		
1.2.7	PPG 8.2.6	Compliance with Health and Safety Requirements	G	sum	1		
1.2.8	PPG 8.1.8	Compliance with record of decision and EMP	G	sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
1.3		<u>SCHEDULE NO: 1.3 - OTHER GENERAL CHARGES</u>					
1.3.1	PPG 8.3.1	Temporary Storage of Equipment	G	m ³ /mth	8		
1.3.2	PPG 8.3.2	Provision of as-built drawings and details	G	Sum	1		
1.3.3	PPG 8.3.3	Provide Operation and Maintenance Manuals	G	Sum	1		
1.4		<u>SCHEDULE NO: 1.4 - TRIAL OPERATION PERIOD</u>					
1.4.1	PPG8.5.3 PSPPG6.3	Maintenance and Servicing of Mechanical and Electrical Equipment	G	Sum	1		
1.4.2	PPG8.5.4 PSPPG6.4	Supply of Chemicals	G	Sum	1		
1.4.3	PPG8.6	Trial Operation Period	G	Sum	1		
		SCHEDULE NO. 1 PRELIMINARY AND GENERAL CARRIED FORWARD TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
	PPG	SCHEDULE NO. 2 PROVISIONAL SUMS, ADDITIONAL SERVICES AND DAY WORKS					
2.1		SCHEDULE NO: 2.1 - SUMS STATED PROVISIONALLY BY THE ENGINEER					
2.1.1	PPG8.4.1	Maintenance Spares	N	P Sum	1	550,000.00	550,000.00
2.1.2	PPG8.4.2	Specialist External Inspectorate	N	P Sum	1	200,000.00	200,000.00
2.1.3	PPG8.4.4	Water Quality Sampling and Testing	N	P Sum	1	100,000.00	100,000.00
2.1.4	PPG8.4.5	Water Quality Instruments	N	P Sum	1	250,000.00	250,000.00
2.1.5	PSPPG8.4.6	CLO/LDO Salaries	N	P Sum	1	400,000.00	400,000.00
2.1.6	PSPPG8.4.7	Socio Economic Development	N	P Sum	1	250,000.00	250,000.00
2.1.7	PSPPG8.4.8	Engineer's Cellular Phone Costs	N	P Sum	1	25,000.00	25,000.00
2.1.8	PSPPG8.4.9	Engineers Site Office Consumables	N	P Sum	1	25,000.00	25,000.00
2.1.9	PSPPG 8.4.10	Electronic Equipment	N	P Sum	1	25,000.00	25,000.00
2.1.10	PSPPG 8.4.11	Acceptance and Control Testing	N	P Sum	1	25,000.00	25,000.00
2.1.11	PSPPG 8.4.12	Specialist Services	N	P Sum	1	200,000.00	200,000.00
2.1.12	PSPPG 8.4.13	Social facilitation	N	P Sum	1	2,500,000.00	2,500,000.00
2.1.13	PPG 8.3.4	Training	N	P Sum	1	200,000.00	200,000.00
2.1.14	PSPPG 8.4.14	Specialised security services, PSiRA registered	N	P Sum	1	1,450,000.00	1,450,000.00
2.1.15	PSPPG 8.4.15	Allowance for the management of local sub-contractors (SMME's) to cover any additional costs incurred (including rate variance)	N	P Sum	1	1,000,000.00	1,000,000.00
2.2		SCHEDULE NO: 2.2 - ADDITIONAL SERVICES					
2.2.1		Additional pH correction at inlet works	N	P Sum	1	300,000.00	300,000.00
2.2.2		Allowance for removal of pipe items and fittings in the existing chlorination room	N	P Sum	1	40,000.00	40,000.00
2.2.3		Allowance for sampling points and stubs for gauges	N	P Sum	1	40,000.00	40,000.00
2.2.4		Allowance for additional pipework, requirement not included elsewhere	N	P Sum	1	900,000.00	900,000.00
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
2.2.5		Allowance for isolation of "old" RGS filters bypass to new clearwater tank	N	P Sum	1	150,000.00	150,000.00
2.2.6		Allowance for installation of new knifegate valve at control valve chamber incl. suitable actuator	N	P Sum	1	150,000.00	150,000.00
2.2.7		Allowance for construction of new flow meter chamber and Box CH6, installation of 600 mm diameter ultrasonic flow meter including all pipe fittings, cutting and removal of existing pipes	N	P Sum	1	700,000.00	700,000.00
2.2.8		Allowance for core drilling 6 openings through 300 mm thick reinforced concrete wall to suit 150 mm nominal diameter steel pipe and puddle flange at existing GAC filters and repair opening with standard non-shrink grout to form watertight joint. Rate to include for removal of all debris to a spoil site established by the contractor	N	P Sum	1	30,000.00	30,000.00
2.2.9		Allowance for construction of Box CH5 including all cutting and removal of existing pipes	N	P Sum	1	150,000.00	150,000.00
2.2.10		Allowance for relocating of existing MCC including all sleeves, cable joints, cable terminations and excavations that may be required	N	P Sum	1	750,000.00	750,000.00
2.2.11	PSA7.9	.1 Locating Existing Services	N	P Sum	1	17,000.00	17,000.00
	PSA7.10	.2 Relocating of Existing Services	N	P Sum	1	34,000.00	34,000.00
		.3 Carrying out pipe coating & lining repairs on existing pipes stored at Boitekong WWTW	N	P Sum	1	340,000.00	340,000.00
2.2.12	PSPPG 6.1	Site visits and reporting	N	P Sum	1	100,000.00	100,000.00
2.2.13	PSA11.1	Allowance for Contractor's mark-up on Provisional sums		%			
2.3		SCHEDULE 2.3 - DAYWORKS					
		Note: Dayworks executed on instruction of the Engineer /Employer only					
		LABOUR					
2.3.1	8.7.1	(a) Skilled		hr	20		
		(b) Semi-skilled		hr	50		
		(c) Un-skilled		hr	100		
		PLANTHIRE (WORK RATES ON SITE)					
		TRUCKS					
2.3.2	8.7.2	Tipper trucks (specify capacity)					
		(a) Capacity _____ m ³ (small)		hr	0		
Carried Forward							

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
		(b) Capacity____m ³ (medium)		hr	25		
		(c) Capacity____m ³ (large)		hr	25		
	8.7.2	<u>Flatbed trucks (specify capacity)</u>					
		(a) Capacity____m ³ (small)		hr	25		
		(b) Capacity____m ³ (medium)		hr	25		
		(c) Capacity____m ³ (large)		hr	0		
		<u>LDV'S</u>					
2.3.3	8.7.2	<u>LDV (specify size)</u>					
		(a) LDV____ton		km	250		
		<u>WATER TANKERS</u>					
2.3.4	8.7.2	<u>Water tankers (specify capacity)</u>					
		(a) Capacity____litre (small, towable)		hr	0		
		(b) Capacity____litre (medium)		hr	25		
		(c) Capacity____litre (large)		hr	25		
		<u>LOADERS</u>					
2.3.5	8.7.2	<u>Wheel loaders (specify capacity)</u>					
		(a) Capacity____m ³ (small)		hr	0		
		(b) Capacity____m ³ (medium)		hr	25		
		(c) Capacity____m ³ (large)		hr	0		
		<u>GRADERS</u>					
2.3.6	8.7.2	<u>Motor graders (specify model/kw)</u>					
		(a) Model____/____kw		hr	25		
		<u>EXCAVATORS</u>					
2.3.7	8.7.2	<u>Crawler excavators (specify model/mass/kw)</u>					
		(a) Model____/____/kg____kw (small)		hr	0		
		(b) Model____/____/kg____kw (medium)		hr	25		
		(c) Model____/____/kg____kw (large)		hr	0		
		<u>TLB'S</u>					
2.3.8	8.7.2	<u>Tractor loader backhoe (TLB)(specify model)</u>					
		(a) Model____		hr	50		
2.3.9		<u>ROLLERS</u>					
	8.7.2	<u>Self propelled vibrating rollers (smooth drum) (specify mass)</u>					
		(a) Mass____kg (medium)		hr	20		
		(b) Mass____kg (large)		hr	0		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
2.3.10	8.7.2	<u>Self propelled vibrating rollers (padfoot)</u> <u>(specify mass)</u> (a) Mass _____ kg (medium) (b) Mass _____ kg (large)		hr	0		
				hr	0		
	8.7.2	<u>Walk behind vibrating rollers (specify model)</u> (a) Model _____ (BW 61) (small) (b) Model _____ (BW 76) (medium) (c) Model _____ (BW 90) (large)		hr	0		
				hr	25		
				hr	25		
		<u>COMPACTORS</u>					
	8.7.2	<u>Plate compactors (specify model)</u> (a) Model _____		hr	40		
	8.7.2	<u>Wackers (specify model)</u> (a) Model _____		hr	40		
		<u>CONCRETE MIXERS</u>					
	8.7.2	<u>Concrete mixers (specify mixing volume)</u> (a) Volume _____ litre (small, towable) (b) Volume _____ litre (medium) (c) Volume _____ litre (large)		hr	0		
2.3.11				hr	25		
				hr	0		
		<u>COMPRESSORS</u>					
	8.7.2	<u>Portable diesel compressors (specify capacity)</u> (a) Capacity _____ cfm (small) (b) Capacity _____ cfm (medium) (c) Capacity _____ cfm (large)		hr	0		
				hr	20		
				hr	0		
		<u>WATERPUMPS</u>					
	8.7.2	<u>Waterpump (specify capacity)</u> (a) Capacity _____ liter/sec (small) (b) Capacity _____ liter/sec (medium) (c) Capacity _____ liter/sec (large)		hr	20		
				hr	20		
				hr	0		
2.3.12		<u>WELDERS</u>					
	8.7.2	<u>Welding unit (specify ampere)</u> (a) _____ Amp (small) (b) _____ Amp (medium) (c) _____ Amp (large)		hr	0		
				hr	20		
				hr	0		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
2.3.15	8.7.2	<u>GENERATORS</u> Mobile generator set (specify KVA) (a) _____ KVA (small) (b) _____ KVA (medium) (c) _____ KVA (large)		hr hr hr	0 25 0		
2.4		<u>TRANSPORT (TRANSPORT COST TO AND FROM SITE)</u> <u>Note:</u> Distance shall be measured one way only (Tender rates shall include for transport in both directions to and from site)					
2.4.1	8.7.3	<u>Low bed</u> (a) Low-bed (suitable for the largest piece of equipment above)		km	200		
2.4.2	8.7.3	<u>Tipper truck</u> (a) Small (b) Medium (c) Large		km km km	0 50 50		
2.4.3	8.7.3	<u>Flatbed truck</u> (a) Small (b) Medium (c) Large		km km km	50 50 0		
2.4.4	8.7.3	<u>Water tanker</u> (a) Small (b) Medium (c) Large		km km km	0 50 50		
2.5	8.6	<u>PRIME COST ITEMS</u>					
2.5.1	PSA8.1	Materials used in the execution of dayworks		PC item	1	25,000.00	25,000.00
<u>DAY WORKS</u> CARRIED FORWARD TO SUMMARY							
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
3	PLK PLKA PLN 3.1 PLQ	<u>SCHEDULE NO. 3</u> <u>STEEL, PIPE FITTINGS AND VALVES</u> The rate for all items shall include for supply, delivery factory applied corrosion protection and off-loading on site					
3.1.1		<u>SCHEDULE NO: 3.1.1 - NEW DAF UNIT STEEL, PIPE FITTINGS AND VALVES</u>					
		ref. dwg. 1890.08.EA.13.M001					
3.1.1.1		DAF 1.2	P	No	2		
3.1.1.2		DAF 1.3	S	No	1		
3.1.1.3		DAF 1.4	S	No	2		
3.1.1.4		DAF 1.5	P	No	4		
3.1.1.5		DAF 1.6	S	No	4		
3.1.1.6		DAF 2.1	P	No	1		
3.1.1.7		DAF 2.2	P	No	1		
3.1.1.8		DAF 2.3	S	No	1		
3.1.1.9		DAF 2.4	S	No	2		
3.1.1.10		DAF 2.5	S	No	2		
3.1.1.11		DAF 2.6	S	No	1		
3.1.1.12		DAF 2.7	P	No	1		
3.1.1.13		DAF 2.8	P	No	1		
3.1.1.14		DAF 3.1	P	No	4		
3.1.1.15		DAF 3.2	S	No	1		
3.1.1.16		DAF 7.1	S	No	2		
3.1.1.17		DAF 9.1	M	No	4		
3.1.1.18		DAF 9.2	M	No	1		
3.1.1.19		DAF 9.3	M	No	1		
3.1.1.20		DAF 12.1a	M	No	1		
3.1.1.21		DAF 12.1b	E	No	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.1.1.22		DAF 14.1	S	No	150		
3.1.2		SCHEDULE NO: 3.1.2 - RGS FILTRATION SYSTEM STEEL, PIPE FITTINGS AND VALVES					
		ref. dwg. 1890.08.FA.14.D002 to D005 and X001 to X004					
3.1.2.1		FA1.4	P	No	3		
3.1.2.2		FA1.5	P	No	2		
3.1.2.3		FA1.6	S	No	8		
3.1.2.4		FA1.7	S	No	8		
3.1.2.5		FA1.8	S	No	8		
3.1.2.6		FA1.9	S	No	4		
3.1.2.7		FA1.10	S	No	4		
3.1.2.8		FA1.11	S	No	2		
3.1.2.9		FA2.1	P	No	1		
3.1.2.10		FA2.2	P	No	1		
3.1.2.11		FA2.3	P	No	3		
3.1.2.12		FA2.4	P	No	8		
3.1.2.13		FA2.5	P	No	8		
3.1.2.14		FA2.6	P	No	1		
3.1.2.15		FA3.1	P	No	2		
3.1.2.16		FA3.2	P	No	1		
3.1.2.17		FA3.3	P	No	1		
3.1.2.18		FA3.4	P	No	8		
3.1.2.19		F4.1	P	No	8		
3.1.2.20		F4.2	P	No	8		
3.1.2.21		FA9.1	M	No	2		
3.1.2.22		F9.2a	M	No	8		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.1.2.23		F9.2b	E	No	8		
3.1.2.24		F9.3	M	No	8		
3.1.2.25		F9.4	M	No	8		
3.1.2.26		F9.5a	M	No	8		
3.1.2.27		F9.5b	E	No	8		
3.1.2.26		F9.6a	M	No	4		
3.1.2.27		F9.6b	E	No	4		
3.1.2.28		FA12.1a	M	No	4		
3.1.2.29		FA12.1b	E	No	4		
3.1.2.30		FAX	P/S	No	1		
3.1.3	SCHEDULE NO: 3.1.3 - GAC FILTRATION SYSTEM STEEL, PIPE FITTINGS AND VALVES						
		ref. dwg. 1890.08.FB.14.D005 to D006 and X002 to X004 and A002					
3.1.3.1		FB1.1	P	No	3		
3.1.3.2		FB1.2	P	No	2		
3.1.3.3		FB1.3	P	No	6		
3.1.3.4		FB1.4	S	No	6		
3.1.3.5		FB1.5	S	No	6		
3.1.3.6		FB1.6	S	No	6		
3.1.3.7		FB1.7	P	No	1		
3.1.3.8		FB1.8	P	No	6		
3.1.3.9		FB1.9	P	No	5		
3.1.3.10		FB1.10	P	No	6		
3.1.3.11		FB2.1	S	No	6		
3.1.3.12		FB2.2	P	No	6		
3.1.3.13		FB2.3	P	No	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.1.3.14		FB2.4	P	No	1		
3.1.3.15		FB2.5	P	No	1		
3.1.3.16		FB2.6	P	No	1		
3.1.3.17		FB2.7	P	No	1		
3.1.3.18		FB2.8	P	No	1		
3.1.3.19		FB3.1	P	No	6		
3.1.3.20		FB3.2	P	No	6		
3.1.3.21		FB3.3	P	No	6		
3.1.3.22		FB3.4	P	No	5		
3.1.3.23		FB4.1	P	No	6		
3.1.3.24		FB4.2	P	No	6		
3.1.3.25		FB7.1	P	No	6		
3.1.3.26		FB9.1a	M	No	6		
3.1.3.27		FB9.1b	E	No	6		
3.1.3.28		FB9.2	M	No	6		
3.1.3.29		FB9.3a	M	No	6		
3.1.3.30		F9.3b	E	No	6		
3.1.3.31		FB9.4a	M	No	6		
3.1.3.32		F9.4b	E	No	6		
3.1.3.33		F9.5a	M	No	6		
3.1.3.34		F9.5b	E	No	6		
3.1.3.35		FB9.6	M	No	12		
3.1.3.36		FA12.1a	M	No	4		
3.1.3.37		FA12.1b	E	No	4		
3.1.3.38		FBX	P	No	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.1.4		SCHEDULE NO: 3.1.4 - FILTRATE SUMP STEEL, PIPE FITTINGS AND VALVES					
		<u>ref. dwg. 1890.08.QB.14.D001</u>					
3.1.4.1		QB1.1	P	No	2		
3.1.4.2		QB1.2	P	No	2		
3.1.4.3		QB1.3	P	No	1		
3.1.4.4		QB2.1	P	No	2		
3.1.4.5		QB2.2	P	No	1		
3.1.4.6		QB2.3	P	No	1		
3.1.4.7		QB2.4	P	No	1		
3.1.4.8		QB3.1	P	No	1		
3.1.4.9		QB4.1	P	No	2		
3.1.4.10		QB6.1	P	No	1		
3.1.4.11		QB8.1	P	No	2		
3.1.4.12		QB9.1	P	No	2		
3.1.4.13		QB10.1	P	No	2		
3.1.4.14		QB13.1	M	No	1		
3.1.5		SCHEDULE NO: 3.1.5 - FLOW METER CHAMBER STEEL, PIPE FITTINGS AND VALVES					
		<u>ref. dwg. 1890.08.QG.14.D001</u>					
3.1.5.1		QG4.1	P	No	1		
3.1.5.2		QG7.1	P	No	2		
3.1.5.3		QG8.1	P	No	1		
3.1.5.4		QG8.2	P	No	1		
3.1.5.5		QG13.1	M	No	1		
3.1.6		SCHEDULE NO: 3.1.6 - OZONE CONTACT TANK STEEL, PIPE FITTINGS AND VALVES					
		<u>ref. dwg. 1890.08.QA.14.D001 and X001</u>					
3.1.6.1		OA7.2	P	No	3		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.1.6.2		OA1.10	P	No	3		
3.1.7		SCHEDULE NO: 3.1.7 - PRE-OZONE SYSTEM PIPE FITTINGS AND VALVES					
		ref. dwg. 1890.08.SUF.12.D001 and 13.D001					
3.1.7.1		PZ1.1	P	No	1		
3.1.7.2		PZ1.2	P	No	1		
3.1.7.3		PZ2.1	P	No	2		
3.1.7.4		PZ3.1	P	No	1		
3.1.7.5		PZ4.2	P	No	1		
3.1.7.6		PZ5.1	P	No	1		
3.1.7.7		PZ13.1	M	No	1		
3.2	Pipe Item Schedule	<u>The rate for all items to include for the handling, installation, testing, site corrosion protection, painting and building into walls</u>					
3.2.1		SCHEDULE NO: 3.2.1 - NEW DAF UNIT STEEL, PIPE FITTINGS AND VALVES					
		ref. dwg. 1890.08.EA.13.M001					
3.2.1.1		DAF 1.2	I	No	2		
3.2.1.2		DAF 1.3	I	No	1		
3.2.1.3		DAF 1.4	I	No	2		
3.2.1.4		DAF 1.5	I	No	4		
3.2.1.5		DAF 1.6	I	No	4		
3.2.1.6		DAF 2.1	I	No	1		
3.2.1.7		DAF 2.2	I	No	1		
3.2.1.8		DAF 2.3	I	No	1		
3.2.1.9		DAF 2.4	I	No	2		
3.2.1.10		DAF 2.5	I	No	2		
3.2.1.11		DAF 2.6	I	No	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.2.1.12		DAF 2.7	I	No	1		
3.2.1.13		DAF 2.8	I	No	1		
3.2.1.14		DAF 3.1	I	No	4		
3.2.1.15		DAF 3.2	I	No	1		
3.2.1.16		DAF 7.1	I	No	2		
3.2.1.17		DAF 9.1	I	No	4		
3.2.1.18		DAF 9.2	I	No	1		
3.2.1.19		DAF 9.3	I	No	1		
3.2.1.20		DAF 12.1a	I	No	1		
3.2.1.21		DAF 12.1b	I	No	1		
3.2.1.22		DAF 14.1	I	No	150		
3.2.2	SCHEDULE NO: 3.2.2 - RGS FILTRATION SYSTEM STEEL, PIPE FITTINGS AND VALVES						
		ref. dwg. 1890.08.FA.14.D002 to D005 and X001 to X004					
3.2.2.1		FA1.4	I	No	3		
3.2.2.2		FA1.5	I	No	2		
3.2.2.3		FA1.6	I	No	8		
3.2.2.4		FA1.7	I	No	8		
3.2.2.5		FA1.8	I	No	8		
3.2.2.6		FA1.9	I	No	4		
3.2.2.7		FA1.10	I	No	4		
3.2.2.8		FA1.11	I	No	2		
3.2.2.9		FA2.1	I	No	1		
3.2.2.10		FA2.2	I	No	1		
3.2.2.11		FA2.3	I	No	3		
3.2.2.12		FA2.4	I	No	8		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.2.2.13		FA2.5	I	No	8		
3.2.2.14		FA2.6	I	No	1		
3.2.2.15		FA3.1	I	No	2		
3.2.2.16		FA3.2	I	No	1		
3.2.2.17		FA3.3	I	No	1		
3.2.2.18		FA3.4	I	No	8		
3.2.2.19		F4.1	I	No	8		
3.2.2.20		F4.2	I	No	8		
3.2.2.21		FA9.1	I	No	2		
3.2.2.22		F9.2a	I	No	8		
3.2.2.23		F9.2b	I	No	8		
3.2.2.24		F9.3	I	No	8		
3.2.2.25		F9.4	I	No	8		
3.2.2.26		F9.5a	I	No	8		
3.2.2.27		F9.5b	I	No	8		
3.2.2.26		F9.6a	I	No	4		
3.2.2.27		F9.6b	I	No	4		
3.2.2.28		FA12.1a	I	No	4		
3.2.2.29		FA12.1b	I	No	4		
3.2.2.30		FAX	I	No	1		
3.2.3	SCHEDULE NO: 3.2.3 - GAC FILTRATION SYSTEM STEEL, PIPE FITTINGS AND VALVES						
		ref. dwg. 1890.08.FB.14.D005 to D006 and X002 to X004 and A002					
3.2.3.1		FB1.1	I	No	3		
3.2.3.2		FB1.2	I	No	2		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.2.3.3		FB1.3	I	No	6		
3.2.3.4		FB1.4	I	No	6		
3.2.3.5		FB1.5	I	No	6		
3.2.3.6		FB1.6	I	No	6		
3.2.3.7		FB1.7	I	No	1		
3.2.3.8		FB1.8	P	No	6		
3.2.3.9		FB1.9	P	No	5		
3.2.3.10		FB1.10	P	No	6		
3.2.3.11		FB2.1	I	No	6		
3.2.3.12		FB2.2	I	No	6		
3.2.3.13		FB2.3	I	No	1		
3.2.3.14		FB2.4	I	No	1		
3.2.3.15		FB2.5	I	No	1		
3.2.3.16		FB2.6	I	No	1		
3.2.3.17		FB2.7	I	No	1		
3.2.3.18		FB2.8	I	No	1		
3.2.3.19		FB3.1	I	No	6		
3.2.3.20		FB3.2	I	No	6		
3.2.3.21		FB3.3	I	No	6		
3.2.3.22		FB3.4	I	No	5		
3.2.3.23		FB4.1	I	No	6		
3.2.3.24		FB4.2	I	No	6		
3.2.3.25		FB7.1	I	No	6		
3.2.3.26		FB9.1a	I	No	6		
Carried Forward							

Contractor

Witness 1


Witness 2

Employer


Witness 1

Witness 2


Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.2.3.27		FB9.1b	I	No	6		
3.2.3.28		FB9.2	I	No	6		
3.2.3.29		FB9.3a	I	No	6		
3.2.3.30		F9.3b	I	No	6		
3.2.3.31		FB9.4a	I	No	6		
3.2.3.32		F9.4b	I	No	6		
3.2.3.33		F9.5a	I	No	6		
3.2.3.34		F9.5b	I	No	6		
3.2.3.35		FB9.6	I	No	12		
3.2.3.36		FA12.1a	I	No	4		
3.2.3.37		FA12.1B	I	No	4		
3.2.3.38		FBX	I	No	1		
3.2.4	SCHEDULE NO: 3.2.4 - FILTRATE SUMP STEEL, PIPE FITTINGS AND VALVES						
		<u>ref. dwg. 1890.08.QB.14.D001</u>					
3.2.4.1		QB1.1	I	No	2		
3.2.4.2		QB1.2	I	No	2		
3.2.4.3		QB1.3	I	No	1		
3.2.4.4		QB2.1	I	No	2		
3.2.4.5		QB2.2	I	No	1		
3.2.4.6		QB2.3	I	No	1		
3.2.4.7		QB2.4	I	No	1		
3.2.4.8		QB3.1	I	No	1		
3.2.4.9		QB4.1	I	No	2		
3.2.4.10		QB6.1	I	No	1		
3.2.4.11		QB8.1	I	No	2		
Carried Forward							




Contractor




Witness 1




Witness 2



Employer



Witness 1



Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.2.4.12		QB9.1	I	No	2		
3.2.4.13		QB10.1	I	No	2		
3.2.4.14		QB13.1	I	No	1		
3.2.5	SCHEDULE NO: 3.2.5 - FLOW METER CHAMBER STEEL, PIPE FITTINGS AND VALVES						
		<u>ref. dwg. 1890.08.QG.14.D001</u>					
3.2.5.1		QG4.1	I	No	1		
3.2.5.2		QG7.1	I	No	2		
3.2.5.3		QG8.1	I	No	1		
3.2.5.4		QG8.2	I	No	1		
3.2.5.5		QG13.1	I	No	1		
3.2.6	SCHEDULE NO: 3.2.6 - OZONE CONTACT TANK STEEL, PIPE FITTINGS AND VALVES						
		<u>ref. dwg. 1890.08.QA.14.D001 and X001</u>					
3.2.6.1		OA7.2	I	No	3		
3.2.6.2		OA1.10	I	No	3		
3.2.7	SCHEDULE NO: 3.2.7 - PRE-OZONE SYSTEM PIPE FITTINGS AND VALVES						
		<u>ref. dwg. 1890.08.SUF.12.D001 and 13.D001</u>					
3.2.7.1		PZ1.1	I	No	1		
3.2.7.2		PZ1.2	I	No	1		
3.2.7.3		PZ2.1	I	No	2		
3.2.7.4		PZ3.1	I	No	1		
3.2.7.5		PZ4.2	I	No	1		
3.2.7.6		PZ5.1	I	No	1		
3.2.7.7		PZ13.1	I	No	1		
3.3	SCHEDULE NO : 3.3 - STEEL PIPE SUPPORTS AND PIPE CLAMPS						
3.3.1		<u>Hot dip galvanized steel pipe supports bolted to concrete slab with mechanical anchors</u>					
Carried Forward							

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
		<u>DAF:</u> i) 150mm Ø pipe support <u>GAC Filters:</u> ii) 150mm Ø pipe clamp <u>Pre-Ozone Building:</u> iii) 250mm Ø pipe support	M	no	2		
			M	no	10		
			M	no	4		
3.4		SCHEDULE NO : 3.4 - CONCRETE PIPE SUPPORTS AND PIPE CLAMPS					
3.4.1		<u>Mild steel pipe clamps bolted to concrete support with mechanical anchors</u> <u>Filtrate Pump Station</u> (1890.08.QB.14.D001) i) 150mm Ø Delivery pipe	M	no	3		
3.5		<u>PUMP STATION - STEEL PIPE FITTINGS AND VALVES DESIGN, DRAWINGS AND GENERAL</u> <u>The rate for all items shall include for supply, delivery factory applied corrosion protection and off-loading on site</u> 3.5.1 Provide design drawings and information as specified 3.5.2 Provide operating and maintenance manuals and "as built" drawings as specified <u>STEEL PIPE FITTINGS AND VALVES</u> <u>ref. dwg. 1890.11.00.WPA.13.D001</u> <u>The rate for all items to include for the handling, installation, testing, site corrosion protection, painting and building into walls</u> 3.5.3 Pump suction reducers to be replaced to suit offered pump inlet dia. and pump dimensions (as applicable) 3.5.4 Connection pipes with reducers to be replaced to suit offered pump inlet and outlet dia.'s and pump dimensions (as applicable)	G	Sum	1		
			G	Sum	1		
			I	No	2		
			I	No	2		
Carried Forward							

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
3.5.5		Delivery reducers to be replaced to suit offered pump outlet dia. and pump dimensions (as applicable)	I	No	2		
SCHEDULE NO. 3 <u>STEEL, PIPE FITTINGS AND VALVES</u> CARRIED FORWARD TO SUMMARY							
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
4	SANS 1200 HA	<u>SCHEDULE: 4</u> <u>STRUCTURAL STEELWORK (SMALL WORKS)</u> Rate to include for supply of material, erection, welding, bolts, nuts, protection, etc.					
4.1		<u>SCHEDULE NO: 4.1 - DISSOLVED AIR FLOTATION (DAF)</u>					
4.1.2		Stainless Steel (316L) adjustable weir plate bolted to concrete wall, complete as per drg 1890.08.EA.13.D003	S	No	2		
4.2		<u>SCHEDULE NO: 4.2 - GAC FILTRATION SYSTEM</u>					
4.2.1		Working platform, RS40 grating on PC140 bolted to concrete wall with side mounted hand rail complete as shown on drg. 1890.08.FB.14.D007	M	No	6		
		SCHEDULE: 4 STRUCTURAL STEELWORK (SMALL WORKS) CARRIED FORWARD TO SUMMARY					
			TOTAL				

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
5	PTB PSPTB	SCHEDULE: 5 DISSOLVED AIR FLOTATION (DAF)					
5.1		SCHEDULE NO: 5.1 - DESIGN AND DRAWINGS					
5.1.1		Detail design calculations, as well as submission of quality assurance documentation, detailed P&ID's, and manufacturing GA layouts, pipe work layouts as may be required for complete installation	G	Sum	1		
5.2		SCHEDULE NO: 5.2 - SATURATOR AND AIR COMPRESSOR					
5.2.1		<u>The rate is to include the supply, delivery, transport, handling, installation and testing etc.</u>					
5.2.1.1	PTB5a PSPTB1	Mild Steel rubber lined saturator complete with media, magnetic level indicator, pressure testing, air piping etc. complete as shown on drawing 1890.08.EA.13.D002	M	No	1		
5.2.1.2	PTB5b PSPTB4	Air compressor with air receiver to feed DAF saturator including piping inside high lift pump station	M	No	1		
5.3		SCHEDULE NO: 5.3 - COMMISSIONING					
5.3.1		Commissioning of one DAF unit	I	Sum	1		
		SCHEDULE: 5 DISSOLVED AIR FLOTATION (DAF) CARRIED FORWARD TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
6	PTG PTTG PSPTTG	SCHEDULE: 6 RGS FILTRATION SYSTEM					
6.1		SCHEDULE NO: 6.1 - DESIGN AND DRAWINGS					
6.1.1		Detail design calculations, as well as submission of quality assurance documentation, detailed P&ID's, and manufacturing GA layouts, pipe work layouts as may be required for complete installation	G	Sum	1		
6.2		SCHEDULE NO: 6.2 - SUPPLY AND DELIVERY TO SITE RGS FILTER EQUIPMENT					
6.2.1	PSPTT 1.2 & 1.3	RAPID GRAVITY SAND FILTER FLOOR Complete rapid gravity sand filter floor system including laterals, nozzles, fixing and sealing materials. Nozzles to be embedded in concrete. (refer to dwgs 1890.08.FA.14.D001 and D002, X001 - X003)	M	No	4		
6.2.2		FILTER MEDIA Note: Volume will be measured of media in place after one complete backwash cycle.					
	PSPTT 1.4 i)	Sand (700 mm)	M	m ³	155		
	PSPTT 1.4 ii)	Grit (100 mm)	M	m ³	25		
	PSPTT 1.4 iii)	Pebbles (150 mm)	M	m ³	35		
6.3		SCHEDULE NO: 6.3 - INSTALLATION OF RGS FILTER EQUIPMENT					
6.3.1	PSPTT 1.2 & 1.3	RAPID GRAVITY SAND FILTER FLOOR Complete rapid gravity sand filter floor system including laterals, nozzles, fixing and sealing materials. Nozzles to be embedded in concrete. (refer to dwgs 1890.08.FA.14.D001 and D002, X001 - X003)	I	No	4		
6.3.2		FILTER MEDIA Note: Volume will be measured of media in place after one complete backwash cycle.					
	PSPTT 1.4 i)	Sand (700 mm)	I	m ³	155		
	PSPTT 1.4 ii)	Grit (100 mm)	I	m ³	25		
	PSPTT 1.4 iii)	Pebbles (150 mm)	I	m ³	35		
Carried Forward							

 Contractor

 Witness 1

 Witness 2

 Employer

 Witness 1

 Witness 2

Brought Forward					
6.4		SCHEDULE NO: 6.4 - COMMISSIONING OF RGS FILTER EQUIPMENT			
6.4.1	PSPTT 1.2 & 1.3	RAPID GRAVITY SAND FILTER FLOOR Commissioning of the RGS Filters complete	I	Sum	1
		SCHEDULE: 6 RGS FILTRATION SYSTEM CARRIED FORWARD TO SUMMARY			
TOTAL					

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
7	PTO PSPTO	<u>SCHEDULE 7: OZONE EQUIPMENT</u>					
7.1		<u>SCHEDULE NO: 7.1 - DESIGN, DRAWINGS AND GENERAL</u>					
		Provide design drawings and design information as specified including as-built and O&M information	G	Sum	1		
		<u>SUPPLY AND DELIVERY OF OZONE EQUIPMENT TO SITE</u>					
7.2	PTO	<u>SCHEDULE NO: 7.2 - OZONE GENERATION EQUIPMENT</u>					
	PSPTO 5	Complete ozone generation system					
7.2.1		Supplier 1: - Ozone generator (13,2 kg/hr at O ₃ concentration of 10 (%wt) and 25°C cooling water temperature) complete with power supply	M	No	2		
7.2.2		- Ozone generation system instrumentation	M	Sum	1		
7.2.3		- Ventilation system in ozone generator room	M	No	1		
7.2.4		- Ozone production control system	M	No	1		
7.2.5		- Ozone generation pipework and valves	M	Sum	1		
7.2.6		- Ozone dosing control system	M	No	1		
7.2.7		Supplier 2 - Ozone generator (13,2 kg/hr at O ₃ concentration of 10 (%wt) and 25°C cooling water temperature) complete with power supply	M	No	2		
7.2.8		- Ozone generation system instrumentation	M	Sum	1		
7.2.9		- Ventilation system in ozone generator room	M	No	1		
7.2.10		- Ozone production control system	M	No	1		
7.2.11		- Ozone generation pipework and valves	M	Sum	1		
7.2.12		- Ozone dosing control system	M	No	1		
		(NOTE: The rates from both suppliers shall be completed, only the highest rate shall be carried forward to the total)					
7.3	PSPTO 7	<u>SCHEDULE NO: 7.3 - NITROGEN BLEED EQUIPMENT</u>					
7.3.1		A complete dual air compressor system with air receiver, air filters, refrigerant and desiccant driers, flow, pipework, valves, pressure control valves and dew point analyzer with a capacity of at least 10 Nm ³ /hr.	M	No	1		
7.4	PSPTO 8	<u>SCHEDULE NO: 7.4 - COOLING WATER EQUIPMENT</u>					
7.4.1		Cooling water pumpsets suitable for operation with ozone generators	M	No	2		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.4.2		Cooling water pipework, valves and instrumentation to complete the cooling water system	M	Sum	1		
7.5		SCHEDULE NO: 7.5 - OZONE DIFFUSION AND INJECTION EQUIPMENT					
	PSPTO 9	MAIN OZONE BUBBLE DIFFUSION EQUIPMENT					
7.5.1		Pipework and valves from ozone generation to diffusers	M	Sum	1		
		Stage 1 diffusers					
7.5.2		Ceramic dome diffusers, manifold, gaskets, couplings supports, valves and feed pipes for dissolved ozone gas into water at a maximum rate of 6 mg/l.	M	No	1		
		Stage 2 and 3 diffusers					
7.5.3		Ceramic dome diffusers, manifold, gaskets, couplings supports, valves and feed pipes for dissolved ozone gas into water at a maximum rate of 3 mg/l.	M	No	2		
7.5.4		200NB pressure relief and vacuum breaker for ozone contact tank	M	No	4		
	PSPTO 10	(PRE-OZONE) SIDESTREAM DIFFUSION AND DEGASSING EQUIPMENT					
7.5.5		Pipework and valves from ozone generation to pre-ozone dosing point including pipe special on main pipeline	M	Sum	1		
7.5.6		Sidestream pumpsets with flow rate of at least 100 m³/h	M	No	2		
7.5.7		Ozone injection device each capable of 16 m³/hr	M	No	2		
7.5.8	PSPLT 1	Water flow meter with measuring range of 0 - 300 m³/hr	M	No	1		
7.5.9		Pre-ozone diffusion Instrumentation		Sum	1		
7.6	PSPTO 11	SCHEDULE NO: 7.6 - OZONE DESTRUCTION EQUIPMENT					
	PSPTO 11	MAIN OZONE VENT OFF-GAS DESTRUCTION EQUIPMENT					
7.6.1		Complete off-gas destruction system including extraction fan, thermo-catalytic converter, ozone off-gas analyser and demister	M	Sum	1		
7.6.2		Pipework and valves	M	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.6.3		Main ozone diffusion Instrumentation	M	Sum	1		
7.7	PSPTO 15	<u>SCHEDULE NO: 7.7 - ADDITIONAL OZONE INSTRUMENTATION</u>					
		(Not included above)					
7.7.1		Oxygen concentration analyser	M	No	2		
7.7.2		Ozone gas analyser (low concentration)	M	No	4		
7.7.3		Ozone off-gas analyser	M	No	2		
7.7.4		Ozone gas analyser (high concentration)	M	No	4		
7.7.5		UV254 analyser	M	No	4		
7.7.6		Dew point analyser	M	No	2		
7.7.7		Mass flow meter (ozone gas flow)	M	No	5		
7.8		<u>SCHEDULE NO: 7.8 - ADDITIONAL EQUIPMENT REQUIRED</u>					
7.8.1		a).....	M	Sum	1		
7.8.2		b).....	M	Sum			
7.8.3		c).....	M	Sum			
7.8.4		d).....	M	Sum			
7.8.5		e).....	M	Sum			
7.8.6		f).....	M	Sum			
7.8.7		g).....	M	Sum			
		<u>INSTALLATION OF OZONE EQUIPMENT</u>					
7.9	PTO	<u>SCHEDULE NO: 7.9 - OZONE GENERATION EQUIPMENT</u>					
	PSPTO 5	Complete ozone generation system					
		Supplier 1:					
7.9.1		- Ozone generator (13,2 kg/hr at O ₃ concentration of 10 (%wt) and 25°C cooling water temperature) complete with power supply	I	No	2		
7.9.2		- Ozone generation system instrumentation	I	Sum	1		
7.9.3		- Ventilation system in ozone generator room	I	No	1		
7.9.4		- Ozone production control system	I	No	1		
7.9.5		- Ozone generation pipework and valves	I	Sum	1		
7.9.6		- Ozone dosing control system	I	No	1		
7.9.7							
		Supplier 2					
7.9.8		- Ozone generator (13,2 kg/hr at O ₃ concentration of 10 (%wt) and 25°C cooling water temperature) complete with power supply	I	No	2		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.9.9		- Ozone generation system instrumentation	I	Sum	1		
7.9.10		- Ventilation system in ozone generator room	I	No	1		
7.9.11		- Ozone production control system	I	No	1		
7.9.12		- Ozone generation pipework and valves	I	Sum	1		
7.9.13		- Ozone dosing control system	I	No	1		
(NOTE: The rates from both suppliers shall be completed, only the highest rate shall be carried forward to the total)							
7.1	PSPTO 7	SCHEDULE NO: 7.10 - NITROGEN BLEED EQUIPMENT					
7.10.1		A complete dual air compressor system with air receiver, air filters, refrigerant and desiccant driers, flow, pipework, valves, pressure control valves and dew point analyzer with a capacity of at least 10 Nm ³ /hr.	I	No	1		
7.11	PSPTP 8	SCHEDULE NO: 7.11 - COOLING WATER EQUIPMENT					
7.11.1		Cooling water pumpsets suitable for operation with generators	I	No	2		
7.11.2		Cooling water pipework, valves and instrumentation to ozone complete the cooling water system	I	Sum	1		
7.12		SCHEDULE NO: 7.12 - OZONE DIFFUSION AND INJECTION EQUIPMENT					
	PSPTO 9	MAIN OZONE BUBBLE DIFFUSION EQUIPMENT					
		Stage 1 diffusers					
7.12.1		Ceramic dome diffusers, manifold, gaskets, couplings supports, valves and feed pipes for dissolved ozone gas into water at a maximum rate of 6 mg/l.	I	No	1		
		Stage 2 and 3 diffusers					
7.12.2		Ceramic dome diffusers, manifold, gaskets, couplings supports, valves and feed pipes for dissolved ozone gas into water at a maximum rate of 3 mg/l.	I	No	2		
7.12.3		200NB pressure relief and vacuum breaker for ozone contact tank	M	No	4		
	PSPTO 10	(PRE-OZONE)SIDESTREAM DIFFUSION AND DEGASSING EQUIPMENT					
7.12.4		Pipework and valves from ozone generation to pre-ozone dosing point including pipe special on main pipeline	I	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.12.5		Sidestream pumpsets with flow rate of at least 100 m³/hr	I	No	2		
7.12.6		Ozone injection device each capable of 16 m³/hr	I	No	2		
7.12.7	PSPLT 1	Water flow meter with measuring range of 0 - 300 m³/hr	I	No	1		
7.12.8		Pre-ozone diffusion Instrumentation	I	Sum	1		
7.13		<u>SCHEDULE NO: 7.13 - OZONE DESTRUCTION EQUIPMENT</u>					
	PSPTO 11	MAIN OZONE VENT OFF-GAS DESTRUCTION EQUIPMENT					
7.13.1		Complete off-gas destruction system including extraction fan, thermo-catalytic converter, ozone off-gas analyser, demister, piping and valves	I	Sum	1		
7.13.2		Pipework and valves	I	Sum	1		
7.13.3		Main ozone destruction instrumentation	I	Sum	1		
7.14	PSPTO 15	<u>SCHEDULE NO: 7.14 - OZONE INSTRUMENTATION</u>					
7.14.1		Oxygen concentration analyser	I	No	2		
7.14.2		Ozone gas analyser (low concentration)	I	No	4		
7.14.3		Ozone off-gas analyser	I	No	2		
7.14.4		Ozone gas analyser (high concentration)	I	No	4		
7.14.5		UV254 analyser	I	No	4		
7.14.6		Dew point analyser	I	No	4		
7.14.7		Mass flow meter (ozone gas flow)	I	No	5		
		<u>COMMISSIONING</u>					
7.15		<u>SCHEDULE NO: 7.15 - GENERAL</u>					
7.15.1	PSPTO18.1	Factory acceptance testing of ozone generators (Client representative and Engineer expenses for 7 days)	I	Sum	1		
7.15.2	PSPTO 18.2	On-site performance testing and fingerprinting of ozone generation and dosing system	I	Sum	1		
7.15.3	PSPTO18.3	Ozone generation and dosing system optimization	I	Sum	1		
7.16	PTO	<u>SCHEDULE NO: 7.16 - OZONE GENERATION EQUIPMENT</u>					
	PSPTO 5	Commission complete ozone generation system					
7.16.1		Supplier 1	I	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.16.2		Supplier 2	I	Sum	1		
7.17	PSPTO 7	<u>SCHEDULE NO: 7.17 - NITROGEN BLEED EQUIPMENT</u>					
7.17.1		Commission nitrogen bleed system complete	I	Sum	1		
7.18	PSPTP 8	<u>SCHEDULE NO: 7.18 - COOLING WATER EQUIPMENT</u>					
7.18.1		Commission cooling water system complete	I	Sum	1		
7.19		<u>SCHEDULE NO: 7.19 - OZONE DIFFUSION AND INJECTION EQUIPMENT</u>					
	PSPTO 9	MAIN OZONE BUBBLE DIFFUSION EQUIPMENT					
7.19.1		Commission main ozone bubble diffusion system complete	I	Sum	1		
	PSPTO 10	(PRE-OZONE) SIDESTREAM DIFFUSION					
7.19.2		Commission pre-ozone sidestream diffusion system complete	I	Sum	1		
7.20		<u>SCHEDULE NO: 7.20 - OZONE DESTRUCTION EQUIPMENT</u>					
	PSPTO 11	MAIN OZONE VENT OFF-GAS DESTRUCTION EQUIPMENT					
7.20.1		Commission main ozone vent off-gas destruction system	I	Sum	1		
7.21	PSPTO 15	<u>SCHEDULE NO: 7.21 - OZONE INSTRUMENTATION</u>					
7.21.1		Commission all instrumentation complete	I	Sum	1		
		<u>MISCELLANEOUS</u>					
7.22	PSPTO 19	<u>SCHEDULE NO: 7.22 - CRITICAL SPARES</u>					
		Suggested critical spares:					
		Item Description					
7.22.1		No 1 _____	I	No	1		
7.22.2		No 2 _____	I	No			
7.22.3		No 3 _____	I	No			
7.22.4		No 4 _____	I	No			
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
7.22.5		No 5 _____	I	No			
7.22.6		No 6 _____	I	No			
	PSPT0 19.2	MAINTENANCE AGREEMENT					
7.22.7		Optional support agreement for first year after defects notification period	I	Sum	1		
7.23	PSPTO 20	<u>SCHEDULE NO: 7.23 - TRAINING</u>					
7.23.1	PSPTO 20.1	Training of operating and maintenance personnel during and after commissioning	I	Sum	1		
7.23.2	PSPTO 20.2	Servicing of ozone equipment during defects notification period	I	Sum	1		
7.24	PSPTO 22	<u>SCHEDULE NO: 7.24 - OCCUPATIONAL, HEALTH AND SAFETY REQUIREMENTS</u>					
7.24.1	PSPTO 22.1	Ambient ozone analyser in ozone generator building	I	No	1		
7.24.2		Ozone gas mask and throw-away cartridge	I	No	3		
7.24.3	PSPTO 22.2	Self contained breathing apparatus set	I	No	2		
7.25	PSPTO 16.2	<u>SCHEDULE NO: 7.25 - HAND HELD INSTRUMENTS</u>					
7.25.1		Residual ozone analyser	I	No	1		
7.25.2		Ozone gas analyser (low concentration)	I	No	1		
7.25.3		ORP analyser	I	No	1		
7.25.4		UV254 analyser	I	No	1		
		SCHEDULE: 7 OZONE EQUIPMENT CARRIED FORWARD TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
8	PTG PTTG PSPTTG	SCHEDULE: 8 GAC FILTRATION SYSTEM					
8.1		SCHEDULE NO: 8.1 - DESIGN AND DRAWINGS					
8.1.1		Detail design calculations, as well as submission of quality assurance documentation, detailed P&ID's, and manufacturing GA layouts, pipe work layouts as may be required for complete installation	G	Sum	1		
8.2		SCHEDULE NO: 8.2 - SUPPLY AND DELIVERY TO SITE GAC FILTER EQUIPMENT					
8.2.1	PSPTTG 2.3 & 2.4	GAC FILTER FLOOR Complete GAC filter floor system including laterals, nozzles, fixing and sealing materials. Nozzles to be embedded in concrete. (refer to dwgs 1890.08.FB.14.D005 - D007 and X002 to X004)	M	No	6		
8.3		SCHEDULE NO: 8.3 - INSTALLATION OF GAC FILTER EQUIPMENT					
8.3.1	PSPTTG 2.3 & 2.4	GAC FILTER FLOOR Complete GAC filter floor system including laterals, nozzles, fixing and sealing materials. Nozzles to be embedded in concrete. (refer to dwgs 1890.08.FB.14.D005 - D007 and X002 to X004)	I	No	6		
8.4		SCHEDULE NO: 8.4 - COMMISSIONING OF GAC FILTER EQUIPMENT					
8.4.1	PSPTTG 2.3 & 2.4	GAC FILTER FLOOR Commissioning of GAC Filter complete	I	Sum	1		
		SCHEDULE: 8 GAC FILTRATION SYSTEM CARRIED FORWARD TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
9	PTG PSPTG PSPTTG	SCHEDULE: 9 GAC MEDIA					
9.1		SCHEDULE NO : 8.1 - SUPPLY AND DELIVER TO SITE GAC MEDIA AS SPECIFIED					
	PSPTTG 2.5	GAC MEDIA					
		Supplier 1 : _____					
9.1.1		i) 8 X 16 GAC	M	m ³	180		
		Supplier 2 : _____					
9.1.2		ii) 8 X 16 GAC	M	m ³	180		
		Supplier 3 : _____					
9.1.3		iii) 8 X 16 GAC	M	m ³	180		
		Supplier 4 : _____					
9.1.4		iv) 8 X 16 GAC	M	m ³	180		
		(NOTE: Only highest rate to be carried forward to schedule total)					
	PTG5	PROVISIONAL SUM FOR TESTING OF GAC MEDIA					
9.1.5		Laboratory Testing of GAC media	G	Sum	1		
9.2		SCHEDULE NO : 9.2 - INSTALLATION AND HANDLING OF GAC MEDIA AS SPECIFIED					
	PSPTTG 2.5	GAC MEDIA					
		Supplier 1 : _____					
9.2.1		i) 8 X 16 GAC	M	m ³	180		
		Supplier 2 : _____					
9.2.2		ii) 8 X 16 GAC	M	m ³	180		
		Supplier 3 : _____					
9.2.3		iii) 8 X 16 GAC	M	m ³	180		
		Supplier 4 : _____					
9.2.4		iv) 8 X 16 GAC	M	m ³	180		
		(NOTE: Only highest rate to be carried forward to schedule total)					
		SCHEDULE: 9 GAC MEDIA CARRIED FORWARD TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
10	PT PSPT	<u>SCHEDULE NO. 10</u> <u>PUMPS</u>					
10.1		<u>SCHEDULE NO: 10.1 - DAF RECYCLE PUMPS</u>					
10.1.1		DESIGN, DRAWING AND GENERAL					
10.1.1.1	PT12.1	Provide design drawings and information as specified	G	Sum	1		
10.1.1.2		Provide operating and maintenance manuals and "as built" drawings as specified	G	Sum	1		
10.1.2	PT12.2	SUPPLY AND DELIVERY TO SITE					
10.1.2.1	PSPT1.1	DAF recycle water pump	M	No	1		
10.1.2.2	PT12.2.2	Monitoring Devices					
		a) Pressure gauges, piping	M	Sum	1		
		b) Pedestals and number plates	M	Sum	1		
		c) Pump vents and drain fittings	M	Sum	1		
10.1.3	PT12.3	INSTALLATION WORK					
10.1.3.1	PSPT1.1	DAF recycle water pumps (PSPT 1.1)	I	No	1		
10.1.3.2	PT12.3.2	Monitoring Devices					
		a) Pressure gauges, piping	I	Sum	1		
		b) Pedestals and number plates	I	Sum	1		
		c) Pump vents and drain fittings	I	Sum	1		
10.1.4	PT	COMMISSIONING					
10.1.4.1	PT10	Testing and commissioning of pumps and appertaining pipework					
10.1.4.2	PSPT1.1	DAF recycle water pumps	I	No	1		
10.2		<u>SCHEDULE NO: 10.2 - FILTRATE PUMPS</u>					
10.2.1		DESIGN, DRAWING AND GENERAL					
10.2.1.1	PT12.1	Provide design drawings and information as specified	G	Sum	1		
10.2.1.2		Provide operating and maintenance manuals and "as built" drawings as specified	G	Sum	1		
10.2.2	PT12.2	SUPPLY AND DELIVERY TO SITE					
10.2.2.1	PSPT1.2	Filtrate pumps	M	No	2		
			Carried Forward				

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
			Brought Forward				
10.2.2.2	PT12.2.2	Monitoring Devices					
		a) Pressure gauges, piping	M	Sum	1		
		b) Pedestals and number plates	M	Sum	1		
		c) Pump vents and drain fittings	M	Sum	1		
10.2.3	PT12.3	INSTALLATION WORK					
10.2.3.1	PSPT1.2	Filtrate pumps	I	No	2		
10.2.3.2	PT12.3.2	Monitoring Devices					
		a) Pressure gauges, piping	I	Sum	1		
		b) Pedestals and number plates	I	Sum	1		
		c) Pump vents and drain fittings	I	Sum	1		
10.2.4	PT	COMMISSIONING					
10.2.4.1	PT10	Testing and commissioning of pumps and appertaining pipework:					
	PSPT1.2	Filtrate pumps	I	No	2		
10.3		SCHEDULE NO: 10.3 - LOW LIFT PUMPS					
10.3.1		DESIGN, DRAWING AND GENERAL					
10.3.1.1	PT12.1	Provide design drawings and information as specified	G	Sum	1		
10.3.1.2		Provide operating and maintenance manuals and "as built" drawings as specified	G	Sum	1		
10.3.2	PT12.2	SUPPLY AND DELIVERY TO SITE					
10.3.2.1	PSPT1.3	Low Lift pumps	M	No	2		
10.3.2.2	PT12.2.2	Monitoring Devices					
		a) Pressure gauges, piping	M	Sum	1		
		b) Pedestals and number plates	M	Sum	1		
		c) Pump vents and drain fittings	M	Sum	1		
10.3.3	PT12.3	INSTALLATION WORK					
10.3.3.1	PSPT1.3	Low Lift pumps	I	No	2		
			Carried Forward				

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
			Brought Forward				
10.3.3.2	PT12.3.2	Monitoring Devices					
		a) Pressure gauges, piping	I	Sum	1		
		b) Pedestals and number plates	I	Sum	1		
		c) Pump vents and drain fittings	I	Sum	1		
10.3.4	PT	COMMISSIONING					
10.3.4.1	PT10	Testing and commissioning of pumps and appertaining pipework					
10.3.4.2	PSPT1.3	Low Lift pumps	I	No	2		
10.4		<u>SCHEDULE NO: 10.4 - REFURBISHMENT OF SLUDGE PUMPS</u>					
10.4.1	PSPT1.4	Rate to include for supply and installation of VSD's for the existing sludge pumps	M	No	2		
10.5		<u>SCHEDULE NO: 10.5 - REFURBISHMENT OF RAW WATER PUMPS</u>					
10.5.1		Rate to include for removal and transport of pumps to workshop, replacement of all seals and bearings, sand blasting and re-coating, installation and comissioning	N	Prov-Sum	1	250,000.00	250,000.00
10.6		<u>HIGH LIFT PUMPS</u>					
10.6.1	PT12.1	DESIGN, DRAWINGS AND GENERAL					
10.6.1.1		Provide design drawings and information as specified	G	Sum	1		
10.6.1.2		Provide operating and maintenance manuals and "as built" drawings as specified	G	Sum	1		
10.6.2	PT12.2	<u>SUPPLY AND DELIVERY TO SITE</u>					
10.6.2.1		Pump and motor set complete with pump, motor, couplings, foundation steelwork and baseplate	M	No	4		
10.6.2.2		Monitoring Devices					
		a) Pressure gauges, piping	M	Sum	1		
		b) Temperature sensors	M	Sum	1		
		c) Vibration sensors	M	Sum	1		
		d) Air vents and gland leakage detection	M	Sum	1		
			Carried Forward				

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
			Brought Forward				
10.6.3	PT12.3	<u>INSTALLATION WORK</u>					
10.6.3.1	PSPT 1	Dismantle existing pumps, motors, couplings foundation steelwork, baseplates, and other redundant equipment	I	No	4		
10.6.3.2	PSPT 1	Adjust plinth level and dimensions to suit new pumps	I	No	4		
10.6.3.3		Pump and motor set complete on base plate	I	No	4		
10.6.3.4		Monitoring Devices					
		a) Pressure gauges, piping	I	Sum	1		
		b) Temperature sensors	I	Sum	1		
		c) Vibration sensors	I	Sum	1		
		d) Air vents and gland leakage detection	I	Sum	1		
10.6.4		<u>COMMISSIONING</u>					
10.6.4.1	PT12.4.1	Testing and commissioning of pumps and appertaining pipework	I	Sum	1		
10.6.4.2	PT12.5.1	Supply and delivery of specified equipment to the store facility of the Employer	I	Sum	1		
SCHEDULE: 10 PUMPS CARRIED FORWARD TO SUMMARY							
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
11	PTN PSPTN	<u>SCHEDULE: 11</u> <u>DEWATERING EQUIPMENT</u>					
11.1	PSPTN 15.1	<u>SECTION NO: 11.1 - DESIGN, DRAWING AND GENERAL</u>					
11.1.1		Detail design calculations, as well as submission of quality assurance documentation, detailed P&ID's, and manufacturing GA layouts, pipe work layouts as may be required for complete installation	G	Sum	1		
11.2	PSPTN 15.2	<u>SCHEDULE NO: 11.2 - SUPPLY AND DELIVERY TO SITE</u>					
11.2.1		The tendered rate shall include for the ordering, manufacture, factory-acceptance testing, factory-applied corrosion protection, supply and delivery to Site. Tendered rate shall include supply of spares for key components. Spares list shall be included in Technical Schedules.					
11.2.1		<u>Dewatering Equipment</u>					
11.2.1.1	PSPTN 15.2.1	Mechanical dewatering belt filter press complete, including flocculation tanks, in-line mixers, pressure transmitters, piping and valves;					
		Supplier 1:	M	No	2		
		Supplier 2:	M	No	2		
		Supplier 3:	M	No	2		
		(NOTE: Only highest rate to be carried forward to schedule total)					
11.2.1.2	PSPTN 15.2.3	Poly-electrolyte batching and dosing system		Sum	1		
11.2.2		<u>Pumping Equipment</u>					
11.2.2.1	PSPTN 15.2.2 PSPLT 1	Belt filter press feed pipework, valves, flow meters and ultrasonic level transmitter, pressure gauges and transmitters etc.	M	Sum	1		
11.2.2.2	PSPTN 15.2.5 PSPLT 1	Belt filter press Washwater pumps, including all pipework, valves, flow meters and ultrasonic level transmitter. pressure gauges and transmitters etc.	M	Sum	1		
11.2.3		<u>Pipework and Specials</u>					
11.2.3.1	PSPTN 15.2.4	a) Filtrate & Washwater pipework and specials	P	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
11.2.3.2	PSPTN 15.2.6	b) Sludge feed pipework and specials	P	Sum	1		
11.2.4	PSPTN 15.2.7	Sludge outloading equipment	M	No	1		
11.2.5	PSPTN 15.2.12	7 m³ waste skip	M	Sum	1		
11.3	PSPTN 15.3	<u>SCHEDULE NO: 11.3 - INSTALLATION</u>					
11.3.1		<u>Dewatering Equipment</u>					
11.3.1.1	PSPTN 15.3.1	Mechanical dewatering belt filter press complete, including flocculation tanks, in-line mixers, pressure transmitters, piping and valves;					
		Supplier 1:	I	No	2		
		Supplier 2:	I	No	2		
		Supplier 3:	I	No	2		
		(NOTE: Only highest rate to be carried forward to schedule total)					
11.3.1.2	PSPTN 15.3.3	Poly-electrolyte batching and dosing system	I	Sum	1		
11.3.2		<u>Pumping Equipment</u>					
11.3.2.1	PSPTN 15.3.2 PSPLT 1	Belt filter press feed pipework, valves, flow meters and ultrasonic level transmitter, pressure gauges and transmitters etc.	I	Sum	1		
11.3.2.2	PSPTN 15.3.5 PSPLT 1	Belt filter press washwater pumps, including all pipework, valves, flow meters and ultrasonic level transmitter.	I	Sum	1		
11.3.3		<u>Pipework and Specials</u>					
11.3.3.1	PSPTN 15.3.4	a) Filtrate & Washwater pipework and specials	I	Sum	1		
11.3.3.2	PSPTN 15.3.6	b) Sludge feed pipework and specials	I	Sum	1		
11.3.4	PSPTN 15.3.7	Sludge outloading equipment	I	No	1		
11.3.6	PSPTN	7 m³ waste skip	I	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
11.4	15.3.12 PSPTN	SCHEDULE NO: 10.4 - COMMISSIONING					
11.4.1	15.4 PSPTN	Testing, Comissioning and trial and operation of the Complete Sludge Dewatering system	I	Sum	1		
	15.4.1						
		SCHEDULE: 11 DEWATERING EQUIPMENT CARRIED TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer


Witness 1

Witness 2


Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
12	PLC, PSPLC	SCHEDULE: 12 CHEMICAL DOSING SYSTEM					
12.1		SCHEDULE NO: 12.1 - DESIGN, DRAWING AND GENERAL					
12.1.1		Detail design calculations, as well as submission of quality assurance documentation, detailed P&ID's, and manufacturing GA layouts, pipe work layouts as may be required for complete installation	G	Sum	1		
12.2		SCHEDULE NO: 12.2 - SUPPLY AND DELIVERY TO SITE					
12.2.1		POLY-ELECTROLYTE DOSING SYSTEM (Drawing No 1890.08.AA.01.A12)					
12.2.2.1	PLC 6 (a)	Poly-electrolyte dosing pumps (PSPLC 5.1.1)	M	No	1		
12.2.2.2	PLC 6 (b)	Poly-electrolyte pipework (excluding clearwater feed) complete including bends fixing brackets, calibrating cylinder, etc. all as shown on the drawings in Class 16 uPVC from the bulk tanks to the dosing points.	M	Sum	1		
12.2.2		FERRIC-CHLORIDE DOSING SYSTEM (Drawing No 1890.08.AA.01.A12)					
12.2.2.1	PLC 6 (a)	Ferric Chloride dosing pumps (PSPLC 5.1.1)	M	No	1		
12.2.2.2	PLC 6 (b)	Ferri-chloride pipework (excluding clearwater feed) complete including bends fixing brackets, calibrating cylinder, etc all as shown on the drawings in Class 16 uPVC from the bulk tanks to the dosing points.	M	Sum	1		
12.2.3		HYDROGEN PEROXIDE DOSING SYSTEM (Drawing No 1890.08.SUG.16.D001)					
12.2.3.1	PLC 6 (a)	Hydrogen Peroxide dosing pumps (PSPLC 5.1.2)	M	No	2		
12.2.3.2	PLC 6 (c)	5000 l Storage Tank for Hydrogen Peroxide complete with sight glass entry manhole, nozzels and emergency vent etc complete. (PSPLC5.2.1)	M	No	2		
12.2.3.3	PLC 6 (b)	Hydrogen Peroxide pipework (including clearwater feed) complete including bends fixing brackets, calibrating cylinder, etc. all as shown on the drawings from the bulk tanks to the dosing points.	M	Sum	1		
12.2.3.4		Spraydrench epoxy coated, platform-operated emergency safety shower with eyewash station	M	No	1		
Carried Forward							




Contractor



Witness 1




Witness 2



Employer



Witness 1



Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
12.2.4		CHLORINE DOSING SYSTEM					
12.2.4.1	PTU 6.4 PSPTU 3	Chlorinators complete with ejectors, multiple flow meter assemblies, control valves, clear water supply piping to clear water supply connection, solenoid valves, inline strainers, pressure gauges, by-pass connection, vacuum regulators, auto change over system and inter connecting pipework	M	No	1		
12.3		<u>SCHEDULE NO: 12.3 - INSTALLATION</u>					
12.3.1		<u>POLY-ELECTROLYTE DOSING SYSTEM</u> (Drawing No 1890.08.AA.01.A12)					
12.3.1.1	PLC 6 (a)	Poly-electrolyte dosing pumps (PSPLC 5.1.1)	I	No	1		
12.3.1.2	PLC 6 (b)	Poly-electrolyte pipework (excluding clearwater feed) complete including bends fixing brackets, calibrating cylinder, etc. all as shown on the drawings in Class 16 uPVC from the bulk tanks to the dosing points.	I	Sum	1		
12.3.2		<u>FERRIC-CHLORIDE DOSING SYSTEM</u> (Drawing No 1890.08.AA.01.A12)					
12.3.2.1	PLC 6 (a)	Ferric Chloride dosing pumps (PSPLC 5.1.1)	I	No	1		
12.3.2.2	PLC 6 (b)	Ferri-chloride pipework (excluding clearwater feed) complete including bends fixing brackets, calibrating cylinder, etc all as shown on the drawings in Class 16 uPVC from the bulk tanks to the dosing points.	I	Sum	1		
12.3.3		<u>HYDROGEN PEROXIDE DOSING SYSTEM</u> (Drawing No 1890.08.SUG.16.D001)					
12.3.3.1	PLC 6 (a)	Hydrogen Peroxide dosing pumps (PSPLC 5.1.2)	I	No	2		
12.3.3.2	PLC 6 (c)	5000 l Storage Tank for Hydrogen Peroxide complete with sight glass entry manhole, nozzels and emergency vent etc complete. (PSPLC5.2.1)	I	No	2		
12.3.3.3	PLC 6 (b)	Hydrogen Peroxide pipework (including clearwater feed/injector) complete including bends fixing brackets, calibrating cylinder, etc. all as shown on the drawings from the bulk tanks to the dosing points.	I	Sum	1		
12.3.3.4		Spraydrench epoxy coated, platform-operated emergency safety shower with eyewash station	I	No	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
12.3.4		CHLORINE DOSING SYSTEM					
12.3.4.1	PTU 6.4 PSPTU 3	Chlorinators complete with ejectors, multiple flow meter assemblies, control valves, clear water supply piping to clear water supply connection, solenoid valves, inline strainers, pressure gauges, by-pass connection, vacuum regulators, auto change over system and inter connecting pipework	I	No	1		
12.4		<u>SCHEDULE NO: 11.4 - COMMISSIONING</u>					
12.4.1		Commissioning of Chemical Dosing system complete	I	Sum	1		
12.4.2		Commissioning of Chlorination system complete	I	Sum	1		
		SCHEDULE: 12 CHEMICAL DOSING SYSTEM CARRIED TO SUMMARY					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
13	PTP, PSPTP	<u>SCHEDULE: 13</u> <u>HOISTING EQUIPMENT</u>					
13.1		<u>SCHEDULE NO: 13.1 - SUPPLY AND DELIVERY TO SITE OF HOISTING EQUIPMENT</u>					
13.1.1	PSPTP	<u>Low Lift Pump Station</u> Portal A - frame bolted to concrete floor complete with i-beam, trolley and chain hoist for a max load of 750kg complete as shown on drg 1890.08.OA.13.D002	M	Sum	1		
13.1.2	PSPTP	<u>Pre-Ozone Building</u> i-beam fixed to ring beam with trolley and chain hoist for max load of 1000 kg complete as shown on drg 1890.08.SUF.14.D001 and D002	M	Sum	1		
13.1.3	PSPTP	<u>Dewatering Building</u> Portal A - frame bolted to concrete floor complete with i-beam, trolley and chain hoist for a max load of 1500 kg complete as shown on drg 1890.08.SUD.16.X002	M	Sum	1		
13.1.4	PSPTP	<u>GAC Filters</u> i-beam fixed to beams with trolley and chain hoist for max load of 1000 kg complete as shown on drg 1890.08.FB.14.X002	M	No	1		
13.2		<u>SCHEDULE NO: 13.2 - INSTALLATION OF HOISTING EQUIPMENT</u>					
13.2.1	PSPTP	<u>Low Lift Pump Station</u> Portal A - frame bolted to concrete floor complete with I-beam, trolley and chain hoist for a max load of 750kg complete as shown on drg 1890.08.OA.13.D002	I	Sum	1		
13.2.2	PSPTP	<u>Pre-Ozone Building</u> I-beam fixed to ring beam with trolley and chain hoist for max load of 1000 kg complete as shown on drg 1890.08.SUF.14.D001 and D002	I	Sum	1		
13.2.3	PSPTP	<u>Dewatering Building</u> Portal A - frame bolted to concrete floor complete with I-beam, trolley and chain hoist for a max load of 1500 kg complete as shown on drg 1890.08.SUD.16.X002	I	Sum	1		
13.2.4	PSPTP	<u>GAC Filters</u> I-beam fixed to beams with trolley and chain hoist for max load of 1000 kg complete as shown on drg 1890.08.FB.14.X002	I	No	1		
		<u>SCHEDULE: 13</u> <u>HOISTING EQUIPMENT</u> <u>CARRIED TO SUMMARY</u>					
TOTAL							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E1	EMVS	<u>SCHEDULE NO. E1</u> <u>MEDIUM VOLTAGE SWITCHGEAR</u>					
E1.1	EMVS	<u>SCHEDULE E1.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	35.1						
E1.1.1	EMVS 35.1 (a)	Provide design drawings and design information for medium voltage switchgear (refer to project specification PSEMVS)	G	Sum	-		
E1.1.2	EMVS 35.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to project specification PSEMVS)	G	Sum	-		
E1.1.3	EMVS 35.1 (c)	Protection short circuit analysis and coordination study and protection setting calculations for protection relays (refer to project specification PSEMVS)	G	Sum	-		
E1.2	EMVS	<u>SCHEDULE E1.2 - SUPPLY AND DELIVERY TO SITE</u>					
	35.2						
E1.2.1	EMVS 35.2 (a)	Supply and delivery to site of medium voltage switchgear (refer to project specification PSEMVS)	E	Sum	-		
E1.2.2	EMVS 35.2 (b)	Supply and delivery to site of charger and battery unit (refer to project specification PSEMVS)	E	Sum	-		
E1.3	EMVS	<u>SCHEDULE E1.3 - INSTALLATION</u>					
	35.3						
E1.3.1	EMVS 35.3 (a)	Site installation of medium voltage switchgear (refer to project specification PSEMVS)	I	Sum	-		
E1.3.2	EMVS 35.3 (b)	Installation of charger and battery unit (refer to project specification PSEMVS)	I	Sum	-		
E1.3.3	EMVS 35.3 (d)	Programming of protection settings (refer to project specification PSEMVS)	I	Sum	-		
E1.4	EMVS	<u>SCHEDULE E1.4 - COMMISSIONING</u>					
	35.4						
E1.4.1	EMVS 35.4 (a)	Commissioning of complete medium voltage switchgear inclusive of charger and battery unit (refer to project specification PSEMVS)	I	Sum	-		
		SCHEDULE NO. E1 MEDIUM VOLTAGE SWITCHGEAR CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E2	ERMU	<u>SCHEDULE NO. E2</u> <u>RING MAIN UNITS</u>					
E2.1	ERMU	<u>SCHEDULE E2.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	3.1						
E2.1.1	ERMU 3.1 (a)	Provide design drawings and design information for ring main units (refer to project specification PSERMU)	G	Sum	-		
E2.1.2	ERMU 3.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to project specification PSERMU)	G	Sum	-		
E2.1.3	ERMU 3.1 (c)	Protection short circuit analysis and coordination study and protection setting calculations for protection relays (refer to project specification PSERMU)	G	Sum	-		
E2.2	ERMU	<u>SCHEDULE E2.2 - SUPPLY AND DELIVERY TO SITE</u>					
	3.2						
E2.2.1	ERMU 3.2 (a)	Supply and delivery to site of ring main units complete as specified (refer to project specification PSERMU)	E	Sum	-		
E2.2.2	ERMU 3.2 (b)	Supply and delivery to site of all additional assosries (refer to project specification PSERMU)	E	Sum	-		
E2.3	ERMU	<u>SCHEDULE E2.3 - INSTALLATION</u>					
	3.3						
E2.3.1	ERMU 3.3 (a)	Site installation of ring main units complete as specified (refer to project specification PSERMU)	I	Sum	-		
E2.3.2	ERMU 3.3 (b)	Site installation of all additional assosries as specified (refer to project specification PSERMU)	I	Sum	-		
E2.3.3	ERMU 3.3 (d)	Programming of protection settings (refer to project specification PSERMU)	I	Sum	-		
E2.4	ERMU	<u>SCHEDULE E2.4 - COMMISSIONING</u>					
	3.4						
E2.4.1	ERMU 3.4 (a)	Commissioning of all complete ring main units on site inclusive of charger and battery unit (refer to project specification PSERMU)	I	Sum	-		
		SCHEDULE NO. E2 RING MAIN UNITS CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E3	EPPT	<u>SCHEDULE NO. E3</u> <u>POWER TRANSFORMERS</u>					
E3.1	GEN	<u>SCHEDULE E3.1 - DESIGN, DRAWINGS AND GENERAL</u>					
E3.1.1	PSGEN B	Provide all design drawings and wiring diagrams	G	Sum	-		
E3.1.2	PSGEN B	Provide all operating and maintenance manuals and "as-built" drawings	G	Sum	-		
E3.2	EPPT	<u>SCHEDULE 3.2 - SUPPLY AND DELIVERY TO SITE</u>					
	12.1						
E3.2.1	EPPT 12.1 (a)	Supply and delivery to site of power transformers (refer to project specification PSEPPT-2 and PSEPPT-7)	E	Sum	-		
E3.2.2	EPPT 12.1 (b)	Supply and delivery to site of substation earthing system as specified under PSPPT-11	E	Sum	-		
3.3	EPPT	<u>SCHEDULE 3.3 - INSTALLATION</u>					
	12.2						
3.3.1	EPPT 12.2 (a)	Site Installation of power transformers (refer to project specification PSEPPT-2 and PSEPPT-7)	I	Sum	-		
3.3.2	EPPT 12.2 (b)	Installation of substation earthing system as specified under PSPPT-11	I	Sum	-		
3.4	EPPT	<u>SCHEDULE 3.4 - COMMISSIONING</u>					
	11.3						
3.4.1	EPPT 12.3 (a)	Commissioning of refurbished power transformers (refer to project specification PSEPPT-2 and PSEPPT-7)	I	Sum	-		
3.4.2	EPPT 12.3 (b)	Commissioning of substation earthing system as specified under PSPPT-11	I	Sum	-		
		SCHEDULE NO. E3 POWER TRANSFORMERS CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E4	EMSS	<u>SCHEDULE NO. E4</u> <u>MINIATURE SUBSTATIONS</u>					
E4.1	EMSS	<u>SCHEDULE E4.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	15.1						
E4.1.1	EMSS 15.1 (a)	Provide design drawings and design information for miniature substation (refer to particular specifications EMVS)	G	Sum	-		
E4.1.2	EMSS 15.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to particular specification EMVS)	G	Sum	-		
E4.1.3	EMSS 15.1 (c)	Protection short circuit analysis and coordination study and protection setting calculations for protection relays (refer to particular specification EMVS)	G	Sum	-		
E4.2	EMSS	<u>SCHEDULE E4.2 - SUPPLY AND DELIVERY TO SITE</u>					
	15.2						
E4.2.1	EMSS 15.2 (a)	Supply and delivery to site of miniature substations complete with concrete plinth (refer to project specification PSEMSS)	E	Sum	-		
E4.3	EMSS	<u>SCHEDULE E4.3 - INSTALLATION</u>					
	15.3						
E4.3.1	EMSS 15.3 (a)	Site installation of miniature substation complete with concrete plinth and floor screed (refer to particular specification EMSS)	I	Sum	-		
E4.3.2	EMSS 15.3 (b)	Installation of protection settings (refer to particular specification EMVS)	I	Sum	-		
E4.4	EMSS	<u>SCHEDULE E4.4 - COMMISSIONING</u>					
	15.4						
E4.4.1	EMSS 15.4 (a)	Commissioning of miniature substation (refer to particular specification EMSS)	I	Sum	-		
E4.4.2	EMSS 15.4 (b)	Commissioning of protection settings (refer to particular specification EMVS)	I	Sum	-		
		SCHEDULE NO. E4 MINIATURE SUBSTATIONS CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E5	EMCC	<u>SCHEDULE NO. E5</u>					
		<u>MOTOR CONTROL CENTERS AND DISTRIBUTION BOARDS</u>					
E5.1	EMCC	<u>SCHEDULE E5.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	21.1						
E5.1.1	EMCC 21.1 (a)	Provide motor control center design drawings and wiring diagrams (refer to particular specifications EMCC)	G	Sum	-		
E5.1.2	EMCC 21.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to particular specification EMCC)	G	Sum	-		
E5.2	EMCC	<u>SCHEDULE E5.2 - SUPPLY AND DELIVERY TO SITE</u>					
	21.2						
E5.2.1	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.A)	E	Each	1		
E5.2.2	EMCC 21.2 (a)	Supply and delivery to site complete VFD enclosure (refer to project specification PSEMCC-6.B)	E	Each	4		
E5.2.3	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.C)	E	Each	1		
E5.2.4	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.D)	E	Each	1		
E5.2.5	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.E)	E	Each	1		
E5.2.6	EMCC 21.2 (a)	Supply and delivery to site complete RGS FCP (refer to project specification PSEMCC-6.F)	E	Each	4		
E5.2.7	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.G)	E	Each	1		
E5.2.8	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.H)	E	Each	1		
E5.2.9	EMCC 21.2 (a)	Supply and delivery to site complete BFPP (refer to project specification PSEMCC-6.I)	E	Each	2		
E5.2.10	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.J)	E	Each	1		
E5.2.11	EMCC 21.2 (a)	Supply and delivery to site complete GAC FCP (refer to project specification PSEMCC-6.K)	E	Each	6		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E5.2 .12	EMCC 21.2 (a)	Supply and delivery to site complete MCC (refer to project specification PSEMCC-6.L)	E	Each	1		
E5.3	EMCC 21.3	<u>SCHEDULE E5.3 - INSTALLATION</u>					
E5.3 .1	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.A)	I	Each	1		
E5.3 .2	EMCC 21.3 (a)	Site installation to site complete VFD enclosure (refer to project specification PSEMCC-6.B)	I	Each	4		
E5.3 .3	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.C)	I	Each	1		
E5.3 .4	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.D)	I	Each	1		
E5.3 .5	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.E)	I	Each	1		
E5.3 .6	EMCC 21.3 (a)	Site installation to site complete RGS FCP (refer to project specification PSEMCC-6.F)	I	Each	4		
E5.3 .7	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.G)	I	Each	1		
E5.3 .8	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.H)	I	Each	1		
E5.3 .9	EMCC 21.3 (a)	Site installation to site complete BFPP (refer to project specification PSEMCC-6.I)	I	Each	2		
E5.3 .10	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.J)	I	Each	1		
E5.3 .11	EMCC 21.3 (a)	Site installation to site complete GAC FCP (refer to project specification PSEMCC-6.K)	I	Each	6		
E5.3 .12	EMCC 21.3 (a)	Site installation to site complete MCC (refer to project specification PSEMCC-6.L)	I	Each	1		
E5.4	EMCC 21.4	<u>SCHEDULE E5.4 - COMMISSIONING</u>					
E5.4 .1	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.A)	I	Each	1		
E5.4 .2	EMCC 21.4 (a)	Commissioning to site complete VFD enclosure (refer to project specification PSEMCC-6.B)	I	Each	4		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E5.4 .3	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.C)	I	Each	1		
E5.4 .4	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.D)	I	Each	1		
E5.4 .5	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.E)	I	Each	1		
E5.4 .6	EMCC 21.4 (a)	Commissioning to site complete RGS FCP (refer to project specification PSEMCC-6.F)	I	Each	4		
E5.4 .7	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.G)	I	Each	1		
E5.4 .8	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.H)	I	Each	1		
E5.4 .9	EMCC 21.4 (a)	Commissioning to site complete BFPP (refer to project specification PSEMCC-6.I)	I	Each	2		
E5.4 .10	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.J)	I	Each	1		
E5.4 .11	EMCC 21.4 (a)	Commissioning to site complete GAC FCP (refer to project specification PSEMCC-6.K)	I	Each	6		
E5.4 .12	EMCC 21.4 (a)	Commissioning to site complete MCC (refer to project specification PSEMCC-6.L)	I	Each	1		
SCHEDULE NO. E5 MOTOR CONTROL CENTRE & DISTRIBUTION BOARDS CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E6	EPLC	SCHEDULE NO. E6 PROGRAMMABLE & LOGIC CONTROLLERS					
E6.1	EPLC	SCHEDULE E6.1 - DESIGN, DRAWINGS AND GENERAL					
	26.1						
	EPLC 26.1 (a)	The Contractor will provide the following design calculations, Drawings and wiring diagrams for approval by the Engineer: a) Fibre loss design calculations in excel format which will include but limited to From, To, Distance losses and Tag numbers and total losses through the fibre network [fibre losses] b) Electrical Load lists in excel format of all PLC equipment c) Engineer design drawings of network layout which contains all IP addresses, equipment and drawings d) Report which will include antennae radio paths, drawings which have line of sight of all locations in AutoCad Format, Connection speeds with the radio or wireless communication, details of all Radio & Wireless Radio losses e) Input and Output schedules in excel format which contains all tag numbers, names, commands, and description of all I/O f) Loop diagrams in AutoCAD format g) Cable schedules in excel format which will include but limited to From, To, Distance and Tag numbers h) AutoCAD drawing of all equipment positions, equipment layouts, cable layouts, rack layouts, router / modems, switches connections and layouts. i) P&ID drawings of the entire system which is implemented and equipment in AutoCAD format which shall strictly accordance to ANSI/ISA-5.1 [American national Standard] j) Functional design specification which will include but not limited to all mimic diagrams, control procedures compared to control philosophy and a detail description how the PLC will control the entire system [broken down into each component]. (Refer to particular specifications)					
E6.1.1			G	Sum	-		
E6.1.2	EPLC 26.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to particular specification EPLC)	G	Sum	-		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.2	EPLC	SCHEDULE E6.2- SUPPLY AND DELIVERY TO SITE					
	26.2						
E6.2.1	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.A]	E	Each	1		
E6.2.2	EPLC 26.2 (b)	Supply and delivery to site complete UPS as specified [refer to project specification PSEPLC-6.A]	E	Each	1		
E6.2.3	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.A]	E	Each	1		
E6.2.4	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.B]	E	Each	1		
E6.2.5	EPLC 26.2 (b)	Supply and delivery to site complete UPS as [refer to project specification PSEPLC-6.B]	E	Each	1		
E6.2.6	EPLC 26.2 (c)	Supply and delivery to site complete HMI as [refer to project specification PSEPLC-6.B]	E	Each	1		
E6.2.7	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.C]	E	Each	1		
E6.2.8	EPLC 26.2 (b)	Supply and delivery to site complete UPS as [refer to project specification PSEPLC-6.C]	E	Each	1		
E6.2.9	EPLC 26.2 (c)	Supply and delivery to site complete HMI as [refer to project specification PSEPLC-6.C]	E	Each	1		
E6.2.10	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.D]	E	Each	1		
E6.2.11	EPLC 26.2 (b)	Supply and delivery to site complete UPS as [refer to project specification PSEPLC-6.D]	E	Each	1		
E6.2.12	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.D]	E	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.2.13	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.E]	E	Each	4		
E6.2.14	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.E]	E	Each	4		
E6.2.15	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.F]	E	Each	1		
E6.2.16	EPLC 26.2 (b)	Supply and delivery to site complete UPS as [refer to project specification PSEPLC-6.F]	E	Each	1		
E6.2.17	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.F]	E	Each	1		
E6.2.18	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.G]	E	Each	1		
E6.2.19	EPLC 26.2 (b)	Supply and delivery to site complete UPS as specified [refer to project specification PSEPLC-6.G]	E	Each	1		
E6.2.20	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.G]	E	Each	1		
E6.2.21	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.H]	E	Each	2		
E6.2.22	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.H]	E	Each	2		
E6.2.23	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.I]	E	Each	1		
E6.2.24	EPLC 26.2 (b)	Supply and delivery to site complete UPS as specified [refer to project specification PSEPLC-6.I]	E	Each	1		
E6.2.25	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.I]	E	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.2.26	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.J]	E	Each	6		
E6.2.27	EPLC 26.2 (c)	Supply and delivery to site complete HMI as specified [refer to project specification PSEPLC-6.J]	E	Each	6		
E6.2.28	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.K]	E	Each	1		
E6.2.29	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specification PSPLC-6.K)	E	Each	1		
E6.2.30	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.K)	E	Each	1		
E6.2.31	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.L]	E	Each	1		
E6.2.32	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specification PSPLC-6.L)	E	Each	1		
E6.2.33	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.L)	E	Each	1		
E6.2.34	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.M]	E	Each	1		
E6.2.35	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specification PSPLC-6.M)	E	Each	1		
E6.2.36	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.M)	E	Each	1		
E6.2.37	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.N]	E	Each	1		
E6.2.38	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specification PSPLC-6.N)	E	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.2.39	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.N)	E	Each	1		
E6.2.40	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.O]	E	Each	1		
E6.2.41	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specifaion PSPLC-6.O)	E	Each	1		
E6.2.42	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.O)	E	Each	1		
E6.2.43	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.P]	E	Each	1		
E6.2.44	EPLC 26.2 (b)	Supply and delivery to site a complete UPS (refer to project specifaion PSPLC-6.P)	E	Each	1		
E6.2.45	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.P)	E	Each	1		
E6.2.46	EPLC 26.2 (a)	Supply and delivery to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.Q]	E	Each	1		
E6.2.47	EPLC 26.2 (c)	Supply and delivery to site a complete of HMI (refer to project specification PSPLC-6.Q)	E	Each	1		
E6.2.48	EPLC 26.2 (d)	Supply and delivery to site complete cable connections and programming of SCADA, PLC's & HMI's and peripheral equipment for an complete system	E	Each	1		
E6.3	EPLC 26.3	<u>SCHEDULE E6.3 - INSTALLATION</u>					
E6.3.1	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
E6.3.2	EPLC 26.3 (b)	Installation to site complete UPS as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.3.3	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
E6.3.4	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.3.5	EPLC 26.3 (b)	Installation to site complete UPS as [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.3.6	EPLC 26.3 (c)	Installation to site complete HMI as [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.3.7	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.C]	I	Each	1		
E6.3.8	EPLC 26.3 (b)	Installation to site complete UPS as [refer to project specification PSEPLC-6.C]	I	Each	1		
E6.3.9	EPLC 26.3 (c)	Installation to site complete HMI as [refer to project specification PSEPLC-6.C]	I	Each	1		
E6.3.10	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.D]	I	Each	1		
E6.3.11	EPLC 26.3 ©	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.D]	I	Each	1		
E6.3.12	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.E]	I	Each	4		
E6.3.13	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.E]	I	Each	4		
E6.3.14	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.F]	I	Each	1		
E6.3.15	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.F]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.3.16	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.3.17	EPLC 26.3 (b)	Installation to site complete UPS as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.3.18	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.3.19	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.H]	I	Each	2		
E6.3.20	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.H]	I	Each	2		
E6.3.21	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.3.22	EPLC 26.3 (b)	Installation to site complete UPS as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.3.23	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.3.24	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.J]	I	Each	6		
E6.3.25	EPLC 26.3 (c)	Installation to site complete HMI as specified [refer to project specification PSEPLC-6.J]	I	Each	6		
E6.3.26	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.K]	I	Each	1		
E6.3.27	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.K)	I	Each	1		
E6.3.28	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.K)	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.3.29	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.L]	I	Each	1		
E6.3.30	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.L)	I	Each	1		
E6.3.31	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.L)	I	Each	1		
E6.3.32	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.M]	I	Each	1		
E6.3.33	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.M)	I	Each	1		
E6.3.34	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.M)	I	Each	1		
E6.3.35	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.N]	I	Each	1		
E6.3.36	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.N)	I	Each	1		
E6.3.37	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.N)	I	Each	1		
E6.3.38	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.O]	I	Each	1		
E6.3.39	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.O)	I	Each	1		
E6.3.40	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.O)	I	Each	1		
E6.3.41	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.P]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.3.42	EPLC 26.3 (b)	Installation to site a complete UPS (refer to project specification PSPLC-6.P)	I	Each	1		
E6.3.43	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.P)	I	Each	1		
E6.3.44	EPLC 26.3 (a)	Installation to site complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.Q]	I	Each	1		
E6.3.45	EPLC 26.3 (c)	Installation to site a complete of HMI (refer to project specification PSPLC-6.Q)	I	Each	1		
E6.3.46	EPLC 26.3 (d)	Installation to site complete cable connections and programming of SCADA, PLC's & HMI's and peripheral equipment for an complete system	I	Each	1		
E6.4	EPLC 26.4	SCHEDULE E6.4 - COMMISSIONING					
E6.4.1	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
E6.4.2	EPLC 26.4 (b)	Commissioning of complete UPS as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
E6.4.3	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.A]	I	Each	1		
E6.4.4	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.4.5	EPLC 26.4 (b)	Commissioning of complete UPS as [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.4.6	EPLC 26.4 (c)	Commissioning of complete HMI as [refer to project specification PSEPLC-6.B]	I	Each	1		
E6.4.7	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.C]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.4.8	EPLC 26.4 (b)	Commissioning of complete UPS as [refer to project specification PSEPLC-6.C]	I	Each	1		
E6.4.9	EPLC 26.4 (c)	Commissioning of complete HMI as [refer to project specification PSEPLC-6.C]	I	Each	1		
E6.4.10	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.D]	I	Each	1		
E6.4.11	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.D]	I	Each	1		
E6.4.13	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.E]	I	Each	4		
E6.4.13	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.E]	I	Each	4		
E6.4.14	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.F]	I	Each	1		
E6.4.15	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.F]	I	Each	1		
E6.4.16	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.4.17	EPLC 26.4 (b)	Commissioning of complete UPS as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.4.18	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.G]	I	Each	1		
E6.4.19	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.H]	I	Each	2		
E6.4.20	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.H]	I	Each	2		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.4.21	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.4.22	EPLC 26.4 (b)	Commissioning of complete UPS as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.4.23	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.I]	I	Each	1		
E6.4.24	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.J]	I	Each	6		
E6.4.25	EPLC 26.4 (c)	Commissioning of complete HMI as specified [refer to project specification PSEPLC-6.J]	I	Each	6		
E6.4.26	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.K]	I	Each	1		
E6.4.27	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specification PSPLC-6.K)	I	Each	1		
E6.4.28	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.K)	I	Each	1		
E6.4.29	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.L]	I	Each	1		
E6.4.30	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specification PSPLC-6.L)	I	Each	1		
E6.4.31	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.L)	I	Each	1		
E6.4.32	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.M]	I	Each	1		
E6.4.33	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specification PSPLC-6.M)	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.4.34	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.M)	I	Each	1		
E6.4.35	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.N]	I	Each	1		
E6.4.36	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specifaion PSPLC-6.N)	I	Each	1		
E6.4.37	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.N)	I	Each	1		
E6.4.38	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.O]	I	Each	1		
E6.4.39	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specifaion PSPLC-6.O)	I	Each	1		
E6.4.40	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.O)	I	Each	1		
E6.4.41	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.P]	I	Each	1		
E6.4.42	EPLC 26.4 (b)	Commissioning of a complete UPS (refer to project specifaion PSPLC-6.P)	I	Each	1		
E6.4.43	EPLC 26.4 (a)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.P)	I	Each	1		
E6.4.44	EPLC 26.4 (a)	Commissioning of complete PLC and peripheral equipment installed in or other specified enclosures, all as specified [refer to project specification PSEPLC-6.Q]	I	Each	1		
E6.4.45	EPLC 26.4 (c)	Commissioning of a complete of HMI (refer to project specification PSPLC-6.Q)	I	Each	1		
E6.4.46	EPLC 26.4 (d)	Commissioning of complete cable connections and programming of SCADA, PLC's & HMI's and peripheral equipment for an complete system	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E6.4.47		Provisional Sums					
		a) Rocla Telemetry Hut Prov. Sum and offloading to site	E	Prov. Sum	1		300,000.00
E6.4.48		b) Overheads, charges and profit on above	E	%			
E6.4.49		c) Rerbishment of existing electrical infrastructure to Engineers approval	E	Prov. Sum	1		250,000.00
E6.4.50		d) Overheads, charges and profit on above	E	%			
E6.4.51		e) Removal of existing PLC backplane and equipment in PLC Cubicle	E	Prov. Sum	1		350,000.00
E6.4.52		f) Overheads, charges and profit on above	E	%			
SCHEDULE NO. E6 PROGRAMMABLE & LOGIC CONTROLLERS CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E7	ESCA	<u>SCHEDULE NO. E7</u>					
		<u>SCADA SYSTEM</u>					
E7.1	GEN	<u>SCHEDULE E7.1 - DESIGN, DRAWINGS AND GENERAL</u>					
E7.1.1	PSGEN B	Provide all design drawings and wiring diagrams	G	Sum	-		
E7.1.2	PSGEN B	Provide all operating and maintenance manuals and "as-built" drawings	G	Sum	-		
E7.2	ESCA	<u>SCHEDULE E7.2 - SUPPLY AND DELIVERY TO SITE</u>					
	12.1						
E7.2.1	ESCA 12.1 (a)	Supply and delivery to site of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.A]	E	Each	1		
E7.2.2	ESCA 12.1 (a)	Supply and delivery to site of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.B]	E	Each	1		
E7.2.3	ESCA 12.1 (a)	Supply and delivery to site of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.C]	E	Each	1		
E7.2.4	ESCA 12.1 (a)	Supply and delivery to site of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.D]	E	Each	2		
E7.2.5	ESCA 12.1 (b)	Supply and delivery to site of SCADA system associated soft ware as specified. [refer to project specification PSESCA]	E	Sum	-		
E7.2.6	ESCA 12.1 (c)	Supply and delivery to site of SCADA UPS [refer to project specification PSESCA]	E	Sum	-		
E7.3	ESCA	<u>SCHEDULE E7.3 - INSTALLATION</u>					
	12.2						
E7.3.1	ESCA 12.2 (a)	Site installation of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.A]	I	Each	1		
E7.3.2	ESCA 12.2 (a)	Site installation of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.B]	I	Each	1		
E7.3.3	ESCA 12.2 (a)	Site installation of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.C]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E7.3.4	ESCA 12.2 (a)	Site installation of SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.D]	I	Each	2		
E7.3.5	ESCA 12.2 (b)	Configuration of SCADA system associated hardware and software	I	Sum	-		
E7.3.6	ESCA 12.4 (c)	Site installation of SCADA UPS [refer to project specification PSESCA]	I	Sum	-		
E7.4	ESCA 12.3	SCHEDULE E7.4 - COMMISSIONING					
E7.4.1	ESCA 12.3 (a)	Commissioning of complete SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.A]	I	Each	1		
E7.4.2	ESCA 12.3 (a)	Commissioning of complete SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.B]	I	Each	1		
E7.4.3	ESCA 12.3 (a)	Commissioning of complete SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.C]	I	Each	1		
E7.4.4	ESCA 12.3 (a)	Commissioning of complete SCADA system associated hardware as specified. [refer to project specification PSESCA-4-5.D]	I	Each	2		
E7.4.5	ESCA 12.3 (b)	Commissioning of complete SCADA supplementary soft ware as specified. [refer to project specification PSESCA]	I	Sum	-		
E7.4.6		Commissioning of configuration of SCADA system associated hardware and software	I	Sum	-		
E7.4.7	ESCA 12.3 (d)	Commissioning of complete SCADA UPS. [refer to project specification PSESCA]	I	Sum	-		
E7.4.8	PSESCA 1	New Tag no./code allocation [refer to project specification PSESCA]	I	Sum	-		
		SCHEDULE NO. E7 SCADA SYSTEM CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
E8	ECIS	<u>SCHEDULE NO. E8</u>					
		<u>CONTROL AND INSTRUMENTATION SYSTEM</u>					
E8.1	ECIS	<u>SCHEDULE E8.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	13.1						
E8.1.1	ECIS 13.1 (a)	Provide general layout drawings and wiring diagrams of the enclosure and instrumentation for approval [Refer to particular specification]	G	Sum	-		
E8.1.2	ECIS 13.1 (b)	Provide operating and maintenance manuals, data sheets of all equipment and "as built" drawings	G	Sum	-		
E8.2	ECIS	<u>SCHEDULE E8.2 - SUPPLY AND DELIVERY TO SITE</u>					
	13.2						
E8.2.1	ECIS 13.2 (a)	Supply and delivery to site a complete pressure transducer (refer to project specification PSECIS-2.A)	E	Each	20		
E8.2.2	ECIS 13.2 (c)	Supply and delivery to site of electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.A)	E	Each	3		
E8.2.3	ECIS 13.2 (c)	Supply and delivery to site of electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.B)	E	Each	2		
E8.2.4	ECIS 13.2 (c)	Supply and delivery to site of electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.C)	E	Each	4		
E8.2.5	ECIS 13.2 (c)	Supply and delivery to site of electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.D)	E	Each	4		
E8.2.6	ECIS 13.2 (c)	Supply and delivery to site of electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.E)	E	Each	6		
E8.2.7	ECIS 13.2 (b)	Supply and delivery to site a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.A)	E	Each	2		
E8.2.8	ECIS 13.2 (b)	Supply and delivery to site a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.B)	E	Each	30		
E8.2.9	ECIS 13.2 (b)	Supply and delivery to site a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.C)	E	Each	4		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E8.2.10	ECIS 13.2 (b)	Supply and delivery to site a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.D)	E	Each	3		
E8.2.11	ECIS 13.2 (a)	Supply and delivery to site a complete no-flow sensor transducer (refer to project specification PS ECIS-5.A)	E	Each	12		
E8.2.12	ECIS 13.2 (a)	Supply and delivery to site a complete Free Chlorine Analyzer (refer to project specification PS ECIS-6)	E	Each	2		
E8.2.13	ECIS 13.2 (b)	Supply and delivery to site a complete pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-7.A)	E	Each	2		
E8.2.14	ECIS 13.2 (b)	Supply and delivery to site a complete turbidity transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.A)	E	Each	16		
E8.2.15	ECIS 13.2 (b)	Supply and delivery to site a complete turbidity and pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.B)	E	Each	2		
E8.2.16	ECIS 13.2 (b)	Supply and delivery to site all instrumentation for Dewatering System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-12)	E	Sum	1		
E8.2.17	ECIS 13.2 (b)	Supply and delivery to site all instrumentation for Ozone System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-13)	E	Sum	1		
E8.2.18	ECIS 13.2 (b)	Supply and delivery to site a complete Thermal Mass Flow meter and controller complete with mounting bracket and kiosk (refer to project specification PSECIS-14)	E	Each	2		
E8.2.19	ECIS 13.2 (b)	Supply and delivery to site a complete proximity sensor complete with mounting bracket and kiosk (refer to project specification PSECIS-15)	E	Each	26		
E8.3	ECIS 13.3	<u>SCHEDULE E8.3 - INSTALLATION</u>					
E8.3.1	ECIS 13.3 (a)	Installation on site of a complete pressure transducer (refer to project specification PSECIS-2.A)	I	Each	20		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E8.3.2	ECIS 13.3 (c)	Installation on site of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.A)	I	Each	3		
E8.3.3	ECIS 13.3 (c)	Installation on site of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.B)	I	Each	2		
E8.3.4	ECIS 13.3 (c)	Installation on site of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.C)	I	Each	4		
E8.3.5	ECIS 13.3 (c)	Installation on site of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.D)	I	Each	4		
E8.3.6	ECIS 13.3 (c)	Installation on site of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.E)	I	Each	6		
E8.3.7	ECIS 13.3 (b)	Installation on site of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.A)	I	Each	2		
E8.3.8	ECIS 13.3 (b)	Installation on site of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.B)	I	Each	30		
E8.3.9	ECIS 13.3 (b)	Installation on site of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.C)	I	Each	4		
E8.3.10	ECIS 13.3 (b)	Installation on site of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.D)	I	Each	3		
E8.3.11	ECIS 13.3 (a)	Installation on site of a complete no-flow sensor transducer (refer to project specification PS ECIS-5)	I	Each	12		
E8.3.12	ECIS 13.3 (a)	Installation on site of a complete Free Chlorine Analyzer (refer to project specification PS ECIS-6)	I	Each	2		
E8.3.13	ECIS 13.3 (b)	Installation on site of a complete pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-7.A)	I	Each	2		
E8.3.14	ECIS 13.3 (b)	Installation on site of a complete turbidity transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.A)	I	Each	16		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E8.3.15	ECIS 13.3 (b)	Installation on site of a complete turbidity and pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.B)	I	Each	2		
E8.3.16	ECIS 13.3 (b)	Installation on site all instrumentation for the Dewatering System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-12)	I	Sum	1		
E8.3.17	ECIS 13.3 (b)	Installation on site all instrumentation for Ozone System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-13)	I	Sum	1		
E8.3.18	ECIS 13.3 (b)	Installation on site of a complete complete Thermal Mass Flow meter and controller complete with mounting bracket and kiosk (refer to project specification PSECIS-14)	I	Each	2		
E8.3.19	ECIS 13.3 (b)	Installation on site a complete proximity sensor complete with mounting bracket and kiosk (refer to project specification PSECIS-15)	I	Each	26		
E8.4	ECIS 13.4	SCHEDULE E8.4 - COMMISSIONING					
E8.4.1	ECIS 13.4 (a)	Commissioning of a complete pressure transducer (refer to project specification PSECIS-2.A)	I	Each	20		
E8.4.2	ECIS 13.4 (c)	Commissioning of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.A)	I	Each	3		
E8.4.3	ECIS 13.4 (c)	Commissioning of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.B)	I	Each	2		
E8.4.4	ECIS 13.4 (c)	Commissioning of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.C)	I	Each	4		
E8.4.5	ECIS 13.4 (c)	Commissioning of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.D)	I	Each	4		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E8.4.6	ECIS 13.4 (c)	Commissioning of a complete electrical installation equipment at and in flow meter manholes (refer to project specification PSECIS-3.E)	I	Each	6		
E8.4.7	ECIS 13.4 (b)	Commissioning of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.A)	I	Each	2		
E8.4.8	ECIS 13.4 (b)	Commissioning of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.B)	I	Each	30		
E8.4.9	ECIS 13.4 (b)	Commissioning of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.C)	I	Each	4		
E8.4.10	ECIS 13.4 (b)	Commissioning of a complete level transducer and controller complete with mounting bracket (refer to project specification PS ECIS-4.D)	I	Each	3		
E8.4.11	ECIS 13.4 (a)	Commissioning of a complete no-flow sensor transducer (refer to project specification PS ECIS-5)	I	Each	12		
E8.4.12	ECIS 13.4 (a)	Commissioning of a complete Free Chlorine Analyzer (refer to project specification PS ECIS-6)	I	Each	2		
E8.4.13	ECIS 13.4 (b)	Commissioning of a complete pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-7.A)	I	Each	2		
E8.4.14	ECIS 13.4 (b)	Commissioning of a complete turbidity transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.A)	I	Each	16		
E8.4.15	ECIS 13.4 (b)	Commissioning of a complete turbidity and pH transducer and controller complete with mounting bracket (refer to project specification PS ECIS-8.B)	I	Each	2		
E8.4.16	ECIS 13.4 (b)	Commissioning of all instrumentation for the Dewatering System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-12)	I	Sum	1		
E8.4.17	ECIS 13.4 (b)	Commissioning of all instrumentation for Ozone System. All complete with mounting bracket and all coordination with mechanical Contrator for Instrumentation (refer to project specification PSECIS-13)	I	Sum	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E8.4.18	ECIS 13.4 (b)	Commissioning of a complete Thermal Mass Flow meter and controller complete with mounting bracket and kiosk (refer to project specification PSECIS-14)	I	Each	2		
E8.4.19	ECIS 13.3 (b)	Commissioning of a complete proximity sensor complete with mounting bracket and kiosk (refer to project specification PSECIS-15)	I	Each	26		
SCHEDULE NO. E8 <u>CONTROL INSTRUMENTATION SYSTEM</u> <u>CARRIED TO SUMMARY</u>							
Total							



Contractor



Witness 1



Witness 2



Employer



Witness 1



Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
E9	EG&M	<u>SCHEDULE NO. E9</u> <u>GENERAL AND MISCELLANEOUS</u>					
E9.1	EG&M	<u>SCHEDULE E9.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	13.1						
E9.1.1	EG&M 13.1 (a)	Provide general layouts drawings, notice drawings and wiring diagrams for approval.	G	Sum	-		
E9.1.2	EG&M 13.1 (b)	Provide operating and maintenance manuals, data sheets of all equipment and "as built" drawings	G	Sum	-		
E9.2	EG&M	<u>SCHEDULE E9.2 - SUPPLY AND DELIVERY TO SITE</u>					
	13.2						
E9.2.1	EG&M 13.2 (a)	Supply and delivery to site of emergency stop stations [Refer to particular specification specification EG&M 10]	E	Each	78		
E9.2.2	EG&M 13.2 (b)	Supply and delivery to site of emergency stop stations with built in motor cable termination box [refer to particular specification EG&M 10]	E	Each	6		
E9.2.3	EG&M 13.2 (c)	Supply and delivery to site of complete fire extinguishers with outdoor bracket, enclosure and fire signage (refer to project specifications PS EG&M-9)	E	Each	26		
E9.2.4	EG&M 13.2 (d)	Supply and delivery to site of complete all notices and all danger plates as may be required (refer to project specifications PS EG&M-8)	E	Sum	-		
E9.3	EG&M	<u>SCHEDULE E9.3 - INSTALLATION</u>					
	13.3						
E9.3.1	EG&M 13.3 (a)	Installation on site of emergency stop stations [refer to particular specification EG&M 10]	I	Each	78		
E9.3.2	EG&M 13.3 (b)	Installation on site of emergency stop stations with built in motor cable termination box [refer to particular specification EG&M 10]	I	Each	6		
E9.3.3	EG&M 13.3 (c)	Installation on site of fire extinguishers with outdoor bracket, enclosure and fire signage (refer to project specifications PS EG&M-9)	I	Each	26		
E9.3.4	EG&M 13.3 (d)	Installation on site of all notices and all danger plates as may be required (refer to project specifications PS EG&M-8)	I	Sum	-		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate	Amount (R)
Brought Forward							
E9.4	EG&M 13.4	SCHEDULE E9.4 - COMMISSIONING					
E9.4.1	EG&M 13.4 (a)	Commissioning of a complete of emergency stop stations [refer to particular specification EG&M 10]	I	Each	78		
E9.4.2	EG&M 13.4 (b)	Commissioning of a complete of emergency stop stations with built in motor cable termination box [refer to particular specification EG&M 10]	I	Each	6		
E9.4.3	EG&M 13.4 (c)	Commissioning of a complete of fire extinguishers with outdoor bracket, enclosure and fire signage (refer to project specifications PS EG&M-9)	I	Each	26		
E9.4.4	EG&M 13.4 (d)	Commissioning of a complete of all notices and all danger plates as may be required (refer to project specifications PS EG&M-8)	I	Sum	-		
SCHEDULE NO. E9 GENERAL AND MISCELLANEOUS CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E10	EPTM	<u>SCHEDULE NO. E10</u> <u>TELEMETRY SYSTEM</u>					
E10.1	EPTM	<u>SCHEDULE E10.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	25.1						
E10.1.1	EPTM 25.1 (a)	Provide design calculations, design drawings and drawings for programmable & logic controllers, antennae, Input and output schedules, loop diagrams, cable schedules, cable layouts, control philosophy, control network layout and wiring diagrams (refer to particular specifications EPTM)	G	Sum	1		
E10.1.2	EPTM 25.1 (b)	Provide operating all maintenance manuals and "as-built" drawings as specified (refer to particular specification EPTM)	G	Sum	1		
E10.2	EPTM	<u>SCHEDULE E10.2 - SUPPLY AND DELIVERY TO SITE</u>					
	25.2						
E10.2.1	EPTM 25.2 (a)	Supply and delivery to site of complete telemetry outstation with antenna and earthing system at the Bospoort to Vaalkop / Bospoort North HLPL Link Chamber (refer to project specifications PSEPTM-6.A & PSEPTM-19.A)	E	Sum	1		
E10.2.2	EPTM 25.2 (a)	Supply and delivery to site of complete telemetry outstation with antenna and earthing system at the Bospoort Reservoirs [Megalies Water] (refer to project specifications PSEPTM-6.B & PSEPTM-19.B)	E	Sum	1		
E10.2.3	EPTM 25.2 (a)	Supply and delivery to site of complete telemetry outstation with antenna and earthing system at the Bospoort Water Treatment Works (refer to project specifications PSEPTM-6.C & PSEPTM-19.C)	E	Sum	1		
E10.3	EPTM	<u>SCHEDULE E10.3 - INSTALLATION</u>					
	25.3						
E10.3.1	EPTM 25.3 (a)	Installation of a complete telemetry outstation with antenna and earthing system at the Bospoort to Vaalkop / Bospoort North HLPL Link Chamber (refer to project specifications PSEPTM-6.A & PSEPTM-19.A)	I	Sum	1		
	EPTM 25.3 (a)	Installation of a complete telemetry outstation with antenna and earthing system at the Bospoort Reservoirs [Megalies Water] (refer to project specifications PSEPTM-6.B &					
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E10.3.2		PSEPTM-19.B)	I	Sum	1		
	EPTM 25.3 (a)	Installation of a complete telemetry outstation with antenna and earthing system at the Bospoort Water Treatment Works (refer to project specifications PSEPTM-6.C & PSEPTM-19.C)	I	Sum	1		
E10.3.3			I	Sum	1		
	EPTM 25.3 (c)	Complete site cable connections, programming of the entire Telemetry System and all peripheral equipment	I	Sum	1		
E10.3.4			I	Sum	1		
E10.4	EPTM 25.4	<u>SCHEDULE E10.4 - COMMISSIONING</u>					
	EPTM 25.4 (a)	Commissioning of a complete telemetry outstation with antenna and earthing system at the Bospoort to Vaalkop / Bospoort North HLPL Link Chamber (refer to project specifications PSEPTM-6.A & PSEPTM-19.A)	I	Sum	1		
E10.4.1			I	Sum	1		
	EPTM 25.4 (a)	Commissioning of a complete telemetry outstation with antenna and earthing system at the Bospoort Reservoirs [Megabies Water] (refer to project specifications PSEPTM-6.B & PSEPTM-19.B)	I	Sum	1		
E10.4.2			I	Sum	1		
	EPTM 25.4 (a)	Commissioning of a complete telemetry outstation with antenna and earthing system at the Bospoort Water Treatment Works (refer to project specifications PSEPTM-6.C & PSEPTM-19.C)	I	Sum	1		
E10.4.3			I	Sum	1		
	EPTM 25.4 (c)	Commissioning site cable connections, programming of the entire Telemetry System and all peripheral equipment	I	Sum	1		
E10.4.4			I	Sum	1		
Total							
		SCHEDULE NO. E10 TELEMETRY SYSTEM CARRIED TO SUMMARY					

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E11	EELP	SCHEDULE NO. E11					
		EARTHING & LIGHTNING PROTECTION					
E11.1	EELP	SCHEDULE E11.1 - DESIGN, DRAWINGS AND GENERAL					
	22.1						
E11.1.1	PSGEN B	Provide designs, calculations as stipulated in the contract (refer to PSGEN.B Design and Drawings)	G	Sum	-		
E11.1.2	EELP 22.1 (a)	Provide design drawings and design information for Earthing and Lightning Protection System	G	Sum	-		
E11.1.3	EELP 22.1 (b)	Provide operating and maintenance manuals and "as built" drawings as specified	G	Sum	-		
E11.1.4	EELP 22.1 (c)	Provide risk management calculations and IEC Program as specified	G	Sum	-		
E11.2	EELP	SCHEDULE E11.2- SUPPLY AND DELIVERY TO SITE					
	22.2						
E11.2.1		Allowance for specialist to visit the site and measure the earth readings, record and complete a detail soil resistivity survey. Earth resistance report shall be sent for approval to the Engineer	E	Sum	-		
E11.2.2	EELP 22.2	Earth rods - 1500mm long driven into ground with top ends up to 500mm below excavation level.	E	Each	98		
E11.2.3	EELP 22.2	Earth rods - 2400mm long driven into ground with top ends up to 500mm below excavation level. Holes predrilled as mentioned below.	E	Each	4		
E11.2.4	EELP 22.2	Earth rods - 3000mm long driven into ground with top ends up to 500mm below excavation level. Holes predrilled as mentioned below.	E	Each	2		
E11.2.5	EELP 22.2	Drill 1500mm holes for earth rods in hard soil conditions as for 1500mm holes [10% allowance]	E	Each	98		
E11.2.6	EELP 22.2	Drill 2400mm holes for earth rods in hard soil conditions as for 2400mm holes [10% allowance]	E	Each	4		
E11.2.7	EELP 22.2	Drill 3000mm holes for earth rods in hard soil conditions as for 3000mm holes [10% allowance]	E	Each	2		
E11.2.8	EELP 22.2	Marcionite conductive slurry including installing slurry into drilled holes as required	E	m ³	18		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.2.9	EELP 22.2	Earth wells or test points against building for future earth readings and continuity tests. Include for all concrete work and manhole covers. 300x300mm min.	E	Each	20		
E11.2.10	EELP 22.2	Supply 70mm ² bare copper earth 1mx1mx1m earth mat	E	Each	20		
E11.2.11	EELP 22.2	Earth bar mounted on two insulators against wall at 300mm above final floor level below DB / MCC. 500mm x 80mm x 6mm minimum	E	Each	40		
E11.2.12	EELP 22.2	70mm ² PVC insulated green / yellow earth conductor	E	m	400		
E11.2.13	EELP 22.2	70mm ² insulated green earth conductor terminations.	E	Each	80		
E11.2.14	EELP 22.2	70mm ² bare copper earth conductor [earth ring]	E	m	1070		
E11.2.15	EELP 22.2	70mm ² bare copper earth conductor [earth ring] terminations	E	Each	138		
E11.2.16	EELP 22.2	70mm ² galvanised anti-theft conductor (avoid galvanic corrosion).	E	m	490		
E11.2.17	EELP 22.2	70mm ² galvanised anti-theft conductor terminations (avoid galvanic corrosion).	E	Each	196		
E11.2.18	EELP 22.2	Clamps/bolts at each rod connection plus seal termination as per specification (avoid galvanic corrosion).	E	Each	98		
E11.2.19	EELP 22.2	Exothermic weld at earth wire connection plus seal termination as per specification (avoid galvanic corrosion).	E	Each	196		
E11.2.20	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Clear Water Tank' [7m(W), 21m(L) and 3m(H)]	E	Each	1		
E11.2.32	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'DAF Tank No.3 Extension' [26m(W), 27m(L) and 6m(H)]	E	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.2.22	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'RGS Filters' [19m(W), 26m(L) and 9m(H)]	E	Each	1		
E11.2.23	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Ozone Contact Tank' [16m(W), 62m(L) and 11m(H)]	E	Each	1		
E11.2.31	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Ozone Building' [7m(W), 20m(L) and 8m(H)]	E	Each	1		
E11.2.25	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Dewatering Building' [12m(W), 20m(L) and 9m(H)]	E	Each	1		
E11.2.26	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Filtrate Washwater Sump' [10m(W), 12m(L) and 1m(H)]	E	Each	1		
E11.2.31	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Hydrogen Peroxide Store' [7m(W), 7m(L) and 4.5m(H)]	E	Each	1		
E11.2.28	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'GAC Filters' [18.5m(W), 29.5m(L) and 9m(H)]	E	Each	1		
E11.2.29	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Transformer Yard' [9m(W), 12m(L) and 3m(H)]	E	Each	1		
E11.2.30	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Miniature Substation' [1m(W), 2.6m(L) and 2m(H)]	E	Each	1		
E11.2.31	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Containerised Standby Generators on a concrete' plinth [10m(W), 30m(L) and 0.5m(H)]	E	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.2.32	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Pre-Ozonation Building' [7m(W), 10m(L) and 9m(H)]	E	Each	1		
E11.2.33	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Lox Building' [8m(W), 10m(L) and 3m(H)]	E	Each	1		
E11.2.34	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Bospoort to Vaalkop/ Bospoort North Link Chamber' [3m(W), 3m(L) and 3m(H)]	E	Each	1		
E11.2.35	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Bospoort Reservoirs Telemetry' [3m(W), 3m(L) and 3m(H)]	E	Each	1		
E11.2.36	EELP 22.2 (a)	Supply and delivery to site of a complete surface mounted Class 4 lightning protection system for the 'Bospoort - Thlabane - Boitekong Chamber Telemetry' [3m(W), 3m(L) and 3m(H)]	E	Each	1		
E11.2.37	EELP 22.2 (d)	Supply and delivery all connection points, terminals, interconnections, bonding points and test joints for the entire system including for "natural" components all for above specified location	E	Sum	-		
E11.3	EELP 22.3	<u>SCHEDULE E11.3 - INSTALLATION</u>					
E11.3.1	EELP 22.3	Allowance for specialist to visit the site and measure the earth readings, record and complete a detail soil resistivity survey. Earth resistance report shall be sent for approval to the Engineer	I	Sum	-		
E11.3.2	EELP 22.3	Earth rods - 1500mm long driven into ground with top ends up to 500mm below excavation level.	I	Each	98		
E11.3.3	EELP 22.3	Earth rods - 2400mm long driven into ground with top ends up to 500mm below excavation level. Holes predrilled as mentioned below.	I	Each	4		
E11.3.4	EELP 22.3	Earth rods - 3000mm long driven into ground with top ends up to 500mm below excavation level. Holes predrilled as mentioned below.	I	Each	2		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.3.5	EELP 22.3	Drill 1500mm holes for earth rods in hard soil conditions as for 1500mm holes [10% allowance]	I	Each	98		
E11.3.6	EELP 22.3	Drill 2400mm holes for earth rods in hard soil conditions as for 2400mm holes [10% allowance]	I	Each	4		
E11.3.7	EELP 22.3	Drill 3000mm holes for earth rods in hard soil conditions as for 3000mm holes [10% allowance]	I	Each	2		
E11.3.8	EELP 22.3	Marcionite conductive slurry including installing slurry into drilled holes as required	I	m ³	18		
E11.3.9	EELP 22.3	Earth wells or test points against building for future earth readings and continuity tests. Include for all concrete work and manhole covers. 300x300mm min.	I	Each	20		
E11.3.10	EELP 22.3	Install 70mm ² bare copper earth 1mx1mx1m earth mat	I	Each	20		
E11.3.11	EELP 22.3	Earth bar mounted on two insulators against wall at 300mm above final floor level below DB / MCC. 500mm x 80mm x 6mm minimum	I	Each	40		
E11.3.12	EELP 22.3	70mm ² PVC insulated green / yellow earth conductor	I	m	400		
E11.3.13	EELP 22.3	70mm ² insulated green earth conductor terminations.	I	Each	80		
E11.3.14	EELP 22.3	70mm ² bare copper earth conductor [earth ring]	I	m	1070		
E11.3.15	EELP 22.3	70mm ² bare copper earth conductor [earth ring] terminations	I	Each	138		
E11.3.16	EELP 22.3	70mm ² galvanised anti-theft conductor (avoid galvanic corrosion).	I	m	490		
E11.3.17	EELP 22.3	70mm ² galvanised anti-theft conductor terminations (avoid galvanic corrosion).	I	Each	196		
E11.3.18	EELP 22.3	Clamps/bolts at each rod connection plus seal termination as per specification (avoid galvanic corrosion).	I	Each	98		
E11.3.19	EELP 22.3	Exothermic weld at earth wire connection plus seal termination as per specification (avoid galvanic corrosion).	I	Each	196		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.2.57	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Clear Water Tank' [7m(W), 21m(L) and 3m(H)]	I	Each	1		
E11.2.69	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'DAF Tank No.3 Extension' [26m(W), 27m(L) and 6m(H)]	I	Each	1		
E11.2.59	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'RGS Filters' [19m(W), 26m(L) and 9m(H)]	I	Each	1		
E11.2.60	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Ozone Contact Tank' [16m(W), 62m(L) and 11m(H)]	I	Each	1		
E11.2.68	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Ozone Building' [7m(W), 20m(L) and 8m(H)]	I	Each	1		
E11.2.62	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Dewatering Building' [12m(W), 20m(L) and 9m(H)]	I	Each	1		
E11.2.63	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Filtrate Washwater Sump' [10m(W), 12m(L) and 1m(H)]	I	Each	1		
E11.2.68	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Hydrogen Peroxide Store' [7m(W), 7m(L) and 4.5m(H)]	I	Each	1		
E11.2.65	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'GAC Filters' [18.5m(W), 29.5m(L) and 9m(H)]	I	Each	1		
E11.2.66	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Transformer Yard' [9m(W), 12m(L) and 3m(H)]	I	Each	1		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.2.67	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Miniature Substation' [1m(W), 2.6m(L) and 2m(H)]	I	Each	1		
E11.2.68	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Containerised Standby Generators on a concrete' plinth [10m(W), 30m(L) and 0.5m(H)]	I	Each	1		
E11.2.69	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Pre-Ozonation Building' [7m(W), 10m(L) and 9m(H)]	I	Each	1		
E11.2.70	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Lox Building' [8m(W), 10m(L) and 3m(H)]	I	Each	1		
E11.2.71	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Bospoort to Vaalkop/ Bospoort North Link Chamber' [3m(W), 3m(L) and 3m(H)]	I	Each	1		
E11.2.72	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Bospoort Reservoirs Telemetry' [3m(W), 3m(L) and 3m(H)]	I	Each	1		
E11.2.73	EELP 22.3 (a)	Site installation of a complete surface mounted Class 4 lightning protection system for the 'Bospoort - Thlabane - Boitekong Chamber Telemetry' [3m(W), 3m(L) and 3m(H)]	I	Each	1		
E11.3.37	EELP 22.3 (d)	Site installation of a complete surface terminals, interconnections, bonding points and test joints for the entire system including for "natural" components all for above specified location	I	Sum	-		
E11.3.38		Excavating, back filling, consolidation, importation of soil and dumping of all rock and stone removed during excavations including cleaning of cable routes all according to particular specifications					
E11.3.38	a)	Pickable soil	I	m³	390		
E11.3.39	b)	Soft rock	I	m³	120		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E11.3.40		c) Hard rock	I	m³	80		
E11.3.41		Importation of additional soil for the bedding of cables and the backfilling of trenches and drilling complete as per particular specification.	I	m³	33		
E11.3.42		Dumping and removing of all rock and stone removed during excavations including cleaning of cable routes complete as per particular specification.	I	m³	200		
E11.3.43		Nett amount for core drilling 100mm diameter holes through 250mm concrete	I	Each	20		
E11.4	EELP	<u>SCHEDULE E11.4 - COMMISSIONING</u>					
	22.4						
E11.4.1	EELP 22.4 (a)	Commissioning of complete lightning protection system (refer to protection system PSEELS-10)	I	Sum	-		
E11.4.2	EELP 22.4 (e)	Certificate of compliance of earthing system as specified under SANS 10313	I	Each	20		
SCHEDULE NO. E11 EARTHING & LIGHTNING PROTECTION CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E12	ESPL	<u>SCHEDULE NO. E12</u> <u>SMALL POWER AND LIGHTING INSTALLATIONS</u>					
E12.1	ESPL	<u>SCHEDULE E12.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	12.1						
E12.1.1	ECIS 12.1 (a)	Provide wiring diagrams for approval [Refer to Motor Control centre and Distribution particular specification]	G	Sum	-		
E12.1.2	ECIS 12.1 (b)	Provide operating and maintenance manuals, data sheets of all equipment and "as built" drawings	G	Sum	-		
E12.2	ESPL	<u>SCHEDULE E12.2 - SUPPLY AND DELIVERY TO SITE</u>					
	12.2						
E12.2.1	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-A)	E	Sum	-		
E12.2.2	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-B)	E	Sum	-		
E12.2.3	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-C)	E	Sum	-		
E12.2.4	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-D)	E	Sum	-		
E12.2.5	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-E)	E	Sum	-		
E12.2.6	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-F)	E	Sum	-		
E12.2.7	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-G)	E	Sum	-		
E12.2.8	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-H)	E	Sum	-		
E12.2.9	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-I)	E	Sum	-		
E12.2.10	ESPL 12.2 (a)	Supply and delivery to site of a complete electrical installation (refer to project specification PSESPL-J)	E	Sum	-		
E12.3	ESPL	<u>SCHEDULE E12.3 - INSTALLATION</u>					
	12.3						
E12.3.1	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-A)	I	Sum	-		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E12.3.2	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-B)	I	Sum	-		
E12.3.3	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-C)	I	Sum	-		
E12.3.4	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-D)	I	Sum	-		
E12.3.5	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-E)	I	Sum	-		
E12.3.6	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-F)	I	Sum	-		
E12.3.7	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-G)	I	Sum	-		
E12.3.8	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-H)	I	Sum	-		
E12.3.9	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-I)	I	Sum	-		
E12.3.10	ESPL 12.3 (a)	Site Installation of a complete electrical installation (refer to project specification PSESPL-J)	I	Sum	-		
E12.4	ESPL	SCHEDULE E12.4 - COMMISSIONING					
E12.4.1	12.4 ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-A)	I	Sum	-		-
E12.4.2	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-B)	I	Sum	-		-
E12.4.3	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-C)	I	Sum	-		-
E12.4.4	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-D)	I	Sum	-		-
E12.4.5	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-E)	I	Sum	-		-
E12.4.6	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-F)	I	Sum	-		-
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E12.4.7	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-G)	I	Sum	-		-
E12.4.8	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-H)	I	Sum	-		-
E12.4.9	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-I)	I	Sum	-		-
E12.4.10	ESPL 12.4 (a)	Commissioning to site of a complete electrical installation (refer to project specification PSESPL-J)	I	Sum	-		-
SCHEDULE NO. E12 SMALL POWER AND LIGHTING INSTALLATIONS CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E13	EMCA	<u>SCHEDULE NO. E13</u> <u>MULTICORE CABLES & EARTH WIRES</u>					
E13.1	EMCA	<u>SCHEDULE E13.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	18.1						
E13.1.1	EMCA 18.1 (a)	The Contractor will provide the following design calculations, drawings, method statements, cable routes, cable schedules in excel format which will include but limited to From, To, Distance and Tag numbers all to the approval of the Engineer [Refer to particular specification EMCA 3.3.2, 8.7 & 17]	G	Sum	-		
E13.1.2	EMCA 18.1 (b)	Provide operating and maintenance manuals, all data sheets [a) cables, b) joint kits, c) ladders, d) glands, conduit, fasteners and all that are used and etc] and furthermore the Contractor to supply as built" drawings	G	Sum	-		
E13.2	EMCA	<u>SCHEDULE E13.2 - SUPPLY AND DELIVERY TO SITE</u>					
	18.2						
E13.2.1	EMCA 18.2 (a)	Supply and delivery to site of multicore cables and earthwires and cable name tags for the following cables as per the particular:					
		120mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	E	m	335		
E13.2.2		70mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	E	m	20		
E13.2.3		240mm ² 4C PVC SWA PVC Cu Cable	E	m	280		
E13.2.4		185mm ² 4C PVC SWA PVC Cu Cable	E	m	580		
E13.2.5		150mm ² 4C PVC SWA PVC Cu Cable	E	m	300		
E13.2.6		95mm ² 4C PVC SWA PVC Cu Cable	E	m	200		
E13.2.7		70mm ² 4C PVC SWA PVC Cu Cable	E	m	160		
E13.2.8		50mm ² 4C PVC SWA PVC Cu Cable	E	m	260		
E13.2.9		35mm ² 4C PVC SWA PVC Cu Cable	E	m	275		
E13.2.10		25mm ² 4C PVC SWA PVC Cu Cable	E	m	286		
E13.2.11		16mm ² 4C PVC SWA PVC Cu Cable	E	m	1870		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.2.12		10mm ² 4C PVC SWA PVC Cu Cable	E	m	540		
E13.2.13		6mm ² 4C PVC SWA PVC Cu Cable	E	m	850		
E13.2.14		4mm ² 4C PVC SWA PVC Cu Cable	E	m	850		
E13.2.15		2.5mm ² 4C PVC SWA PVC Cu Cable	E	m	5979		
E13.2.16		2.5mm ² 3C PVC SWA PVC Cu Cable	E	m	2180		
E13.2.17		1.5mm ² 3C PVC SWA PVC Cu Cable	E	m	2945		
E13.2.18		1.5mm ² 4C PVC SWA PVC Cu Cable	E	m	200		
E13.2.19		95mm ² Bare Copper Conductor	E	m	335		
E13.2.20		70mm ² Bare Copper Conductor	E	m	940		
E13.2.21		35mm ² Bare Copper Conductor	E	m	260		
E13.2.22		25mm ² Bare Copper Conductor	E	m	80		
E13.2.23		16mm ² Bare Copper Conductor	E	m	286		
E13.2.24		10mm ² Bare Copper Conductor	E	m	1624		
E13.2.25		6mm ² Bare Copper Conductor	E	m	330		
E13.2.26		4C PVC CST PVC Heavy Duty Fibre Optic Cable Singlemode	E	m	1960		
E13.2.27		1mm ² x 1pr twisted PVC SWA PVC (individually and overall screened)	E	m	2081		
E13.2.28		1mm ² x 2pr twisted PVC SWA PVC (individually and overall screened)	E	m	1860		
E13.2.29		1mm ² x 4pr twisted PVC SWA PVC (individually and overall screened)	E	m	9620		
E13.2.30		1mm ² x 6pr twisted PVC SWA PVC (individually and overall screened)	E	m	328		
E13.2.31		1mm ² x 8pr twisted PVC SWA PVC (individually and overall screened)	E	m	470		
E13.2.32		4pr twisted PVC, Non-Woven Tape + alu Foil (Industrial CAT6)	E	m	1060		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
	EMCA 18.2 (b)	Supply and delivery to site of all multicore cables and earthwires termination materials [equal or similar to Enviro Glands, neoprene shrouds, lugs, insulating, materials, cable ties and corrosion proof bolts, washers, spring washers, nuts, etc] to terminate the following cables as per the particular specification					
E13.2.33		120mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	E	Each	6		
E13.2.34		70mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	E	Each	4		
E13.2.35		240mm ² 4C PVC SWA PVC Cu Cable	E	Each	28		
E13.2.36		185mm ² 4C PVC SWA PVC Cu Cable	E	Each	40		
E13.2.37		150mm ² 4C PVC SWA PVC Cu Cable	E	Each	12		
E13.2.38		95mm ² 4C PVC SWA PVC Cu Cable	E	Each	8		
E13.2.39		70mm ² 4C PVC SWA PVC Cu Cable	E	Each	4		
E13.2.40		50mm ² 4C PVC SWA PVC Cu Cable	E	Each	6		
E13.2.41		35mm ² 4C PVC SWA PVC Cu Cable	E	Each	8		
E13.2.42		25mm ² 4C PVC SWA PVC Cu Cable	E	Each	6		
E13.2.43		16mm ² 4C PVC SWA PVC Cu Cable	E	Each	52		
E13.2.44		10mm ² 4C PVC SWA PVC Cu Cable	E	Each	24		
E13.2.45		6mm ² 4C PVC SWA PVC Cu Cable	E	Each	46		
E13.2.46		4mm ² 4C PVC SWA PVC Cu Cable	E	Each	28		
E13.2.47		2.5mm ² 4C PVC SWA PVC Cu Cable	E	Each	424		
E13.2.48		2.5mm ² 3C PVC SWA PVC Cu Cable	E	Each	110		
E13.2.49		1.5mm ² 3C PVC SWA PVC Cu Cable	E	Each	158		
E13.2.50		1.5mm ² 4C PVC SWA PVC Cu Cable	E	Each	20		
E13.2.51		95mm ² Bare Copper Conductor	E	Each	6		
E13.2.52		70mm ² Bare Copper Conductor	E	Each	72		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.2.53		35mm ² Bare Copper Conductor	E	Each	6		
E13.2.54		25mm ² Bare Copper Conductor	E	Each	2		
E13.2.55		16mm ² Bare Copper Conductor	E	Each	6		
E13.2.56		10mm ² Bare Copper Conductor	E	Each	76		
E13.2.57		6mm ² Bare Copper Conductor	E	Each	26		
E13.2.58		4C PVC CST PVC Heavy Duty Fibre Optic Cable Singlemode	E	Each	44		
E13.2.59		1mm ² x 1pr twisted PVC SWA PVC (individually and overall screened)	E	Each	902		
E13.2.60		1mm ² x 2pr twisted PVC SWA PVC (individually and overall screened)	E	Each	94		
E13.2.61		1mm ² x 4pr twisted PVC SWA PVC (individually and overall screened)	E	Each	638		
E13.2.62		1mm ² x 6pr twisted PVC SWA PVC (individually and overall screened)	E	Each	40		
E13.2.63		1mm ² x 8pr twisted PVC SWA PVC (individually and overall screened)	E	Each	20		
E13.2.64		4pr twisted PVC, Non-Woven Tape + alu Foil (Industrial CAT6)	E	Each	62		
E13.2.65	EMCA 18.2 (c)	Supply and delivery to site of cable route markers	E	Each	166		
E13.2.66	EMCA 18.2 (d)	Supply and delivery to site of concrete cable slabs	E	Each	80		
	EMCA 18.2 (e)	Supply, delivery to site of hot dipped galvanised heavy-duty cable ladder, trunking, welded wire mesh and accessories including all necessary supports, clamps strapping, brackets, reducer splice, hangers, threaded rods, trunking, bolts, nuts and anchor bolts etc as per the particular specification					
E13.2.67		150mm Wide cable ladder	E	m	165		
E13.2.68		200mm Wide cable ladder	E	m	86		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.2.69		300mm Wide cable ladder	E	m	53		
E13.2.70		400mm Wide cable ladder	E	m	8		
E13.2.71		500mm Wide cable ladder	E	m	13		
E13.2.72		600mm Wide cable ladder	E	m	22		
E13.2.73		800mm Wide cable ladder	E	m	93		
E13.2.74		150mm Wide cable ladder flat covers	E	m	17		
E13.2.75		200mm Wide cable ladder flat covers	E	m	9		
E13.2.76		300mm Wide cable ladder flat covers	E	m	6		
E13.2.77		400mm Wide cable ladder flat covers	E	m	1		
E13.2.78		500mm Wide cable ladder flat covers	E	m	2		
E13.2.79		600mm Wide cable ladder flat covers	E	m	3		
E13.2.80		800mm Wide cable ladder flat covers	E	m	10		
E13.2.81	EMCA 18.2 (g)	Supply, delivery to site of all hot dipped galvanised heavy-duty cable ladder supports, bolts, holders and etc that is required as per the particular specification	E	Sum	-		
E13.2.82	EMCA 18.2 (h)	Supply and delivery to site of pump set sensor termination cubicles	E	Each	20		
	EMCA 18.2 (i)	Supply and delivery to site of HPDE heavy-duty cable sleeves, joints, sealing rings, couplings, end plugs, spacer modules, bell mounth, manderel, duct brush flexibend, stainless steel draw wire long bend as per the particular specification					
E13.2.83		110mm ² HDPE Sleeves equal or similar to kabelflex	E	m	250		
E13.2.84		160mm ² HDPE Sleeves equal or similar to kabelflex	E	m	150		
	EMCA 18.2 (j)	Equal or similar CCG with solid cover IP68 including non sparking connectors, insulating sleeves, identification tag, mounting screws, locknuts, lockout device with lock, lid securing chain and all accessories					
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.2.85		Box 0	E	Each	11		
E13.2.86		Compression Kits (Small)	E	Each	44		
E13.2.87		Compression Kits (large)	E	Each	44		
E13.2.88		Blanking Plugs	E	Each	22		
E13.2.89		Box 1	E	Each	10		
E13.2.90		Reducing Glands [25-20]	E	Each	20		
E13.2.91		Compression Kits (Small)	E	Each	20		
E13.2.92		Compression Kits (large)	E	Each	20		
E13.2.93		Blanking Plugs	E	Each	20		
E13.2.94		Box 2	E	Each	6		
E13.2.95		Reducing Glands [32-20]	E	Each	12		
E13.2.96		Reducing Glands [32-25]	E	Each	12		
E13.2.97		Compression Kits	E	Each	12		
E13.2.98		Blanking Plugs	E	Each	12		
E13.2.99		Box 3	E	Each	6		
E13.2.100		Reducing Glands [40-20]	E	Each	12		
E13.2.101		Reducing Glands [40-25]	E	Each	12		
E13.2.102		Reducing Glands [40-32]	E	Each	12		
E13.2.103		Compression Kits	E	Each	12		
E13.2.104		Blanking Plugs	E	Each	12		
E13.2.105		Box 4	E	Each	6		
E13.2.106		Reducing Glands [50-20]	E	Each	12		
E13.2.107		Reducing Glands [50-25]	E	Each	12		
E13.2.108		Reducing Glands [50-32]	E	Each	12		
E13.2.109		Reducing Glands [50-40]	E	Each	24		
E13.2.110		Compression Kits	E	Each	12		
E13.2.111		Blanking Plugs	E	Each	12		
	EMCA 18.2 (k)	Hot dipped galvanised conduit with saddles, fasteners,surface mounted against brick or concrete every 500mm and all accessories					
E13.2.112		20mm Conduit	E	m	681		
E13.2.113		20mm conduit saddles	E	Each	350		
E13.2.114		Solid Coupling Female Threaded Adaptor	E	Each	350		
E13.2.115		Round Conduit box plus cover	E	Each	100		
	EMCA 18.2 (l)	Supply and delivery to site of all soil for the bedding of cables during excavations including cleaning of cable routes complete as per particular specification					
E13.2.116			E	m³	235		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3	EMCA 18.3	<u>SCHEDULE E13.3 - INSTALLATION</u>					
	EMCA 18.3 (a)	Installation of all multicore cables and earthwires and cable name tags for the following cables as per the particular:					
E13.3.1		120mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	I	m	335		
E13.3.2		70mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	I	m	20		
E13.3.3		240mm ² 4C PVC SWA PVC Cu Cable	I	m	280		
E13.3.4		185mm ² 4C PVC SWA PVC Cu Cable	I	m	580		
E13.3.5		150mm ² 4C PVC SWA PVC Cu Cable	I	m	300		
E13.3.6		95mm ² 4C PVC SWA PVC Cu Cable	I	m	200		
E13.3.7		70mm ² 4C PVC SWA PVC Cu Cable	I	m	160		
E13.3.8		50mm ² 4C PVC SWA PVC Cu Cable	I	m	260		
E13.3.9		35mm ² 4C PVC SWA PVC Cu Cable	I	m	275		
E13.3.10		25mm ² 4C PVC SWA PVC Cu Cable	I	m	286		
E13.3.11		16mm ² 4C PVC SWA PVC Cu Cable	I	m	1870		
E13.3.12		10mm ² 4C PVC SWA PVC Cu Cable	I	m	540		
E13.3.13		6mm ² 4C PVC SWA PVC Cu Cable	I	m	850		
E13.3.14		4mm ² 4C PVC SWA PVC Cu Cable	I	m	850		
E13.3.15		2.5mm ² 4C PVC SWA PVC Cu Cable	I	m	5979		
E13.3.16		2.5mm ² 3C PVC SWA PVC Cu Cable	I	m	2180		
E13.3.17		1.5mm ² 3C PVC SWA PVC Cu Cable	I	m	2945		
E13.3.18		1.5mm ² 4C PVC SWA PVC Cu Cable	I	m	200		
E13.3.19		95mm ² Bare Copper Conductor	I	m	335		
E13.3.20		70mm ² Bare Copper Conductor	I	m	940		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.21		35mm ² Bare Copper Conductor	I	m	260		
E13.3.22		25mm ² Bare Copper Conductor	I	m	80		
E13.3.23		16mm ² Bare Copper Conductor	I	m	286		
E13.3.24		10mm ² Bare Copper Conductor	I	m	1624		
E13.3.25		6mm ² Bare Copper Conductor	I	m	330		
E13.3.26		4C PVC CST PVC Heavy Duty Fibre Optic Cable Singlemode	I	m	1960		
E13.3.27		1mm ² x 1pr twisted PVC SWA PVC (individually and overall screened)	I	m	2081		
E13.3.28		1mm ² x 2pr twisted PVC SWA PVC (individually and overall screened)	I	m	1860		
E13.3.29		1mm ² x 4pr twisted PVC SWA PVC (individually and overall screened)	I	m	9620		
E13.3.30		1mm ² x 6pr twisted PVC SWA PVC (individually and overall screened)	I	m	328		
E13.3.31		1mm ² x 8pr twisted PVC SWA PVC (individually and overall screened)	I	m	470		
E13.3.32		4pr twisted PVC, Non-Woven Tape + alu Foil (Industrial CAT6)	I	m	1060		
	EMCA 18.3 (b)	Installation of all multicore cables and earthwires termination materials [equal or similar to Enviro Glands, neoprene shrouds, lugs, insulating, materials, cable ties and corrosion proof bolts, washers, spring washers, nuts, etc] to terminate the following cables as per the particular specification					
E13.3.33		120mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	I	Each	6		
E13.3.34		70mm ² 3C 12.7kV/22kV XLPE PVC SWA PVC Cable	I	Each	4		
E13.3.35		240mm ² 4C PVC SWA PVC Cu Cable	I	Each	28		
E13.3.36		185mm ² 4C PVC SWA PVC Cu Cable	I	Each	40		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.37		150mm ² 4C PVC SWA PVC Cu Cable	I	Each	12		
E13.3.38		95mm ² 4C PVC SWA PVC Cu Cable	I	Each	8		
E13.3.39		70mm ² 4C PVC SWA PVC Cu Cable	I	Each	4		
E13.3.40		50mm ² 4C PVC SWA PVC Cu Cable	I	Each	6		
E13.3.41		35mm ² 4C PVC SWA PVC Cu Cable	I	Each	8		
E13.3.42		25mm ² 4C PVC SWA PVC Cu Cable	I	Each	6		
E13.3.43		16mm ² 4C PVC SWA PVC Cu Cable	I	Each	52		
E13.3.44		10mm ² 4C PVC SWA PVC Cu Cable	I	Each	24		
E13.3.45		6mm ² 4C PVC SWA PVC Cu Cable	I	Each	46		
E13.3.46		4mm ² 4C PVC SWA PVC Cu Cable	I	Each	28		
E13.3.47		2.5mm ² 4C PVC SWA PVC Cu Cable	I	Each	424		
E13.3.48		2.5mm ² 3C PVC SWA PVC Cu Cable	I	Each	110		
E13.3.49		1.5mm ² 3C PVC SWA PVC Cu Cable	I	Each	158		
E13.3.50		1.5mm ² 4C PVC SWA PVC Cu Cable	I	Each	20		
E13.3.51		95mm ² Bare Copper Conductor	I	Each	6		
E13.3.52		70mm ² Bare Copper Conductor	I	Each	72		
E13.3.53		35mm ² Bare Copper Conductor	I	Each	6		
E13.3.54		25mm ² Bare Copper Conductor	I	Each	2		
E13.3.55		16mm ² Bare Copper Conductor	I	Each	6		
E13.3.56		10mm ² Bare Copper Conductor	I	Each	76		
E13.3.57		6mm ² Bare Copper Conductor	I	Each	26		
E13.3.58		4C PVC CST PVC Heavy Duty Fibre Optic Cable Singlemode	I	Each	44		
E13.3.59		1mm ² x 1pr twisted PVC SWA PVC (individually and overall screened)	I	Each	902		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.60		1mm ² x 2pr twisted PVC SWA PVC (individually and overall screened)	I	Each	94		
E13.3.61		1mm ² x 4pr twisted PVC SWA PVC (individually and overall screened)	I	Each	638		
E13.3.62		1mm ² x 6pr twisted PVC SWA PVC (individually and overall screened)	I	Each	40		
E13.3.63		1mm ² x 8pr twisted PVC SWA PVC (individually and overall screened)	I	Each	20		
E13.3.64		4pr twisted PVC, Non-Woven Tape + alu Foil (Industrial CAT6)	I	Each	62		
E13.3.65	EMCA 18.3 (c)	Installation of all cable route markers	I	Each	166		
E13.3.66	EMCA 18.3 (d)	Installation of all concrete cable slabs	I	Each	80		
	EMCA 18.3 (e)	Installation of all hot dipped galvanised heavy-duty cable ladder, trunking, welded wire mesh and accessories including all necessary supports, clamps strapping, brackets, reducer splice, hangers, threaded rods, trunking, bolts, nuts and anchor bolts etc as per the particular specification					
E13.3.67		150mm Wide cable ladder	I	m	165		
E13.3.68		200mm Wide cable ladder	I	m	86		
E13.3.69		300mm Wide cable ladder	I	m	53		
E13.3.70		400mm Wide cable ladder	I	m	8		
E13.3.71		500mm Wide cable ladder	I	m	13		
E13.3.72		600mm Wide cable ladder	I	m	22		
E13.3.73		800mm Wide cable ladder	I	m	93		
E13.3.74		150mm Wide cable ladder flat covers	I	m	17		
E13.3.75		200mm Wide cable ladder flat covers	I	m	9		
E13.3.76		300mm Wide cable ladder flat covers	I	m	6		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.77		400mm Wide cable ladder flat covers	I	m	1		
E13.3.78		500mm Wide cable ladder flat covers	I	m	2		
E13.3.79		600mm Wide cable ladder flat covers	I	m	3		
E13.3.80		800mm Wide cable ladder flat covers	I	m	10		
E13.3.81	EMCA 18.3 (g)	Installation of all hot dipped galvanised heavy-duty cable ladder supports, bolts, holders and etc that is required as per the particular specification	I	Sum	-		
E13.3.82	EMCA 18.3 (h)	Installation of all pump set sensor termination cubicles	I	Each	20		
	EMCA 18.3 (i)	Installation of all HPDE heavy-duty cable sleeves, joints, sealing rings, couplings, end plugs, spacer modules, bell mounth, manderel, duct brush flexibend, stainless steel draw wire long bend as per the particular specification					
E13.3.83		110mm ² HDPE Sleeves equal or similar to kabelflex	I	m	250		
E13.3.84		160mm ² HDPE Sleeves equal or similar to kabelflex	I	m	150		
	EMCA 18.3 (j)	Installation of all Equal or similar CCG with solid cover IP68 including non sparking connectors, insulating sleeves, identification tag, mounting screws, locknuts, lockout device with lock, lid securing chain and all accessories					
E13.3.85		Box 0	I	Each	11		
E13.3.86		Compression Kits (Small)	I	Each	44		
E13.3.87		Compression Kits (large)	I	Each	44		
E13.3.88		Blanking Plugs	I	Each	22		
E13.3.89		Box 1	I	Each	10		
E13.3.90		Reducing Glands [25-20]	I	Each	20		
E13.3.91		Compression Kits (Small)	I	Each	20		
E13.3.92		Compression Kits (large)	I	Each	20		
E13.3.93		Blanking Plugs	I	Each	20		
E13.3.94		Box 2	I	Each	6		
E13.3.95		Reducing Glands [32-20]	I	Each	12		
E13.3.96		Reducing Glands [32-25]	I	Each	12		
E13.3.97		Compression Kits	I	Each	12		
E13.3.98		Blanking Plugs	I	Each	12		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.99		Box 3	I	Each	6		
E13.3.100		Reducing Glands [40-20]	I	Each	12		
E13.3.101		Reducing Glands [40-25]	I	Each	12		
E13.3.102		Reducing Glands [40-32]	I	Each	12		
E13.3.103		Compression Kits	I	Each	12		
E13.3.104		Blanking Plugs	I	Each	12		
E13.3.105		Box 4	I	Each	6		
E13.3.106		Reducing Glands [50-20]	I	Each	12		
E13.3.107		Reducing Glands [50-25]	I	Each	12		
E13.3.108		Reducing Glands [50-32]	I	Each	12		
E13.3.109		Reducing Glands [50-40]	I	Each	24		
E13.3.110		Compression Kits	I	Each	12		
E13.3.111		Blanking Plugs	I	Each	12		
	EMCA 18.3 (k)	Installation of all hot dipped galvanised with saddles, fasteners, surface mounted against brick or concrete every 500mm and all accessories					
E13.3.112		20mm Conduit	I	m	681		
E13.3.113		20mm conduit saddles	I	Each	350		
E13.3.114		Solid Coupling Female Threaded Adaptor	I	Each	350		
E13.3.115		Round Conduit box plus cover	I	Each	100		
	EMCA 18.3 (l)	Installation of all soil for the bedding of cables during excavations including cleaning of cable routes complete as per particular specification					
E13.3.116			I	m³	235		
	EMCA 18.3 (m)	Excavating, back filling, consolidation, importation of soil and dumping of all rock and stone removed during excavations including cleaning of cable routes all according to particular specifications (including hand excavations where necessary along existing cable routes)					
E13.3.117		a) Pickable soil	I	m³	295		
E13.3.118		b) Soft rock	I	m³	100		
E13.3.119		c) Hard rock	I	m³	135		
		Dumping and removing of all rock and stone removed during excavations including cleaning of cable routes complete as per particular specification.					
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Pay. Ref.	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E13.3.120		Dumping will at a registered dumping site within the border of Municipal Area. Contractor to allow dumping within a vicinity of 30km the site	I	m³	235		
E13.3.121		Contractor to allow all labour, truck hire and dumping site payments					
E13.3.121		Sifting soil through a 4mm mesh size for the bedding of cables and the backfilling of trenches complete as per particular specification.	I	m³	295		
E13.3.122		Nett amount for core drilling 100mm diameter holes through 250mm concrete	I	Each	26		
E13.4	EMCA	SCHEDULE E13.4 - COMMISSIONING					
	18.4						
E13.4.1	EMCA 18.4 (a)	Testing and commissioning of all cables as above mentioned	I	Sum	-		
E13.4.2	EMCA 18.4 (b)	Updating, verifying and submission of Electronic Cable schedules with Tag numbers and final agreed lengths	I	Sum	-		
E13.4.3	EMCA 18.4 (c)	Surveyor to mark-up as-built cable route plans and all mark-up must be on made on the AutoCAD format	I	Sum	-		
SCHEDULE NO. E13 MULTICORE CABLES & EARTH WIRES CARRIED TO SUMMARY							
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E14	ESLS	<u>SCHEDULE NO. E14</u> <u>SITE LIGHTING</u>					
E14.1	GEN	<u>SCHEDULE E14.1 - DESIGN, DRAWINGS AND GENERAL</u>					
E14.1.1	PSGEN B	Provide all design drawings and wiring diagrams	G	Sum	-		
E14.1.2	PSGEN B	Provide operating all maintenance manuals and "as-built" drawings	G	Sum	-		
E14.2	ESLS	<u>SCHEDULE E14.2 - SUPPLY AND DELIVERY TO SITE</u>					
	5.1						
E14.2.1	ESLS 5.1 (a)	Supply and delivery to site of complete mast (refer to project specification PSESLS-2)	E	No.	10		
E14.3	ESLS	<u>SCHEDULE E14.3 - INSTALLATION</u>					
	5.2						
E14.3.1	ESLS 5.2 (a)	Installation of complete mast (refer to project specification PSESLS-2)	I	No.	10		
E14.4	ESLS	<u>SCHEDULE E14.4 - COMMISSIONING</u>					
	5.3						
E14.4.1	ESLS 5.3 (a)	Commissioning of complete mast (refer to project specification PSESLS-2)	I	No.	10		-
		SCHEDULE NO. E14 SITE LIGHTING CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
E15	ESGS	<u>SCHEDULE NO.E15</u> <u>STANDBY GENERATOR SYSTEM</u>					
E15.1	ESGS	<u>SCHEDULE E15.1 - DESIGN, DRAWINGS AND GENERAL</u>					
	17						
E15.1.1	PSGEN B	Provide general layout drawings and wiring diagrams for approval [Refer to particular specification]	G	Sum	-		
E15.1.2	PSGEN B	Provide operating and maintenance manuals, data sheets of all equipment and "as built" drawings	G	Sum	-		
E15.2	ESGS	<u>SCHEDULE E15.2 - SUPPLY AND DELIVERY TO SITE</u>					
	17.1						
E15.2.1	ESGS 17.1 (a)	Supply and delivery to site of complete Standby generator set as specified with suitable alternator (refer to project specification PSESGS)	E	Sum	-		
E15.2.2	ESGS 17.1 (b)	Supply and delivery to site of complete automatic mains failure Start-up system as specified (refer to project specification PSESGS)	E	Sum	-		
E15.2.3	ESGS 17.1 (c)	Supply and delivery to site of complete automatic change over system as specified (refer to project specification PSESGS)	E	Sum	-		
E15.2.4	ESGS 17.1 (d)	Supply and delivery to site of complete container enclosure as specified (refer to project specification PSESGS)	E	Sum	-		
E15.2.5	ESGS 17.1 (e)	Supply and delivery to site of complete fuel tank complete with mounting frame (refer to project specification PSESGS)	E	Sum	-		
E15.3	ESGS	<u>SCHEDULE E15.3 - INSTALLATION</u>					
	17.2						
E15.3.1	ESGS 17.2 (a)	Installation of complete Standby generator set as specified suitable alternator (refer to project specification PSESGS)	I	Sum	-		
E15.3.2	ESGS 17.2 (b)	Installation of complete automatic mains failure Start-up system as specified (refer to project specification PSESGS)	I	Sum	-		
E15.3.3	ESGS 17.2 (c)	Installation of complete automatic change over system as specified (refer to project specification PSESGS)	I	Sum	-		
Carried Forward							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	CPA Code	Unit	Qty	Rate (R)	Amount (R)
Brought Forward							
E15.3.4	ESGS 17.2 (d)	Installation of complete container enclosure as specified (refer to project specification PSESGS)	I	Sum	-		
E15.3.5	ESGS 17.2 (e)	Installation of complete fuel tank complete with mounting frame (refer to project specification PSESGS)	I	Sum	-		
E15.4	ESGS 17.3	<u>SCHEDULE E15.4 - COMMISSIONING</u>					
E15.4.1	ESGS 17.3 (a)	Commissioning of complete Standby generator set as specified with suitable alternator (refer to project specification PSESGS)	I	Sum	-		
E15.4.2	ESGS 17.3 (b)	Commissioning of complete automatic mains failure Start-up system as specified (refer to project specification PSESGS)	I	Sum	-		
E15.4.3	ESGS 17.3 (c)	Commissioning of complete automatic change over system as specified (refer to project specification PSESGS)	I	Sum	-		
E15.4.4	ESGS 17.3 (d)	Commissioning of complete container enclosure as specified (refer to project specification PSESGS)	I	Sum	-		
E15.4.5	ESGS 17.3 (e)	Commissioning of complete fuel tank complete with mounting frame (refer to project specification PSESGS)	I	Sum	-		
		SCHEDULE NO. E15 STANDBY GENERATOR SYSTEM CARRIED TO SUMMARY					
Total							

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C3		<u>SCHEDULE C3: EARTHWORKS AND PIPELINES</u>				
C3.1	SANS 1200 D	<u>SCHEDULE C3.1 - EARTHWORKS</u>				
C3.1.1	8.3.1.2	<u>Remove topsoil to nominal depth of 150 mm and stockpile</u>				
		iv) Filtrate Sump	m ²	45		
C3.1.2	8.3.2	<u>Bulk excavation</u>				
		a) Excavation in all materials and use for backfill or embankment or dispose, as ordered within a freehaul distance of 0,5 km				
		viii) Filtrate Sump	m ³	212		
		b) Extra-over 8.3.2 a) for:				
		i) Hard rock excavation (Provisional Item)				
		.5 Filtrate Sump	m ³	106		
C3.1.3	8.3.3	<u>Restricted excavation</u>				
		a) Excavate in all materials and use for backfill, embankments or dispose				
		i) Filtrate Sump	m ³	5		
		ii) Chambers on Site	m ³	280		
		b) <u>Extra-over 8.3.3 a) for:</u>				
		i) Hard rock excavation				
		.1 Chambers on Site	m ³	140		
C3.1.4		Overbreak in rock foundation removal of loose material and building up area with class 15/19 mass concrete up to 200mm. Deeper 200mm to be at contractors cost				
		.3 Filtrate sump	m ²	38		
C3.1.5		Soilcrete for backfill of excavation where ordered by Engineer or shown on the drawing with 5% cement (OPC) (PROVISIONAL ITEM)				
		i) Filtrate Sump	m ³	20		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.1.6	8.3.8	<u>Existing services</u>				
	8.3.8.1	c) Excavate by hand in soft material to expose existing services	m ³	50		
C3.1.7	8.3.8.2.	<u>Dealing with services that are at risk because of the construction of earthworks</u>				
		a) Cables	no	4		
C3.1.8	8.3.9	<u>Topsoiling</u>				
		From stock, hauling and spreading over site				
		i) Horizontal areas	m ²	900		
		Note: accurate position to be determined on site by Engineer.				
C3.1.9	8.3.10	Grassing with Kikuyu roots on horizontal or nearly horizontal surfaces				
		i) Kikuyu	m ²	900		
C3.1.10		Allow for rejuvenation, fertilizer and planting of indigenous drought resistant plants	sum	1		
C3.2	SANS 1200 DB PSDB	<u>SCHEDULE 3.2 - EARTHWORKS (Pipe trenches)</u>				
C3.2.1	8.3.2	<u>Excavate in all material for trenches, backfill, compact and dispose of surplus material</u>				
		Pipe diameter 100 dia up to 500 nom dia with 300 mm side allowance each side including 500 nom dia. 600 nom dia and larger side allowance 500 mm each side.				
		i) 0,00 m - 1,00 m depth	m ³	0		
		ii) 1,01 m - 1,50 m depth	m ³	188		
		iii) 1,51 m - 2,00 m depth	m ³	537		
		iv) 2,01 m - 2,50 m depth	m ³	161		
		v) 2,51 m - 3,00 m depth	m ³	107		
		vi) 3,01 m - 3,50 m depth	m ³	54		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.2.2		vii) 3,51 m - 4,00 m depth	m³	0		
		viii) 4,01 m - 4,50 m depth	m³	0		
		Water network for 25 mm dia to 90 mm dia pipes, trench width 0.60 m and max depth 0.8 m				
C3.2.3		i) 0,00 m - 0,80 m depth	m³	54		
		Extra-over 3.2.1 & 3.2.2 for:				
C3.2.4	8.3.5	i) Hard rock excavation	m³	644		
		Existing services that intersect or adjoin a pipe trench				
C3.2.5	8.3.5.1	Services that intersect a trench				
		.1 Water pipes				
		.1 varying sizes	no	8		
C3,3	SANS 1200 LB	SCHEDULE 3.3 - BEDDING (Pipes)				
C3.3.1	8.2.1	Provision of bedding from trench excavation for flexible pipes				
		a) Selected granular material	m³	20		
		b) Selected fill material	m³	20		
C3.3.2	8.2.2	Supply of bedding by importation				
		a) Selected granular material	m³	304		
		b) Selected fill material	m³	135		
C3.3.3	8.2.4	Class 20/19 concrete for pipe thrust blocks				
		i) pipe thrust blocks	m³	12		
		ii) encasing of pipes	m³	10		
C3,4	SANS 1200 L, PSL	SCHEDULE 3.4 - MEDIUM - PRESSURE PIPELINE				
	8.2.1	Supply, lay and bed pipes complete with couplings				
C3.4.1		uPVC Pipelines, Class 9				
		i) 110 mm dia	m	35		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.4.2		ii) 160 mm dia	m	70		
		iii) 200 mm dia	m	45		
		<u>uPVC pipeline, Class 6 for electric cable sleeves, including draw wires</u>				
C3.4.3		i) 110 mm dia	m	40		
		ii) 160 mm dia	m	64		
		<u>Hot dip galvanized steel pipes</u>				
C3.4.4		i) 150mm dia medium class screwed and socketed steel pipes to SANS 62 (PROVISIONAL ITEM)	m	65		
		ii) 200mm dia medium class screwed and socketed steel pipes to SANS 62 (PROVISIONAL ITEM)	m	65		
		<u>Type 4 HDPE, Class 12 pipes for water reticulation. Rate to include for all bends, cut lengths, couplings, tees reducers, etc.</u>				
		i) 50 mm dia	m	130		
		ii) 40 mm dia	m	40		
		iii) 25 mm dia	m	50		
C3.4.5	8.2.2	<u>Supply and bedding of specials complete with couplings</u>				
		<u>uPVC bends</u>				
		i) 110 mm dia x 45° uPVC	no	1		
		ii) 160 mm dia x 90° uPVC	no	3		
		iii) 160 mm dia x 45° uPVC	no	6		
		iv) 160 mm dia x 22,5° uPVC	no	1		
		v) 200 mm dia x 90° uPVC	no	4		
		vi) 200 mm dia x 45° uPVC	no	1		
		vii) 200 mm dia x 22,5° uPVC	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.4.6		<u>Galvanized steel bends</u>				
		i) 150 mm dia x 45° galvanized steel	no	6		
		ii) 200 mm dia x 45° galvanized steel	no	6		
		iii) 200 mm dia x 90° galvanized steel	no	2		
C3.4.7		<u>Saddles</u>				
		i) 75 mm dia with 50 mm dia drilling on uPVC pipe	no	1		
C3.4.8		<u>Couplings</u>				
		i) Stepped coupling 150 mm dia GS to 160mm dia uPVC	no	2		
C3.4.9		Stand pipe with tap garden hose connection clamped to concrete or brick wall or fixed on to MS iron dropper, complete as shown on dwg. 1890.08.AA.14.D001	no	3		
C3.4.10		<u>Stop cock chamber complete as shown on drawing 1890.08.AA.14.D001</u>				
		i) for 40mm dia. Bronze globe valve	no	1		
C3.4.11		<u>Hose reel installation</u>				
		Approved fire hose reel from Centurion or similar and approved. Complete with union, isolating valve with hand wheel, 25 mm diam pipe from Dunlop, length 25 m mounted on panel against steel column, ref drg. 1890.08.AA.14.D001				
		i) RGS Filters	no	1		
		ii) Dewatering building	no	1		
	8.2.4	Extra over item 8.2.1 for the straight cutting of the pipe preparing ends and repairing of protection and the supplying and fixing of the extra coupling if required.				
C3.4.12		<u>uPVC pipes, Class 9</u>				
		i) 110 mm dia	no	1		
		ii) 160 mm dia	no	8		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.4.13		iii) 200 mm dia <u>Galvanized steel pipes</u>	no	7		
		i) 150 mm dia medium class	no	6		
		ii) 200 mm dia medium class	no	8		
C3.4.14	8.2.11	Soilcrete backfill with 5% OPC for pipelines where vehicle traffic is expected. Top 500 mm of trench at positions to be determined by Engineer on site.	m ³	20		
C3.4.15		<u>MISCELLANEOUS</u>				
		<u>FILTRATE PIPE TO INLET WORKS</u>				
		i) 150 mm dia screwed and socketed steel pipe in accordance to SANS 62, medium Class from uPVC Filtrate sump pipe, vertical against existing Inlet works concrete wall. Total length of vertical pipe ±5,0m. Rate to include for 3 NO 90° GS bends, cutting of pipe and 2 NO hot dip galvanized pipe clamps bolted to concrete wall.	no	1		
		<u>GAC FILTERS</u>				
		iii) Cut 600mm dia steel pipe after construction of chamber at both sides of chamber, remove cut length and repair protection. Ref. drg. 1890.08.FB.14.D006 and FB.14.X004	no	1		
		<u>INTER CONNECTING PIPE WORK</u>				
		iv) cut existing 400mm dia wash water steel pipe to suit T-piece measured under item SP1.9 and repair pipe ends	no	1		
		v) Cut existing galvanized 150mm dia steel air pipe to suit T-Piece measured under item SP 1.10 and repair pipe ends	no	1		
		note: earthworks measured elsewhere				
C3,5	SANS 1200 LE	<u>SCHEDULE 3.5 - STORMWATER DRAINAGE</u>				
C3.5.1	8.2.1	<u>Supply, lay and bed concrete interlocking joint pipes in accordance to SANS 677 (spigot and socket)</u>				
		i) 525 mm dia, Class 50 D	m	52		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.5.2	8.2.4	ii) 525 mm dia, Class 75 D <u>Extra over item 8.2.1 for cutting the end units for culverts on site</u>	m	20		
C3.5.3	8.2.8	a) Straight cut i) 525mm dia Construct Stormwater Outlet structure complete as shown on drg. 1890.08.AA.14.D001	no	6		
C3.6 SCHEDULE 3.6 - DEMOLITIONS AND ANCILLARY WORK						
	SANS 1200 C	<u>SITE CLEARANCE WORK</u>				
C3.6.1	8.2.8	Demolish and remove reinforced structures and dismantle steel work, etc. and spoil debris at a spoil site established by the Contractor. <u>Screw Pump Station and O₂ shaft</u>				
		.1 Chamber and pump base walls	m ³	8		
		.2 Screw shaft and stairs	m ³	32		
		.3 Handrail and cat ladder	m	20		
		.4 Grating above screw wall	sum	1		
		.5 Removal of screws, mortar and baseplate and handing over to client	sum	1		
C3.6.2		<u>GAC Filters</u> ref. drg. 1890.08.FB.14.A001, FB.14.D001 to FB.14.D004 and FB.14.X001				
C3.6.2.1		Break out openings in reinforced concrete structure (filters) and repair to nett opening with standard non shrink grout. Rate to include for removal of all debris to a spoil site established by the contractor				
		.1 450mm x 1250mm in 300mm thick reinforced concrete wall	no	1		
		.2 650mm x 650mm in 300mm thick reinforced concrete wall	no	6		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C3.6.2.2		.3 600mm x 600mm in 300mm thick reinforced concrete wall <u>Existing brickwork</u>	no	1		
C3.6.3		.2 Break out 2100 x 900 opening in existing 300mm cavity brickwall to suit new doors, including closing cavity in cavity brick wall with facebrick (Exterior) and plaster and paint (interior) to match existing and spoil debris at a spoil site established by the Contractor	No	1		
C3.6.3.1		<u>SLUDGE SUMP</u> <u>ref. drg. 1890.08.QF.14.D001</u>				
		<u>Break out openings in reinforced concrete walls and repair to nett opening with standard non shrink grout.</u>				
		.1 2,00m x 1,55m opening in 350mm thick reinforced concrete wall.	no	1		
		.2 Cut off 315 Ø uPVC pipe in 350mm thick reinforced concrete wall and increase opening size to suit 525mm dia. concrete pipe	no	1		
C3.6.4		<u>Clearwater Tank and Pump Station</u> <u>ref. drg. 1890.08.GA.14.D001</u>				
		Break out openings in reinforced concrete structure and repair to nett opening with standard non shrink grout				
		.1 2900 x 1200mm opening in 300mm thick reinforced wall	no	2		
SCHEDULE NO: C3 EARTHWORKS AND PIPELINES						
Total						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C4	1200 G PSG	<u>SCHEDULE C4: CONCRETE WORK</u> <u>CONCRETE (STRUCTURAL)</u>				
C4,2		<u>SCHEDULE C4.2 - DAF TANKS</u>				
		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
C4.2.1		.01 <u>300mm thick concrete wall</u>				
		.01 450mm x 450mm opening	no	4		
		.02 500mm x 500mm opening	no	4		
C4.2.2		<u>STERILISATION AND TESTING</u>				
		<u>Testing for watertightness</u>				
		i) DAF tank	sum	1		
		ii) Flocculation channels	sum	1		
C4,3		<u>SCHEDULE C4.3 RAPID GRAVITY SAND FILTERS</u> <u>CONCRETE (STRUCTURAL)</u>				
	SANS 1200 G	<u>SUNDRY ITEMS</u>				
C4.3.1	8.5.2	<u>1:4 Cement riversand screeds to floors</u>				
		.1 10mm Cement screed laid on concrete including steel floated surface finish	m ²	380		
	SANS 1200 LC	<u>CABLE DUCTS</u>				
C4.3.2		<u>EXCAVATION AND BACKFILLING</u>				
	8.2.2	(a) Excavate in all materials, backfill and compact to 90% mod AASHTO density, and dispose of surplus and unsuitable materials within the freehaul distance for trenches				
	8.2.2	.1 Up to 1m wide				
		.2 Over 1m and up to 2m deep	m ³	115		
	8.2.2	(b) Extra over items 8.2.2 (a) for				
		.2 Hard rock excavation	m ³	46		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
	1200 LB	<u>BEDDING (PIPES)</u>				
		<u>BEDDING FROM TRENCH EXCAVATIONS</u>				
C4.3.3	8.2.1	Provision of bedding material from trench excavations				
		(b) Selected fill material	m³	20		
		<u>BEDDING BY IMPORTATION</u>				
C4.3.4	8.2.2	.1 Provision of bedding material by importation from other necessary excavations within the freehaul distance				
		(b) Selected fill material	m³	45		
C4.3.5		<u>GROUTING IN OF PIPES WITH NON SHRINK CROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
		.01 <u>200mm thick concrete wall</u>				
		.01 250 mm x 250 mm opening	no	8		
		.02 500 mm x 500 mm opening	no	8		
		.03 700 mm x 700 mm opeing	no	1		
		.02 <u>250mm thick concrete wall</u>				
		.01 500 mm x 500 mm opening	no	1		
		.03 <u>300mm thick concrete wall</u>				
		01 850mm x 850 mm opening	no	3		
		.04 <u>400mm thick concete wall</u>				
		.01 300mm x 300 mm opening	no	8		
		.02 700 mm x 700 mm opeing	no	4		
		.03 750 mm x 750 mm opeing	no	8		
C4.3.6		<u>STERILISATION AND TESTING</u>				
		<u>Testing for watertightness</u>				
		i) Filters	no	4		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4,4		SCHEDULE C4.4 - OZONE CONTACT TANK AND LOW LIFT PUMP STATION				
		<u>ROUGH FORMWORK</u>				
C4.4.1	8.2.1	(b) <u>Plane vertical</u>				
		.2 Sides of column base	m ²	4		
		.4 Column	m ²	10		
		<u>REINFORCEMENT</u>				
C4.4.2		<u>Steel bars</u>				
	8.3.1	(b) <u>High tensile steel</u>				
		.1 All sizes	ton	0.42		
		<u>CONCRETE</u>				
C4.4.3	8.4.3	(d) <u>Strength concrete 35Mpa/19mm</u>				
		.4 Plinth column	m ³	1.2		
		.5 Column Base	m ³	1.2		
		<u>MISCELLANEOUS ITEMS</u>				
C4.4.4		G7 Granular material compacted to 93% MOD AASHTO, within restricted areas	m ³	40		
C4.4.5		Soilcrete (5% OPC)	m ³	15		
		<u>STERILIZATION AND TESTING</u>				
C4.4.6		<u>Testing for water tightness</u>				
		i) Low lift pump station	sum	1		
		ii) Ozone contact tank	sum	1		
C4,5		SCHEDULE C4.5 - GAC FILTERS				
		<u>CONCRETE</u>				
C4.5.1	8.4.3	(b) <u>Strength concrete 20Mpa/19mm</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.5.2	8.4.3	.1 Steel float benching to floors (Including finish)	m³	19		
		(c) <u>Strength concrete 30Mpa/12mm</u>				
		.1 Concrete infill around piping	m³	18		
		<u>EXPANSION JOINTS</u>				
C4.5.3	8.5	(d) <u>Saw cut joints</u>				
		1. Saw cut joints 100mm deep	m	10		
C4.5.4		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
		.1 <u>200mm thick concrete wall</u>				
		.1 50mm Diameter pipe	no	6		
		.2 200mm Diameter pipe	no	6		
		.2 <u>300mm thick concrete wall</u>				
		.1 200mm Diameter pipe	no	6		
		.2 400mm Diameter pipe	no	6		
		.3 450mm Diameter pipe	no	6		
		.4 600mm Diameter pipe	no	2		
		<u>MISCELLANEOUS ITEMS</u>				
C4.5.5		G7 Granular material compacted to 93% MOD AASHTO, within restricted areas	m³	5		
		<u>STERILIZATION AND TESTING</u>				
C4.5.6		<u>Testing for watertightness</u>				
		i) GAC filters	no	6		
		<u>SCREEDS</u>				
C4.5.7	8.33.0	<u>624/22 Quartz filled epoxy mortar flooring with pigment sealer (Manilla), or similar approved</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
		.1 5mm Thick to floors	m ²	21		
C4,6		<u>SCHEDULE C4.6 - CLEARWATER TANK</u>				
		<u>PRECAST CONCRETE</u>				
C4.6.1		Precast concrete units supplied and fixed complete including all reinforcing, etc Dwg 1890.08.GA.14.D002				
	8.6	(a) <u>Strength concrete 35Mpa/19mm</u>				
		.1 1300 x 1400 x 150mm thick cover slab complete, including placing on top of chamber, lifting hooks, casting in manhole covers, casting in of cast iron valve box, etc Manhole covers and valve boxes to be measured elsewhere.	no	2		
		Break out openings in reinforced concrete structure (clearwater tank) and repair to nett opening with standard non-shrink grout. Rate to include for removal of all debris to a spoil site established by the contractor				
		.1 1200mm x 2825mm in 300mm thick reinforced concrete wall	no	1		
		1200mm x 2975mm in 300mm thick reinforced concrete wall	no	1		
C4.6.2	SANS	<u>STERILIZATION AND TESTING</u>				
		<u>Sterilisation of Structures</u>				
		ii) Clearwater Tank	sum	1.00		
C4,7		<u>SCHEDULE C4.7 - SUMPS AND CHAMBERS</u>				
C4.7.1		<u>INLET WORKS (Emergency Overflow)</u>				
	SANS 1200G	<u>CONCRETE (STUCTURAL)</u>				
		<u>ROUGH FORMWORK</u>				
C4.7.1.1	8.2.1	(b) Plane vertical				
		.1 Sides of floor slabs	m ²	2		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.7.1.2	8.2.2	<u>SMOOTH FORMWORK</u> (b) Plane vertical .1 Sides of floor slabs .2 Walls	m ² m ²	2 13		
C4.7.1.3	8.2.5	<u>Smooth formwork to narrow widths</u> (a) Edges, risers, etc. not exceeding 300mm wide	m	5		
C4.7.1.4		<u>BOXING IN FOR HOLES AND VOIDS</u> (a) Large, circular, up to 1.0m diameter with depth .1 over 0m and up to 0.5m	no	1		
C4.7.1.5		<u>REINFORCEMENT</u> <u>Steel bars</u> (a) Mild steel .1 All sizes (b) High tensile steel .1 All sizes	ton ton	0.1 0.3		
C4.7.1.6	8.4.2	<u>STRENGTH CONCRETE</u> <u>Strength concrete 15Mpa / 19mm</u> (a) Blinding layer 50mm thick	m ³	0.25		
C4.7.1.7		(b) Strength concrete 35Mpa / 19mm .1 Floor slabs .2 Wall	m ³ m ³	1.5 1.5		
C4.7.1.8		<u>SURACE FINISHES</u> <u>Unformed surface finishes</u> (a) Wood floated finish				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
		.1 Floor slabs	m ²	5		
		(b) Steel floated finish				
		.1 Top of walls, beams, etc.	m ²	2		
		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATER TIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
C4.7.1.9		.01 200mm thick concrete wall				
		.02 600mm diameter pipe	no	1		
C4.7.2		<u>OZONE DESTRUCTION CHAMBER</u>				
		<u>SMOOTH FORMWORK</u>				
C4.7.2.1	8.2.1	(b) Plane vertical				
		.1 Sides of roof slabs	m ²	3.4		
C4.7.2.2		<u>SMOOTH FORMWORK</u>				
	8.2.2	(a) Plane horizontal				
		.1 suspended slabs	m ²	17.5		
		<u>REINFORCEMENT</u>				
C4.7.2.3		<u>Steel bars</u>				
	8.3.1	(b) <u>High tensile steel</u>				
		.1 All sizes	ton	0.6		
		<u>STRENGTH CONCRETE</u>				
		.3 Suspended slabs	m ³	3.5		
		<u>SURFACE FINISHES</u>				
C4.7.2.4		<u>Unformed surface finishes</u>				
C4.7.2.5	8.4.4	(b) <u>Steel floated finish</u>				
		.1 Roof slabs	m ²	17.5		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.7.2.6		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
		.01 250mm thick concrete wall				
		.02 600mm diameter pipe	no	2		
C4.7.3		<u>FILTRATE SUMP</u>				
		<u>ROUGH FORMWORK</u>				
C4.7.3.1	8.2.1	(b) <u>Plane vertical</u>				
		.1 Sides of floor slabs	m ²	7		
		.2 Walls	m ²	92		
C4.7.3.2	8.2.5	<u>Rough formwork to narrow widths</u>				
		(a) Edges, risers, etc. not exceeding 300mm wide	m	8		
C4.7.3.3		<u>SMOOTH FORMWORK</u>				
	8.2.2	(b) <u>Plane vertical</u>				
		.1 Sides of floor slabs	m ²	3.5		
		.2 Walls	m ²	79		
		.3 Pipe supports	m ²	2		
C4.7.3.4	8.2.5	<u>Smooth formwork to narrow widths</u>				
		(a) Edges, risers, etc. not exceeding 300mm wide	m	5		
		<u>BOXING IN FOR HOLES AND VOIDS</u>				
C4.7.3.5	8.2.6	(a) <u>Small, circular, up to 0.35m diameter with depth</u>				
		.1 over 0m and up to 0,5m	no	2		
		<u>REINFORCEMENT</u>				
C4.7.3.6		<u>Steel bars</u>				
	8.3.1	(a) <u>Mild steel</u>				
		.1 All sizes	ton	0.6		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.7.3.7	8.3.1	(b) <u>High tensile steel</u> .1 All sizes	ton	3.6		
	8.3.2	<u>High tensile welded mesh</u> (d) Ref no.395	m ²	8		
		<u>STRENGTH CONCRETE</u>				
C4.7.3.8	8.4.2	<u>Strength concrete 15Mpa/19mm</u> (a) Blinding layer 50mm thick	m ³	2		
C4.7.3.9	8.4.3	(a) <u>Strength concrete 20Mpa/19mm</u> .1 Benching including steel floating	m ³	9		
C4.7.3.10	8.4.3	(d) <u>Strength concrete 35Mpa/19mm</u> .1 Floor slabs .2 Walls	m ³ m ³	11 25		
		<u>SURFACE FINISHES</u>				
C4.7.3.11		<u>Unformed surface finishes</u> 8.4.4 (a) <u>Wood floated finish</u> .1 Floor slabs	m ²	11		
C4.7.3.12	8.4.4	(b) <u>Steel floated finish</u> .1 Floor slabs .2 Top of walls, beams, etc.	m ² m ²	5 5.5		
		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
		.01 <u>300mm thick concrete wall</u> .02 160mm diameter pipe .03 250mm diameter pipe	no no	1 1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.7.3.13		<u>SUNDRIES</u> <u>Soilcrete (5% OPC)</u>				
		(a) Backfilling behind walls	m ³	13		
C4.7.4		<u>CHAMBERS ON SITE</u>				
C4.7.4.1		<u>ROUGH FORMWORK</u>				
		(a) <u>Plane vertical</u>				
		.1 Sides of floor slabs	m ²	18		
		.2 Walls	m ²	135		
		<u>SMOOTH FORMWORK</u>				
C4.7.4.2		(a) <u>Plane horizontal</u>				
		.1 suspended slabs	m ²	7		
		(b) <u>Plane vertical</u>				
		.1 Walls	m ²	175		
C4.7.4.3	8.1.1.2	<u>Smooth formwork to chamfers, grooves, rebates, etc. exceeding 20x20mm in size</u>				
		(a) Rebate size 60mm wide x 60mm deep	m	1		
		(b) 175 x 175 mm chamfer	m	2		
C4.7.4.4		<u>BOXING IN FOR HOLES AND VOIDS</u>				
	8.2.6	(a) <u>Small, circular, up to 0,35m diameter with depth</u>				
		.1 over 0m and up to 0,5m	no	9		
		(b) Large, circular up to 1m diameter with depth				
		.1 over 0,5m and up to 1,0m	no	13		
		<u>REINFORCEMENT</u>				
C4.7.4.5		<u>Steel bars</u>				
	8.3.1	(a) <u>Mild steel</u>				
		.1 All sizes	ton	0.4		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
	8.3.1	(b) <u>High tensile steel</u>				
		.1 All sizes	ton	3.7		
		<u>STRENGTH CONCRETE</u>				
C4.7.4.6	8.4.2	<u>Strength concrete 15Mpa/19mm</u>				
		(a) Blinding layer 50mm thick	m³	1.5		
C4.7.4.7	8.4.3	(c) <u>Strength concrete 30Mpa/19mm</u>				
		.1 Floor slabs	m³	16		
		.4 Walls	m³	21		
		.5 Thrust blocks	m³	0.1		
C4.7.4.8	8.4.3	(e) <u>Strength concrete 20Mpa/13mm</u>				
		.1 Benching including steel floated surface	m³	0.5		
		<u>SURFACE FINISHES</u>				
C4.7.4.9		<u>Unformed surface finishes</u>				
	8.4.4	(a) <u>Wood floated finish</u>				
		.2 Floor slabs	m²	21		
		(b) <u>Steel floated finish</u>				
		.1 Floor slabs	m²	4		
		.2 Top of walls, beams, etc.	m²	10		
C4.7.4.10		<u>EXPANSION JOINTS</u>				
	8.5	(a) <u>Polyurethane joint sealer</u>				
		.1 Remove 10 x 20mm tear off strip, prime with an approved primer and fill joint with polyurethane sealer	m	2.5		
C4.7.4.11		<u>GROUTING OF PIPES WITH NON SHRINK GROUT TO FORM A WATERTIGHT JOINT WITH STANDARD BEDDING GROUT</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C4.7.4.12	8.6	.01 <u>250mm thick concrete wall</u>				
		.02 150mm diameter pipe	no	3		
		.02 <u>200mm thick concrete wall</u>				
		.01 450 mm diameter pipe	no	4		
		.02 200 m diameter pipe	no	2		
		.03 525 mm diameter pipe	no	4		
		.04 600 mm diameter pipe	no	1		
		.03 <u>300 mm thick concrete wall</u>				
		.01 160 mm diameter pipe	no	1		
		.02 250 mm diameter pipe	no	1		
		<u>PRECAST CONCRETE</u>				
		<u>Precast concrete units supplied and fixed complete including all reinforcing etc.</u>				
C4.7.5		a) Strength concrete 30MPa / 19mm				
		a) 1250 x 2500mm cover slabs placed on top of chambers, including fixing in place access cover and air vent (access cover and air vent measured elsewhere) roof slab	m³	0.5		
C4.7.5.1		<u>O3 SHAFT</u> <u>ref. drg. 1890.08.OB.14.D001</u>				
		<u>SMOOTH FORMWORK</u>				
		(a) Plane horizontal				
		.1 suspended slabs	m²	3		
		(b) Planed vertical				
		.1 Walls	m²	8		
C4.7.5.2		<u>BOXING IN FOR HOLES AND VOIDS</u>				
		(a) Large, circular, over 0,35m and up to 0,7m diameter with depth				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Contractor
 Witness 1
 Witness 2
 Employer
 Witness 1
 Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C5		<u>SCHEDULE C5: ACCESS, PAVING, DRAINAGE AND FENCING</u>				
C5,1	SANS 1200 DM PSDM	<u>EARTHWORKS (ROAD SUBGRADE)</u>				
		<u>Road bed preparation and compaction of material to a minimum of 93% modified AASHTO maximum density</u>				
C5.1.1	8.3.4	Cut to fill, borrow to fill and compact to a minimum of 90% modified AASHTO maximum density (PROVISIONAL SUM)	m³	210		
C5.1.2	8.3.5	150 mm thick selected layer (subbase) compacted to 95% modified AASHTO density with natural gravel (G6) material from commercial source.	m³	210		
C5.1.3	8.3.7	<u>Cut to spoil or stockpile from: (provisional)</u>				
		a) Soft excavation	m³	40		
		b) Hard Excavation	m³	50		
C5,2	SANS 1200 MF	<u>SUBBASE</u>				
C5.2.1	8.3.3	Construct 150 mm thick base with natural gravel (G5) material from commercial source and compact to 97% modified AASHTO maximum density	m³	210		
C5.2.2	8.3.5	d) Process natural gravel by stabilisation	m³	210		
C5.2.3	8.3.8	<u>Stabilising Agent</u>				
		a) Road Lime	ton	8.4		
		b) Portland cement	ton	8.4		
C5,3	SANS 1200 MJ PSMJ	<u>SEGMENTED PAVING</u>				
C5.3.1	8.2.2	<u>Construction of paving complete with 80 mm grey interlocking precast paving blocks</u>				
		i) used block paving from stock pile	m²	0		
		ii) new paving delivered to site	m²	1400		
C5.3.2	8.2.3	Cutting units to fit edge restraints	m	420		
C5.3.3	8.2.4	Rolling to locked up condition	m²	1400		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C5,4	SANS 1200 MK PSMK	<u>KERBING, CHANNELLING WALKWAYS AND EDGE BEAMS</u>				
		<u>PRECAST KERBING</u>				
C5.4.1		Supply and install precast mountable kerbing complete with haunching and apron				
		a) Straight sections				
		.1 Used sections from stockpile	m	0		
		.2 New sections delivered to site	m	210		
		b) Curved sections, radius over 4m, but up to and including 20m				
		.1 Used sections from stockpile	m	0		
		.2 New sections delivered to site	m	150		
		c) Curved sections, radius over 1 m, but up to and including 4 m	m	10		
		<u>CAST IN-SITU EDGE BEAMS</u>				
	8.2.1	Supply and install cast in-situ concrete elements				
C5.4.2		Class 25/13 cast in-situ concrete, 300 mm wide edge beam, wood floated on top, angle rounded edges and 10 mm thick expansion joints at 3 m centres				
		a) Straight sections	m	35		
C5,5		<u>SCHEDULE 5.7 - PAVING</u>				
C5.5.1		85mm thick class 20/13 concrete apron with 40mm min fall over width, in wood float finish, 12mm thick vertical expansion joints flexcell or similar and approved with bond breaker and 12 x 10 mm polyurethane sealer at min 2,50m distance. All edges receive 5mm corner trim.				
		a) 1,0 m wide	m	45		
C5,6		<u>SCHEDULE 5.8 - DRAINAGE</u>				
C5.6.1		Dished stormwater trench with handraked trimming above sludge dams. (PROVISIONAL ITEM)	m	50		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C5.6.2		3m wide grass side drain with instant lawn lining (Kikuyu) (PROVISIONAL ITEM)	m	50		
		SCHEDULE C5 ACCESS, PAVING, DRAINAGE AND FENCING				
		Total				

□

Contractor

--	--

Witness 1

--	--

Witness 2

11

Employer

11/11/2019

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C6	PU PUA	<u>SCHEDULE C6: BUILDING WORK</u>				
C6,1		<u>SCHEDULE: C6.1 - RGS FILTERS (BY SUBCONTRACTOR)</u>				
		Ref. drg. 1890.08.SUB.16.D001 & SUB.16.E001				
		<u>ONE COAT PLASTER</u>				
C6.1.1	PU 3.1.5	One coat 1:6 cement plaster				
	8.34.1	.2 <u>Steel float finish to</u>				
		.1 Walls	m ²	39		
	PU 3.3.1 PU 5.3	<u>PAINTING</u>				
		Note: All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions				
C6.1.2	8.39.2	<u>Undercoat and two coats interior washable acrylic paint to</u>				
		.1 Plastered walls	m ²	18		
C6.1.3	8.39.3	<u>Undercoat and two coats exterior washable acrylic paint to</u>				
		.1 Plastered walls	m ²	18		
C6,2		<u>SCHEDULE: C6.2 - OZONE BUILDING (BY SUBCONTRACTOR)</u>				
		ref. drg. 1890.08.SUC.16.D004 and E001				
C6.2.1	SANS 1200 GB	<u>CONCRETE (ORDINARY BUILDINGS)</u>				
		<u>REINFORCEMENT</u>				
C6.2.1.1		<u>Steel bars</u>				
	8.2.4	(c) <u>High tensile welded mesh</u>				
		.4 Ref no.395	m ²	110		
		<u>CONCRETE</u>				
C6.2.1.2	8.2.5.1	(a) <u>Strength concrete</u>				
	8.2.5.1	(b) .1 <u>Strength concrete 20Mpa/19mm</u>				
		.8 Apron	m ³	9		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.2.1.3	8.2.5.1	.9 Ramps	m³	1		
		(c) .3 <u>Strength concrete 30Mpa/19mm</u>				
		.1 Floor slabs	m³	20		
		.2 Wall, cable duct	m³	1		
	8.2.5.1	.3 Plinth	m³	0.5		
		(d) <u>Blinding layers</u>				
		.1 <u>Strength concrete 15Mpa/19mm</u>				
	8.2.5.1	.1 50mm Thick	m³	0.3		
		(f) <u>Epoxy Floor Finish</u>				
		.1 <u>Self levelling Ucrete MF epoxy finish applied to manufacturers instructions to</u>				
C6.2.1.4	8.2.5.1	.1 Floors, etc.	m²	148		
		<u>SURFACE FINISHES</u>				
		<u>Unformed surface finishes</u>				
		8.2.6 (a) <u>Wood floated finish</u>				
	8.2.6	.1 Floor slabs	m²	210		
		(b) <u>Steel floated finish</u>				
		.1 Plinths	m²	2		
	C6.2.1.5	<u>JOINTS</u>				
		8.2.8 (a) <u>12mm Thick Flexcell placed vertically between concrete surface and brick wall</u>				
		.1 Vertical Expansion joint between concrete floor and brick walls	m²	27		
8.2.8 (b) <u>Polyurethane joint sealer</u>						
C6.2.1.5	8.2.8	.1 Remove 12 x 10mm tear off strip, prime with an approved primer and fill joint with polyurethane sealer	m	132		
		Carried Forward				

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.2.2	8.2.9 PU	(c) 3 x 30mm Saw Cut Joint BUILDING WORK	m	16		
C6.2.2.1	PU 3.1.8 8.11.1	DAMPPROOFING Polyethylene sheeting				
		.1 250 Micron USB green under floors	m ²	161		
	PU 3.4.3	PRESSED METAL DOORS AND FRAMES				
		Collect free issue from Client & install:				
		Steel doors and frames				
C6.2.2.2	8.25.2	<u>2.0mm Pressed steel transformer doors and frames</u>				
		.1 Combination door and frame with double door size 1511 x 2032mm and frame for 230mm thick wall, including vermin proof louvres size 600 x 600mm in bottom of each door leaf, including locking mechanism, barrel bolts, etc. (D2)	no	2		
C6.2.3	PU 3.3.1 PU 5.3	PAINTING				
		<u>Note:</u> All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions				
C6.2.3.1	8.39.1	<u>Prime Coat, one undercoat and two coats exterior quality gloss enamel paint to</u>				
		.1 Steel door frames	m ²	5		
		.2 Steel doors	m ²	19		
		.4 Timber doors	m ²	19		
C6.2.3.2	8.39.2	<u>Undercoat and two coats interior washable acrylic paint to</u>				
		.1 Plasterboard or asbestos ceilings	m ²	148		
		.2 Plastered walls	m ²	234		
C6.2.3.3		<u>Expoxy paint (yellow)</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.2.4		.1 100mm Wide to concrete slab (PROVISIONAL ITEM)	m	23		
		<u>SUNDRIES</u>				
		.01 Provisional Sum for Signage	Prov Sum	1		
		.02 Profit on Above	%	0		
C6,3		<u>SCHEDULE: C6.2 - OZONE DESTRUCTOR CHAMBER</u>				
		ref. drg. 1890.08.SUC.16.E002				
C6.3.1	PU	<u>BUILDING BRICKWORK</u>				
		<u>BRICKWORK</u>				
		<u>REINFORCED BRICKWORK</u>				
C6.3.1.1	8.2.0	<u>Reinforced stock brickwork in 1:3 cement mortar</u>				
		.1 230mm Thick wall	m ²	16.8		
	PU 5.1.2	<u>FACE BRICKWORK</u>				
C6.3.1.2	8.4.0	<u>Extra over items 805.01.01 and 805.01.02 for face brickwork (Allow R4600.00/1000 for purchasing and delivery of bricks to site excluding VAT)</u>				
		.1 Stretcher course bond	m ²	16.8		
		<u>BRICK REINFORCING</u>				
C6.3.1.3	8.5.0	<u>Brick reinforcing</u>				
		.2 150mm Wide brickforce	m	37		
		.3 Rod reinforcing (all sizes)	kg	2		
		<u>LINTOLS</u>				
C6.3.1.4	8.6.0	<u>Precast pre-stressed concrete lintols built into brickwork</u>				
		.1 75 x 110mm Lintol	m	1.5		
		<u>IRONMONGERY</u>				
C6.3.1.5	8.24.0	<u>Locksets</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.3.1.6		.1 Union C2, two lever lockset including satin chrome furniture	no	1		
	PU 3.4.3	<u>PRESSED METAL DOORS AND FRAMES</u>				
		Steel door frames Dwg 1890.08.AA.16.D001				
	8.25.0	.1 <u>1.6mm Pressed steel door frames</u>				
		.2 Door size 813 x 2032mm and 230mm thick wall (D4)	no	2		
C6.3.1.7	8.24.2	<u>Door stops</u>				
		.1 30mm Diameter rubber door stop	no	1		
		<u>ONE COAT PLASTER</u>				
C6.3.1.8	PU 3.1.5	<u>One coat 1:6 cement plaster</u>				
	8.34.1	.2 <u>Steel float finish to</u>				
		.1 Walls	m ²	40		
C6.3.1.9	PU 3.3.1 PU 5.3	<u>PAINTING</u>				
		<u>Note:</u> All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions				
C6.3.1.10	8.39.1	<u>Prime Coat, one undercoat and two coats exterior quality gloss enamel paint to</u>				
		.1 Steel door frames	m ²	1.5		
		.2 Steel doors	m ²	3.5		
C6.3.1.11	8.39.2	<u>Undercoat and two coats interior washable acrylic paint to</u>				
		.2 Plastered walls	m ²	40		
C6.4		<u>SCHEDULE C6.4 - SLUDGE DEWATERING BUILDING (BY SUBCONTRACTOR)</u>				
		ref. drg. 1890.08.SUD.15.D001, 16.D001, 16.E001 & AA.16.D001				
C6.4.1	SANS 1200 GB	<u>CONCRETE (ORDINARY BUILDINGS)</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.4.1.1	8.2.1	<u>ROUGH FORMWORK</u> a) .2 <u>Plane vertical</u> .3 Sides of floor slabs	m ²	23		
C6.4.1.2	8.2.1	<u>NORMAL FORMWORK</u> (b) .1 <u>Plane horizontal</u> .1 Permanent formwork for soffit for drain channel	m ²	2		
	8.2.1	(b) .2 <u>Plane vertical</u> .1 Walls	m ²	30		
		(b) .3 <u>Plane circular</u> .1 Walls circular on plan to 3.965m radius	m ²	24		
C6.4.1.3	8.2.2	<u>Normal formwork to narrow widths</u> (a) Edges, risers, etc. not exceeding 300mm wide (b) Circular edges, risers, etc. not exceeding 300mm wide	m m	30 15		
		<u>REINFORCEMENT</u>				
	8.2.4	(b) <u>High tensile steel</u> .1 All sizes	ton	2		
	8.2.4	(c) <u>High tensile welded mesh, reference 395</u> .1 Ref 193 .2 Ref 395	m ² m ²	42 495		
		<u>CONCRETE</u>				
C6.4.1.4	8.2.5.1	(b) <u>Strength concrete 25Mpa/19mm</u> .2 Apron around building	m ³	3		
C6.4.1.5	8.2.5.1	(c) <u>Strength concrete 35Mpa/19mm</u> .3 Floor and ramps .4 Channel Floors	m ³ m ³	74 4		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.4.1.6		.5 Walls	m ³	13		
		<u>SURFACE FINISHES</u>				
		<u>Unformed surface finishes</u>				
	8.2.6	(a) <u>Wood floated finish</u>				
C6.4.1.7		.1 Floor slabs including ramps	m ²	303		
	8.2.6	(b) <u>Steel floated finish</u>				
		.1 Floor slabs	m ²	204		
		<u>JOINTS</u>				
	8.2.8	(a) <u>12mm Thick flexcell or similar approved placed vertically between brick and concrete surfaces</u>				
		.1 Depths of 150mm	m	42		
	8.2.8	(b) <u>12mm Thick flexcell or similar approved placed vertically between concrete surfaces</u>				
		.1 Depths of 85mm	m	23		
		.2 Depths of 150mm	m	80		
	8.2.8	(c) <u>Polyurethane joint sealer</u>				
		.1 Remove 12 x 10mm tear off strip, prime with an approved primer and fill joint with polyurethane sealer	m	145		
	8.2.8	(d) 3 x 40 mm deep saw cut joint	m	110		
C6.4.1.8	8.8.0	<u>Hoop iron ties between concrete and brickwork</u>				
		.1 1 x 30mm Galvanised hoop iron tie, 600mm long with one end fixed to steel column and other end built into brickwork	no	50		
		<u>DAMPPROOFING</u>				
C6.4.1.9	8.11.1	<u>Polyethylene sheeting</u>				
		.1 250 Micron USB green under floors	m ²	507		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.4.1.10	8.26.0	<u>PURPOSE MADE DOORS AND FRAMES</u> <u>Collect free issue from Client & install:</u> <u>Purpose made doors and frames</u> <u>Dwg 1890.10.LA.16.E001</u> 1. Supply and install complete 1829 x 3000mm high solid meranti horizontal sliding double door, including connected to top and bottom wall mounted steel frame with rollers, cut out for I-beam and sealed with neoprene flap, door handles, locking mechanism, etc. .2 900x2090mm high single anodised aluminium door and frame (Natural finish), including glazing according to SABS approved special safety glass, hinges, etc. (D1)	no	1		
C6.4.1.11	8.26.2	<u>ROLLER SHUTTER DOORS</u> <u>1.6mm Hot dipped galvanised industrial type roller shutter door complete with locking mechanism, etc.</u> <u>Dwg 1890.10.LA.16.E001</u> .1 Size 3000 x 3000mm high roller shutter door complete, including chain operation, etc. (D8)	no	2		
C6.4.1.12	8.34.1	<u>ONE COAT PLASTER</u> <u>One coat 1:6 cement plaster</u> .2 <u>Steel float finish to</u> .1 Walls	m ²	100		
C6.4.1.13	8.39.2	<u>PAINTING</u> <u>Note:</u> All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions <u>One coat primer and two coats interior washable acrylic paint to</u> .1 Plastered walls	m ²	100		
C6.4.1.14	8.39.6	<u>Three coats Woodcoat polyurethane coating suede</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.4.2		.1 Wooden doors	m ²	12		
		<u>MISCELLANEOUS ITEMS</u>				
		1. G7 Granular material compacted to 93% MOD AASHTO, within restricted areas	m ³	390		
		2. 76mm diam halved uPVC sleeves for drainage	m	3		
		3. 200mm diam uPVC sleeves for drainage	m	20		
		4. Soilcrete (5% OPC), backfilling in restricted areas (Between concrete walls)	m ³	280		
C6,5		<u>SCHEDULE: C6.5 - PRE-OZONATION INSTALLATION (BY SUBCONTRACTOR)</u>				
		ref. drg. 1890.08.SUF.16.D001 and 16.D002				
C6.5.1	SANS 1200 GB	<u>CONCRETE (ORDINARY BUILDINGS)</u>				
		<u>REINFORCEMENT</u>				
C6.5.1.1		<u>Steel bars</u>				
	8.2.4	(c) <u>High tensile welded mesh</u>				
		.5 Ref no.617	m ²	55		
		<u>CONCRETE</u>				
C6.5.1.2	8.2.5.1	(b) <u>Strength concrete</u>				
	8.2.5.1	(b) .1 <u>Strength concrete 20Mpa/19mm</u>				
		.9 Aprons	m ³	2		
		.10 Steps & Ramps	m ³	0.6		
	8.2.5.1	(c) .4 <u>Strength concrete 35Mpa/19mm</u>				
		.7 Surfacebed	m ³	4.5		
		<u>SURFACE FINISHES</u>				
C6.5.1.3		<u>Unformed surface finishes</u>				
	8.2.6	(a) <u>Wood floated finish</u>				
		.1 Floor slabs	m ²	15		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.5.1.4	8.2.6	(b) <u>Steel floated finish</u>				
	.1	Floor slabs	m ²	40		
		<u>JOINTS</u>				
	8.2.8	(a) <u>12mm Thick flexcell placed vertically between concrete surface and brick walls</u> <u>Dwg 1890.08SUF.16.D001 and D002</u>				
	.1	Expansion joint	m	31		
	8.2.8	(b) <u>Polyurethane joint sealer</u>				
	.1	Remove 10 x 12mm tear off strip, prime with an approved primer and fill joint with polyurethane sealer	m	31		
	8.2.10	(d) 4 x 60mm Saw Cut Joint	m	15		
C6.5.2	SANS 1200 H	<u>STRUCTURAL STEELWORK</u>				
		<u>SUPPLY AND FABRICATION OF STEELWORK</u>				
		<u>SINGLE SECTION STEELWORK</u>				
		<u>Single section steelwork</u>				
C6.5.2.1	8.3.1	.2 .1 .1 <u>Single section beam with connection plates, stiffeners, splice material, stop ends,etc</u>				
		.1 203 x 133 x 25kg/m universal beam	ton	0.2		
		<u>FASTENERS</u>				
C6.5.2.2	8.3.1	.2 .8 <u>Fasteners</u>				
		.3 Four x 16mm Diameter anchor bolts 550mm long, including two 200x200x 10mm flat plate as per Dwg 1890.08.SUF.16.D002	no	5		
		<u>TRANSPORT TO SITE</u>				
C6.5.2.3	8.3.2	.1 <u>Normal transport</u>				
		.1 Structural steelwork	ton	0.2		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.5.2.4	8.3.4	<u>OFF LOADING, SITE STORAGE & ERECTION ON SITE</u> .02 <u>Erection bolts</u> .3 Four x 16mm Diameter anchor bolts 550mm long, including two 200x200x 10mm flat plate	no	5		
C6.5.3	SANS 1200HC	<u>CORROSION PROTECTION</u> 8.3.13 <u>Extra over items 8.3.1 to 8.3.9 for corrosion protection</u> <u>At workshop</u>				
C6.5.3.1	8.3.13	.1 .1 <u>Mechanical wire brush or light blast to remove all mill scale and hot dip galvanise</u> .1 General surfaces of structural steel <u>On site after erection</u>	tons	0.2		
C6.5.3.2	8.3.13	.2 .1 <u>Repair damaged primer coat and apply one coat of intermediate Multi-Purpose Undercoat (30 micron DFT) and two coats Alkyd based enamel (30 micron DFT each)</u> .1 General surfaces of structural steel	ton	0.2		
C6.5.4	PU PU 3.1.8	<u>BUILDING WORK</u> <u>DAMPPROOFING</u>				
C6.5.4.1	8.11.1	<u>Polyethylene sheeting</u> .1 250 Micron USB green under floors	m ²	55		
C6.5.4.2	8.26.0	<u>PURPOSE MADE DOORS AND FRAMES</u> <u>Collect free issue from Client & install:</u> <u>Purpose made doors and frames</u> .1 1524 x 2975 mm thick mild steel double door and frame complete, including hinges, door stop, handle, locking device, etc. (D10) <u>SCREEDS</u> 8.33.0 <u>1:3 Cement screed steel floated</u>	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.5.4.4		.2 50mm Average thick to floors to falls	m²	40		
		<u>ONE COAT PLASTER</u>				
	PU 3.1.5	One coat 1:6 cement plaster				
	8.34.1	.2 <u>Steel float finish to</u>	m²	83		
		.1 Walls				
C6.5.6	PU 3.3.1 PU 5.3	<u>PAINTING</u>				
		Note: All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions				
C6.5.6.1	8.39.1	<u>Prime Coat, one undercoat and two coats exterior quality gloss enamel paint to</u>	m²	9		
		.1 Steel door and frames				
C6.5.6.2	8.39.2	<u>Undercoat and two coats interior washable acrylic paint to</u>	m²	83		
		.2 Plastered walls				
6.6		<u>SCHEDULE: 6.6 - HYDROGEN PEROXIDE STORE AND DOSING ROOM</u>				
		Ref. drg. 1890.08.SUG.16.D001				
C6.6.1	SANS 1200 GB	<u>CONCRETE (ORDINARY BUILDINGS)</u>				
		<u>ROUGH FORMWORK</u>				
		a) .1 <u>Plane vertical</u>	m²	2.5		
		.1 Sides of floor slabs				
C6.6.2		<u>REINFORCEMENT</u>				
	8.2.4	(a) <u>High tensile welded mesh, reference 395</u>	m²	25		
		.1 Ref 395				
C6.6.3		<u>SURFACE FINISHES</u>				
		<u>Unformed surface finishes</u>				
	8.2.6	(a) <u>Wood floated finish</u>	m²	25		
		.1 Floor slabs including ramps				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C6.6.4		<u>JOINTS</u>				
	8.2.8	(a) <u>12mm Thick flexcell or similar approved placed vertically between brick and concrete surfaces</u>				
		.1 Depths of 100mm	m	6		
	8.2.8	(b) <u>Polyurethane joint sealer</u>				
		.1 Remove 12 x 10mm tear off strip, prime with an approved primer and fill joint with polyurethane sealer	m	6		
C6.6.5		<u>CONCRETE</u>				
	8.2.5.1	(a) <u>Strength concrete</u>				
	8.2.5.1	(b) .1 <u>Strength concrete 20Mpa/19mm</u>				
		.1 Steps, aprons & Ramps	m³	2.5		
		<u>SCREEDS</u>				
C6.6.6	8.33.0	<u>1:3 Cement screed steel floated</u>				
		.1 50mm Average thick to floors	m²	8		
C6.6.7	PU 3.3.1 PU 5.3	<u>PAINTING</u>				
		<u>Note:</u> All paint to be Plascon or other approved and applied in accordance with the manufacturers instructions				
C6.6.7.1	8.39.1	<u>Prime Coat, one undercoat and two coats exterior quality gloss enamel paint to</u>				
		.1 Steel door and frames	m²	4		
C6.6.7.2	8.39.2	<u>Undercoat and two coats interior washable acrylic paint to</u>				
		.1 Plastered walls	m²	37		
C6,7		<u>SCHEDULE: C6.7 - MISCELLANEOUS</u>				
		.1 Dismantle and re-positioning of light pole between Access road and DAF Tank 3 prior to excavation for new DAF Tank 3	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
		.2 Repositioning of electrical MCC in front of sludge sump complete with new class 20/19 concrete support base and re-laying of all cables. note: Rate to include for commissioning of electrical installation	no	1		
		SCHEDULE C6 BUILDING WORK				
Total						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C7		<u>SCHEDULE C7: STEEL AND METALWORK</u>				
	SANS 120 HA	<u>STRUCTURAL STEELWORK (SMALL WORKS)</u> Rate to include for supply of material, erection, welding, bolts, nuts, protection etc.				
C7,1	8.3.1	<u>SCHEDULE 7.1 - STRUCTURAL STEEL</u>				
C7.1.1		<u>Rapid Gravity Sand filter</u> i) Stainless steel (316L) inlet weir plate with neoprene packing, bolted to concrete wall. Complete as shown on drg 1890.08.FA.14.D003	no	4		
C7.1.2		<u>Ozone Contact Tank and low lift PS</u> i) Hot dip galvanized vermin proof air vent complete as shown on drg. 1890.08.AA.13.D002	no	2		
C7.1.3		<u>SCREW PUMP STATION AND O₃ SHAFT</u> i) Vastap steel stairs with landing, handrails, platform and supports bolted to concrete plinths, complete as shown on drg. 1890.08.OB.14.D001 and detail drg. 1890.08.AA.15.D001	no	1		
C7.1.4		<u>GAC FILTERS</u> i) Stainless steel (316L) weir plate 920 X 250 mm with neoprene packing bolted to concrete wall, complete as shown on drg. 1890.08.FB.14.D007 ii) Stainless steel (316L) washwater weir plate 5220 x 125 mm with neoprene packing bolted to concrete wall, complete as shown on drg. 1890.08.FB.14.X003 iii) Stainless steel (316L) baffle plate bolted to concrete wall. Complete as shown on drg. 1890.08.FB.14.D007	no	6 12 6		
C7.1.5		<u>Chambers</u> i) Hot dip galvanized vermin proof air vent complete as shown on drg 1890.08.AA.13.D002	no	1		
C7,2	8.3.2	<u>SCHEDULE: 7.2 - HANDRAILS</u>				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Contractor Witness 1 Witness 2 Employer Witness 1 Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C7.4.1		<u>Chambers</u>				
		i) 1060 x 1060 mm (span 1000 mm)	no	2		
C7.4.2		<u>Angle iron frame cast into concrete wall with fish tail anchor complete as shown on drg 1890.08.AA.13.D002</u>				
		i) Chambers	m	22		
		<u>Hot dip galvanized banded RS 40 grating with 40 x 4,5mm bearer bar, minimum of 25 bearer bars per metre of grating for details refer drg 1890.08.AA.13.D002</u>				
C7.4.3		<u>Chambers</u>				
		i) 1560 x 1500 mm (span 1500mm)	no	1		
		ii) 1560 x 800 taper x 1250 mm long (span 1500 mm)	no	1		
C7.4.4		<u>Angle iron frame cast into concrete wall with fish anchor complete as shown on drg 1890.08.AA.413.D002</u>				
		i) Chambers	m	8		
C7,5		<u>SCHEDULE 7.5 - MISCELLANEOUS</u>				
C7.5.1		Polypropylene coated step irons with high tensile steel bar				
		i) GAC Filters	no	19		
		ii) Clearwater Tank chambers	no	6		
		iii) Chambers	no	9		
C7.5.2		Cast Iron Valve Box to SANS 558, Fig. 13, Type 7 with square base.				
		i) Chambers	no	3		
C7.5.3		Fire Hose installation bolted to concrete columns, complete as shown on drg. 1890.08.FB.14.D007				
		i) GAC Filters	no	2		
C7.5.4		Heavy duty Cast Iron circular cover and square base frame in accordance to SANS 558, Fig. 3, Type 2A				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C7.5.5		i) Chambers	no	2		
		<u>CLAMPS AND BRACKETS</u> Hot dip galvanized clamp for valve extension spindle bolted to concrete wall with 2 NO 12 mm dia ss bolts.				
		i) for 150 mm dia valve	no	2		
SCHEDULE C7 STEEL AND METALWORK						
Carried forward to Summary of Schedules						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
C8	PLK, PLKA, PLN PLQ	SCHEDULE C8: STEEL, PIPE FITTINGS AND VALVES				
C8,1	Pipe Item Schedule	The rate for all items to include for the supply, delivery factory applied corrosion protection and off-loading on site.				
C8.1.1		<u>Inlet structure</u> ref. drg. 1890.08.CA.13.M001				
C8.1.1.1		BA 1.1	no	1		
C8.1.1.2		BA 2.2	no	1		
C8.1.1.3		BA 2.4	no	1		
C8.1.1.4		BA 4.1	no	1		
C8.1.1.5		BA 5.1	no	1		
C8.1.1.6		BA 5.2	no	3		
C8.1.2		<u>Flocculation Channels</u>				
C8.1.2.1		CA 2.1	no	1		
C8.1.2.2		CA 2.2	no	1		
C8.1.2.3		CA 5.1	no	2		
C8.1.3		<u>Ozone contact tank and low lift pump station</u> ref. drg. 1890.08.OA.13.M001				
C8.1.3.1		OA 5.2	no	1		
C8.1.3.2		OA 9.1	no	1		
C8.1.3.3		OA 9.3	no	1		
C8.1.4		<u>Clearwater tank</u> ref. drg. 1890.08.GA.13.M001				
C8.1.4.1		GA 1.1	no	1		
C8.1.4.2		GA 1.2	no	1		
C8.1.4.3		GA 1.3	no	1		
C8.1.4.4		GA 1.5	no	3		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C8.1.4.5		GA 4.1	no	1		
C8.1.4.6		GA 5.1	no	1		
C8.1.4.7		GA 5.2	no	1		
C8.1.4.8		GA 7.1	no	4		
C8.1.4.9		GA 7.2	no	4		
C8.1.5		<u>Site pipework (Inter connecting pipes between structures)</u> <u>ref. drg. 1890.08.AA.10.M001</u>				
C8.1.5.1		SP 1.10	no	1		
C8.1.5.2		SP 2.2	no	1		
C8.1.5.3		SP 2.4	no	1		
C8.1.5.4		QC 5.1	no	1		
C8.1.6		<u>Site pipework (Chambers)</u> <u>ref. drg. 1890.08.QD.13.M001</u>				
C8.1.6.1		QC 1.1	no	1		
C8.1.6.2		QC 1.2	no	1		
C8.1.6.3		QC 5.1	no	1		
C8.1.6.4		QD 1.1	no	1		
C8.1.6.5		QD 1.2	no	1		
C8.1.6.6		QD 1.3	no	1		
C8.1.6.7		QD 3.1	no	1		
C8.1.6.8		QD 4.1	no	2		
C8.1.6.9		QD 6.1	no	3		
C8.1.6.10		QD 9.1	no	2		
C8.1.6.11		QE 1.1	no	1		
C8.1.6.12		QE 9.1	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C8,2	Pipe Item Schedule	The rate for items supplied by the Contractor to include for the handling, installation, testing, site corrosion protection, painting and building into walls				
		The remaining items to be collected free issue from the Client, to include handling, installation testing, site corrosion protection, painting and building into walls				
C8.2.1		<u>Inlet structure</u> ref. drg. 1890.08.CA.13.M001				
C8.2.1.1		BA 1.1	no	1		
C8.2.1.2		BA 1.2	no	1		
C8.2.1.3		BA 1.3	no	1		
C8.2.1.4		BA 2.1	no	1		
C8.2.1.5		BA 2.2	no	1		
C8.2.1.6		BA 2.3	no	1		
C8.2.1.7		BA 2.4	no	1		
C8.2.1.8		BA 4.1	no	1		
C8.2.1.9		BA 5.1	no	1		
C8.2.1.10		BA 5.2	no	3		
C8.2.1.11		BA 8.1	no	1		
C8.2.2		<u>Flocculation Channels</u>				
C8.2.2.1		CA 2.1	no	1		
C8.2.2.2		CA 2.2	no	1		
C8.2.2.3		CA 5.1	no	2		
C8.2.3		<u>DAF Tanks</u> ref drg. 1890.08.CA.13.M001				
C8.2.3.1		DA 1.1	no	1		
C8.2.4		<u>Rapid Gravity Sand Filters</u> ref. drg. 1890.08.FA.13.M001				
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C8.2.4.1		FA 1.1	no	1		
C8.2.4.2		FA 1.2	no	1		
C8.2.4.3		FA 2.1	no	1		
C8.2.4.4		FA 2.2	no	1		
C8.2.4.5		FA 5.1	no	2		
C8.2.4.6		FA 5.2	no	1		
C8.2.5		<u>Ozone contact tank and low lift pump station</u> <u>ref. drg. 1890.08.OA.13.M001</u>				
C8.2.5.1		OA 1.1	no	1		
C8.2.5.2		OA 1.11	no	1		
C8.2.5.3		OA 5.1	no	1		
C8.2.5.4		OA 5.2	no	1		
C8.2.5.5		OA 9.1	no	1		
C8.2.5.6		OA 9.3	no	1		
C8.2.5.7		OA 12.1	no	1		
C8.2.5.8		OA 12.2	no	1		
C8.2.6		<u>Screw pump station and O₃ shaft</u> <u>ref. drg. 1890.08.OB.13.M001</u>				
C8.2.6.1		OB 1.1	no	1		
C8.2.6.2		OB 2.1	no	1		
C8.2.6.3		OB 2.2	no	1		
C8.2.6.4		OB 2.3	no	1		
C8.2.7		<u>Clearwater tank</u> <u>ref. drg. 1890.08.GA.13.M001</u>				
C8.2.7.1		GA 1.2	no	1		
C8.2.7.2		GA 1.3	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C8.2.7.3		GA 1.5	no	3		
C8.2.7.4		GA 2.1	no	1		
C8.2.7.5		GA 2.2	no	1		
C8.2.7.6		GA 4.1	no	1		
C8.2.7.7		GA 5.1	no	1		
C8.2.7.8		GA 5.2	no	1		
C8.2.7.9		GA 7.1	no	4		
C8.2.7.10		GA 7.2	no	4		
C8.2.7.11		GA 9.1	no	1		
C8.2.7.12		GA 12.1	no	1		
C8.2.8		<u>Site pipework (Inter connecting pipes between structures)</u> <u>ref. drg. 1890.08.AA.10.M001</u>				
C8.2.8.1		SP 1.1	no	1		
C8.2.8.2		SP 1.2	no	1		
C8.2.8.3		SP 1.3	no	1		
C8.2.8.4		SP 1.4	no	1		
C8.2.8.5		SP 1.5	no	1		
C8.2.8.6		SP 1.6	no	1		
C8.2.8.7		SP 1.7	no	1		
C8.2.8.8		SP 1.8	no	1		
C8.2.8.9		SP 1.9	no	1		
C8.2.8.10		SP 1.10	no	1		
C8.2.8.11		SP 1.11	no	1		
C8.2.8.12		SP 1.13	no	1		
C8.2.8.13		SP 1.14	no	1		
Carried Forward						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item	Payment Reference	Description	Unit	Qty	Rate (R)	Amount (R)
Brought Forward						
C8.2.8.14		SP 1.15	no	1		
C8.2.8.15		SP 2.1	no	1		
C8.2.8.16		SP 2.2	no	1		
C8.2.8.17		SP 2.3	no	1		
C8.2.8.18		SP 2.4	no	1		
C8.2.8.19		SP 5.1	no	1		
C8.2.9		<u>Site pipework (Chambers)</u> <u>ref. drg. 1890.08.QD.13.M001</u>				
C8.2.9.1		QC 1.1	no	1		
C8.2.9.2		QC 1.2	no	1		
C8.2.9.3		QC 5.1	no	1		
C8.2.9.4		QD 1.1	no	1		
C8.2.9.5		QD 1.2	no	1		
C8.2.9.6		QD 1.3	no	1		
C8.2.9.7		QD 3.1	no	1		
C8.2.9.8		QD 4.1	no	2		
C8.2.9.9		QD 6.1	no	3		
C8.2.9.10		QD 9.1	no	2		
C8.2.9.11		QE 1.1	no	1		
C8.2.9.12		QE 9.1	no	1		
		SCHEDULE C8 STEEL, PIPE FITTINGS AND VALVES				
Carried forward to Summary of Schedules						

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

**RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT
WORKS – MECHANICAL AND ELECTRICAL WORKS**

C2.3 SUMMARY OF SCHEDULES

Upgrade and Extension of the Bospoort Water Treatment Works to 24 Mℓ/d

Civil, Mechanical & Electrical combined

Summary of Schedules

Schedule No.		Description	Amount (R)
1	MECHANICAL	PRELIMINARY AND GENERAL	
2		PROVINSIONAL SUMS, ADDITIONAL WORK & DAYWORKS	
3		STEEL, PIPE FITTINGS AND VALVES	
4		STEEL AND METALWORK	
5		DISSOLVED AIR FLOTATION (DAF)	
6		RGS FILTRATION SYSTEM	
7		OZONE EQUIPMENT	
8		GAC FILTRATION SYSTEM	
9		GAC MEDIA	
10		PUMPS	
11		DEWATERING EQUIPMENT	
12		CHEMICAL DOSING	
13		HOISTING EQUIPMENT	
E1	ELECTRICAL	MEDIUM VOLTAGE SWITCHGEAR	
E2		RING MAIN UNITS	
E3		POWER TRANSFORMERS	
E4		MINIATURE SUBSTATIONS	
E5		MOTOR CONTROL CENTRES AND DISTRIBUTION BOARDS	
E6		PROGRAMMABLE LOGIC CONTROLLERS	
E7		SCADA SYSTEMS	
E8		CONTROL AND INSTRUMENTATION SYSTEM	
E9		GENERAL AND MISCELLANEOUS	
E10		TELEMETRY SYSTEM	
E11		EARTHING AND LIGHTNING PROTECTION	
E12		SMALL POWER AND LIGHTING INSTALLATIONS	
E13	CIVIL	MULTICORE CABLES AND EARTH WIRES	
E14		SITE LIGHTING	
E15		STANDBY GENERATOR SYSTEM	
C3		EARTHWORKS AND PIPELINES	
C4		CONCRETE (STRUCTURAL)	
C5		ACCESS, PAVING, DRAINAGE AND FENCING	
C6		BUILDING WORK	
C7		STRUCTURAL STEELWORK (SMALL WORKS)	
C8		STEEL, PIPE FITTINGS AND VALVES	
Sub-Total A			
Minimum Contract Skills Development Goal Sum = EP&ME (0,25%) × Sub-Total A [In accordance with the Standard for Developing Skills through Infrastructre Contract]			
Sub-Total B			
Provisional sum: Allowance for Contingencies (10% of Sub-Total B)			
Sub-Total C			
Provisional sum: Allowance for Contract Price Adjustment (10% of Sub-Total C)			
Total Construction Cost			
Value Added Tax at 15%			
Total Amount of Tender Carried Forward to Form of Bid			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Upgrade and Extension of the Bospoort Water Treatment Works to 24 Mℓ/d Civil, Mechanical & Electrical combined

Summary of Schedules

Bankers Details :

Contractor's Name: _____

Name reflected on bank statement: _____

Bank: _____

Branch: _____

Account Number: _____

Cheque Account ☐ or Savings Account ☐

Signature :

By Tenderer : _____

Company Name : _____

Date : _____

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

**RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER
TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS**

T2.3 TECHNICAL SCHEDULES

T2.3.1 Mechanical

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

T2.3.1 MECHANICAL TECHNICAL SCHEDULES

Section	Description	Page
1.	GAC FILTER EQUIPMENT	T2.3.1-2
2.	OZONE GENERATOR EQUIPMENT	T2.3.1-6
3.	OZONE GENERATOR	T2.3.1-9
4.	OZONE CONTACTING	T2.3.1-13
5.	GAC REMOVAL EQUIPMENT	T2.3.1-17
6.	WATER QUALITY AND OTHER OZONE RELATED PROCESS INSTRUMENTATION	T2.3.1-18
7.	PUMP EQUIPMENT	T2.3.1-19
8.	SATURATOR.....	T2.3.1-21
9.	DAF COMPRESSOR.....	T2.3.1-22
10.	RGS FILTER EQUIPMENT	T2.3.1-24
11.	DEATERING EQUIPMENT	T2.3.1-26
12.	CHEMICAL DOSING EQUIPMENT	T2.3.1-34
13.	ELECTRICAL ACTUATORS.....	T2.3.1-35
14.	GENERAL PROCESS EQUIPMENT	T2.3.1-36
15.	SPARE PARTS.....	T2.3.1-37

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

1. GAC FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
1. GAC FILTER EQUIPMENT			
1.1	Filter Floor		
	Nozzle slot size	mm	
	Nozzle spacing	mm	
	Nozzle head loss at specified backwash rate	m	Head loss curves to be included
1.2	Backwash Pumps		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty Point	l/s @ kPa (attached H-Q, η -Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	
1.3	Air Blowers		
	Manufacturer		
	Capacity	l/s	
	Pressure	m	
	Silencer type		
1.4	Valves, Penstocks and Actuators		
	Butterfly valve manufacturer		
	Penstock manufacturer		
	Butterfly valve actuator manufacturer		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

1. GAC FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	Penstock actuator manufacturer		
1.5	Piping		
	Manufacturer (Steel Pipes)		
	Material detail		
	Manufacturer (HDPE, PVC Pipes)		
	Material detail		
1.6	Gac Media		
1.6.1	GAC - Supplier 1		
	Name of GAC Manufacturer		
	Size of GAC (US sieve size) __ x __		Attach sieve analysis
	GAC type (coal, wood, etc.)		
	Iodine number	mg/g	
	Methylene blue	mg/g	
	Surface area	m ² /g	
	Total pore unit volume	cm ³ /g	
	Apparent- and particle density	kg/m ³	
	Bed density, backwashed and drained	kg/m ³	
	Wetability	%	
	Moisture content	%	
	Water soluble matter	%	
	Total ash content	%	
	Ph	%	
	Ball-pan hardness number	%	
1.6.2	GAC - Supplier 2		
	Name of GAC Manufacturer		
	Size of GAC (US sieve size) __ x __		Attach sieve analysis
	GAC type (coal, wood, etc.)		
	Iodine number	mg/g	
	Methylene blue	mg/g	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

1. GAC FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	Surface area	m ² /g	
	Total pore unit volume	cm ³ /g	
	Apparent- and particle density	kg/m ³	
	Bed density, backwashed and drained	kg/m ³	
	Wetability	%	
	Moisture content	%	
	Water soluble matter	%	
	Total ash content	%	
	Ph	%	
	Ball-pan hardness number	%	
1.6.3	GAC - Supplier 3		
	Name of GAC Manufacturer		
	Size of GAC (US sieve size) ___ x ___		Attach sieve analysis
	GAC type (coal, wood, etc.)		
	Iodine number	mg/g	
	Methylene blue	mg/g	
	Surface area	m ² /g	
	Total pore unit volume	cm ³ /g	
	Apparent- and particle density	kg/m ³	
	Bed density, backwashed and drained	kg/m ³	
	Wetability	%	
	Moisture content	%	
	Water soluble matter	%	
	Total ash content	%	
	pH	%	
	Ball-pan hardness number	%	
1.6.4	GAC - Supplier 4		
	Name of GAC Manufacturer		
	Size of GAC (US sieve size) ___ x ___		Attach sieve analysis
	GAC type (coal, wood, etc.)		

<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Contractor	<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Witness 1	<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Witness 2	<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Employer	<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Witness 1	<div style="border: 1px solid black; width: 100px; height: 25px; margin-bottom: 5px;"></div> Witness 2
03_Vol1B_ME_June25_Part T2.3					
June 2025					

1. GAC FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	Iodine number	mg/g	
	Methylene blue	mg/g	
	Surface area	m ² /g	
	Total pore unit volume	cm ³ /g	
	Apparent- and particle density	kg/m ³	
	Bed density, backwashed and drained	kg/m ³	
	Wetability	%	
	Moisture content	%	
	Water soluble matter	%	
	Total ash content	%	
	pH	%	
	Ball-pan hardness number	%	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

2. OZONE GENERATOR EQUIPMENT			
Item no.	Description	Units	Technical Particulars
2. OZONE GENERATOR EQUIPMENT (SUPPLIER 1)			
2.1	AMBIENT REQUIREMENTS		
2.1.1	Maximum operating altitude	MAMSL	
2.1.2	Safe ambient operating temperature		
	Min	°C	
	Max	°C	
2.1.3	Safe ambient operating humidity		
	Average	%	
	Occasional	%	
2.1.4	Heat dissipation to environment (per ozone generator)		
	Min	kW	
	Max	kW	
2.2	FEED GAS		
2.2.1	Oxygen feed rate required (per ozone generator)	Include brochure	
	Min	m³/hr @ STP	
	Max	m³/hr @ STP	
2.2.2	Nitrogen concentration for optimal ozone generation		
	Min	%	
	Max	%	
2.2.3	Maximum dewpoint	°C	
2.2.4	Temperature		
	Min	°C	
	Max	°C	
2.2.5	Pressure		
	Min	kPa	
	Max	kPa	
2.3	COOLING WATER		
2.3.1	Cooling medium		
2.3.2	Cooling medium inlet temperature		
	Min		

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

2. OZONE GENERATOR EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	Max		
2.3.3	Cooling water pressure		
	Min		
	Max		
2.3.4	Temperature rise (ΔT)		
2.3.5	Cooling water quality	Attach requirements	
2.3.6	Cooling water flow rate (per generator)		
	Vessel	l/s	
	PSU	l/s	

Item no.	Description	Units	Technical Particulars
2. OZONE GENERATION EQUIPMENT (SUPPLIER 2)			
2.1	AMBIENT REQUIREMENTS		
2.1.1	Maximum operating altitude	MAMSL	
2.1.2	Safe ambient operating temperature		
	Min	$^{\circ}\text{C}$	
	Max	$^{\circ}\text{C}$	
2.1.3	Safe ambient operating humidity		
	Average	%	
	Occasional	%	
2.1.4	Heat dissipation to environment (per ozone generator)		
	Min	kW	
	Max	kW	
2.2	FEED GAS		
2.2.1	Oxygen feed rate required (per ozone generator)	Include brochure	
	Min	m^3/hr @ STP	
	Max	m^3/hr @ STP	
2.2.2	Nitrogen concentration for optimal ozone generation		
	Min	%	
	Max	%	
2.2.3	Maximum dewpoint	$^{\circ}\text{C}$	
2.2.4	Temperature		
	Min	$^{\circ}\text{C}$	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



	Max	°C	
2.2.5	Pressure		
	Min	kPa	
	Max	kPa	
2.3	COOLING WATER		
2.3.1	Cooling medium		
2.3.2	Cooling medium inlet temperature		
	Min		
	Max		
2.3.3	Cooling water pressure		
	Min		
	Max		
2.3.4	Temperature rise (ΔT)		
2.3.5	Cooling water quality	Attach requirements	
2.3.6	Cooling water flow rate (per generator) Vessel PSU	l/s l/s	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

3. OZONE GENERATOR			
Item no.	Description	Units	Technical Particulars
3. OZONE GENERATOR (SUPPLIER 1)			
3.1	Maximum ozone production rate per generator at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (20°C cooling water temperature and 5°C ΔT)	kg/hr kg/hr kg/hr kg/hr	Attach technical brochure
3.2	Maximum ozone production rate per generator at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (25°C cooling water temperature and 5°C ΔT)	kg/hr kg/hr kg/hr kg/hr	Attach technical brochure
3.3	Maximum oxygen consumption per generator at maximum ozone production at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (20°C cooling water temperature and 5°C ΔT)	Nm³/hr Nm³/hr Nm³/hr Nm³/hr	Attach technical brochure
3.4	Maximum oxygen consumption per generator at maximum ozone production at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (25°C cooling water temperature and 5°C ΔT)	Nm³/hr Nm³/hr Nm³/hr Nm³/hr	Attach technical brochure
3.5	Power consumption per generator at 10%wt, 100% ozone production at 10%wt, 75% ozone production at 10%wt, 50% ozone production (20°C cooling water temperature and 5°C ΔT)	kW kW kW	Attach technical brochure
3.6	Power consumption per generator at 10%wt, 100% ozone production at 10%wt, 75% ozone production at 10%wt, 50% ozone production (25°C cooling water temperature and 5°C ΔT)	kW kW kW	Attach technical brochure
3.7	Maximum gas regulation turn down range	Ratio	1: _____
3.8	Operating pressure (min – max)	kPa	_____ kPa to _____ kPa
3.9	Outlet gas pressure	kPa	_____ kPa to _____ kPa
3.10	No of tubes in generator	No	
3.11	Maximum operating voltage	V	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

3.12	Power requirements		
	Maximum current	A	
	Voltage	V	
3.13	Power factor at duty point		
3.14	Noise level at maximum gas flow rate	dBa	
3.15	Dimensions (attach brochure)	m	____ m(l)x____ m(h)x____ m(w)
3.16	Pipe connections (attach brochure)		
	Gas Inlet dia	mm	
	Gas Outlet dia	mm	
	Cooling water inlet dia	mm	
	Cooling water outlet dia	mm	
3.17	Supply cable voltage	V and A	____ V and ____ A
3.18	Piping material and size		
	Air pipes	Attach list of pipe sizes and material	
	Oxygen pipes	Attach list of pipe sizes and material	
	Ozone pipes	Attach list of pipe sizes and material	
	Cooling water pipes	Attach list of pipe sizes and material	
3.19	Valve material and types	Attach list of valve types, manufacturer, supplier, material of manufacture	
3.20	Actuator details	Attach list of actuator type, manufacturer, supplier, material of manufacture	
3.21	Corrosion guarantee	No of Years	
	Input/Output list (attach brochure)		

Item no.	Description	Units	Technical Particulars
3. OZONE GENERATOR (SUPPLIER 2)			
3.1	Maximum ozone production rate per generator at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (20°C cooling water temperature and 5°C ΔT)	kg/hr kg/hr kg/hr kg/hr	Attach technical brochure
3.2	Maximum ozone production rate per generator at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (25°C cooling water temperature and 5°C ΔT)	kg/hr kg/hr kg/hr kg/hr	Attach technical brochure

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item no.	Description	Units	Technical Particulars
	ΔT)		
3.3	Maximum oxygen consumption per generator at maximum ozone production at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (20°C cooling water temperature and 5°C ΔT)	Nm ³ /hr Nm ³ /hr Nm ³ /hr Nm ³ /hr	Attach technical brochure
3.4	Maximum oxygen consumption per generator at maximum ozone production at 6%wt ozone at 8%wt ozone at 10%wt ozone at 12%wt ozone (25°C cooling water temperature and 5°C ΔT)	Nm ³ /hr Nm ³ /hr Nm ³ /hr Nm ³ /hr	Attach technical brochure
3.5	Power consumption per generator at 10%wt, 100% ozone production at 10%wt, 75% ozone production at 10%wt, 50% ozone production (20°C cooling water temperature and 5°C ΔT)	kW kW kW	Attach technical brochure
3.6	Power consumption per generator at 10%wt, 100% ozone production at 10%wt, 75% ozone production at 10%wt, 50% ozone production (25°C cooling water temperature and 5°C ΔT)	kW kW kW	Attach technical brochure
3.7	Maximum gas regulation turn down range	Ratio	1:_____
3.8	Operating pressure(min – max)	kPa	_____ kPa to _____ kPa
3.9	Outlet gas pressure	kPa	_____ kPa to _____ kPa
3.10	No of tubes in generator	No	
3.11	Maximum operating voltage	V	
3.12	Power requirements		
	Maximum current	A	
	Voltage	V	
3.13	Power factor at duty point		
3.14	Noise level at maximum gas flow rate	dBA	
3.15	Dimensions (attach brochure)	m	_____ m(l)x_____m(h)x_____m(w)
3.16	Pipe connections (attach brochure) Gas Inlet dia Gas Outlet dia Cooling water inlet dia Cooling water outlet dia	mm mm mm mm	
3.17	Supply cable voltage	V and A	_____ V and _____ A
3.18	Piping material and size		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

Item no.	Description	Units	Technical Particulars
	Air pipes	Attach list of pipe sizes and material	
	Oxygen pipes	Attach list of pipe sizes and material	
	Ozone pipes	Attach list of pipe sizes and material	
	Cooling water pipes	Attach list of pipe sizes and material	
3.19	Valve material and types	Attach list of valve types, manufacturer, supplier, material of manufacture	
3.20	Actuator details	Attach list of actuator type, manufacturer, supplier, material of manufacture	
3.21	Corrosion guarantee	No of Years	
	Input/Output list (attach brochure)		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

4. OZONE CONTACTING			
Item no.	Description	Units	Technical Particulars
4. OZONE CONTACTING			
4.1	Diffuser type (main ozone)		
	Size	mm	
	Spacing	mm	
	Gas flow rate	Nm ³ /hr	
4.2	Piping material and size	Attach list of pipe sizes and material	
4.3	Valve material and type	Attach list of valve types, manufacture, supplier, materials of manufacture	
4.4	Thermal mass flow meter	Attach detail	
4.5	Ozone contacting instrumentation	Attach detail	
4.6	Recycle pumps (pre-ozone)		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		Add 0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Piping material and size	Attach list of pipe size signs and material	
	Valve material and type	Attach list of valve types, manufacturer, supplier, material of manufacture	
4.7	Thermal mass flow meter	Attach detail	
4.8	Ozone contacting instrumentation	Attach detail	
4.9	Ozone injectors (pre-ozone)		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

4. OZONE CONTACTING			
Item no.	Description	Units	Technical Particulars
	Type		
	Manufacturer		
	Maximum O ₃ transfer capacity	Nm ³ /hr	Attach performance curve
	Maximum hydraulic capacity	m ³ /hr	
4.10	Static mixer (pre-ozone)		
	Type		
	Manufacturer		
	Capacity	Nm ³ /hr	Attach performance curve
4.11	Recycle pumps (pre-RGSF ozone)		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		Add 0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Piping material and size		
	Valve material and type		
4.12	Thermal mass flow meter	Attach detail	
4.13	Ozone contacting instrumentation	Attach detail	
4.14	Ozone injectors (pre-RGSF ozone)		
	Type		
	Manufacturer		
	Maximum O ₃ transfer capacity	Nm ³ /hr	Attach performance curves
	Maximum hydraulic capacity	m ³ /hr	
4.15	Static mixer		
	Type		
	Manufacturer		
	Capacity	Nm ³ /hr	Attach performance curve

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

4. OZONE CONTACTING			
Item no.	Description	Units	Technical Particulars
4.12	OZONE MIXING AND DEGASSING (PRE-OZONE)		
	Manufacturer		
	Size	m	____ m(h)x____ m(diameter)
	Degassing degassing capacity	Nm ³ /hr	
	Material		
	Instrumentation	Attach list	
4.13	OZONE DESTRUCTION		
	Catalytic converter and heater	Attach Brochure	
	Manufacturer		
	Capacity	Nm ³ /hr	
	Fan		
	Manufacturer		
	Capacity	Nm ³ /hr	
	Pipework material and size		
	Material size		
	Valves		
	Instrumentation	Attach list	
4.14	NITROGEN BLEED SYSTEM		
	Compressor manufacturer		
	Compressor capacity	Nm ³ /hr	
	Motor size	kW	
	Drier manufacturer		
	Air Drier type		
	Air Drier capacity	Nm ³ /hr	
	Power requirements	kW	
	Instrumentation	Attach list	
4.15	COOLING WATER PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

4. OZONE CONTACTING			
Item no.	Description	Units	Technical Particulars
	Motor size	kW	
	Duty point	l/s @ kPa (Attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
4.16	PROCESS PIPING AND PIPE FITTINGS	Attach list with details of pipe size, material, class, manufacturer	
4.17	VALVES AND ACTUATORS		
	Valves	Attach list with details of valve size, type, material, manufacturer and supplier	
	Actuators	Attach list with details of actuator size, type, material, manufacturer and supplier	
4.18	INSTRUMENT AND CONTROL		
	Ozone generation control system	Attach brochure and list of instrumentation and equipment detail	
	Ozone dosing control system		
4.19	OZONE SYSTEM CRITICAL SPARES	Attach list of recommended critical spares	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

5. GAC REMOVAL EQUIPMENT			
Item no.	Description	Units	Technical Particulars
5. GAC REMOVAL EQUIPMENT			
5.1	SELF PRIMING GAC SLURRY PUMP		
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Power requirements	kW	
5.2	PIPING		
	Manufacturer		
	Material		
5.3	VALVES MANUFACTURER MATERIAL		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

6. WATER QUALITY AND OTHER OZONE RELATED PROCESS INSTRUMENTATION			
Item no.	Description	Units	Technical Particulars
6. WATER QUALITY AND OTHER OZONE RELATED PROCESS INSTRUMENTATION			
6.1	OXYGEN SUPPLY		
6.1.1	Dew point analyser	Attach brochure	
6.1.2	Oxygen concentration analyser		
6.2	NITROGEN BLEED SYSTEM		
6.2.1	Dew point analyser	Attach brochure	
6.3	OZONE GENERATION		
6.3.1	Gas (thermal mass) flow meter	Attach brochure	
6.3.2	Ozone gas concentration analyser (high concentration)		
6.3.3	Ambient ozone gas concentration analyser (low concentration)		
6.4	OZONE CONTACTING AND MIXING		
6.4.1	Residual ozone concentration analyser	Attach brochure	
6.4.2	Ozone off-gas concentration analyser (pre destructor)		
6.4.3	Ozone off-gas concentration analyser (post destructor)		
6.4.4	Gas mass flow meter		
6.4.5	UV254 Analyser		
6.5	HANDHELD INSTRUMENTS		
6.5.1	Ozone gas concentration analyser	Attach brochure	
6.5.2	Oxygen gas concentration analyser		
6.5.3	Ozone residual concentration analyser		
6.6	OTHER		
6.6.1	pH Probes	Attach brochure	
6.6.2	Turbidity Meters		
6.6.3	Residual Chlorine		

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

03_Vol1B_ME_June25_Part T2.3

June 2025

7. PUMP EQUIPMENT			
Item no.	Description	Units	Technical Particulars
7. PUMP EQUIPMENT			
7.1	LOW LIFT PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	
7.2	DAF RECYCLE PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

7. PUMP EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	HIGH LIFT PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point	l/s @ kPa (attach H-Q, n-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



8. SATURATOR			
Item no.	Description	Units	Technical Particulars
8. SATURATOR			
8.1	Manufacturer		
8.2	Supplier		
1.3	Material		
8.4	Ultimate tensile stress	MPa	
8.5	Minimum yield stress	MPa	
8.6	Maximum working stress	MPa	
8.7	Installation contractor		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

9. DAF COMPRESSOR			
Item no.	Description	Units	Technical Particulars
9. DAF COMPRESSOR			
9.1	Manufacturer		
9.2	Place of manufacture		
9.3	Supplier		
9.4	Type		
9.5	Model		
9.6	Free air delivery	l/s	
9.7	Air receiver capacity	l	
9.8	Maximum pressure	kPa	
9.9	Speed of rotation	rpm	
9.10	Power absorption at maximum duty	kW	
9.11	Inlet pipe diameter	mm	
9.12	Outlet pipe diameter	mm	
9.13	<u>Electric motors</u>		
9.13.1	Name of manufacture		
9.13.2	Place of manufacturer		
9.13.3	Type of motor		
9.13.4	Type of frame		
9.13.5	Class of insulation		
9.13.6	Speed of rotation	rpm	
9.13.7	Rated output	kW	
9.13.8	Efficiency at:		
(i)	Full load		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

9. DAF COMPRESSOR			
Item no.	Description	Units	Technical Particulars
(ii)	¾ load		
9.13.9	Power factor at:		
(i)	Full load		
(ii)	¾ load		
9.14	Installation contractor		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

10. RGS FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
10. RGS FILTER EQUIPMENT			
10.1	FILTER FLOOR		
	Nozzle slot size	mm	
	Nozzle spacing	mm	
	Nozzle head loss at specified backwash rate	m	Head loss curves to be included
10.2	BACKWASH PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty Point	l/s @ kPa (attached H-Q, p-Q, kW-Q, NPSH-Q curves)	
		0% and 3% NPSH required at duty point	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	
10.3	AIR BLOWERS		
	Manufacturer		
	Capacity	l/s	
	Pressure	m	
	Silencer type		
10.4	VALVES, PENSTOCKS AND ACTUATORS		
	Butterfly valve manufacturer		
	Penstock manufacturer		
	Butterfly valve actuator manufacturer		

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

03_Vol1B_ME_June25_Part T2.3

June 2025

10. RGS FILTER EQUIPMENT			
Item no.	Description	Units	Technical Particulars
	Penstock actuator manufacturer		
10.5	PIPING		
	Manufacturer (Steel Pipes)		
	Material detail		
	Manufacturer (HDPE, PVC Pipes)		
	Material detail		
10.6	RGS FILTER MEDIA		
	Name of RGS Manufacturer		
	Size of RGS (US sieve size) __ x __		Attach sieve analysis
	RGS type (coal, wood, etc.)		
	Iodine number	mg/g	
	Methylene blue	mg/g	
	Surface area	m ² /g	
	Total pore unit volume	cm ³ /g	
	Apparent- and particle density	kg/m ³	
	Bed density, backwashed and drained	kg/m ³	
	Wetability	%	
	Moisture content	%	
	Water soluble matter	%	
	Total ash content	%	
	Ph	%	
	Ball-pan hardness number	%	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11. SLUDGE DEWATERING EQUIPMENT			
11.1	DEWATERING UNIT – OFFER 1		
11.1.1	Manufacturer		
11.1.1.1	Name		
11.1.1.2	Place of manufacture		
11.1.2	Design loads		
11.1.2.1	Design solids loading	kg/h	
11.1.2.2	Design hydraulic loading	m³/h	
11.1.2.3	Maximum solids loading rate	kg/h	
11.1.2.4	Maximum hydraulic loading rate	m³/h	
11.1.3	Performance (guaranteed)		
11.1.3.1	Dewatered solids concentration at design load	%	
11.1.3.2	Dewatered solids concentration at maximum solids load	%	
11.1.3.3	Solids capture at design load		
(i)	At min feed concentration	%	
(ii)	At max feed concentration	%	
11.1.3.4	Polymer consumption at design load	g/kgDS	
11.1.3.5	Polymer consumption at maximum solids load	g/kgDS	
11.1.4	Wash water		
11.1.4.1	Wash water flow rate	m³/h	
11.1.4.2	Wash water pressure	kPa	
11.1.4.3	Maximum size solids allowed in wash water	mm	
11.1.4.4	Suspended solids in wash water at design load	mg/l	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.1.4.5	Suspended solids in filtrate at design load	mg/l	
11.1.5	Drive unit		
11.1.5.1	Maximum power absorbed	kW	
11.1.5.2	Drive unit manufacturer		
11.1.5.3	Place of manufacture		
11.1.5.4	Drive unit model No		
11.1.5.5	Drive unit motor size	kW	
11.1.5.11	Ratio installed to absorbed power		
11.1.6	Bearings		
11.1.6.1	Bearing type		
11.1.6.2	Bearing life	hrs	
11.1.6.3	Bearing seal		
11.1.6.4	Bearing mounting (internal or external)		
11.1.7	Motorised lubrication (for units with internally mounted bearings)		
11.1.7.1	Make and model		
11.1.7.2	Delivery range	mL/hr	
11.1.7.3	Total number of grease points served		
11.1.7.4	Make, model and number of distributor units		
11.1.7.5	Operating speed	rpm	
11.2	DEWATERING UNIT – OFFER 2		
11.2.1	Manufacturer		
11.2.1.1	Name		
11.2.1.2	Place of manufacture		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.2.2	Design loads		
11.2.2.1	Design solids loading	kg/h	
11.2.2.2	Design hydraulic loading	m ³ /h	
11.2.2.3	Maximum solids loading rate	kg/h	
11.2.2.4	Maximum hydraulic loading rate	m ³ /h	
11.2.3	Performance (guaranteed)		
11.2.3.1	Thickened solids concentration at design load	%	
11.2.3.2	Thickened solids concentration at maximum solids load	%	
11.2.3.3	Solids capture at design load	%	
(i)	At min feed concentration	%	
(ii)	At max feed concentration	%	
11.2.3.4	Polymer consumption at design load	g/kgDS	
11.2.3.5	Polymer consumption at maximum solids load	g/kgDS	
11.2.4	Wash water		
11.2.4.1	Wash water flow rate	m ³ /h	
11.2.4.2	Wash water pressure	kPa	
11.2.4.3	Maximum size solids allowed in wash water	mm	
11.2.4.4	Suspended solids in wash water at design load	mg/l	
11.2.4.5	Suspended solids in filtrate at design load	mg/l	
11.2.5	Drive unit		
11.2.5.1	Maximum power absorbed	kW	
11.2.5.2	Drive unit manufacturer		
11.2.5.3	Place of manufacture		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.2.5.4	Drive unit model No		
11.2.5.5	Drive unit motor size	kW	
11.2.5.6	Ratio installed to absorbed power		
11.2.6	Bearings		
11.2.6.1	Bearing type		
11.2.6.2	Bearing life	hrs	
11.2.6.3	Bearing seal		
11.2.6.4	Bearing mounting (internal or external)		
11.2.7	Motorised lubrication (for units with internally mounted bearings)		
11.2.7.1	Make and model		
11.2.7.2	Delivery range	mℓ/hr	
11.2.7.3	Total number of grease points served		
11.2.7.4	Make, model and number of distributor units		
11.2.7.5	Operating speed	rpm	
11.3	DEWATERING UNIT – OFFER 3		
11.3.1	Manufacturer		
11.3.1.1	Name		
11.3.1.2	Place of manufacture		
11.3.2	Design loads		
11.3.2.1	Design solids loading	kg/h	
11.3.2.2	Design hydraulic loading	m³/h	
11.3.2.3	Maximum solids loading rate	kg/h	
11.3.2.4	Maximum hydraulic loading rate	m³/h	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.3.3	Performance (guaranteed)		
11.3.3.1	Thickened solids concentration at design load	%	
11.3.3.2	Thickened solids concentration at maximum solids load	%	
11.3.3.3	Solids capture at design load	%	
(i)	At min feed concentration	%	
(ii)	At max feed concentration	%	
11.3.3.4	Polymer consumption at design load	g/kgDS	
11.3.3.5	Polymer consumption at maximum solids load	g/kgDS	
11.3.4	Wash water		
11.3.4.1	Wash water flow rate	m³/h	
11.3.4.2	Wash water pressure	kPa	
11.3.4.3	Maximum size solids allowed in wash water	mm	
11.3.4.4	Suspended solids in wash water at design load	mg/l	
11.3.4.5	Suspended solids in filtrate at design load	mg/l	
11.3.5	Drive unit		
11.3.5.1	Maximum power absorbed	kW	
11.3.5.2	Drive unit manufacturer		
11.3.5.3	Place of manufacture		
11.3.5.4	Drive unit model No		
11.3.5.5	Drive unit motor size	kW	
11.3.5.6	Ratio installed to absorbed power		
11.3.6	Bearings		
11.3.6.1	Bearing type		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.3.6.2	Bearing life	hrs	
11.3.6.3	Bearing seal		
11.3.6.4	Bearing mounting (internal or external)		
11.3.7	Motorised lubrication (for units with internally mounted bearings)		
11.3.7.1	Make and model		
11.3.7.2	Delivery range	mℓ/hr	
11.3.7.3	Total number of grease points served		
11.3.7.4	Make, model and number of distributor units		
11.3.7.5	Operating speed	rpm	
11.4	POLYELECTOLYTE MAKE-UP SYSTEM		
11.4.1	Dosing tank		
11.4.1.1	Capacity	m ³	
11.4.1.2	Dimensions		
11.4.1.3	Materials & corrosion protection		
11.4.2	Transfer pumps		
11.4.2.1	Number		
11.4.2.2	Type		
11.4.2.3	Manufacturer		
11.4.2.4	Country of manufacture		
11.4.2.5	Model		
11.4.2.6	Speed of rotation	rpm	
11.4.2.7	Delivery	m ³ /h	
11.4.2.8	Head	m	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.4.2.9	Type of over pressure sensor		
11.4.2.10	Power absorbed	kW	
11.4.2.11	Material		
(i)	Stator		
(ii)	Rotor		
11.4.2.11	Motor		
(i)	Manufacturer		
(ii)	Place of manufacture		
(iii)	Power	kW	
(iv)	Speed	rpm	
11.4.2.13	Overall mass of complete pumps unit	kg	
11.4.3	Make-up water		
11.4.3.1	Diameter	mm	
11.4.3.2	Material		
11.4.3.3	Coupling		
11.4.3.4	Valve type		
11.4.3.5	Valve make		
11.4.3.6	Valve material		
11.5	GUARANTEED PERFORMANCE (OFFER 1)		
11.5.1	Dewatering press/screens	No	
11.5.2	Guaranteed polyelectrolyte consumption	g/kgDS	
11.5.4	Guaranteed solids capture	%	
11.5.5	Guaranteed thickened sludge concentration	%	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

11. DEATERING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
11.6	FEED PUMPS		
	Type		
	Manufacturer		
	Model		
	Motor speed	rpm	
	Motor size	kW	
	Duty point (attach H-Q, η -Q, kW-Q, NPSH-Q curves) 0% and 3% NPSH required at duty point	l/s @ kPa	
	Material of pump components	Attach list	
	Pump bearing type		
	Bearing lubrication mechanism		
	Suitable for potable water application		
	Pump and motor dimensions	Attach brochure	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

12. CHEMICAL DOSING EQUIPMENT			
Item no.	Description	Units	Technical Particulars
12. CHEMICAL DOSING EQUIPMENT			
12.1	Ferric chloride Dosing Pumps		
12.1.1	Manufacturer		
12.1.2	Supplier		
12.1.3	Type		
12.1.4	Operating Range	l/s	
12.2	Bulk Storage Tanks - ferric		
12.2.1	Manufacturer		
12.2.2	Supplier		
12.2.3	Type		
12.2.4	Design SG		
12.2.5	Installation Contractor		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

13. ELECTRICAL ACTUATORS			
Item no.	Description	Units	Technical Particulars
13. ELECTRICAL ACTUATORS			
13.1	General Data		
13.1.1	Manufacturer		
13.1.2	Supplier		
13.1.3	Model		
13.1.4	Type		
13.1.5	Country of Origin		
13.1.6	Duration of open/close cycle	min	
13.1.7	Corrosion protection gearbox		
(i)	Inner		
(ii)	Outer		
(iii)	Finishing		
13.1.8	Max torque required by valve		
13.1.9	Available torque transmitted by actuator		
13.1.10	Unbalanced pressure at max torque		
13.1.11	Enclosure rating		
13.1.12	Voltage rating		
13.1.13	Starting current		

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

14. GENERAL PROCESS EQUIPMENT			
Item no.	Description	Units	Technical Particulars
14. GENERAL PROCESS INSTRUMENTATION			
14.1	PRESSURE GAUGES	Attach brochure	
14.2	PRESSURE TRANSMITTERS		
14.3	GAS FLOW METERS (THERMAL MASS)		
14.4	FLOW METERS (LIQUID)		
14.5	TEMPERATURE TRANSMITTERS		
14.6	LEVEL TRANSMITTERS		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

15. SPARE PARTS			
Item no.	Description	No of units	Technical Particulars
15. CRITICAL SPARE PARTS			
15.1			
15.2			
15.3			
15.4			
15.4			
15.5			
15.6			
15.7			
15.8			
15.9			
15.10			

TENDERER

Signature :

Name :

Duly authorised to sign on behalf of:

.....

Telephone :

Fax : Date :

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

**RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER
TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS**

T2.3 TECHNICAL SCHEDULES

T2.3.2 Electrical

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

T2.3.2 ELECTRICAL TECHNICAL SCHEDULES

Section	Description	Page
---------	-------------	------

NO TABLE OF CONTENTS ENTRIES FOUND.

MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
1 GENERAL				
1.1	Manufacturer			
1.2	Country of Origin			
1.3	Mini Sub Rating			
1.3.1	Power Rating	kVA	1000	
1.3.2	Number of Phases		3	
1.3.3	Frequency - As per System Electrical			
	Conditions	Hz	50	
1.4	Voltages			
1.4.1	Primary Voltage	kV	22000	
1.4.2	Secondary Voltage	kV	420	
1.5	Insulation Level			
1.5.1	Primary Voltage	kV	128	
1.5.2	Secondary Voltage	kV	SABS Rating	
1.6	Electrical System Operating Parameters		See Project Specs	
1.7	Physical and Climatic Site Conditions		Outdoors and	
			Non corrosive conditions	
2 CONSTRUCTION AND FITTINGS				
2.1	Minisub Type	A/B	B	
2.2	Minisub Design (Modular/Unitary)		Unitary	
2.3	Enclosure Material		2mm 3CR12	
2.4	Base			
2.4.1	Base type			
2.4.2	Is a base with removable section required	Yes/No	Yes	
2.4.3	Black epoxy tar paint required	Yes/No	Yes	
2.5	Are roof lifting lugs required	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
2.6	Padlock protection facility	Yes/No	Yes	
2.7	10mm Allen cap screw for doors	Yes/No	Yes	
3 MV COMPARTMENT				
3.1	Earth fault indicators	Yes/No	Yes	
3.2	Cables to be Teminated			
3.2.1	Three Core or Single Core		Three core	
3.2.2	Type of cable (PILC/XLPE)		XLPE	
3.2.3	Cable size	mm ²	As specified	
3.2.4	Cable Support (Gland plate / cable clamps)			
3.3	Switchgear			
3.3.1	Manufacturer		Refer to Project	
			Specification [PS]	
3.3.2	Country of Origin			
3.3.3	Configuration			
3.3.4	Voltage present indication system on all			
	switching devices	Yes/No	Yes	
3.3.5	Insulating Medium	SF6 /	SF6	
		Vacuum		
3.3.6	Auxiliary contacts required	Yes/No	Yes	
3.3.7	Local feeder (T-off) protection			
3.3.7.1	Circuit breaker or fuse-switch-disconnector		Circuit Breaker	
3.3.7.2	Rating	A	200	
3.3.7.3	CB type	SF6 /		
		Vacuum	SF6	
3.3.8	Ring Switching Device			
3.3.8.1	Circuit breaker or fuse-switch-disconnector		Fuse-Switch-	
			Disconnecter	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
3.3.8.2	Rating	A	630	
3.3.8.3	Fuse-switch-disconnector type	SF6 /		
		Vacuum	SF6	
4 TRANSFORMER COMPARTMENT				
4.1	Manufacturer			
4.2	Country of Origin			
4.3	Transformer Type	Oil-type/	Oil Type	
		Dry-type		
4.4	Oil-level gauge	Yes/No	Yes	
4.5	Indicating Thermometer	Yes/No	No	
4.6	Transformer Rating			
4.6.1	Continuous Overload Capacity	%	10	
4.6.2	Impedance	%	Maximum 5.1%	
4.6.3	Vector Group		Dyn 11	
4.6.4	Cooling method	ONAN /		
		ONAF	ONAN	
4.6.4	Losses			
4.6.4.1	No-load Losses	W		
4.6.4.2	Full load Losses	W		
4.7	Tapping Method			
4.7.1	Number of Taps	No	5	
4.7.2	Tapping Range	%	0±2.5; ±5	
4.7.3	Switch or Bolted Links	Off-load	Switch	
4.8	Terminations			
4.8.1	Medium Voltage Bushings			
4.8.1.1	Material			
4.8.1.2	Creepage Distance	mm		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
4.8.1.3	Basic Insulation Level (BIL)	kV	128	
4.8.1.4	Type		C	
4.8.2	Low Voltage Bushings			
4.8.2.1	Material			
4.8.2.2	Creepage Distance	mm		
4.8.2.3	Basic Insulation Level (BIL)	kV	SABS Rating	
5	LV COMPARTMENT			
5.1	Separate LV earth bar required	Yes/No	Yes	
5.2	Main LV circuit breaker	Yes/No	Yes	
5.3	Main LV switch disconnecter	Yes/No	No	
5.4	Number of LV feeders		Refer to PS	
5.5	LV feeder protection			
5.5.1	MCCBs or fuses to be used		Refer to PS	
5.5.2	Rating of protection for each feeder	A	Refer to PS	
5.6	LV Metering			
5.6.1	Main LV Meter required	Yes/No	Refer to PS	
5.6.2	Manufacturer and model Number		Refer to PS	
5.6.3	Metering on each feeder required	Yes/No	Refer to PS	
5.6.4	Manufacturer and model Number		Refer to PS	
5.6.5	Equipment Specification		Refer to PS	
6	CONFIRMATION OF MINI SUB TESTS CONDUCTED			
6.1	Minisub routine test certificate	Yes/No	Yes	
6.2	Minisub type test certificate	Yes/No	Yes	
6.3	Transformer Type Tested to IEC 60076-11			
a	Temperature-rise Test (IEC 60076-2)	Yes / No	Yes	
b	Dielectric Type Test (IEC 60076-3)	Yes / No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
c	Determination of Sound Level (IEC 60076-10) for each method of cooling for which a guaranteed sound level is specified	Yes / No	Yes	
6.4	Transformer Routine Test to be Conducted			
a	Measurement of winding resistance	Yes / No	Yes	
b	Measurement of voltage ratio and check of phase displacement	Yes / No	Yes	
c	Measurement of short-circuit impedance and load loss	Yes / No	Yes	
d	Measurement of no-load loss and current	Yes / No	Yes	
e	Dielectric routine test (IEC 60076-3)	Yes / No	Yes	
f	Test on on-load tap-changers, where appropriate	Yes / No	Yes	
g	Leak testing with pressure for liquid-immersed transformers (tightness test)	Yes / No	Yes	
h	Tightness tests and pressure tests for tanks for gas-filled transformers (refer to 60076-15)	Yes / No	Yes	
i	Check for the ratio and polarity of built-in current transformers	Yes / No	Yes	
j	Check of core and frame insulation for liquid immersed transformers with core or frame insulation	Yes / No	Yes	
7	LABELLING AND MARKING TO SANS 1029	Yes/No	Yes	
8	RATING PLATES			
8.1	Rating plates to SANS 1029	Yes/No	Yes	
9	OVERALL DIMENSIONS		1000kVA	800kVA
9.1	Length	mm		
9.2	Width	mm		
9.3	Height	mm		
9.4	Total mass	kg		
10	FINISHING			
10.1	Colour of Minisub to SANS 1091		C12 - Avocado Green	
10.2	Paintwork finish		Matt	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



MINIATURE SUBSTATIONS				
Item no.	Description	Units	Specified	Proposed
11	DATA SHEET	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MV CABLES AND CABLE SYSTEMS				
Item no.	Description	Units	Specified	Offered
1 MEDIUM VOLTAGE CABLES				
1.1	Manufacturer		SABS Approved	
1.2	Country of Origin		RSA	
1.3	Operating Voltage	kV	22	
1.4	Number of Cores	No	3	
1.5	Size	mm ²	Various	
1.6	Conductor Type	Cu/Al	Cu	
1.7	Insulation	PILC/ XLPE	XLPE	
1.8	Armouring		SWA	
1.9	Serving		PVC	
1.12	Bear SANS Mark	Yes/No	Yes	
2 MEDIUM VOLTAGE CABLE TERMINATION KIT				
2.1	Manufacturer		SABS Approved	
2.2	Country of Origin		RSA	
2.3	Operating Voltage	kV	22	
2.4	Size	mm ²	As Specified	
2.5	Cable Conductors	Cu/Al	Cu	
2.6	Type of Lugs		Shear-off	
2.7	Full Earth Kit required	Yes/No	Yes	
2.8	Heat Shrink Type required	Yes/No	Yes	
2.9	Complete Kit by one Manufacturer	Yes/No	Yes	
2.10	Type Test Certificate	Yes/No	Yes	
2.11	Bear SANS Mark	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

MV CABLES AND CABLE SYSTEMS				
Item no.	Description	Units	Specified	Offered
3 MEDIUM VOLTAGE CABLE JOINT KIT				
3.1	Manufacturer		SABS Approved	
3.2	Country of Origin		RSA	
3.3	Operating Voltage	kV	22	
3.4	Size	mm ²	As Specified	
3.5	Cable Conductors	Cu/Al	Cu	
3.6	Type of Ferrules		Shear-off	
3.7	Full Earth Kit required	Yes/No	Yes	
3.8	Type required (Heatshrink / Cast Iron)		Heatshrink	
3.9	Complete Kit by one Manufacturer	Yes/No	Yes	
3.10	Type Test Certificate	Yes/No	Yes	
3.11	Bear SANS Mark	Yes/No	Yes	
4 INSTALLATION				
4.1	Depth	mm	1000	
4.2	Outdoor Cable Markers [Refer to Particular Specification]	Yes/No	Yes	
4.3	Cable Concrete Slabs [Refer to Particular Specification]	Yes/No	Yes	
5	DATA SHEET OF ALL CABLES	Yes/No	Yes	

LV CABLE SYSTEMS FOR MOTOR AND EQUIPMENT				
Item no.	Description	Units	Specified	Offered
1 LOW VOLTAGE CABLES				
1.1	Manufacturer		SABS Approved	
1.2	Country of Origin		RSA	
1.3	Operating Voltage	V	600/1000	
1.4	Number of Cores	No	Refer to Project Specs and BOQ	
1.5	Size	mm ²		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV CABLE SYSTEMS FOR MOTOR AND EQUIPMENT				
Item no.	Description	Units	Specified	Offered
1.6	Conductor Type	Cu/Al		
1.7	Cable Type			
1.8	Full Load Current	A		
1.9	Armouring	Yes/No	Yes, SWA	
2 CABLE LADDER				
2.1	Manufacturer		SABS Approved	
2.2	Country of Origin		RSA	
2.3	Type			
2.4	Material		Galvanised	
2.5	Duty	Heavy / Medium	Heavy	
2.6	Application		LV cables	
3 WIRED MESH				
3.1	Manufacturer		SABS Approved	
3.2	Country of Origin		RSA	
3.3	Type			
3.4	Material		Galvanised	
3.5	Duty	Heavy / Medium	Heavy	
3.6	Application		LV cables	
4 INSTALLATION				
4.1	Depth	mm	750	
4.2	Outdoor Cable Markers [Refer to Particular Specification]	Yes/No	Yes	
4.3	Cable Concrete Slabs [Refer to Particular Specification]	Yes/No	Yes	
5 DATA SHEET OF ALL CABLES		Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
1 ASSEMBLY CONSTRUCTION				
1.1	Manufacturer			
1.2	Access	<i>Back/Front/ Side</i>	Refer to PS	
			Various	
1.3	Doors / Removable Panels		Doors	
1.4	Hinges	<i>Yes / No</i>	Yes	
1.5	Hinges - Type		Refer to project and particular specification [PS - Project specification]	
1.6	Hinges - Material			
1.7	Stays at 95° opening	<i>Yes / No</i>		
1.8	Door Locks	<i>Yes / No</i>		
1.9	Door Locks - Type			
1.10	Door Locks - Material			
1.11	Door Interlock per compartment	<i>Yes / No</i>	Yes	
1.12	Cable Entry	<i>Top / Bottom</i>	Bottom	
1.13	Size of Panel:			
1.13.1	<i>Height</i>	<i>mm</i>	Max 2100	
1.13.2	<i>Length</i>	<i>mm</i>		
1.13.3	<i>Width</i>	<i>mm</i>		
1.14	Spare Space Required	<i>%</i>	<i>>=</i>	
1.15	Estimated Weight	<i>kg</i>		
1.16	Type Tested with Stated Deviations to SANS 1973-1, 3 & 8	<i>Yes/No</i>	Yes	
1.17	Deviations from original Type Tested Assembly:	<i>Specify</i>		
1.18	Type Test Certificate Required	<i>Yes / No</i>	Yes	
1.19	Motor Starter Circuits	<i>Withdrawable / Fixed</i>	Fixed	
1.20	Ingress Protection (doors closed)	<i>IP</i>	Refer to PS	
1.21	Form of Internal Separation		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
1.22	Method of Installation: <i>Floor standing / Wall mounted / Flush / Pedestal Mounted / Kiosk / Architrave / Surface Mounted</i>		Floor Standing	
1.23	Material of Construction: <i>2mm Mild Steel / 2.0mm Mild Steel / Electro Galvanized / Stainless Steel / 3CR12 / Fibre Glass</i>		3CR12	
1.24	Epoxy Powder Coated	Yes / No	Yes	
1.25	Incomer Section Required	Yes / No	Yes	
1.26	Essential Section Required	Yes / No	Yes	
1.27	UPS Section Required	Yes / No	Yes	
1.28	Colour of Assembly:			
1.28.1	<i>Doors</i>		electric orange	
1.28.2	<i>Normal Section</i>		electric orange	
1.28.3	<i>Essential Section</i>		Purple	
1.28.4	<i>UPS Section</i>		Purple	
2 COMPONENTS				
2.1	Busbars			
2.1.1	Material		Copper	
2.1.2	Tinned	Yes / No	Yes	
2.1.3	Current Density	A/mm ²	As type test require	
2.2	Air Circuit Breakers	-	-	
2.2.1	Manufacturer			
2.2.2	Type		Fixed	
2.2.3	Model			
2.2.4	Rated Current	A		
2.2.5	Service short-circuit breaking capacity (Ics)	kA		
2.2.6	Overload release		Electronic	
2.2.7	Short-circuit release		Electronic	
2.2.8	Motorised	Yes/No	Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
2.3	Moulded Case Circuit Breakers	-	-	
2.3.1	Manufacturer			
2.3.2	Type		Fixed	
2.3.3	Model			
2.3.4	Rated Current	A		
2.3.5	Service short-circuit breaking capacity (Ics)	kA		
2.3.6	Overload release		Refer to PS	
2.3.7	Short-circuit release		Refer to PS	
2.4	Miniature Circuit Breakers	-	-	
2.4.1	Manufacturer			
2.4.2	Type			
2.4.3	Model			
2.4.4	Rated Current	A	Refer to PS	
2.4.5	Service short-circuit breaking capacity (Ics)	kA	Refer to PS	
2.4.6	Tripping Curve		Refer to PS	
2.5	Fuse-Switch-Disconnecter	-	-	
2.5.1	Manufacturer			
2.5.2	Model			
2.6	High Rupture Capacity (HRC) Fuse Links	-	-	
2.6.1	Manufacturer			
2.6.2	Model			
2.7	Contactors	-	-	
2.7.1	Manufacturer			
2.7.2	Model			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
2.7.3	Contactor rating		Refer to PS	
2.7.4	Coordination		Type 2	
2.8	Overload Relays	-	-	
2.8.1	Manufacturer			
2.8.2	Type			
2.8.3	Model			
2.8.4	Rated Current	A	Refer to PS	
2.8.5	Resettable from front of Panel	Yes / No	Refer to PS	
2.9	Miniature Relays	-	-	
2.9.1	Manufacturer			
2.9.2	Model			
2.10	Pushbutton and Selector Switches	-	-	
2.10.1	Manufacturer			
2.10.2	Model			
2.11	Indicator Lamps	-	-	
2.11.1	Manufacturer			
2.11.2	Model			
2.12	Surge Arrestors	-	-	
2.12.1	Power Circuits - Manufacturer			
2.12.2	Power Circuits - Model			
2.12.3	Power Circuits - Rating	kA	Refer to PS	
2.12.4	Remote Indication to PLC	Yes / No	No	
2.12.5	Control Circuits - Manufacturer		Refer to PS	
2.12.6	Control Circuits - Model		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
2.12.7	Remote Indication to PLC	Yes / No	No	
3 POWER FACTOR CORRECTION				
3.1	Controller			
3.1.1	Manufacturer			
3.1.2	Model			
3.2	Capacitors		Refer to PS	
3.2.1	Manufacturer		Refer to PS	
4 ACTIVE HARMONIC FILTER (if applicable)				
4.1	Manufacturer			
4.2	Model			
4.3	Type			
5 SOFT STARTERS				
5.1	Manufacturer			
5.2	Model			
5.3	Integrated bypass contactor	Yes / No	Yes	
6 FIELD E-STOP/START LOCAL CONTROL STATIONS				
6.1	Method of Installation: Wall mounted / Flush / Pedestal Mounted		Pedestal	
6.2	Manufacturer			
6.3	Model			
6.4	Height above final ground level	mm	See Project Specs	
6.5	Keyswitch Required	Yes / No	No	
6.6	Canopy required	Yes / No	Yes	
6.7	Material		304 S/S	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - MCCs and Distribution Boards				
Item no.	Description	Units	Specified	Offered
6.8	IP rating	IP	Refer to Particular specification	
7 AIR CONDITIONING MCC'S ROOM				
7.1	Manufacturer			
7.2	Model			
7.3	Rating			
7.4	Type			
7.5	Number of units			
8	DATA SHEET	Yes/No		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - LOCAL CONTROL PANELS				
Item no.	Description	Units	Specified	Offered
1 GENERAL				
1.1	Distribution Board Manufacturer			
1.2	Control Voltage	230V/ 24VDC	Refer to PS	
2 CONSTRUCTION REQUIREMENTS				
2.1	Steel Work Manufacturer			
2.2	Form of Internal Separation		1	
2.3	Material of Construction		3CR12	
2.4	Ingress Protection (doors closed)	IP	54	
2.5	Method of Installation		Floor	
2.6	Epoxy Powder Coated	Yes / No	Yes	
2.7	Colour of Assembly			
2.8	Size of Panel	HxWxD		
2.9	Spare Space Required	%	5	
2.10	Access	Back / Front / Side	Front	
2.11	Cable Entry	Top / Bottom	Top	
2.12	Doors / Removable Panels		Doors	
2.13	Door Locks	Yes / No	Yes	
2.14	Door Locks - Type			
2.15	Door Locks - Material		Refer to PS	
2.16	Incomer Section Required	Yes / No	Yes	
2.17	Corrosion protection		Yes	
2.18	Gland Plates		3CR12, Not painted	
3 ELECTRICAL COMPONENTS				
3.1	Moulded Case Circuit Breakers	-	-	
3.1.1	Manufacturer		Refer to PS	
3.1.2	Type		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - LOCAL CONTROL PANELS				
Item no.	Description	Units	Specified	Offered
3.1.3	Model		Refer to PS	
3.1.4	Rated Current	A	Refer to PS	
3.1.5	Service short-circuit breaking capacity (Ics)	kA	Refer to PS	
3.1.6	Overload release		Refer to PS	
3.1.7	Short-circuit release		Refer to PS	
3.2	Miniature Circuit Breakers	-	-	
3.2.1	Manufacturer		Refer to PS	
3.2.2	Type		Refer to PS	
3.2.3	Model		Refer to PS	
3.2.4	Rated Current	A	Refer to PS	
3.2.5	Service short-circuit breaking capacity (Ics)	kA	Refer to PS	
3.2.6	Tripping Curve		Refer to PS	
3.3	Fuse-Switch-Disconnecter	-	-	
3.3.1	Manufacturer	Refer to PS	Refer to PS	
3.3.2	Model	Refer to PS	Refer to PS	
3.4	High Rupture Capacity (HRC) Fuse Links	-	-	
3.4.1	Manufacturer		Refer to PS	
3.4.2	Model		Refer to PS	
3.5	Surge Arrestors	-	-	
3.5.1	Power Circuits - Manufacturer	Refer to PS	Refer to PS	
3.5.2	Power Circuits - Model	Refer to PS	Refer to PS	
3.5.3	Power Circuits - Rating	kA	Refer to PS	
3.5.4	Remote Indication	Yes / No	Refer to PS	
3.5.5	Control Circuits - Manufacturer		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - LOCAL CONTROL PANELS				
Item no.	Description	Units	Specified	Offered
3.5.6	Control Circuits - Model		Refer to PS	
3.5.7	Remote Indication	Yes / No	Refer to PS	
3.6	Contactors	-	-	
3.6.1	Manufacturer		Refer to PS	
3.6.2	Model		Refer to PS	
3.6.3	Contactor rating		Refer to PS	
3.6.4	Coordination		Type 2	
3.7	Overload Relays	-	-	
3.7.1	Manufacturer		Refer to PS	
3.7.2	Type		Refer to PS	
3.7.3	Model		Refer to PS	
3.7.4	Rated Current	A	Refer to PS	
3.7.5	Resettable from front of Panel	Yes / No	Yes	
3.8	Miniature Relays	-	-	
3.8.1	Manufacturer		Refer to PS	
3.8.2	Model		Refer to PS	
3.9	Control switches and pushbuttons	-	-	
3.9.1	Manufacturer			
3.9.2	Model			
3.10	Indicating Lamps	-	-	
3.10.1	Manufacturer		Refer to PS	
3.10.2	Model		Refer to PS	
3.10.3	Type		LED	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

LV SWITCHGEAR AND CONTROLGEAR ASSEMBLIES - LOCAL CONTROL PANELS				
Item no.	Description	Units	Specified	Offered
3.11	Control-Circuit and auxiliary supply transformer			
3.11.1	Manufacturer		Refer to PS	
4	FIELD E-STOP/START LOCAL CONTROL STATIONS			
4.1	Method of Installation		Refer to PS	
4.2	Material of Construction		Refer to PS	
4.3	Manufacturer		Refer to PS	
4.4	Keyswitch Required	Yes / No	No	
4.5	IP rating	IP	refer to the particular	
			specification	
5	DATA SHEET	Yes/No	Yes	

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
1 GENERAL				
1.1	Manufacturer			
1.2	Model			
1.3	Place of manufacture			
1.4	Expected life (for spares availability)	Years		
2 ELECTRICAL SERVICE CONDITIONS				
2.1	Normal service conditions varied in Project Specification	Yes/No	Refer to conditions of Contract	
2.2	Unusual electrical service conditions specified	Yes/No	No	
2.3	Supply network characteristics			
2.3.1	Voltage (nominal)	V	400	
2.3.2	Frequency	Hz	50	
3 ENVIRONMENTAL SERVICE CONDITIONS				
3.1	Standard climatic conditions varied in Project Specification	Yes/No	No	
3.2	Forced ventilation or air conditioning in VFC room	FV/AC	AC	
3.3	Unusual mechanical installation conditions specified	Yes/No	No	
3.4	Unusual environmental service conditions specified	Yes/No	No	
3.5	Airflow required per VFC	m ³ /s		
3.6	Heatload per VFC	kW		
4 LOAD DETAILS				
4.1	Type of motor-driven load		Various	
4.2	Load torque characteristic			
4.3	Number of operation quadrants			
4.4	Dynamic braking required			
4.5	Operating speed range		As per mechanical specification	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
5	CONVERTER TRANSFORMER			N/A
5.1	Type (oil-filled or dry)			
5.2	Number of secondary windings			
5.3	Primary rated voltage	V		
5.4	Secondary rated voltage	V		
5.5	Rated power	kVA		
5.6	Free-standing (FS) or integral (I) to VFC	FS/I		
5.7	No-load losses	W		
5.8	Load losses	W		
6	CONVERTER CONFIGURATION			
6.1	Form of converter (package/chassis/cabinet unit)		Package	
6.2	Rectifier type: diode- or active front end (DFE/AFE)		DFE	
6.3	Rectifier pulse number		12	
6.4	Bypass/redundancy arrangement specified	Yes/No	No	
6.5	Input air circuit-breaker	Yes/No	No	
6.6	Input switch-disconnector	Yes/No	No	
6.7	Input semi-conductor fuses	Yes/No	Yes	
6.8	Input contactor	Yes/No	Yes	
6.9	Input earthing switch	Yes/No	No	
7	CONVERTER FILTERS			
7.1	Line-side reactor	Yes/No	Yes for >20kW	
7.2	Line-side reactor relative short-circuit voltage	%		
7.3	Line harmonic filters (LHF)	Yes/No	Yes	
7.4	LHF free-standing (FS) or integral to VFC (I)	FS/I		
7.5	Motor-side reactor	Yes/No	Yes	
7.6	Motor-side dv/dt filter	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
7.7	Motor-side sine filter	Yes/No		
7.8	Motor-side common-mode filter	Yes/No	Yes	
8 CONVERTER PROTECTION				
8.1	Overcurrent and overload	Yes/No	Yes	
8.2	Undervoltage and overvoltage	Yes/No	Yes	
8.3	Phase loss and unbalance	Yes/No	Yes	
8.4	Earth fault	Yes/No	Yes	
8.5	Over-temperature	Yes/No	Yes	
8.6	DC link overvoltage and overcurrent	Yes/No	Yes	
8.7	Over-temperature of DC link reactor (if installed)	Yes/No	Yes	
9 MOTOR PROTECTION				N/A
9.1	Short-circuit	Yes/No	Yes	
9.2	Start (max starting time)/Stall	Yes/No	Yes	
9.3	Earth fault	Yes/No	Yes	
9.4	Overload	Yes/No	Yes	
9.5	Number of starts	Yes/No	Yes	
9.6	Loss of phase	Yes/No	Yes	
9.7	Unbalance	Yes/No	Yes	
9.8	Loss of load/undercurrent	Yes/No	Yes	
9.9	Thermal by means of motor thermistors/RTDs	Yes/No	Yes	
10 CONVERTER RATINGS				
10.1	Rated system voltage	V	400	
10.2	Line-side rated current	A		
10.3	Input total power factor	pu		
10.4	Line-side displacement power factor	pu		

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
10.5	Rated continuous output current	A		
10.6	Overload capability and time	A & s		
10.7	Efficiency of complete drive module	%		
10.8	Total losses of complete drive module	W		
11 CONTROL PERFORMANCE REQUIREMENTS				
11.1	Open loop speed control	Yes/No	Yes	
11.2	Steady state deviation band	%	±1 to ±2	
11.3	Closed loop speed control with indirect feedback	Yes/No	No	
11.4	Steady state deviation band	%		
11.5	Closed loop speed control with direct feedback	Yes/No	No	
11.6	Steady state deviation band	%		
12 PROCESS CONTROL INTERFACE				
12.1	Compliant with SANS 61800-7	No/Yes	Yes	
12.2	Communications Interface Quantity	No.		
12.3	Communications Interface Type(s) and Connector(s)	No.		
12.4	Communications Interface Protocol(s)	No.		
12.5	Communications Interface Power Drive System Profile	Process / Drive / Motion Control	Process	
12.6	Communications Interface Message Structure to SANS 61800-7		Yes	
13 SPECIAL CONTROL FEATURES				
13.1	Automatic restart facility	Yes/No	Yes	
13.2	Flying restart facility	Yes/No	Yes	
13.3	Adjustable ramp times (acceleration/deceleration)	Yes/No	Yes	
13.4	Dip ride-through using load kinetic energy	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
14 TESTING				
	Where indicated the following tests shall be carried out in addition to the specified mandatory tests.			
14.1	Special Tests for Converter			
14.1.1	Overcurrent capability	Yes/No	No	
14.1.2	Measurement of ripple voltage and current	Yes/No	No	
14.1.3	Power factor measurement	Yes/No	No	
14.1.4	Measurement of inherent voltage regulation	Yes/No	No	
14.1.5	Audible noise	Yes/No	No	
14.1.6	Additional tests	Yes/No	No	
14.2	Drive System Site Tests			
14.2.1	Load duty	Yes/No	No	
14.2.2	Allowable full load current versus speed	Yes/No	No	
14.2.3	Temperature rise	Yes/No	No	
14.2.4	Efficiency	Yes/No	No	
14.2.5	Current sharing	Yes/No	No	
14.2.6	Voltage division	Yes/No	No	
14.2.7	Shaft current - bearing insulation	Yes/No	No	
14.2.8	Audible noise	Yes/No	No	
14.2.9	Motor vibration	Yes/No	No	
14.2.10	EMC tests	Yes/No	No	
14.2.11	Harmonic content of CDM output	Yes/No	No	
14.2.12	Current limit and current loop	Yes/No	No	
14.2.13	Speed loop	Yes/No	No	
14.2.14	Torque pulsation	Yes/No	No	
14.2.15	Automatic restart	Yes/No	No	
14.2.16	System full load test	Yes/No	No	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2



VARIABLE FREQUENCY DRIVES : <100kW				
Item no.	Description	Units	Specified	Offered
14.2.17	Overall drive system efficiency	Yes/No	No	
14.3	Witnessed factory acceptance test	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

STREETLIGHTS				
Item no.	Description	Units	Specified	Offered
1 STREETLIGHTING KIOSKS				
1.1	Manufacturer			-
1.2	Type			
1.3	Details		See Project Specs	
1.4	Surge Arrestors	Yes/No	Yes	
1.5	SANS compliant	Yes/No	Yes	
2 STREETLIGHTS				
2.1	Manufacturer		Beka or similar and approved	
2.2	Type			
2.3	Power	W	45	
2.4	Lamp Type	LED	LED	
2.5	Switching		Timer	
3 POLES				
3.1	Material	GRP / Steel	Refer to PS	
3.2	Manufacturer /Supplier		BEKA or similar and approved	
3.3	Height		8.5m	
4 HIGH MAST				
4.1	Manufacturer		Beka or similar and approved	
4.2	Type			
4.3	Power	W	135	
4.4	Lamp Type	LED	LED	
4.5	Switching		Timer	
5 HIGH MAST				
5.1	Material	GRP / Steel	Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

STREETLIGHTS				
Item no.	Description	Units	Specified	Offered
5.2	Manufacturer /Supplier		BEKA or similar and approved	
5.3	Height		15m	
6	DATA SHEET	Yes/No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

CONTROL, INSTRUMENTATION AND DATA CABLES				
Item no.	Description	Units	Specified	Offered
1 CONTROL CABLES				
1.1	Manufacturer			
1.2	Size (minimum size)	mm ²	Refer to BOQ	
1.3	Rated Voltage	V	24VDC/230VAC	
1.4	Number of Cores	No	See Project Specs and BOQ	
1.5	Size	mm ²		
1.6	Conductor Type	Cu/Al		
1.7	Cable Type			
1.8	Full Load Current	A		
1.9	Armouring	Yes/No	Yes, SWA	
2 INSTRUMENTATION CABLES				
2.1	Manufacturer			
2.2	Rated Voltage	V	24VDC/230VAC	
2.3	Size (minimum size)	mm ²	Refer to BOQ	
2.4	Cable Type		Twisted Pair	
2.5	Screened		Individually and Overall	
			(Aluminium)	
2.6	Armouring	Yes/No	Yes / SWA	
3 WIRE MESH CABLE TRAY				
3.1	Manufacturer			
3.2	Type			
3.3	Material		(outdoors) / Galvanised	
			(outdoors) / Galvanised	
			Steel (indoors)	
3.4	Duty	Heavy / Medium	Medium	
3.5	Application		Instrumentation Cables	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

CONTROL, INSTRUMENTATION AND DATA CABLES				
Item no.	Description	Units	Specified	Offered
4 FIBRE OPTIC				
4.1	Manufacturer			
4.2	Type		Single Mode	
4.3	Armouring	Yes/No	Yes, for all outdoor and exposed cables	
4.3	Cores	No.	Refer to BOQ	
4.4	Termination Type		ST / Industrial LC	
4.7	Cable Category		min OM 2	
4.8	Modal Bandwidth	MHz.km	min 500 / 500	
5 ETHERNET COPPER CABLES				
5.1	Manufacturer			
5.2	Type		CAT6	
5.3	Armouring	Yes/No	Yes	
5.4	Termination Type		Industrial Earthed RJ45	
6 FIELDBUS CABLING				
6.1	Fieldbus Protocol			
6.2	Manufacturer			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
1 PROGRAMMABLE LOGIC CONTROLLERS				
1.1	Manufacturer		Refer to PS	
1.2	Model		Refer to PS	
1.3	Digital Inputs	No.		
1.4	Digital Outputs	No.		
1.5	Analogue Inputs	No.		
1.6	Analogue Outputs	No.		
1.7	Fieldbus interface	Yes/No	Yes	
1.8	Fieldbus protocol	E.g. Profibus,		
		Modbus		
1.9	ASI Bus interface	Yes/No	No	
1.7	Spare I/O	%	10%	
1.8	Ports			
1.8.1	Ethernet	No.		
1.8.2	Serial	No.		
1.8.3	Other	No.		
1.9	Software			
1.10	All engineering software included with PLC	Yes / No	Yes	
1.11	Annual Software License renewal required	Yes / No	No, should be once	
			off fee	
1.12	Programming Language		Refer to PS	
1.13	Backplate		Refer to PS	
			I/O module	
1.14	Datasheets included with tender	Yes / No	Yes	
		-		
2 PLC PANEL				
2.1	Enclosure Material		inside MCC	
2.2	Enclosure Colour		Orange	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
2.3	Enclosure Rating	<i>IP</i>	Refer to PS	
2.4	Enclosure Mounting	<i>Floor Standing / wall mounted</i>	Floor Standing	
2.5	Supply and Control Circuit Voltages	<i>V</i>	230V AC	
2.6	Wire Colours			
2.7	Termination Preferences		Phoenix screw terminals (or approved equivalent)	
2.8	Glanding preferences		Pratley (or approved equivalent)	
2.9	Power Supply Unit vendor preferences		Phoenix (or approved equivalent)	
2.10	Panel light required	<i>Yes / No</i>	Yes, LED	
2.11	Socket outlet required	<i>Yes / No</i>	Yes	
2.12	Physical spare space	<i>%</i>	Refer to PS	-
		-		-
3 HUMAN MACHINE INTERFACE (HMI)				
3.1	Manufacturer		Refer to PS	
3.2	Model		Refer to PS	
3.3	Screen Size	<i>Inches</i>	Refer to PS	
3.1	Screen Type	<i>Colour/</i>		
		Monochrome	Refer to PS	
3.2	Resolution	<i>Pixels</i>	Refer to PS	
3.5	Touch Screen	<i>Yes / No</i>	Yes	
3.6	Type of Touch Screen	<i>Capacitive/</i>		
		<i>Resistive</i>	Refer to PS	
3.7	Touch Screen grid size		Refer to PS	
3.3	Backlight		Refer to PS	
3.5	Memory (Flash EPROM)		Refer to PS	
3.6	Data Backup (SRAM)		Refer to PS	
3.7	Interfaces Protocol		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
3.8	Interface Port		Refer to PS	
3.9	Sound (for Alarm)		Refer to PS	
3.10	Data Transfer		Refer to PS	
3.11	Printer Port		Refer to PS	
3.12	Enclosure Rating	IP	Refer to PS	
3.13	Position of Installation	Inside Panel /		
		Flush Fronted /		
		Front Access	Flush Fronted	
3.14	Software			
3.15	Datasheets included with tender	Yes / No	Yes	
4 UPS				
4.1	Manufacturer			
4.2	Model			
4.3	Place of manufacture			
4.4	Type		Industrial inline double	
			conversion with full	
			static bypass; floor	
			standing box type	
4.5	Power	W	Refer to PS	
4.6	Backup Time	min	Refer to PS	
4.7	Output Voltage	V	230V +-5%	
4.8	Nominal Frequency	Hz	50	
4.9	Output Waveform		Pure sine wave	
4.9	Number of Phases	1 or 3	Refer to PS	
4.10	Communication		Serial/Ethernet	
4.11	Battery Life	Years		
4.12	Battery Type		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
4.13	Datasheets included with tender	Yes / No	Yes	
5 NETWORK SWITCHES				
5.1	Manufacturer			
5.2	Model			
5.3	Type		Industrial	
5.4	Ports - RJ45	No.		
5.5	Fibre ports - SFP	No.	Refer to PS	
5.6	Rack mounted	Yes/No	DIN rail box type	
5.7	Power Supply	VAC	230V	
5.8	Speed	Mbit	1000	
5.9	Datasheet included with tender	Yes / No	Yes	
6 FIELDBUS GATEWAYS (if applicable)				
6.1	Manufacturer			
6.2	Model			
6.3	Type			
SCADA				
Item no.	Description	Units	Specified	Offered
1 DESKTOP COMPUTER				
1.1	Manufacturer			-
1.2	Model			-
1.3	CPU			
1.3.1	Type		Refer to PS	
1.3.2	Speed	GHz	Refer to PS	
1.4	Memory	MB	Refer to PS	
1.5	Hard Drive Storage	GB	Refer to PS	
1.6	Operating System		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
1.8	Optical Storage		Refer to PS	
1.9	Network Card		Refer to PS	
1.10	Graphics Card		Refer to PS	
1.11	Keyboard		Refer to PS	
1.12	Mouse		Refer to PS	
1.13	Form Factor			
2 HOT-STANDBY SERVER				
2.1	Manufacturer			-
2.2	Model			-
2.3	CPU			
2.3.1	Type		Refer to PS	
2.3.2	Speed	GHz	Refer to PS	
2.4	Memory	MB	Refer to PS	
2.5	Hard Drive Storage	GB	Refer to PS	
2.6	Motherboard		Industrial motherboard,	
			conformal coating	
2.7	Hard drives		Raid hot swappable	
2.8	Power supplies		Hot swappable	
2.9	Operating System		Refer to PS	
2.10	Optical Storage		Refer to PS	
2.11	Network Card		Refer to PS	
2.12	Graphics Card		Refer to PS	
2.13	Keyboard		Refer to PS	
2.14	Mouse		Refer to PS	
2.15	KVM Switch		Refer to PS	
2.15.1	Class		Refer to PS	
2.15.2	Manufacturer		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
2.15.3	Type		Refer to PS	
2.15.4	USB	Yes/No	Yes	
2.15.5	HDMI	Yes/No	Yes	
	VGA	Yes/No	Yes	
3 DISPLAY				
3.1	Manufacturer		Refer to PS	
3.2	Model		Refer to PS	
3.3	Type		Refer to PS	
3.4	Size No. 1		Refer to PS	
3.5	Size No. 2		Refer to PS	
4 SOFTWARE				
4.1	SCADA software		Refer to PS	
4.2	Amount of Tags	No.	Refer to PS	
4.3	Clients	No.	Refer to PS	
4.4	Anti-Virus Software		Yes	
4.5	Additional Reporting and Business			
	Intelligence		Yes	
4.6	Alarm Management Package		Yes	
5 PRINTER				
5.1	Manufacturer		Refer to PS	
5.2	Model		Refer to PS	
5.3	Type		Refer to PS	
5.4	Feeding Paper Size		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
6 UPS				
6.1	Manufacturer		Refer to PS	
6.2	Model		Refer to PS	
6.3	UPS Type		Inline floor standing, dual type	
6.4	Load type		SCADA server, operator computers and screens	
6.5	Nominal input voltage	V	230V ± 15%	
6.6	Number of phases	Num	Single	
6.7	Nominal input frequency	Hz	50 Hz ± 5%	
6.8	Place of manufacture			
6.9	Rated output power		To suit load plus 30% (minimum 1 kVA)	
7	Configuration		bypass	
7.1	Power	W	Refer to PS	
7.2	Backup Time	min	Refer to PS	
7.3	Communication		Serial / Ethernet interface	
7.4	Battery life	Years	Refer to PS	
7.5	Battery type		Refer to PS	
7.6	Output Waveform		Pure sine wave	
7.7	Datasheets included with tender	Yes / No	Yes	
8 SCADA ETHERNET SWITCH				
8.1	Manufacturer		Refer to PS	
8.2	Model		Refer to PS	
8.3	Ports	No.	Refer to PS	
8.4	Fibre ports	No.	Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

PROGRAMMABLE LOGIC CONTROLLER				
Item no.	Description	Units	Specified	Offered
8.5	Rack mounted	Yes/No	Refer to PS	
8.6	Power Supply	VAC	230V	
8.7	Speed	Mbit	Refer to PS	
8.8	Datasheet included with tender	Yes / No	Yes	
9.3	Sketch/Drawing included with tender	Yes / No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
1 ABSOLUTE PRESSURE TRANSMITTERS				
1.1	Manufacturer			
1.2	Sensor Model			
1.3	Transmitter Model			
1.4	Detection Range	kPa		
1.5	Number of Relay outputs	No.		
1.6	Process Connection		Refer to PS	
1.7	Seal type		Refer to PS	
1.8	Industrial Ethernet Enabled	Yes / No	Yes	
1.9	Surge Protection Required	Yes / No	Yes	
1.10	Local Indication Required	Yes / No	No	
1.11	Additional datasheet from manufacturer included with tender	Yes / No	Yes	
2 TURBINE FLOW METER				
2.1	Manufacturer			
2.2	Model			
2.3	Pipe Diameter	mm / DN	Refer to mechanical spec	
2.4	Flow range	m³/hr	Refer to PS	
2.5	Process Connection		Refer to PS	
2.6	Number of Relay outputs	No.		
2.7	Industrial Ethernet Enabled	Yes / No	No	
2.8	Local Indication Required	Yes / No	Yes	
2.9	Surge Protection Required	Yes / No	Yes	
2.10	Additional datasheet from manufacturer included with tender for each flow meter type	Yes / No	Yes	
3 MAGNETIC FLOW METER				
3.1	Manufacturer		Refer to mechanical spec	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
3.2	Model		Refer to mechanical spec	
3.3	Flange Size	mm / DN	Refer to mechanical spec	
3.4	Flow Rate	m ³ /hr	Refer to mechanical spec	
3.5	PN Rating		As indicated on PID	
3.6	Number of Relay outputs	No.	Refer to mechanical spec	
3.7	Industrial Ethernet Enabled	Yes / No	Yes	
3.8	Local Indication Required	Yes / No	Yes	
3.9	Surge Protection Required	Yes / No	Yes	
3.10	Additional datasheet from manufacturer included with tender	Yes / No	Yes	
4 ULTRASONIC FLOW METER				
4.1	Manufacturer			
4.2	Model			
4.3	Flow Rate	m ³ /hr	As indicated on PID	
4.4	PN Rating		As indicated on PID	
4.5	Number of Relay outputs	No.	As indicated on PID	
4.6	Industrial Ethernet Enabled	Yes / No	Yes	
4.7	Local Indication Required	Yes / No	Yes	
4.8	Surge Protection Required	Yes / No	Yes	
4.9	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
5 CLAMP ON FLOW FLOW METER				
5.1	Manufacturer			
5.2	Model			
5.3	Flange Size	mm / DN	As indicated on PID	
5.4	Flow Rate	m ³ /hr	As indicated on PID	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
5.5	Process Connection		As indicated on PID	
5.6	Number of Relay outputs	No.		
5.7	Industrial Ethernet Enabled	Yes / No	Yes	
5.8	Local Indication Required	Yes / No	Yes	
5.9	Surge Protection Required	Yes / No	Yes	
5.10	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
6 THERMAL MASS MASS FLOW METER				
6.1	Manufacturer		As indicated on PID	
6.2	Model		As indicated on PID	
6.3	Flange Size	mm / DN	Refer to mechanical spec	
6.4	Flow Rate	m ³ /hr	Refer to mechanical spec	
6.5	PN Rating		Refer to PS	
6.6	Number of Relay outputs	No.	Refer to PS	
6.7	Industrial Ethernet Enabled	Yes / No	Yes	
6.8	Local Indication Required	Yes / No	Yes	
6.9	Surge Protection Required	Yes / No	Yes	
6.10	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
7 POINT LEVEL SWITCH				
7.1	Manufacturer			
7.2	Sensor Model			
7.3	Transmitter Model			
7.4	Number of Relay outputs	No.	Refer to PS	
7.5	Detection Range	m	Refer to PS	
7.6	Industrial Ethernet Enabled	Yes / No	No	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
7.7	Surge Protection Required	Yes / No	No	
7.8	Local Indication Required	Yes / No	No	
7.9	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
8 LEVEL METER : ULTRASONIC TYPE				
8.1	Manufacturer		Endress Hausser, similar or equivalent	
8.2	Sensor Model		Refer to PS	
8.3	Transmitter Model		Refer to PS	
8.4	Number of Relay outputs	No.	Refer to PS	
8.5	Level Range	m	Refer to PS	
8.6	Accuracy	%	Refer to PS	
8.7	Resolution	%/mm	Refer to PS	
8.8	Repeatability	%	Refer to PS	
8.9	Dead band	%	Refer to PS	
8.10	Ambient temperature fluctuation	%/span/10°C	Refer to PS	
8.11	Industrial Ethernet Enabled	Yes / No	No	
8.12	Surge Protection Required	Yes / No	No	
8.13	Local Indication Required	Yes / No	No	
8.14	Additional datasheet from manufacturer			
	included with tender for each ultrasonic level			
	meter type	Yes / No	Yes	
9 LEVEL METER: ULTRASONIC TYPE WITH CONTROLLER				
9.1	Manufacturer		Endress Hausser, similar or equivalent	
9.2	Sensor Model			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
9.3	Transmitter Model			
9.4	Number of Relay outputs	No.	Refer to PS	
9.5	Level Range	m	Refer to PS	
9.6	Accuracy	%	Refer to PS	
9.7	Resolution	%/mm	Refer to PS	
			Refer to PS	
9.8	Repeatability	%	Refer to PS	
9.9	Dead band	%	Refer to PS	
9.10	Ambient temperature fluctuation	%/span/10°C	Refer to PS	
9.11	Industrial Ethernet Enabled	Yes / No	Yes	
9.12	Surge Protection Required	Yes / No	Yes	
9.13	Local Indication Required	Yes / No	Yes	
9.14	Additional datasheet from manufacturer			
	included with tender for each hydrostatic level			
	meter type	Yes / No	Yes	
10 BALL TYPE LEVEL SWITCHES				
10.1	Manufacturer		Refer to PS	
10.2	Sensor Model		Refer to PS	
10.3	Transmitter Model		Refer to PS	
10.4	Number of Relay outputs	No.	Refer to PS	
10.5	Industrial Ethernet Enabled	Yes / No	No	
10.6	Surge Protection Required	Yes / No	No	
10.7	Local Indication Required	Yes / No	No	
10.8	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
11 NO-FLOW SENSORS				
11.1	Manufacturer		Refer to PS	
11.2.	Model		Refer to PS	
11.3	Flow range	m ³ /hr		
11.4	Process Connection		Refer to PS	
11.5	Number of Relay outputs	No.	Refer to PS	
11.6	Industrial Ethernet Enabled	Yes / No	No	
11.7	Local Indication Required	Yes / No	No	
11.8	Surge Protection Required	Yes / No	No	
11.9	Additional datasheet from manufacturer			
	included with tender for each flow meter type	Yes / No	Yes	
12 pH ANYLYZER				
12.1	Manufacturer		Refer to PS	
12.2	Sensor Model		Refer to PS	
12.3	Transmitter Model		Refer to PS	
12.4	Number of Relay outputs	No.	Refer to PS	
12.5	Detection Range	pH	Refer to PS	
12.6	Process Connection		Refer to PS	
12.7	Industrial Ethernet Enabled	Yes / No	Yes	
12.8	Surge Protection Required	Yes / No	Yes	
12.9	Local Indication Required	Yes / No	Yes	
12.10	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
13 TURBIDITY METER				
13.1	Manufacturer		Refer to PS	
13.2	Sensor Model		Refer to PS	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
13.3	Transmitter Model		Refer to PS	
13.4	Detection Range	NTU	Refer to PS	
13.5	Number of Relay outputs	No.	Refer to PS	
13.6	Process Connection		Refer to PS	
13.7	Industrial Ethernet Enabled	Yes / No	Yes	
13.8	Surge Protection Required	Yes / No	Yes	
13.9	Local Indication Required	Yes / No	Yes	
13.10	Additional datasheet from manufacturer			
	included with tender	Yes / No	Yes	
14 LEVEL SWITCHES: FLOAT				
14.1	Manufacturer			
14.2	Model			
14.3	Type			
15 LIMIT SWITCHES				
15.1	Manufacturer			
15.2	Model			
15.3	Type		Inductive Proxy	
16 SURGE PROTECTION				
16.1	Instrument Power Supply Circuits - Manufacturer			
16.2	Instrument Power Supply Circuits - Model			
16.3	Instrument Signal Loop - Manufacturer			
16.4	Instrument Signal Loop Circuits - Model			
16.5	Instrument Transducer Loop - Manufacturer			
16.6	Instrument Transducer Loop Circuits - Model			

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

INSTRUMENTATION				
Item no.	Description	Units	Specified	Offered
17	INSTRUMENT CONTROLLER KIOSKS			
17.1	Manufacturer			
17.2	Material of Construction: 1.6mm Mild Steel /		1.6mm 3CR12 minimum	
	2.0mm Mild Steel / Electro Galvanized /			
	Stainless Steel / 3CR12 / Fibre Glass			
17.3	Epoxy Powder Coated	Yes / No	Yes	
17.4	Colour		Electric Orange	
17.5	IP Rating (Indoor)	IP	54	
17.6	IP Rating (Outdoor)	IP	54	
17.6	Vent Plug	Yes/No	Yes	

1.1 TENDERER

Signature :

Name :

Duly authorised to sign on behalf of :

Telephone :

Fax :

Date :

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

RUSTENBURG WATER SERVICES TRUST

BID No RLM/RWST/OMM/0103/2024/25

RE-ADVERT: UPGRADE AND EXTENSION OF BOSPOORT WATER TREATMENT WORKS – MECHANICAL AND ELECTRICAL WORKS

T2.3 TECHNICAL SCHEDULES

T2.3.3 Civil

--	--	--	--	--	--

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

T2.3.3 CIVIL TECHNICAL SCHEDULES

Section	Description	Page
1.	RESILIENT SEAL GATE VALVE.....	T2.3.3-3
2.	WEDGE GATE VALVE.....	T2.3.3-3
3.	BUTTERFLY VALVES	T2.3.3-3
4.	CHECK/NON-RETURN VALVES.....	T2.3.3-4
5.	AIR VALVES.....	T2.3.3-4
6.	HYDRAULIC CONTROL VALVES.....	T2.3.3-5
7.	ULTRASONIC FLOW METERS	T2.3.3-5
8.	TURBINE FLOW METERS.....	T2.3.3-5
9.	MAGNETIC FLOW METERS	T2.3.3-6
10.	PIPE FITTINGS AND SPECIALS.....	T2.3.3-6
11.	STEEL PIPE LENGTHS	T2.3.3-7

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

IMPORTANT NOTE:

Refer to the Particular Specifications

No.	Item	Technical Particulars
1. RESILIENT SEAL GATE VALVE		
1.1	General Data	
1.1.1	Country of origin	
1.1.2	Manufacturer (name & country)	
1.1.3	Supplier	
1.1.4	Product name	
1.2	Materials	
1.2.1	Valve body	
1.2.2	Spindle	
1.2.3	Disc	
1.2.4	Valve seat	
2. WEDGE GATE VALVE		
2.1	General data	
2.1.1	Country of origin	
2.1.2	Manufacturer (name & country)	
2.1.3	Supplier	
2.1.4	Product name	
2.2	Materials	
2.2.1	Valve body	
2.2.2	Spindle	
2.2.3	Disc	
2.2.4	Valve seat	
3. BUTTERFLY VALVES		
3.1	General Data	
3.1.1	Country of origin	
3.1.2	Manufacturer (name & country)	

Contractor	Witness 1	Witness 2	Employer	Witness 1	Witness 2

No.	Item	Technical Particulars
3.1.3	Supplier	
3.1.4	Product name	
3.2	Materials	
3.2.1	Valve body	
3.2.2	Sub-shaft	
3.2.3	Disc	
3.2.4	Valve seat	
4. CHECK/NON-RETURN VALVES		
4.1	General data	
4.1.1	Country of origin	
4.1.2	Manufacturer (name & country)	
4.1.3	Supplier	
4.1.4	Product name	
4.2	Materials	
4.2.1	Valve body	
4.2.2	Spindle	
4.2.3	Disc	
4.2.4	Valve seat	
5. AIR VALVES		
5.1	General data	
5.1.1	Country of origin	
5.1.2	Manufacturer (name & country)	
5.1.3	Supplier	
5.1.4	Model number	
5.1.5	Product name	
5.2	Materials	
5.2.1	Valve body	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

No.	Item	Technical Particulars
5.2.2	Float	
6.	HYDRAULIC CONTROL VALVES	
6.1	General Data	
6.1.1	Country of origin	
6.1.2	Manufacturer (name & country)	
6.1.3	Product name	
6.2	Materials	
6.2.1	Valve body	
6.2.2	Spindle	
6.2.3	Disc	
6.2.4	Valve seat	
6.2.5	Others (Tenderer to specify)	
7.	ULTRASONIC FLOW METERS	
7.1	Manufacturer (name & country)	
7.2	Supplier	
7.3	Type	
7.4	Model	
7.5	Country of manufacturer	
7.6	Installation contractor	
8.	TURBINE FLOW METERS	
8.1	Manufacturer (name & country)	
8.2	Supplier	
8.3	Type	
8.4	Model	
8.5	Country of manufacturer	
8.6	Installation contractor	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

No.	Item	Technical Particulars
9.	MAGNETIC FLOW METERS	
9.1	Manufacturer (name & country)	
9.2	Supplier	
9.3	Type	
9.4	Model	
9.5	Country of manufacturer	
9.6	Installation contractor	
10.	PIPE FITTINGS AND SPECIALS	
10.1	Steel	
10.1.1	Country of origin	
10.1.2	Manufacturer (name & country)	
10.1.3	Place of manufacture	
10.1.4	Supplier	
10.1.5	Material grade	
10.2	Stainless Steel	
10.2.1	Country of origin	
10.2.2	Manufacturer (name & country)	
10.2.3	Place of manufacture	
10.2.4	Supplier	
10.2.5	Material grade	
10.3	Coating and Lining	
10.3.1	Application factory name	
10.3.2	Location of factory	
10.3.3	Epoxy lining product name	
10.3.4	Epoxy coating product name	
10.3.5	UV-Resistant multi-purpose epoxy product name	
10.3.6	Aliphatic polyurethane product name	
10.3.7	Polymer modified bitumen (Bituguard or Densotherm) product name	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

No.	Item	Technical Particulars
10.3.8	Rigid polyurethane product name	
11. STEEL PIPE LENGTHS		
11.1	General Data	
11.1.1	Country of origin	
11.1.2	Manufacturer (name & country)	
11.1.3	Place of manufacture	
11.1.4	Supplier	
11.1.5	Material grade	
11.2	Coating	
11.2.1	Polymer modified bitumen (Bituguard)	
	Application factory	
	Name of product	
11.2.2	3 Layer high density polyethylene	
	Application factory	
	Names of products	
11.2.3	Fusion bonded medium density polyethylene (Sintakote)	
	Application factory	
	Name of product	
11.2.4	Rigid Polyurethane	
	Application factory	
	Name of product	
11.3	Lining	
11.3.1	Epoxy (product name)	
11.3.2	Epoxy application factory	
11.3.3	Cement mortar application factory	

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2

TENDERER

.....
Name

.....
Date

.....
Position

.....
Signature

Duly authorised to sign on behalf of:

Telephone :

Contractor

Witness 1

Witness 2

Employer

Witness 1

Witness 2