	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		


Project Name : Coal Plant Maintenance Resources
Project location : Eskom Lethabo PowerStation

Scope of the project : Mechanical maintenance works including but not limited to inspection, refurbishments, removal, replacement and repairs, installations, lubrication and housekeeping on the following equipment: All coal conveyors; Fire and Dust suppression system; spillage control systems; chutes and silos

Eskom Contract's Custodian

Name: Bongumenzi Mavundla

Date: 20/07/2022

Signature: 

Eskom's SHE Functionary

Name: Tshokolo Mofokeng

Date: 20/07/2022

Signature: 

Eskom's Engineer

Name:

Date : _____

Signature: _____

Eskom's Procurement

Name: N/A


Date : _____

Signature: _____

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		


Content

	Page
1. Introduction	5
2. Supporting Clauses	5
2.1 Scope	5
2.1.1 Purpose	5
2.1.2 Applicability	5
2.2 Normative/Informative References	6
2.2.1 Normative	6
2.2.2 Informative	6
2.3 Definitions	7
2.4 Abbreviations	10
2.6 Roles and Responsibilities	10
2.6.1 Commitment	10
2.5 Related/Supporting Documents	19
3. Specification	19
3.1 Scope of work	19
3.2 Legal Compliance	20
3.2.1 Section 37(2) (Legal) Agreement	20
3.2.2 Hazardous work by children (Child Labour)	20
3.3 Eskom Requirements	21
3.4 Construction Professional Registration	21
3.5 Notification of Construction Work	21
3.6 SHE Policy	22
3.7 COID	22
3.8 Costing for SHE within the Project	22
3.9 Statutory Appointments	22
3.10 Eskom Life-saving Rules	24
3.11 Substance Abuse	25
3.12 Contractor organisational Structure	25
3.12.1 Principal Contractor Organogram	25

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.


	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.12.2 Appointed Contractor/s Organogram	25
3.13 Risk assessment (refer to 32-520)	26
3.14 Safe work procedures / method statements	30
3.15 Roof work (refer to 32- 418)	31
3.16 Construction Sites	31
3.17 Fire Equipment and maintenance	31
3.18 Flammable and Combustible Liquids	32
3.18.1 Refuelling at the construction site	32
3.19 First Aid and Equipment	32
3.19.1 Boxes and equipment	33
3.20 SHE Communication Systems	34
3.20.1 Statutory Health and Safety Committees	34
3.20.2 Non-statutory health and safety committees	35
3.20.3 Agenda	35
3.20.4 Minutes and action items for all health and safety committee meetings	36
3.20.5 Tool box talks / Daily team talks / pre job meetings	36
3.21 SHE Training	37
3.21.1 Induction training	37
3.21.2 Site specific induction training	37
3.21.3 Visitors to site induction	38
3.21.4 General training	38
3.22 Contractor Site Establishment	38
3.22.1 Site roads	38
3.22.2 Construction vehicle safety	38
3.23 Housekeeping and Order	39
3.23.1 Stacking	40
3.24 Workplace Signage and Colour Coding	40
3.25 Tools and Equipment	41
3.25.1 Hand tools	41
3.26 Ladders	41
3.27 Scaffolding	42
3.28 Auditing	42

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.


	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.28.1 Approval and compliance of principal contractor SHE plan	42
3.28.2 Eskom SHE audits	43
3.28.1 Contractor audits	43
3.29 Smoking	43
3.30 Cellular Phones	43
3.31 Occupational Health, Hygiene and Rehabilitation	43
3.31.1 Medicals	43
3.32 Working at Heights	44
3.32.1 General Requirements	44
3.33 Risk Assessments	45
3.34 Safe Work Procedures and Practices / Safe Operating	45
3.35 Personal Protective Equipment Requirements	46
3.36 Incident Investigation	46
3.37 Emergency Management	46
3.38 Non-Conformance and Compliance	46
3.39 SHE File	47
3.40 Work Stoppage	47
3.41 Hours of Work	48
3.41.1 Normal work	48
3.41.2 Night work	48
3.41.3 Overtime	48
3.42 Omissions from Safety and Health Requirements Specification	49
3.43 Contract Sign-Off	49
4. Acceptance	49
5. Revisions	49

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

1. Introduction

Eskom's responsibility and commitment is to ensure a safe working environment is in line with its Safety, Health, Environmental and Quality Policy, along with legislative obligations.

This SHE specification is Eskom the minimum requirements which are required to be met for the specific contract and for the duration of the contract period by contractors and where required, the delivery organisation.

The contractor has to develop a SHE plan, which meets these requirements as well as all the relevant applicable legislation that they have to conform to.

Eskom in no way assumes the contractor's legal responsibilities. The contractor is and remains accountable for the quality and the execution of his/her health and safety programme for his/her employees and appointed contractor employees.

This SHE specification reflects minimum requirements and should not be construed as all encompassing.

Note 1: All the requirements listed hereunder are in relation to the contract and do not supersede or replace any organizational SHE requirements.

Where requirements listed are already in place, then the organisational requirements must be taken cognisance of and listed in the respective SHE plans. If there are any additional Eskom and or legislative requirements listed in the SHE specification, then these must be addressed.

2. Supporting Clauses

2.1 Scope

This SHE specification lists the legislative and Eskom requirements and where applicable, any requirements pertaining to Local Authorities / Municipal by-laws / Environmental legislation that must be met by the contractor.

2.1.1 Purpose

This document will provide a standardised approach to the compilation of SHE specifications throughout Eskom for contracts, standards and NEC 3 contracts.


2.1.2 Applicability

This SHE specification is applicable to any contracting organisation who intends tendering for the contract.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2.2 Normative/Informative References

Parties using this document shall apply the most recent edition of the documents listed in the following paragraphs.

2.2.1 Normative

- [1] Basic Conditions of Employment Act No 75 of 1997.
- [2] Occupational Health and Safety Act and Regulations No 85 of 1993.
- [3] National Environmental Management Act 107 of 1998.
- [4] National Road Traffic Act 93 of 1996.
- [5] 32-37 Eskom Substance Abuse Procedure.
- [6] 32-136 Contractor Health and Safety Requirements
- [7] 240-62196227 Life- saving Rules
- [8] 32-95 Environmental, Occupational Health and Safety Incident Management Procedure
- [9] 32-727 SHEQ Policy
- [10] 32- 418 Working at Heights Procedure
- [11] 240-62946386 Vehicle and Driver Safety Management Procedure
- [12] 32-520 Risk Assessment procedure
- [13] Plant Safety Regulations.


2.2.2 Informative

- [1] Tobacco Products Control Act 83 of 1993 (Updated 2011.05.19)
- [2] SANS 1186 Symbolic Safety Signs
- [3] Constitution of the Republic of South Africa No 108 of 1996
- [4] DMN 34-110 Operating A Vehicle Mounted Crane
- [5] DMN 34-1981 Excavations.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.


	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2.3 Definitions	Explanation
Appointed contractor	Means a contractor appointed by the principal contractor
Baseline risk assessment	(32-520) baseline operational risks refer to the health and safety risks associated with all standard processes and routine activities in the business
Business unit (BU)	(32-296) means any defined unit within the Eskom environment, operating as a business under a particular cost-centre number. In the context of this document and in terms of health and safety, any reference to a BU includes a defined unit within any Eskom division and its subsidiaries
Client	(OHS Act) Eskom representative (Internal – Asset Owner), also referred to as the contract administrator/custodian or agent or project manager (as defined in the contract). He/she is the person responsible for ensuring that the works or services are executed in terms of the contract, as well as adherence to legislation pertaining to the contract.
Competent person	(OHS Act) means any person having the knowledge, training, experience, and qualifications, specific to the work or task being performed, provided that, where appropriate, qualifications and training are registered in terms of the South African Qualifications Authority Act, 1995 (Act No. 58 of 1995)
Contractor	(OHS Act) means an employer as defined in section 1 of the Act who performs contracted work and includes principal contractors
Construction work	Any work in connection with <ul style="list-style-type: none"> a. the construction, erection, alteration, renovation, repair, demolition or dismantling of or addition to a building or any similar structure. b. the construction, erection, maintenance, demolition or dismantling of any bridge, dam, canal, road, railway, runway, sewer or water reticulation system or the moving of earth, clearing of land, the making of excavation, piling or any similar civil engineering structure or type of work.
Consultant	means a person providing professional advice
Controlled disclosure	controlled disclosure to external parties (either enforced by law or discretionary)
Duty of care to the environment	(32-136) anybody who causes or has caused or may cause significant pollution or degradation of the environment must take reasonable measures to prevent such pollution or degradation from occurring, continuing, or recurring. If such harm to the environment is authorised by law or cannot reasonably be avoided or stopped, such person must minimise and rectify such pollution or degradation of the environment
Employee	(OHS Act) means, subject to the provisions of subsection (2), any person who is employed by or works for an employer and who receives or is entitled to receive any remuneration or who works under the direction or supervision of an employer or any other person
Employer	(OHS Act) means, subject to the provisions of subsection (2), any person who employs or provides work for any person and remunerates that person or expressly or tacitly undertakes to remunerate him/her, but excludes a TES (ex labour broker) as defined in section 1(1) of the Labour Relations Act 1956 (Act No. 28 of 1956)

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.


	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2.3 Definitions	Explanation
Environment	(32-94) means: a. the land, water, and atmosphere of the earth; b. micro-organisms and plant and animal life; and c. any part or combination of (a) and (b) and the interrelationships among and between them, and the physical, chemical, aesthetic, and cultural properties and conditions of the foregoing that influence human health and well-being
Environmental Management plan	A detailed plan of action prepared to ensure that recommendations for enhancing or ensuring positive impacts and limiting or preventing negative environmental impacts are implemented during the life-cycle of a project. This Environmental Management Plan should preferably form part of Eskom's Environmental Management System
Eskom requirements	Eskom requirements flowing from directives, policies, standards, procedures, specifications, work instructions, guidelines, or manuals
Fall protection plan	(OHS Act) means a documented plan of all risks relating to working from an elevated position, considering the nature of work undertaken, and setting out the procedures and methods to be applied in order to eliminate the risk
Hazard	(OHS Act) means a source of, or exposure to, danger
Hazard identification	(OHS Act) means the identification and documenting of existing or expected hazards to the health and safety of persons, which are normally associated with the type of construction work being executed or to be executed
Health and safety file	(OHS Act) means a file or other record in permanent form, containing the information required in relation to the contract.
Health and safety plan	(OHS Act) means a document plan that addresses hazards identified and includes safe work procedures to mitigate, reduce, or control hazards identified
Health and safety specification	(OHS Act) means a document specification of all health and safety requirements pertaining to associated to a contract, so as to ensure the health and safety of persons.
Health and safety requirements	means comprehensive health and safety requirements for a contract, project, site, and scope of work. This specification is intended to ensure the health and safety of persons, both workers and the public, and the duty of care to the environment. The health and safety requirements must be specific to each contract, project, site, and scope of work
Lifesaving Rules	(240-62196227) a rule that, if not adhered to, has the potential to cause serious harm to people
Medical Certificate of fitness	(OHS Act) means a certificate valid for one year, issued by an occupational health practitioner, issued in terms of the regulations, whom shall be registered with the Health Professions Council of South Africa
Medical surveillance	(OHS Act) means a planned programme or periodic examination (which may include clinical examinations, biological monitoring, or medical tests) of employees by an occupational health practitioner or, in prescribed cases, by an occupational medicine practitioner

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.


	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2.3 Definitions	Explanation
Method statement	(OHS Act) means a written document detailing the key activities to be performed in order to reduce, as reasonably as practicable, the hazards identified in any risk assessment
Organisation	may be defined as a group of individuals (large of small) that is cooperating under the direction of executive leadership in accomplishment of certain common objects
Pre-job meetings	(34-227) means a meeting that is held prior to the commencement of the day's work and that is attended by all the relevant employees associated with the work task
Principal contractor	(In the text of this document) Means an employer, as defined in section 1 of the OHS Act, who intends to tender for or has signed a contract with Eskom for services rendered.
Provincial director	(OHS Act) means the provincial director as defined in Regulation 1 of the General Administrative Regulations under the Act
Responsible Manager	Is a Manager of a department, section or operating/business unit who has been appointed as part of the Eskom delegation of authority process with the aim to assist the applicable 16(2) assigned person in executing his/her duties in terms of the Occupational Health and Safety Act
Risk assessment	(OHS Act) means a programme to determine any risk associated with any hazard at a construction site in order to identify the steps needed to be taken to remove, reduce, or control such hazard.
Site	(34-228) means an Eskom department, unit, complex, building, specific project, work site, or the site where agents, clients, principal contractors, contractors, suppliers, vendors, and service providers provide a service to Eskom, directly or indirectly
Service provider	any private person or legal entity that provides any service(s) to Eskom for compensation
Subsidiary	(32-94) an enterprise controlled by another (called the parent) through the ownership of greater than 50% of its voting stock
Supplier	(32-1034) means a natural or legal person who renders a service and may include the following current or potential supplier vendor, contractor, consultant
Task	(34-227) a segment of work that requires a set of specific and distinct actions for its completion
Toolbox talks	(34-227) where the team leader, after conducting pre-task planning, shares all the tasks at hand and discusses task allocation, the identified risks, and the control measures with all his/her team members on site before commencing a specific task and documenting the agreed strategy. (This shall be done to ensure common understanding of the tasks, risks, and control measures required.)
The Act	(OHS Act) means the Occupational Health and Safety Act No. 85 of 1993, as amended, and the Regulations thereto
Visitor	any person visiting a workplace with the knowledge of, or under the supervision of, an employer.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2.4 Abbreviations

Abbreviation	Description
AIA	Approved Inspection Authority
BU	Business Unit
CE	Chief Executive
CNC	(Eskom) Customer Network Centre
CR	Construction Regulations of the OHS Act
COID Act	Compensation for Occupational Injuries and Diseases Act
DMR	Driven Machinery Regulations
DoL	Department of Labour (Inspection and Enforcement services – Provincial office)
EAP	Employee Assistance Program
EP	Emergency Preparedness
ERfW	Environmental Regulations for Workplaces
GAR	General Administrative Regulations
GSR	General Safety Regulations
HCS	Hazardous Chemical Substances
LDV	Light Delivery Vehicle
LoG	(COID) Letter of Good Standing
MSDS	Material Safety Data Sheets
NEMA	National Environmental Management Act
OHS Act	Occupational Health and Safety Act and Regulations, 85 of 1993
SACPCMP	South African Council for the Project & Construction Management Professions
SABS	South African Bureau Standard
SANS	South African National Standard

2.6 Roles and Responsibilities

2.6.1 Commitment


Visible commitment is essential to providing a safe work environment. Managers, supervisors and employees at all levels must demonstrate their commitment by being proactively involved in the day-to-day operations, in particular the Occupational Health and Safety aspects of any project / contract. Legislation requires that each employee must take reasonable care of themselves and their fellow workers, from management level down to the lowest employee level.

2.6.2 Principal contractors and appointed contractors

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		


Note 1: Most of the roles and responsibilities listed apply to both principal contractors and any appointed contractors. Where some of the listed do not apply to both, then the specific responsibilities will be listed and titled. The **Principal Contractor** shall:

1. Carry out all duties as listed in section 8, 9 and 10, the various other regulations that form part of the OHS Act and Regulation 7 of the Construction Regulations.
2. **Principal Contractor** must notify the provincial director of the Department of Labour in writing of all construction work if it falls within the scope of Regulation 4 of the Construction Regulations (if this has not been arranged and or done by the client/agent);
3. Carry accountability and responsibility for the safety and health of their employees and their appointed contractors within their working area, as contemplated by section 37(2) of the OHS Act;
4. Shall keep a record of all employees including the appointed contractor employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.
5. Ensure that all their appointees are made aware of their accountabilities and responsibilities in terms of their appointment and that they advise and assist these appointees in the execution of their duties.
6. Ensure that the minimum legislative, regulatory and Eskom SHE requirements are complied with on all work sites.
7. Give the Eskom project managers and line managers / responsible managers their full participation and cooperation.
8. Compile a SHE (health and safety) file where all relevant health and safety records must be kept for each work site.
9. **Principal Contractor** must hand over a consolidated (to include any appointed contractors files) health and safety file to the Eskom project manager on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.
10. **Principal Contractor** must hand over a consolidated (to include any appointed contractors files) health and safety file to the **Eskom Project Manager** on completion of the project. This is to include all drawings, designs, lists of materials used and other applicable information about the completed project, as well as the list of appointed contractors, the agreement, and the type of work completed.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		


11. **Principal Contractor** must provide the project manager with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company. Similarly, the principal contractor must provide the Eskom project manager with all the valid letters of good standing from their appointed contractors.
12. **Appointed Contractor** must provide the principal contractor with a certified copy of his/her Compensation Commissioner's valid letter of good standing before the commencement of work and any future renewal letters obtained during the project for record-keeping purposes. The letter of good standing shall reflect the name of the contractor's company.
13. Appoint competent staff to perform the project work and ensure that all employees are trained in the health and safety aspects relating to such work and that the employees understand the hazards associated with all other work being carried out on the project.
14. Ensure that all employees are conversant with all relevant work procedures and that they adhere to such procedures. Similarly (without removing the appointed contractors' responsibilities), ensure that their appointed contractors and their employees are conversant with all relevant work procedures and that they adhere to such procedures.
15. Co-ordinate the activities of all the appointed contractors in the interests of safety and health;
16. Ensure that potential contractors (whom they intend appointing) submitting tenders have made detailed provision for the cost of safety and health measures throughout the project.
17. Stop his /her employees and any appointed contractors if project work is not in accordance with the health and safety plan or if such work poses a threat to the health and safety of persons or a risk of degradation to the environment.
18. Take reasonable steps to ensure cooperation between all their appointed contractors.
19. Only appoint contractors to do work, if satisfied that the contractor has the necessary competencies and resources to perform the work safely.
20. Appoint full-time competent employees in writing to supervise the performance of all specified work throughout the contract period.

Note 2: No work may commence and or continue without the presence of the appointed project manager or project supervisor during performance of the contracted work.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

21. Ensure that the supervisor or manager do not supervise work on any site other than the site for which such supervisor has been appointed for.

Note 3: In determining the number of appointed competent supervisors, the nature and scope of work being performed, shall be taken into consideration.


Note 4: If a sufficient number of competent employee(s) have been appointed to assist the construction supervisor, the construction supervisor may supervise more than one site.

22. Appoint a part time safety officer in writing.
23. Not victimise or dismiss employees, by virtue of the employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements;
24. Follow a process of disciplinary action if any of their employees or their appointed contractor employees have transgressed any of the requirements of the health and safety specification, safety and health plans, site rules or any other requirements.
25. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
26. Before the commencement of any work, conduct risk assessments which shall include public safety. This should be done by a competent person appointed in writing with a view to identify hazardous and potentially hazardous work operations.
27. Ensure that pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task or not.
28. Take prime responsibility for all aspects of environmental management associated with the project activity for which they are responsible.
29. Provide any appointed contractor who is making a bid or is appointed to perform work on Eskom's behalf, with the relevant sections of the documented Eskom's SHE Specification.
30. are required to approve appointed contractor's health and safety plans if they meet all the requirements.
31. Must ensure that an organisation medical surveillance programme for the duration of the contract is in place and maintained.
32. Prior to having pre-employment and periodic medicals fitness examinations conducted, person/man job specifications must be compiled and handed to the occupational health practitioner.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

33. Ensure that pre-employment, periodic and exit medicals are carried out on their employees. Medical assessments must be conducted by a registered Occupational Health Practitioner. During the pre-employment medical, where employees will be required to work at heights, they will also be required to undergo the required employee physical and psychological fitness examinations.
34. Ensure, prior to the commencement of construction work, that all persons involved in the project work, as well as the appointed contractors, have received a health and safety induction training session. Similarly, ensure that all visitors to site undergo the site's induction training.
35. Ensure, prior to the commencement of construction work or contracted work, that all their employees involved in the project work, as well as the appointed contractors, have received task-specific training.
36. Issue risk-based personal protective equipment (PPE) as a measure of last resort to their employees, inspect such equipment regularly and ensure recipients of PPE are trained in the proper use, care and where necessary, the maintenance of PPE;

Note 5: should the principal contractor or his/her appointed contractors entertain visitors on site, they will be held responsible for the provision and wearing PPE.


37. Erect their own site huts, temporary buildings, storage areas, toilets, fencing, and any other structure as may be required. Any such structures shall be positioned and erected in compliance with any instructions from the Eskom project manager and the relevant site safety and fire prevention requirements;
38. On completion of the work remove all structures erected by them, and where required by law rehabilitate the environment.
39. Where performing work with the environment, ensure that minimal damage is done and that where an Environment Management Plan is in place, then adhere to the plan.
40. Respect the rights of land owners/lessors and the preservation of their registered activities;
41. Must have a substance abuse program which must be in line with the requirements of the OHS Act.
42. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on the work sites.

Note 6: Eskom will not tolerate the presence of anyone who is or who appears to be under the influence of alcohol or any other intoxicating substance whilst performing work for them or on any work site.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

43. Ensure that all equipment and tools used comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these;
44. Ensure that all incidents are reported and investigated timeously by competent incident investigators.
45. Be involved in all of their appointed contractor's investigations.
46. Establish health and safety committees, hold such committee meetings on all sites, and ensure that appointed contractors participate in their health and safety meetings.
47. Chair their own health and safety committee meetings and record such meetings.
48. Appoint sufficient number of health and safety representatives in terms of legislative requirements and ensure that the appointed contractors appoint health and safety representatives for their work sites.
49. When appointing contractors, advise the project manager in writing timeously and obtain his/her approval prior to them commencing work.
50. Shall keep a record of all employees including the appointed contractor's employees, including date of induction, relevant skills and licenses and be able to produce this list at the request of the Eskom Project Manager.

2.6.3 Construction Managers/ Contract Managers


Note 1: No work may commence and or continue without the appointed supervisor or manager during the performance of the contracted work.

1. Not supervise construction work on any construction site other than the site they have been appointed to supervise;
2. Assist the contractor and/or the appointed safety officer in conducting site induction training for new staff and site visitors;
3. Instruct and train all employees under their control on any hazardous and related work procedures, before any work commences and thereafter, at such times as may be determined by a risk assessment;
4. Ensure that the minimum legislative and Eskom SHE requirements are complied with on all work sites;
5. Stop any construction work that is not in accordance with the safety and health plan or if such work poses a threat to the safety and health of persons or a risk of degradation to the environment;
6. Ensure that risk-based personal protective equipment (PPE) has been issued and employees wear/use the PPE as instructed.
7. Inspect such PPE on a regular basis and record the inspections;
8. Ensure that all incidents are reported to the client and are investigated.
9. Be involved in all investigations that occur within their area of responsibility.
10. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

11. Ensure that employees under their control are conversant with all relevant work procedures and that they adhere to such procedures;
12. Before the commencement of any work, where possible, assist in the conducting of risk assessments and ensure that appropriate mitigating measures have been considered and implemented.
13. Ensure that daily or pre-task risk assessments are conducted and documented daily and prior to the starting of any new task, irrespective of whether it is a repetitive task. Ensure that the team are involved in the abovementioned risk assessments;
14. Hold tool box talks at the start of each day/ task to discuss health and safety issues as well as confirming the requirements of the daily risk assessments;
15. Ensure that all appropriate precautions are taken to protect persons (visitors, members of the public, and other contractors) present at work or in the vicinity of a construction site against all risks that may arise from such site.
16. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/she is under the influence. Furthermore, report such instances to contract management;
17. Ensure that all equipment and tools used on site comply with OHS Act requirements with respect to condition, use, care, storage, maintenance, and the management of these.
18. Ensure that they and their contractor managers give clear and unambiguous instructions for the project work, to the employees for whom they are responsible for.
19. Not victimise their employees by virtue of their employees divulging health and safety information or suspecting such information has been divulged, in the interests of health and safety requirements (reference – section 26 of the OHS Act).
20. Where any work is performed which involves the environment, ensure that minimal damage is done to the environment and that where an Environment Management Plan is in place, then the plan adhere to the plan.
21. Stop any employee or contractor from performing construction work which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.

2.6.4 Contractor site supervisor or Contract Supervisor


Must:

1. Be competent to perform the required supervisory tasks;
2. Ensure their employees and all appointed contractors comply with the required statutory and Eskom project requirements;
3. Inspect all work done by the Contractors to ensure adherence to Eskom's standards and specifications
4. Conduct follow-up inspections to ensure findings are closed out and preventative action is in place.
5. Monitor contractors for adhere to statutory requirements and safety standards.
6. Monitor contractors overall SHE performance on site in order to achieve excellent results

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

7. Ensuring a Safe working environment is established and maintained by the contractor for the elimination of unsafe acts by all people whilst on the project site.
8. Discuss all SHE related problems with the relevant contractor management timeously in the first instance and thereafter the Eskom project manager in the second instance relating to procedure requirements, non-conformance's identified ,corrective actions, audits and inspection schedules.
9. Ensuring that quality records are maintained in accordance with legislative and Eskom requirements;
10. Continual liaison between the **Principal Contractor**, appointed contractors and employees.
11. Ensures that employees and appointed contractors are aware of latest standards, procedures, work instructions and safety regulations issued by Eskom:
12. Conduct site Inspections for compliance to SHE requirements and compiles the relevant inspection reports.
13. Submit the observation reports to the relevant management.
14. Have meaningful participation in the project statutory health and safety committee meetings.
15. Participate in all appointed contractor incident investigations.
16. Participate in the **Principal Contractor** emergency preparedness planning.
17. Ensure that their own employees and those of any appointed contractor are competent to perform the tasks assigned.
18. Issue site instructions on behalf of the **Principal Contractor** where and when the appointed contractors deviate from safety requirements.
19. Assist the **Principal Contractor** with the handing over process, in particular the SHE file and relevant documentation.

2.6.5 Employees


Must:

1. Be responsible for their own safety and health and that of their co-workers;
2. Co-operate with their employer to meet all of the employer's as well as legislative and Eskom requirements;
3. Familiarise themselves with their responsibilities during induction and awareness training sessions, some of which are:
 - a. familiarising themselves with their workplaces and safety and health procedures;
 - b. working in a manner that does not endanger them or cause harm to others;
 - c. ensuring that the work area is kept tidy;
 - d. reporting all incidents and near misses;
 - e. protecting fellow workers against injury by performing job observations;
 - f. reporting unsafe acts and unsafe conditions;
 - g. reporting any situation that may become dangerous; and
 - h. carrying out lawful orders and obeying safety and health rules;
4. Who become aware of any person disregarding a safety notice, instruction, or regulation, immediately report this to the person concerned. If the person persists,

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- stop that person from working, and report the matter to contractor management and/or Eskom's project manager or supervisor immediately.
- Not damage, alter, remove, render ineffective, or interfere with anything that has been provided for the protection of the site or for the health and safety of persons this includes any guarding of machinery or equipment.
 - Obey any safety signs and adhere to any site demarcation at all times.
 - When entering or leaving the site, do so via the official designated access/departure routes. Where reflective jackets/bibs are required to be worn, wear them.
 - Be subjected to any disciplinary action, if having transgressed any of the requirements of the health and safety site rules, Eskom requirements, company requirements, or legislative requirements.
 - Avoid any act that may endanger their own health and safety or that of fellow employees, members of the public, or visitors who may be affected by their acts and/or omissions at work.
 - Have the right to obtain proper information from their employer regarding health and safety risks and measures related to the work processes.
 - Use facilities placed at their disposal and not misuse anything provided for their own protection or that of others.
 - Have the right to remove themselves from danger when they have good reason to believe that there is an imminent and serious danger to their health and safety and have the duty to inform their supervisor immediately of such danger.
 - Report to their supervisor (in the first instance), the principal contractor (in the second instance), and/or the Eskom project manager, any substandard acts and/or conditions that have come to their attention and that have not been rectified or acted on by their contractor management timeously.
 - Have the right and the duty at any workplace to participate in ensuring healthy and safe working conditions, to the extent of their control, over the equipment and methods of work adopted.
 - Maintain the surrounding area of the work site in a neat and tidy condition.
 - Have meaningful participation in regular health and safety meetings.
 - Have the right to refuse to perform or continue to perform any task/job on the grounds of health, safety, and environmental concerns.
 - When given instructions, understand the instructions and be permitted to clarify those instructions.


2.6.6 Contractor Health and Safety officer

- Promote a SHE culture within the organisations involved in the project / contract.
- The contractor's safety and health officer shall assist in the control of all health and safety-related matters on the sites.
- Be involved in the developing the project SHE plan and SHE policy.
- Be in constant liaison and cooperate with Eskom's SHE professionals responsible for providing them with a health and safety service.
- Ensure that this SHE specification is adhered to by his/her principal contractor and is submitted to any appointed contractors.
- Conduct audits and inspections of all work sites for the duration of the project.
- Be involved in the organisations incident investigations when required.
- Participate in the organisation's statutory and non-statutory health and safety committees meetings.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

9. Conduct organisational, site and visitor induction training.
10. Stop any employee or contractor from performing construction work, which is not in accordance with the principal contractor's and or appointed contractors health and safety plan which poses a threat to the health and safety of persons.
11. Ensure that no alcohol or other intoxicating substances are brought on to, or remains on, the premises / work sites and that no employee remains on site if he/she is under the influence. Furthermore, report such instances to contract management.
12. Make themselves available and ensure co-operation of employees under their control to undergo breathalyser and drug testing while entering and/or being on any Eskom work site by Eskom.
13. Carry out audits and or inspections on their contractors at least monthly and any appointed contractors on instructions of their contractor;
14. Carry out frequent behaviour observations of employees under their control at least monthly and any appointed contractors on instructions of their contractor.

2.5 Related/Supporting Documents

Eskom OHS Act 85 of 1993 section 37 (2) agreement to be signed at procurement during the signing of the NEC contract, it is the responsibility of the project manager to ensure that the 37(2) agreement is signed and a copy be kept in the contractor file at procurement. And contractor appointment in terms of Construction Regulation 2014 (5.1)(k)

3. Specification

3.1 Scope of work


Mechanical maintenance works including but not limited to inspection refurbishments, removal, replacement and repairs, installations, lubrication and housekeeping on the following equipment: All coal conveyors; Fire and Dust suppression system; spillage control systems; chutes and silos

Note: The contractor who will be awarded this contract will be known as the “**principal contractor**” and any contractor appointed by the principal contractor will be known as the “**appointed contractor**”.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.2 Legal Compliance

3.2.1 Section 37(2) (Legal) Agreement) & Principal Contractor Appointment CR 5.1(k)

A section 37(2) agreement & Contractor Appointment CR 5.1(k) must be signed between Eskom and the at the time of awarding the contract. **Principal Contractor** must ensure that a section 37(2) agreement & Contractor Appointment CR 5.1(k) are compiled between the **Principal Contractor** and all their appointed contractors for the contract.

The original copy of the section 37(2) Agreement & Contractor Appointment CR 5.1(k) must be retained by the contractor and a copy retained by the responsible project manager.

A copy of all the agreements must form part of the respective contractor's SHE file.

3.2.2 Hazardous work by children (Child Labour)

The constitution of the Republic of South Africa, in the "Bill of Rights" is clear on the rights of children, especially when it comes to:

1. being protected from exploitative labour practices;
2. not to be required or permitted to perform work or provide services that
 - i. are inappropriate for a person of that child's age; or
 - ii. place at risk the child's well-being, education, physical or mental health or spiritual, moral or social development;

and the Basic Conditions of Employment Act, Chapter six Section 43 "Prohibition of employment of children".

Before resorting to the use of child labour, due consideration must be given to the rights of the child in terms of the constitution. Where work is being performed which is not prohibited in terms of the constitution, then such work must be conducted in terms of the OHS Act "Regulations on Hazardous Work by Children in South Africa" with emphasis on paragraph 2 Purpose and Interpretation. Eskom does not condone the use of child labour and therefore all effort must be exercised and child labour should not be used.

3.2.3 OHS Act 85 of 1993

Principal Contractor and appointed contractors shall have an up to date copy of the OHS Act and regulations which will be available to all employees.


3.2.4 Legislative compliance

Principal Contractor will comply with all the legislation pertaining to this contract being:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

and all appointed contractors **Principal Contractor** will comply with all the legislation pertaining to this project being:

- The Constitution of the Republic of South Africa (particularly Section 24 of the Bill of Rights).
- Occupational Health and Safety Act 1993 (Act 85 of 1993) and its Regulations.
- National Environmental Management Act 1998 (Act 107 of 1998).
- Environment Conservation Act 1989 (Act 73 of 1989).
- National Water Act 1998 (Act 36 of 1998).
- Civil and Building Work Act.
- National Road Traffic Act 93 of 1996.
- Compensation for Occupational Injuries and Diseases Act.
- SANS Standards –Contractor shall use the relative standards applicable to the project.

3.3 Eskom Requirements

Principal Contractor shall, before commencement of the project ensure that all their employees are familiar with the relevant Eskom SHE documentation that is applicable to contract services.

3.4 Construction Professional Registration & Qualifications

Where applicable, **Principal Contractor** contractor and all his/her appointed contractors shall be registered in their respective levels as professionals in terms of the requirements of the SACPCMP.


The SACPCMP web address is <http://www.sacpcmp.org.za>

- SHE professionals (which include Construction Safety Officers) are required to register as professionals with the SACPCMP and possess National Diploma in Safety Management as a minimum qualification, other short course will be an advantage..
- Construction Managers are required to register as professionals with the SACPCMP.
- Construction agents are required to register as a professional with the SACPCMP if applicable.

3.5 Notification of Construction Work

Unless otherwise contractually agreed upon, the principal contractor must notify the relevant provincial director of the Department of Labour of the intention of carrying out any construction work as defined in Construction Regulation 4 of the OHS Act 85 of 1993. The notification form

Public

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

of construction work is listed as an annexure to the construction regulations of the OHS Act. A copy of the notification letter sent to the DoL shall be forwarded to the Project Manager on the same day as sent to the DoL. A copy of the letter and their approval must be kept in the SHE file. When the DoL provide a letter of approval, a copy of the approval must be sent to the Eskom Project Manager and a copy filed in the SHE file.

3.6 SHE Policy

SHE policy is a statement of intent and a commitment by the organisation's CE and senior management in relation to the relevant SHE roles and responsibilities, the achievement of their strategic objectives, values of integrity, customer satisfaction, excellence, and innovation.

The **Principal Contractor** and all appointed contractors, if already not in place, will be required to compile an organisational SHE policy in line with their SHE responsibilities. The policy must be signed by the organisation's CE or the appointed assistant to the CE OHS Act Section 16(2). The policy must be displayed in a prominent place within the workplace. A copy of the policy must be filed in the contractor SHE files and attached as an annexure in the SHE Plan.

3.7 COID Act

and all his/her appointed contractors shall be registered with an appropriate employment compensation commissioner and have available a valid letter of good standing (LoG) from such commissioner. The obligation lies with the contractors to ensure that the LoG remain valid throughout the contract period. A copy of the LoG must be filed in the contractor SHE files.

3.8 Costing for SHE within the Project


The costing for SHE must be itemised based on the overall scope of the project (i.e.) Training, provision of PPE, safety equipment purchases etc.

3.9 Statutory Appointments

For the duration of the contract, and all appointed contractors shall appoint competent employees who will meet the requirements of the OHS Act. Where appointments are made, contractors shall ensure that the appointees have been suitably trained and or informed of their responsibilities before getting them to accept such appointment. The relevant statutory appointments shall be made in accordance with the requirements of the OHS Act which includes the requirement of a competent person being appointed in the relevant roles. The statutory appointments should include but not limited to the following:

- Appointee 16.2
- OHS Act Construction Regulation 8(1) - Construction Manager (Full time)|

Public

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- OHS Act Construction Regulation 8(7) – Construction Supervisor
- OHS Act Construction Regulation 8(8) – Assistant Construction Supervisor
- OHS Act Construction Regulation 8(5) – Construction Health and Safety Officer(Full time)
- OHS Act General Administrative Regulation 9(2) – Incident Investigator
- OHS Act Hazardous Chemical Substances Regulation 3(3) Hazardous Chemical Substances Co-coordinator
- OHS Act, Section 17 – Health and Safety Representative.
- OHS Act General Machinery Regulation 2(1) – Supervision of Machinery
- OHS Act Construction Regulation 7(1)(V) Appointment of a Contractor (if appointing subcontractors)
- OHS Act Construction Regulation 9(1) - Person to Compile Risk Assessments
- OHS Act Construction Regulation 9(3) – Competent Person for Risk Assessments training
- OHS Act Construction Regulation 10(1) - Competent Person to Compile Fall Protection Plan
- OHS Act: Construction Regulations 23(1)(d)(i) Construction Vehicle and Mobile Plant Operator
- OHS Act: Construction Regulations 24(c) Electrical Installations and Machinery on construction sites
- OHS Act: Construction Regulations 28(a) Stacking and Storage Supervisor on Construction sites
- OHS Act: Construction Regulations 24(c) Elect construction sites
- OHS Act: Construction Regulations 29(h) Firefighting Equipment Inspector
- OHS Act General Safety Regulations 3(4) – First Aider/s
- Operator of Lifting Machinery, Lifting Tackles & Forklift Training DMR 18(11)
- Inspector of Lifting Machinery & Tackles DMR 18(5)


3.9.1 Non-statutory appointments

- Eskom requirement – Emergency Planning Co-coordinator
- Eskom requirement - Chairperson of Health and Safety Committee

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.10 Eskom Life-saving Rules

1. Eskom views health and safety in high esteem and encourages that any organisation who performs work for Eskom in Eskom adopt the same view.
2. Five Life-saving rules have been developed that will apply to all Eskom Employees, agents, consultants, and **contractors**. Failure to adhere to these rules by any Eskom employee, Principal **Contractor** employee or **Appointed Contractor** is considered a serious transgression. To prevent serious injury or death of any employee, labour broker or contractor working in any area within Eskom these rules are being implemented
3. Contractor performing any contractual work on Eskom premises (including delivery of any product), any contractor and their employees shall obey then the rules.


The rules are:

RULE	DESCRIPTION OF RULE
Rule 1	OPEN, ISOLATE, TEST, EARTH, BOND, AND/OR INSULATE BEFORE TOUCH (That is plant, any plant operating above 1000 V)
Rule 2	HOOK UP AT HEIGHTS Working at height is defined as any work performed above a stable work surface or where a person puts himself/herself in a position where he/she exposes himself/herself to a fall from or into.
Rule 3	BUCKLE UP No person may drive any vehicle on Eskom business and/or on Eskom premises: Unless the driver and all passengers are wearing seat belts.
Rule 4	BE SOBER No person is allowed to be under the influence of intoxicating liquor or drugs while on duty
Rule 5	PERMIT TO WORK Where an authorisation limitation exists, no person shall work without the required permit to work.
Rule 6 Site Specific	USE OF CELLPHONES ON SITE Use of cell phones (either texting or talking) when walking or driving is strictly prohibited.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

Eskom will take a stance of zero tolerance on these rules.

Non-compliance to a Life Saving rule will be considered serious misconduct and will lead to serious disciplinary action, which may include dismissal.

This is to ensure that **every person** who works on or visits an Eskom **returns home safely to his or her family**.

3.11 Substance Abuse

1. Alcohol and substance abuse poses a significant threat to any business, more so in industrial incidents and the driving of vehicles. Eskom is therefore, entitled to take reasonable steps to ensure that intoxicated persons are identified and prevented from entering Eskom.
2. General Safety Regulation 2A is clear on the legal stance regarding intoxication.
3. **Principal Contractor** shall comply with Eskom's procedure 32-37 ("Substance Abuse Procedure"), taking in to account that this is an Eskom Life-saving Rule number 4: BE SOBER", this means anyone entering the Eskom will be subjected to ad hoc alcohol testing.
4. **Principal Contractor** are encouraged to compile their own manual and to carry out regular alcohol testing of their own employees. The legislative alcohol level is deemed to be zero.
5. Test records must be treated as "Confidential" and filed in the employees' personal file.

3.12 Contractor organisational Structure

3.12.1 Principal Contractor Organogram

Principal Contractor must provide an organisational organogram related to this contract, depicting all the levels of responsibility from the CE down to the supervisors responsible for the contract. List the relevant positions held, names of appointees and legal appointments.

Principal Contractor must ensure that all appointed contractors comply with this requirement. The principal contractor is responsible for keeping copies of all the organograms' as well as submitting them with the SHE plan. All organograms shall be updated timeously when appointments are changed.

This diagram must be kept up to date and filed in the project SHE files.


3.12.2 Contractors Organogram

1. **Principal Contractor** are required to compile their company organogram for the project, listing the reporting structure from their CE down to their project supervisors. The diagram must list the names, positions held and any appointments made.
2. This diagram must be kept up to date, a copy of which must be given to the principal contractor and a copy filed in the relevant project SHE files.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3. This diagram must be kept up to date and filed in the project SHE files.

3.13 Risk assessment (refer to 32-520)

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken.

It is essentially a three-stage process:

- identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example if a job / task is extended over a day or halted due to inclement weather.


Guidelines for actual steps involved in a job/task specific risk assessment are:

- Each activity is listed;
- Specific hazards are identified and listed against each activity;
- The magnitude of each risk is rated as Low. Medium or High;
- All known documentary and supervisory controls are listed. For instance: What safe work procedures exist for ladders;
- The relevance, effectiveness and sufficiency of these controls are assessed;
- In the event of insufficient or deficient controls for the particular activity, steps to be taken to rectify this shall be recorded, and safe working procedures drawn up;
- Persons responsible for implementing and supervising the task shall be identified, nominated and duly assigned;
- Persons responsible for monitoring the task and carrying out the planned job observation must be nominated;

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- Completed risk assessment shall be handed to the Eskom project manager representative for comment and approval.

The relevant section of the risk assessment shall be issued with a Transmittal Note to the Supervisor nominated as the responsible person; and the names of workmen who have received instruction on the work content and the sequence of the activities listed in the risk assessment shall be recorded, and their competence established. This instruction shall be done through an interpreter if required and recorded on the Pre-Job Brief (Daily Safe Task Instructions), with reference to applicable Risk Assessments.

The risk assessment from Eskom Lethabo PowerStation for the project is as indicated:

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.



SHE SPECIFICATION


HIGH RISK/CONSTRUCTION SERVICES

Template Identifier	240-73416879	Rev	2
Document Identifier	LBS0067PS-H	Rev	06
Effective Date	30 September 2018		
Review Date	August 2023		

Business/Operating unit:	LethaboPower Station				Department:	MMS OSP							
Date:					Prepared by:				Authorised by:				Manager: Mwan Designation: MM Signed: Date:
Refer to Occupational Health and Safety Risk assessment procedure 32-529													
List activity	Activity type (Routine/Non-routine)	Hazard Identification	Associated risk	Risk type	Cause(s) of the risk	Exposed group/employees	Risk Owner	Exposure patterns	What are the possible consequences ?	Existing Controls	Consequence	Likelihood	Risk Priority Rating
List specific activities to be performed taking into consideration the equipment to be used, the personnel involved in the task.	Indicate R or N 1. Routine activities and situations create hazards through day-to-day	Anything with potential to cause of harm. Note: A hazard can pose more than one risk.	A chance that injury, ill health or damage could occur as a result of uncontrolled hazard.	Safety or health	What causes the risk to come into effect?	Who is exposed to the hazard i.e. visitors, members of the public, etc.	Who is accountable for making sure the controls and monitors are: - in place, - implemented, - regularly	The frequency and duration the person/group is exposed to the hazard e.g. Daily for 3 hrs.	Consider the worse case scenario without controls?	Include: - Preventative Controls (controls implemented to eliminate hazards or reduce the likelihood of the risk occurring), and - Reactive Controls (controls implemented to reduce the immediate impact of the risk occurring) Elimination Engineering: Guarding/barriers/rails. Administrative: Load testing of slings and rigging equipment, equipment inspection, Person job specifications, training, task risk assessment, PPE: Full PPE. Engineering: Mandatory Signs Administrative: Hearing conservation training, task risk assessments, Medical Surveillance, PPE: HPD.			
On line maintenance - changing - motors, fluid drives, gear boxes, couplings, rigging, lifting and material handling	No	Exposure to Suspended material	Falling object-Injuries	Safety	Falling of suspended material/objects	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Falling object-Injuries	Engineering: Guarding/barriers/rails. Administrative: Load testing of slings and rigging equipment, equipment inspection, Person job specifications, training, task risk assessment, PPE: Full PPE.	4	C	1
On line maintenance - changing - motors, fluid drives, gear boxes, couplings, rigging, lifting and material handling	No	Exposure to Noise	NHL	Health	Exposure to excessive noise	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	NHL	Engineering: Amandatory Signs Administrative: Hearing conservation training, task risk assessments, Medical Surveillance, PPE: HPD.	4	C	1
On line maintenance - changing - motors, fluid drives, gear boxes, couplings, rigging, lifting and material handling	No	Exposure to Coal Dust	Lung disease	Health	Inhalation of coal dust	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Lung Disease	Engineering: Dust supression system. Administrative: Task Risk assessment, Dust mask, regular clearing, Medical Surveillance, Person Job Spec, PPE: Respiratory PPE	4	C	1
On line maintenance - changing - motors, fluid drives, gear boxes, couplings, rigging, lifting and material handling	No	Uneven floor surfaces	Tripping and falling	Safety	Uneven floor surfaces	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Injuries	Administrative: Being Careful of your surrounding task risk assessment, Toolbox talk, reporting of any unsafe conditions, PPE: Full PPE	4	C	1
Repair/replace idlers	Yes	Manual handling	Falling when handling	Safety	Slipping out of hands	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	Daily 3hrs	Injuries	Engineering: Use lifting Equipment where possible. Administrative: Use Buddy System, task risk assessment, Toolbox talk, Gloves PPE: Applicable PPE	4	C	1
Conveyors - , belts, drive motors, pulleys, bearings, installing counter weights (60-600kg)	No	Suspended loads	Falling load	Safety	Falling of suspended material/objects	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Fatality	Engineering: Guarding/barriers/rails. Administrative: Use of competent personnel, Load testing, equipment inspection, Person job specifications, training, task risk assessment, PPE.	4	C	1
Conveyors - repair/replace idlers, belts, drive motors, pulleys, bearings, rigging counter weights (60-600kg)	Yes	Incorrect use of Sharp tools - spliking and cutting belts - tools used have sharp blades and edges.	Cut/wounds/lacerations	Safety	Incorrect use of Sharp tools - spliking and cutting belts -	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Cut/wounds/lacerations	Administrative: Safe work methods, task risk assessment, Use of competent persons, Being careful when using these tools, PTW, PPE: Full PPE.	4	C	1
Conveyors - repair/replace idlers, belts, drive motors, pulleys, bearings, rigging counter weights (60-600kg)	Yes	Working at heights	Falling from heights - fatality	Safety	Working at heights	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Falling from heights fatality	Engineering: Guarding/barriers/rails, hook up points. Administrative: Training - working at heights, medical surveillance, PTW, Task Risk Assessment, Local safe work procedures, PPE: Full PPE (Safety Harness)	5	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	Yes	Exposure to Toxic gases / coal dust	Inhalation of gases/dust	Health	Inhalation of coal dust/toxic gases	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	6 hours in a month	Lung Disease	Engineering: Ventilation/extraction. Administrative: Training/awareness, medical surveillance, PTW, Task risk assessment, Local safe work procedures, PPE: Full PPE (Respiratory protection).	4	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	Yes	Incorrect manual lifting - and material handling	Back trauma	Health	Incorrect manual lifting - and material handling	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	6 hours in a month	Back trauma	Administrative: Use buddy system to manually lift, make use of lifting equipment where possible, Education and awareness, person job specifications, Task risk assessment, local safe work procedures, PTW.	4	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	No	Limited space when lifting counter weights - rigging, lifting, material handling	Body injuries	Safety	Limited space when lifting counter weights - rigging, lifting, material handling	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	4 hours as and when necessary (breakdown)	Body injuries	Engineering: Approved rigging equipment. Administrative: Communication / awareness, training - rigging operator, PTW, Task Risk Assessment, Local safe work procedures.	4	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	No	Working at heights	Falling from heights	Safety	Working at heights	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Fatality	Engineering: Approved scaffolding, guarding barriers, rails. Administrative: Training - working at heights, medical surveillance, person job specifications, PTW, Local Safe Work procedures, Task Risk Assessment, PPE: Full PPE.	5	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	No	Toxic gases from welding, cutting, grinding, heating bolts.	Inhalation - irritation / asphyxiation.	Health	Inhalation of Toxic gases from welding, cutting, grinding, heating bolts.	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Lung Disease	Engineering: Ventilation/extraction. Administrative: Training/awareness, medical surveillance, task risk assessment, PTW, Local safe work procedures, PPE: Full PPE (Respiratory protection).	4	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	No	Ultra violet rays from welding.	Arc eyes	Health	Exposure to Ultra violet rays from welding.	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Arc eyes	Administrative: Task Risk Assessment, training/awareness, PPE: Full PPE (Eye protection)	4	C	1
Liner replacement in chutes and silos - use stainless steel sheets are bolted to walls and floors.	Yes	Noise from cutting and grinding	NHL	Health	Exposure to Noise from cutting and grinding	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours in 1 months	NHL	Administrative: Zoned noise areas, training/awareness, PTW, Task risk assessment, local safe work procedures, PPE: Hearing protection.	4	C	1
Replacement of defective grizzling/grating	No	Toxic gases from welding, cutting, grinding, heating bolts.	Inhalation - irritation / asphyxiation.	Health	Inhalation of Toxic gases from welding, cutting, grinding, heating bolts.	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Lung Disease	Engineering: Ventilation/extraction. Administrative: Training/awareness, medical surveillance, task risk assessment, PTW, Local safe work procedures, PPE: Full PPE (Respiratory protection).	4	C	1
Replacement of defective grizzling/grating	No	Heat from welding, cutting, grinding	Body Burns	Safety	Exposure to heat when welding, cutting, grinding	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8 hours as and when necessary (breakdown)	Body Burns	Administrative: PTW, local safe work procedures, task risk assessment, PPE: Full PPE.	4	C	1
Night time travelling	Yes	Lack of rest	MVA-Injuries	Safety	Lack of rest	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	MVA-Injuries	Administrative: Compliance to rest period, Eskom driving assessment, Driver not to drive when feeling exhausted, Use of transport service provider	4	C	1
Night time travelling	Yes	Stray on the road	MVA-Injuries/Property Damage	Safety	Line Manager	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	MVA-Injuries/Property Damage	Engineering: Proper vehicle light, Road Worthiness, Administrative: Road worthy vehicle- Vehicle Inspektion, (Lights working) Training: Driver permit, awareness, Travelling Risk Assessment	4	C	1
Travelling	Yes	Bad road conditions	MVA - Injuries	Safety	Driving in the Bad road conditions	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	MVA - Injuries	Administrative: Training, travelling on same road every time, Eskom Driver assessment, adherence to speed limit, Travelling Risk Assessment	4	C	1

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

Travelling	Yes	Speeding	MVA - Injuries	Safety	Driving at high speed	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	MVA - Injuries	Administrative: Training, travelling on same road every time. Eskom Driver assessment, adherence to speed limit, Travelling Risk Assessment	4	C	5
Travelling	Yes	Rural/dangerous roads	High jacking	Safety	Rural/dangerous roads	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	High jacking	Administrative: Training, travelling on same road every time, Travelling Risk Assessment	4	C	5
Walking to and from site	Yes	Uneven road/floor surfaces	Trip and fall - injury	Safety	Uneven road/floor surfaces	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8hrs Daily	Trip and fall - injury	Administrative: Training on relevant procedures and risks.	4	C	5
Walking to and from site	Yes	Slippery road/floor surfaces	Slip and fall - injury	Safety	Slippery road/floor surfaces	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8hrs Daily	Slip and fall - injury	Administrative: Training on relevant procedures and risks.	4	C	5
Walking to and from site	Yes	Open manholes	Falling in-injuries	Safety	Open manholes	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	8hrs Daily	Falling in-injuries	Administrative: Inspections, training on relevant procedures and risks.	4	C	5
Driving	Yes	Distraction while driving	MVA - Injuries	Safety	Distraction while driving	Coal Plant Riggers, Artisan, Tech Official, Technicians, Ssr Supervisor, Service Providers	Line Manager	2hrsDaily	MVA - Injuries	Engineering: Bluetooth device installed, installation of vehicle cameras systems. Administrative: training/awareness, Task risk assessment. The driver to focus on the road and avoid distractions.	4	C	5


	Consequence criteria
Consequence rating	Description
	Health and Safety
1	No injuries or health effects(near misses)
2	First-aid treatment case, and temporary discomfort case
3	Medical treatment case; occupational disease with reversible/non-permanent effect
4	Lost Time Injury. Irreversible health effects/occupational disease with permanent consequence
5	Fatality or life threatening health effects
6	Multiple fatalities

Likelihood criteria				
Score	Descriptor	Safety and Environment	Exposure	Occupational Hygiene
				Probability of exceeding OEL
1	Highly unlikely	<ul style="list-style-type: none"> <5% probability occurrence requires exceptional circumstances exceptionally unlikely, even in the long-term future only occurs as a "100-year event" 	Rare(once a year)	No exposure (or exposure < 10% of OEL)
2	Unlikely	<ul style="list-style-type: none"> >5% probability, or may occur but not anticipated, or could occur in "years to decades" 	Short periods of time, a few times per day / intermittent (once in 6, 3 or a month)	Low exposure (<50% of OEL)
3	Possible	<ul style="list-style-type: none"> >20% probability, or may occur shortly but a distinct probability it will not, or could occur within "months to years" 	Continuous for between 1 and 2 hours (often / weekly)	Moderate exposure (chronic exposure > 50% of OEL or acute exposure >/-OEL)
4	Likely	<ul style="list-style-type: none"> >70% probability, or balance of probability it will occur, or could occur within "weeks to months" 	Continuous for between 2 and 4 hours (frequent / daily)	High exposure (chronic exposure > OEL, or exposure exceeding OEL-STEL)
5	Unavoidable	<ul style="list-style-type: none"> 99% probability, or impact is occurring now, or could occur within "days to weeks" 	Continuous for 8 hour shift	Very high exposure (chronic exposure > 2 x OEL or exposure exceeding OEL-C)

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

RISK MATRIX						
Consequences	6	III	II	I	I	I
	5	III	II	II	I	I
	4	IV	III	II	I	I
	3	IV	III	II	II	I
	2	IV	IV	III	II	II
	1	IV	IV	III	III	III
		1	2	3	4	5
		Likelihood				
Priority	Risk ranking	Action required				
I	Very high	Immediate action required				
II	High	Strong mandatory action required				
III	Medium	Action required, possibly at administrative level				
IV	Low	Minor or no action required				

3.14 Safe work procedures / method statements

Method statements / written safe work procedure are control measures used to prevent an incident from occurring during the execution of the project. A written safe work procedure/ method statements provide guidance how to execute the task safely. A safe working procedure should be written when: -

- Designing a new job or task;
- Changing a job or task;
- Introducing new equipment or substances; and


The safe working procedure should identify:

- The supervisor for the task or job and the employees who will undertake the task;
- The tasks that are to be undertaken that pose risks;
- The equipment and substances that are used in these tasks;
- The control measures that have been built into these tasks;
- Any training or qualification needed to undertake the task;
- The personal protective equipment to be worn;
- Actions to be undertaken to address safety issues that may arise while undertaking the task.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.15 Roof work (Where applicable)

Where roof work is to be performed, a risk assessment must be carried out prior to climbing on to the roof to determine the hazards (stability, suitability strength etc.), consequences of climbing and control measures that are required.

3.16 Construction Sites

Note1:No area is to be stripped of vegetation to create firebreaks, to prevent or make fires. No open fires are allowed on site. The contractor must ensure that operations are in compliance with statutory requirements at all times.

1. **Principal Contractor** must develop a fire safety procedure for the construction site prior to commencing work. The procedure must take into consideration the size of the site/s, the type of work performed and amount of combustible materials. Cognisance of OHS Act CR 29 must be made.
2. It must be developed in accordance with the hot work permit of the Eskom Plant Safety Regulations, Eskom Fire Risk Management requirements and all other applicable Regulations. All workers entering and working in the construction site need to be trained in fire safety and any duties they are required to perform.
3. A suitable fire warning system for alerting site personnel of fire shall be provided, and capable of being heard in all areas of the site.
4. Appropriate portable extinguishers must be available on the construction site and in cases of hot work, be readily available at the location.
5. Storage of combustible and flammable liquid in the construction site is not permitted unless stored in approved flammable cabinets or outdoors away from the buildings.
6. Site Smoking Restrictions must be enforced. No open flames are permissible and where hot work is performed, the work areas must be cleared of any combustibles prior to commencement of work.


3.17 Fire Equipment and maintenance

1. All firefighting equipment's that have been provided shall:
 - a. Be clearly labelled
 - b. Conspicuously numbered
 - c. Entered in a register
 - d. Inspected monthly by a competent person
2. Tested and serviced at recommended intervals by an accredited supplier
3. Results entered in the register and signed by competent person.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.18 Flammable and Combustible Liquids

- Proposals to store fuel on site must have written approval from the Eskom Project Manager. The volumes of fuel allowed to be stored will depend on site conditions and Statutory Regulations.
- A maximum storage of 40 litres of fuel is allowed to be stored. Anything greater than 40 litres to be stored in a flammable/combustible liquid store.
- Adequate numbers of dry chemical fire extinguishers, each with a minimum capacity of 4.5 kg, shall be provided, installed and maintained.
- All fuel storage areas must comply with the following requirements: -
 - Storage should be well clear of buildings.
 - Storage areas must be kept free from all combustible materials.
 - All Safety signs must be prominently displayed i.e.
 - Flammable Liquid.
 - No Smoking.
 - No open flames.
 - Adequate firefighting equipment must be available.
- Diesel tanks are to be installed in a bonded area; bonded area must be able to contain 110% of tank capacity.
- Bonded area shall be of a concrete or steel construction and lined with a leak proof sealing material.
- bonded area shall have a drain valve.
- No other material/equipment shall be stored in the bonded area.

3.18.1 Refuelling at the construction site

With the exception of construction vehicles and mobile equipment, before a machine is refuelled, the motor must be stopped. Refuelling shall take place at designated safe areas and appropriate warning signs installed. Suitable drip trays must be used to prevent spillage at the filling nozzle.


3.19 First Aid and Equipment

- The requirements of the OHS Act GSR 3 must be observed.
- First aid appointments must be made to meet the requirements; this includes construction sites. Appointees must be trained to level 2. It is good practice for all employees to be trained to at least level 1.
- When appointing employees for work sites, cognisance must be taken into account the type of work performed, the distance teams are working apart and the terrain to be covered if an emergency should arise.
- A list of emergency numbers must be displayed on the notice boards and made accessible for all employees.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

5. **Principal Contractor** must ensure that his /her employees and appointed contractor employees are familiar with the emergency numbers.
6. **Principal Contractor** shall have one first aid box for the first 5 persons and thereafter one for every 50 or team of workers on site or part thereof, taking into account the type of work performed and the distance between teams.
7. More first aid boxes shall be provided in accordance with the risk assessment. Boxes must be available and accessible for the immediate treatment of injured persons at the workplace.
8. For offices, signs indicating where the first aid box or boxes are kept as well as the name and contact details of the First Aider of such first aid box or boxes shall be erected. N/A
9. **Principal Contractor** and appointed contractor shall ensure that alternative arrangements be made for incidents occurring after working hours.

3.19.1 Boxes and equipment


The following is a list of minimum contents of a first aid box:

- Item 1: Wound cleaner/antiseptic (100ml).
- Item 2: Swabs for cleaning wounds.
- Item 3: Cotton wool for padding (100 g).
- Item 4: Sterile gauze (minimum quantity 10).
- Item 5: 1 Pair of forceps (for splinters).
- Item 6: 1 Pair of scissors (minimum size 100 mm).
- Item 7: 1 Set of safety pins.
- Item 8: 4 Triangular bandages.
- Item 9: 4 Roller bandages (75 mm X 5 m).
- Item 10: 4 Roller bandages (100 mm X 5 m).
- Item 11: 1 Roll of elastic adhesive (25 mm X 3 m).
- Item 12: 1 Non-allergenic adhesive strip (25 mm X 3 m).
- Item 13: 1 Packet of adhesive dressing strips (minimum quantity, 10 assorted sizes).
- Item 14: 4 First aid dressings (75 mm X 100 mm).
- Item 15: 4 First aid dressings (150 mm x 200 mm).
- Item 16: 2 Straight splints.
- Item 17: 2 Pairs large and 2 pairs medium disposable latex gloves.
- Item 18: 2 CPR mouth pieces or similar devices.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

A content check list must be available with all boxes and boxes shall be checked on a regular basis, kept clean and dust free.

3.20 SHE Communication Systems

Principal Contractor and their appointed contractors must develop a communication strategy outlining how they intend to communicate SHE issues to their staff, the mediums they will employ and how they will measure the effectiveness of their SHE communication. Below is a brief on how communication should take place. Where project meetings conducted on site, SHE shall be included as a standing agenda point and minutes of these meetings shall be available on site at all times. Minutes of meeting must be compiled and filed in the relevant SHE files. All employees shall have access to these minutes. Attendance register shall be kept for all the health and safety meetings.


3.20.1 Statutory Health and Safety Committees

1. **Principal Contractor** shall establish statutory health and safety committee in terms of Section 19 of the OHS Act, Act. Similarly, appointed contractors shall establish their own statutory health and safety committee.
2. All appointed contractors shall be members of the principal contractor's safety committee.
3. The Committee shall meet to discuss SHE issues concerning the current work being performed, training, upcoming work and SHE requirements, incidents and lessons learned specific SHE problems, safety performance, action plans and other relevant SHE issues. Listed below is a preferred agenda.
4. SHE representatives for a workplace shall be members of the relevant workplace safety committees (Refer to Section 19 (2) (a) of the OHS Act).
5. The number of persons nominated by employer must not be more than the Health and Safety Representatives on that specific statutory health and safety committee. (Refer to Section 19(2)(c) of the OHS Act)
6. A statutory health and safety committee meeting shall be held at least 1 monthly (where medium to high risk work is involved, more frequent if required), and all appointed members of the committee shall attend the meeting.
7. Statutory health and safety committees may make recommendations to the principal contractor and the project manager and the Inspector at DoL.
8. All health and safety committees shall discuss all projects related OHS Act Section 24 and 25 incidents and other notified serious incidents.
9. Health and safety committees shall follow up on incident investigation recommendations and shall keep record of all recommendations made by the committee.
10. Statutory health and safety committees may make recommendations for the revision of current standards, procedures and practices.
11. The **Principal Contractor** and **Appointed Contractors** shall ensure that statutory and non-statutory health and safety committees carry out their duties.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

12. The chairperson of the health and safety committees shall be selected and appointed by the contractor. The appointed chairperson must be competent to chair meetings and be able to make informed decisions.

3.20.2 Non-statutory health and safety committees

1. Where there are large worksites, then non-statutory sub-committee must be established within that worksite to assist with the communication of health and safety related matters between the statutory health and safety committee and the workplace.
2. The duties and responsibilities of the non- statutory health and safety committees will be the same as the statutory safety committee


3.20.3 Agenda

1. The following serves as the guideline for the SHE Committee meeting agenda.
 - List of agenda items:
 - Matters arising from previous minutes
 - Matters arising from Contractor's SHE meetings.
 - Audit results and feedback
 - Review Health and Safety Representative Inspection Reports
 - Review
 - Incident investigation reports
 - Non-Conformances
 - Announcements (near miss/injury/damage)
 - Follow up on recommendations made by the employer in incident investigation reports
 - Accident Prevention – Safety Promotion
 - Planned Job Observations
 - SHE Training
 - Protective clothing and equipment
 - Incident Announcements / Recall
 - Forthcoming High hazard activities.
 - Non-conformances.
 - Housekeeping.
 - Work permits.
 - Work procedures.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- Hazardous materials / substances.
- Fire Prevention
- Occupational Hygiene Assessments, Health Risks and Actions
- Security
- Construction vehicles and mobile equipment
- Rules, Instructions
- Public Safety
- Environmental Management
- Emergency Preparedness
- Statistics report
- Closure

3.20.4 Minutes and action items for all health and safety committee meetings

1. Minutes and record of action items shall be kept of all health and safety committee meetings.
2. Action column with target dates and responsible person shall be clearly visible on the minutes and shall be completed during the meeting.
3. Statutory health and safety committee meeting minutes and record of action items shall be kept for the duration of the project or a minimum period of three years.
4. Non-statutory health and safety committee meeting minutes shall be kept for the duration of the project or a minimum period of 12 months.
5. All other meeting minutes where SHE is on the agenda, shall be kept for a minimum period of 12 months.
6. The original copy of the minutes and record of the action items must be signed by the chairperson.
7. The relevant project manager and principal contractor shall endorse the relevant minutes with his/her recommendations and return the minutes to the relevant contractors chairperson within 14 calendar days of the meeting.


3.20.5 Tool box talks / Daily team talks / pre job meetings

1. A meeting must be held prior to the commencement of the day's work with all relevant personnel associated with the work task in attendance. The job, relevant procedures, associated hazards, safety measures, i.e. the task risk assessments shall be discussed. Each employee who attends the briefing shall sign an attendance list of that pre-job brief form undertaking that they have an understanding of the tasks, risks and control measures required.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- Where possible, tool box talks can be included in the pre-job brief meetings. If this does not occur, then weekly tool box talks must be conducted. The toolbox talk topics will be based on SHE issues pertaining to the construction site and or the project. The topic contents shall be in writing. Attendance registers with the topic listed shall be kept.

3.21 SHE Training

- Principal Contractor** when making a bid for this project shall provide a breakdown list of the SHE training requirements and the costing of such requirements. Similarly, appointed contractor must provide the same requirements when bidding with the principal contractor.
- The scope of training includes but is not limited to the type of work being performed and the relevant procedures. Additional to the requirements, will be that the principal contractor and appointed contractors must have the appropriate qualifications, certificates and employees should always be under competent supervision.
- Where legislative and Eskom recommended appointments are made, the relevant training shall be given to those appointees prior to the acceptance of those appointments.
- When there is an amendment to the Acts and/or to the regulations, SHE specification and SHE plan, all affected staff shall undergo the applicable refresher training.
- Appropriate time must be set aside for training (induction and other) of all employees.
- Records of all training and qualifications of all contractor employees must be kept on the SHE file.


3.21.1 Induction training

- Principal Contractor** shall ensure that all his / her employees, appointed contractors and their employees have undergone the Eskom Safety Contractor Management induction training prior to commencing work on site.
- Attendance registers must be completed of any induction training given, which must indicate that they have received and understood the induction training.
- Prior to attending the induction training, all employees must undergo a pre-employment medical examination and found fit for duty. A copy of the certificate of fitness must be in the SHE file on site for the duration of the project.
- All employees and visitors on site shall carry the proof of induction training.

3.21.2 Site specific induction training

Principal Contractor shall ensure that all his / her employees and appointed contractor employees undergo site specific work induction with regard to the approved project SHE plan, general hazards prevalent on the construction site, construction risk assessment, rules and

Public

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

regulations, and other related aspects. The induction training should also include identification of sensitive features such as wetlands/vlei areas, red data species, graves, etc.

3.21.3 Visitors to site induction

1. Visitors to the site shall be required to undergo and comply with the **Principal Contractor's** site-specific safety induction prior to being allowed access to site.
2. All visitors must remain in the care and custody of a person (host) who has been properly inducted. No visitors are permitted to undertake any work onsite, of any nature.
3. Visitors who have completed site induction must be provided with a record of proof of Induction training.

3.21.4 General training

Principal Contractor will be required to ensure that before an employee commences work on the project, the respective supervisor informs the employee of his scope of authority, the hazards associated with work as well as the control measures to take. This will include man-job specifications, the discussion of any task procedures or hazardous operational procedures to be performed by the employee. **Principal Contractor** is to ensure that the supervisor has satisfied himself that the employee understands the hazards associated with any work performed by conducting task/job observations.

3.22 Contractor Site Establishment

1. Contractor Site facilities should be managed at all times
2. Prior to establishing a project site, a site plan is required to be drawn listing position of all buildings, amenities, storage and stacking areas. The appropriate colour coding and demarcation of storage and stacking areas must be carried out.
3. Where, working in the field and material is stored at the work sites, then proper stacking and storage shall be carried out.
4. When compiling the site plan, cognisance must be taken to the establishment of the site camp, ablution facilities and dining area in relation to one another and away from stacking and storage areas.

3.22.1 Site roads

1. When planning, sufficient areas must be allocated for parking of construction vehicles and mobile equipment's as well as roadways for ease of manoeuvrability of these vehicles.
2. Sufficient width roads to be provided and adequate space is to be allowed for large vehicles traversing the sites.


3.22.2 Vehicle safety It is the responsibility of the driver to ensure:

- a. Their passengers wear seat belts whilst the vehicle is in motion.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

- b. Comply with all traffic road rules, safety, direction and speed signs.
- c. Ensure that vehicles are not overloaded.
- 1. No drivers may text, talk on cell phones or two way radios whilst driving, unless a hands free kit is used.
- 2. All drivers of vehicles are to have valid personal driver's licence.
- 3. Each Project site that is enclosed by demarcation will have system/ process to manage vehicle access to site.
- 4. **Principal Contractor** must maintain their vehicles in a roadworthy condition and a vehicle license must be valid at all times.
- 5. Drivers of light vehicles must avoid stopping or parking near machines. At least 30 (thirty) meters must be left clear between such a vehicle and such a machine
- 6. **Principal Contractor** vehicles can be subject to inspections by the Client/Agent's representative. Vehicles which are not roadworthy will not be permitted to be used on the project.
- 7. Drivers/operators shall be responsible for the travel-worthiness of all loads conveyed by them. Precautions shall be taken to secure all loads properly. Loads projecting from vehicles shall be securely loaded and in daytime a red flag and during darkness a red light or red reflective material shall be attached to the extreme end of such projecting material.


3.23 Housekeeping and Order

- 1. **Principal Contractor** shall maintain a high standard of housekeeping within their sites and vehicles for the duration of the project.
- 2. Prompt disposal of waste materials, scrap and rubbish is essential.
- 3. Materials/objects shall not be left unsecured in elevated areas –falling objects may cause serious injuries/fatalities.
- 4. Nails protruding through timber shall be bent over or removed so as not to cause injury.
- 5. All packaging material including boxes, pallets, crates, etc. to be removed from the work area immediately.
- 6. On completion of his / her work, the contractor is responsible for clearing his / her work area of all materials, scrap, temporary buildings and building bases to the satisfaction of the client/agent.
- 7. In cases where an inadequate standard of housekeeping has developed, compromising safety and cleanliness, anyone has the responsibility to bring it to the attention of the principal contractor in the first instance and the Eskom project/site manager in the second instance.
- 8. The Eskom Project/Site Manager has the right to instruct the principal contractor and appointed contractors to cease work until the area has been tidied up and made safe.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

Neither additional costs nor extension of time to the contract shall be allowed as a result of such a stoppage. Failure to comply with this requirement will result into site cleaning by another cleaning contractor company at the cost of the principal contractor.

- The principal contractor shall carry out regular safety/housekeeping inspections (at least weekly) to ensure maintenance of satisfactory standards. The principal contractor shall document the results of each inspection and shall maintain records for viewing.

3.23.1 Stacking

- Before stacking any material, the contractors or their employees must consult the contract manager for authorisation to use such an area for stacking purposes. This is to prevent haphazard arrangements.
- Adequate care must be taken by the contractor to ensure that storage and stacking is carried out correctly and safely.
- Correct shelf stacking must be carried out, heavy and bulky on the bottom, light and small on top.


3.24 Workplace Signage and Colour Coding

- Symbolic safety signage shall be displayed where it is required by legislation.
- All symbolic safety signage shall conform to the requirements of SANS standard 1186.
- Signs shall be positioned to be seen from most positions within the work sites / areas.
- All signage must be clear at all times and be replaced timeously when worn out.
- Contractors establishing sites must erect a company sign at their site offices to reflect the name and contact details of the: Construction Supervisor; Health and Safety Manager/Practitioner; First Aider; Health and Safety Representative and Evacuation warden
- The location of every first aid box; fire extinguisher and emergency exit is to be clearly indicated by means of a sign.
- When using, an explosive power tool the appropriate signage shall be erected, warning people of its use.
- Principal Contractor** shall provide signage where work is conducted and where unauthorised entry is prohibited and/or where alerting and cautioning passers-by to be aware of potential dangers.
- The meanings of the appropriate symbolic signage must be discussed during induction training and toolbox talks.
- Where possible, within workshops, work areas and established premises, the appropriate sign indicating the meaning of symbolic safety signs must be displayed.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.25 Tools and Equipment

1. **Principal Contractor** shall ensure that all tools and equipment are identified, safe to use, are maintained and in a good condition.
2. **Principal Contractor** shall ensure that all tools and equipment listed on an inventory list, be regularly inspected at least monthly or as required by legislation and risk assessments. The equipment should be numbered or tagged so that it can be properly monitored and inspected.
3. Where applicable, tools and equipment must have the necessary approved test or calibration documentation prior to project commencement and the records shall form part of the SHE plan. Maintenance calibration shall be undertaken in terms of the manufacturer's requirements.
4. All fuel driven equipment must be properly maintained in accordance with the manufacturer's recommendations and legal requirements.
5. Eskom reserves the right to inspect tools or items of equipment brought to site by contractors for use on this project.
6. Should Eskom personnel find any item that is inadequate, faulty, un-safe or in any other way unsuitable for the safe and satisfactory execution of the work for which it is intended, the Eskom personnel shall advise the contractor in writing and the **Principal Contractor** shall forthwith remove the item from site and replace it with a safe and adequate substitute.

Note: In such cases, the contractor shall not be entitled to extra payments or extensions of time in respect of delay caused by Eskom's instructions.

7. Where defective tools and equipment's are identified, such tools and equipment shall be removed out of site immediately, locked away to prevent further use until such time as the tool or piece of equipment has been repaired.
8. **Principal Contractor** shall ensure that the appropriate records are kept for all tools and equipment used on the project. Such tools and equipment's shall be subjected to regular inspections.

3.25.1 Hand tools

1. All hand tools (hammers, chisels, spanners, etc.) must be recorded on a register and inspected by the construction supervisor on a monthly basis as well as by users prior to use.
2. Tools with sharp points be protected with a cover and be kept in toolboxes.
3. All files and similar tools must be fitted with handles.
4. No homemade tools are permissible on the project.


3.26 Ladders

1. Ladders used shall conform to the requirements of GSR 13A and used in terms of GSR 6.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons
3. The ladder wheels, brakes and platform must be in good condition.
4. All metal parts to be in good condition, no cracks.
5. Non-slip devices must be in good condition and no paint to be on wooden ladders
6. Climbing irons are permitted to be used in place of ladders on condition that the requirements of GSR 6 are not compromised and from an electrical point of view not damage any cabling. The working at heights risk assessment must indicate the use of climbing irons.
7. Employees using climbing irons shall be suitably trained in the use, care and maintenance of such climbing irons.
8. When using climbing irons, the appropriate rope grab fall prevention system shall be used.
9. The correct fall protection equipment shall be worn and used whilst climbing up, working from and climbing down ladders
10. The appropriate head protection, with chin strap shall be worn by employees working from a ladder or with climbing irons.
11. A detailed inspection of all ladders shall be conducted monthly by a competent person and every time prior to climbing by employees using such ladders. The inspection check lists must be filed in the site SHE files.

3.27 Scaffolding

1. Scaffolding use shall conform to the requirements of CR 14, Eskom procedure 32-418 and used in terms of GSR 6.
2. The requirements for using a scaffold platform shall be determined by the work at heights risk assessment.
3. All scaffolding that will be used shall conform to the SANS standard 10085 and the requirements of CR 16 shall be carried out.
4. Scaffolding shall be erected and inspected by the competent personnel.
5. The appropriate training for scaffold users shall be conducted prior to climbing on to the scaffold.
6. The correct fall protection equipment shall be worn and used whilst climbing up, working from and climbing down the scaffolds.
7. A detailed inspection of all scaffolding shall be conducted monthly by a competent person and every time prior to climbing by employees using such scaffolding. The inspection check lists must be filed in the site SHE files.


3.28 Auditing

3.28.1 Approval and compliance of principal contractor SHE plan

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

Principal Contractor SHE Plan will be evaluated against compliance checklist so as to verify compliance to the requirements of the Eskom SHE specifications. Once there is compliance only then will **Principal Contractor** SHE plan be approved by the project manager or an appointed Eskom contract custodian. The implementation of the SHE Plan shall be assessed / audited by Eskom personnel on a regular basis. This will include physical conditions evaluation.

3.28.2 Eskom SHE audits

Eskom shall evaluate **Principal Contractor** SHE performance on an ongoing basis against the legal, Eskom requirements, SHE specification and the contractors SHE plans.

Note: Eskom reserves the right to conduct unannounced audits on contractors

There will be monthly audits conducted by Eskom on the **Principal Contractor** and/or appointed contractors. These audits shall be attended by the contractor's site manager, Safety Officer & Health and Safety representative.

If there are any findings / non-compliance identified as serious in these audits, an activity will be stopped for that specific **Principal Contractor** and **Appointed Contractor**. Refer to section on "Work Stoppage" in this SHE Specification.

3.28.1 Contractor audits

Principal Contractor are required to conduct internal audits on their appointed contractors on the implementation of their SHE Plan on a monthly basis or when the scope of work changes. A summary of the findings and the proposed corrective actions shall be submitted to Eskom project manager within one week after completion of the audit. Where appointed contractors are audited by the principal contractor a copy of the audit report shall be submitted to the appointed contractor within 7 days of the audit.

3.29 Smoking

The national smoking policy must be observed and smoking is permitted in designated areas only (Eskom Smoking Procedure 32-36).

3.30 Cellular Phones

The national requirements regarding the use of cellular phones must be observed, in particular when driving and or operating mobile equipment and or machinery.

3.31 Occupational Health, Hygiene and Rehabilitation


Principal Contractor required developing an Occupational Health, Hygiene and Rehabilitation program. The program is intended to ensure that the risks to health are identified and controlled.

3.31.1 Medicals

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

Note: Eskom will only accept medical surveillances conducted by an Occupational Health Practitioner who holds a qualification in occupational health.

1. **Principal Contractor** must ensure that their employees and their appointed contractor employees have a medical surveillance program whereby their employees undergo entry, periodic and exit medical fitness examinations.
2. In order for the appropriate medical examinations to be conducted, each employee must have a man job specification, which must indicate the description of work, list of hazards and potential occupational exposure limits, physical hazards and required physical attributes.
3. Medical fitness certificates shall be renewed annually for employees who are working on site. This shall be maintained until completion of the contract.
4. **Principal Contractor** must ensure that his / her employees and appointed contractor employees have undergone pre-entry medical examination before starting work on the contract.
5. **Principal Contractor** shall provide a documented process for managing those employees who are issued with a conditional certificate of fitness.

3.32 Working at Heights

3.32.1 General Requirements


Wherever reasonably practicable, preference is given to the performance of work at ground level as opposed to the elevated position. Where work in an elevated position is necessary, preference is given to fall prevention measures such as, but not limited to, effective barricading and the use of work platforms. Persons may only work from a fall risk position if a site-specific fall protection plan is in place and correctly implemented and consists of the following:

1. All appointments for the fall protection plan developer and implementer are in place.
2. The fall protection developer shall develop a fall protection plan.
3. Baseline risk assessment, which is specific and incorporates the working at height risk assessment, as well as the site-specific risk assessment, has been completed for the work to be conducted.
4. Safe working procedure/task analysis and work instructions, approved by a competent person, are in place.
5. A fall rescue plan, along with necessary equipment and trained rescuers, is in place.
6. Appropriate training, as determined by the risk assessment, has been provided.
7. Appropriate height safety equipment and personal protective equipment have been issued to the individual.
8. There are equipment inspection procedures and up-to-date inspection records.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

9. Individuals are medically fit to work at height, and records of this are kept.

10. A site-specific risk assessment is performed.

While work is in progress, adequate warning signs and/or barricades shall be used in all areas where there is a risk of persons being injured by materials or equipment falling from the work area. Barricades should be continuous and easily visible.

A drop zone shall be established with appropriate warning signs and barricading, warning personnel below of workers above and potential falling objects.

Every employer shall ensure that work at height is:

1. properly planned;
2. appropriately supervised; and
3. carried out in a manner that is, as far as is reasonably practicable, safe and that its planning includes the selection of work equipment.

3.33 Risk Assessments

It is a legal requirement in terms of Section 8 (2)(d) of the OHS Act for an employer to carry out risk assessments, to establish which risks and hazards are attached to the health and safety of persons due to any work which is performed, any article or substance which is, handled, stored, transported. A risk assessment is defined as an identification of the hazards present in an organisation and an estimate of the extent of the risks involved, taking into account whatever precautions are already being taken. It is essentially a three stage process:


- identification of all hazards;
- evaluation of the risks;
- Measures to control the risks.

Risk assessments are required to be maintained. This means that significant changes to a process or activity, or any new process or activity should be subjected to a risk assessment and that if new hazards come to light during the work process, then these should also be subjected to risk assessments. Risk assessments for long term processes should be periodically reviewed and updated. Method statements or written safe work procedures are an effective method as information and record of the way jobs / tasks must be performed. Daily or issue based or task specific or on the job risk assessments must be conducted at the place where work is to be performed/ conducted to allow managers and employees to assess any inherent risks that could have been overlooked during the initial risk assessment or any changes that might have occurred in a period of absence. For example, if a job / task is extended over a day or halted due to inclement weather.

3.34 Safe Work Procedures and Practices / Safe Operating

There must be written safe work procedures for all activities, the safe work procedures must be aligned with the risk assessments.

Public

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.35 Personal Protective Equipment Requirements

1. **Principal Contractor** must provide a detailed programme that includes the issuing, maintenance and replacement of PPE for all his employees and appointed contractors on site.
2. **Principal Contractor** shall comply with the requirements of GSR 2 of the OHS Act.
3. The risk based PPE matrix must be compiled detailing the types of PPE that is required to be issued to employees performing the respective tasks.
4. Where there are unusual instances where particular activities require additional type of PPE, then a risk assessment must be conducted where such PPE requirements will be identified and the issuing be carried out.
5. **Principal Contractor** shall ensure that their visitors wear and use the correct PPE whilst on worksites.
6. Where PPE is required and visitors are not in possession of, then it is the individual contractor's responsibility to provide the PPE.
7. All PPE purchased and used by all contractor employees including visitors must comply with the relevant SANS standards.
8. Where deemed as a requirement, then high visibility vests shall be worn.

3.36 Incident Investigation

All incidents shall be investigated in terms of OHS Act General Administrative Regulations 8 and 9, using Eskom Procedure 32-95 as a reference, and where injuries as contemplated in **Principal Contractor** shall use the standard General Administrative Regulation Annexure 1 "Recording of an Incident" form for all incident investigation reports. The objective of incident investigation, should not only be a legal requirement, but should establish why and how the incident occurred and find out the real root cause of the incident and to decide on precautionary measures that are required to address the root cause to prevent any further recurrences of the same or similar incidents.

3.37 Emergency Management

The art of emergency preparedness and response is to minimise the effects of any emergency and to restore normal activities as soon as practical. **Principal Contractor** must familiarise themselves with the Eskom emergency response plan and procedure. Periodic emergency drills must be undertaken to test the effectiveness of the plan. This must be recorded and provided on request.


3.38 Non-Conformance and Compliance

1. Any non-compliance to any health and safety requirement in this SHE specification is subject to discipline in terms of the Eskom Procurement and Supply Management Procedure.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

2. **Principal Contractor** are required to implement a non-conformance procedure (if not already in place) for issuing to contractors for transgressions. The procedure can include “quality” related non-conformance issues. Similarly, appointed contractors must implement a non-conformance procedure.
3. The procedure for the issuing and closing off non-conformance reports shall be strictly adhered to.
4. Contractor project management must monitor the close out non-conformances issued, in not doing so; any recommendations made may not be implemented.
5. Where non-conformances are issued by Eskom then one of the close-out steps of the procedure will be for the offender to be called by the responsible project manager to explain the non-conformance issued and what plan is in place to prevent a recurrence of the non-conformance.
6. Should **Principal Contractor** fail to provide adequate PPE to their employees for the tasks being performed and/or to visitors; failure to enforce the wearing of such PPE will be viewed as a transgression of the legislative and Eskom requirements.

3.39 SHE File

1. A SHE file means a file or other record in permanent form, containing the information about the safety and health management system during construction and all information relating to the post-construction phase after handover to the client, so that the client can maintain the works in a healthy and safe way.
2. **Principal Contractor** are required to keep a SHE file on every project site. If there is more than one site per project, a file per site shall be kept at that site.
3. **Principal Contractor** may keep additional files at their head office as additional records. The SHE file shall be maintained by all the contractors on their construction sites and shall be available on request for audit and inspection purposes.
4. The SHE file shall consist of the requirements in terms of the project’s safety specification, the contractor’s safety and health plans.
5. The sequence of filing the documentation must be kept in the same sequence as listed in this SHE specification and the SHE plan.
6. Each record shall be separated by partitions to afford easy identification and access. Each partition must be labelled.
7. On completion of the construction work/project, **Principal Contractor** must hand over a consolidated health and safety file to the project manager. **Principal Contractor** must also hand over all drawings, designs, lists of materials used, and other applicable information about the completed structure, as well as the list of subcontractors, the agreement, and the type of work completed.


3.40 Work Stoppage

1. Any person may stop any activity where an unsafe act or unsafe condition that poses or may pose an imminent threat to the safety and health of an individual or create a

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

risk of degradation of the environment. This includes any unauthorised work or service performed by, or legally or contractually non-compliant acts or omissions by, any contractor contracted to work at that site.

2. Work stoppages that are initiated due to SHE concerns, non-compliance, or poor performance related to the contractor's works or services shall not warrant any financial compensation claim lodged against Eskom where the contractor has not met the requirements defined legally or contractually.
3. Where stoppages are carried out, the required non-conformance report shall be raised.
4. All work stoppages ideally should be investigated and documented by contract custodians.

3.41 Hours of Work

The requirements of the Basic Conditions of Employment Act, Chapter Two "Regulation of Working Time" must be adhered to. All contractors are required to maintain an accurate record of time worked by each employee.

3.41.1 Normal work

All work conducted on site shall fall within the legal requirements in accordance with the Basic Conditions of Employment Act. Contractors will notify their Eskom Supervisor or project manager of any work that needs to be performed after hours according to the agreed arrangements. (The application needs to be submitted timeously). Where applicable, the notification should include proof of application, for overtime, to the Department of Labour and /or the letter of approval from the Department of Labour.

3.41.2 Night work/Standby work

When night work is to be performed, contractors shall provide sufficient lighting to enable the entire work site to be illuminated to a degree that employees will not work in dark (un-illuminated) or dimly lit areas. Care must be exercised as not to use few lights with high light intensives as this will cause night blindness.

If work is continuing from day light into night, at dusk, a tool box talk must be held where all employees will be advised of the hazards of night work and the extra precautions which require to be taken, i.e. poor housekeeping, stepping on uneven ground, stepping into holes etc.


3.41.3 Overtime

When overtime is required to be performed, **Principal Contractor** shall inform the Eskom project manager of such action. Schindler shall be aware of the effects of human fatigue and regulate overtime accordingly. The baseline risk assessment must be reviewed to include the management of overtime work.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.

	SHE SPECIFICATION HIGH RISK/CONSTRUCTION SERVICES	Template Identifier	240-73416879	Rev	2
		Document Identifier	LBS0067PS-H	Rev	06
		Effective Date	30 September 2018		
		Review Date	August 2023		

3.42 Omissions from Safety and Health Requirements Specification

By drawing up this SHE specification Eskom has endeavoured to address the most critical aspects relating to SHE issues in order to assist **Principal Contractor** to adequately provide for the health and safety of employees on site.

Should Eskom not have addressed all SHEQ aspects pertaining to the work that is tendered for, the contractor needs to include it in the SHE plan and inform Eskom of such issues when signing the contract.

3.43 Contract Sign-Off

On completion of the project, all appointed contractors shall close out their project documentation; SHE files and forward **Principal Contractor** shall likewise close out his/her project documentation and SHE file and forward such to the Eskom project manager.

4. Acceptance

Null.

1. REVISIONS

Date	Rev.	Compiler	Remarks
3 January 2022	1	Erick Ramadie	This provides the initial SHE specification requirements that must be met by the relevant contractors who have been awarded a contract for the work to be performed for Eskom.
3 January 2022	2	Erick Ramadie	Inclusion of the Baseline Risk Assessment in the Specifications for Contractors.
11 May 2022	3	Tshokolo Mofokeng	Making the specifications to be scope specific and also included scope risk assessment.

Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.