## SPECIFICATIONS FOR TILLAGE SERVICES AT DAMPLAATS

Location: Damplaats, Marobala Village, Capricon District, Limpopo

Total land area for the required tractor services = 0.75 ha (Three quarters of a hectare)

| Service Required | Date        | Implements to use                | Land area         |
|------------------|-------------|----------------------------------|-------------------|
| Ploughing and    | 10 November | 1. Tractor                       | 0.25 Ha (quarter  |
| discing          | 2025        | 2. Tractor drawn                 | of a hectare)     |
|                  |             | mouldboard plough                |                   |
|                  |             | 3. Tractor-drawn plough disc     |                   |
| Planting sorghum | 11 November | 2-row or 6-row tractor-drawn No- | 0.25 Ha (quarter  |
|                  | 2025        | Till planter                     | of a hectare)     |
| Ploughing and    | 1 December  | 1. Tractor                       | 0.5 Ha (Half of a |
| discing          | 2025        | 2. Tractor drawn                 | hectare)          |
|                  |             | mouldboard plough                |                   |
|                  |             | 3. Tractor-drawn plough disc     |                   |
| Planting sorghum | 2 December  | 2-row or 6-row tractor-drawn No- | 0.5 Ha (Half of a |
|                  | 2025        | Till planter                     | hectare)          |

## **Mandatory requirements:**

- Only 2-row or 6-row tractor drawn No-till planter **MUST** be used
- No-till planter **MUST HAVE** seed and fertilizer bins
- No-till planter **MUST USE** sorghum seed plates or be calibrated for sorghum seed.
- All implements should be in good working condition
- No exceptions will be made for the above requirements