

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
<p>14.7.1 The payment reduction of the value certified in a <b>payment certificate</b> shall be <i>mutatis mutandi</i> in terms of 31.8(B)</p> <p>14.7.2 The <b>employer</b> shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the <b>employer</b> complies with the provisions of 33.4 in which event the <b>employer's</b> entitlement shall take precedence over his obligations to refund the payment reduction or portions thereof to the <b>contractor</b></p> <p>14.8 Payments made by the guarantor to the <b>employer</b> in terms of the fixed or variable <b>construction guarantee</b> shall not prejudice the rights of the <b>employer</b> or <b>contractor</b> in terms of this <b>agreement</b></p> <p>14.9 Should the <b>contractor</b> fail to furnish the <b>security</b> in terms of 14.2, the <b>employer</b>, in his sole discretion and without notification to the <b>contractor</b>, is entitled to change the <b>contractor's</b> selected form of <b>security</b> to that of a ten per cent (10%) payment reduction of the value certified in the <b>payment certificate</b> (excluding VAT), whereafter 14.7 shall be applicable</p> <p>Fixed:..... Value related:..... Time related:.....</p> <p><b><u>EXECUTION</u></b></p> <p>13 <b>A15 PREPARATION FOR AND EXECUTION OF THE WORKS</b></p> <p>Clause 15.0</p> <p>Clause 15.1.1 is amended by replacing it with:</p> <p>No Clause</p> <p>Clause 15.1.2 is amended by replacing it with:</p> <p>The <b>security</b> selected in terms of 14.0</p>	Item		
	<b>Carried Forward</b>		R
<p>Section No. 1 Bill No. 1 Preliminaries</p>			

RJ

101  
  
 R. M. - T. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		R
	<p>Clause 15.1 is amended by the addition of the following clause:</p> <p>15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within twenty one (21) <b>calendar days of commencement date</b></p> <p>Clause 15.2.1 is amended by replacing it with the following clause:</p> <p>Give the <b>contractor</b> possession of the <b>site</b> within ten (10) <b>working days</b> of the <b>contractor</b> complying with the terms of 15.1.2 and 15.1.4</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
14	<p><b>A16 ACCESS TO THE WORKS</b></p> <p>Clause 16.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
15	<p><b>A17 CONTRACT INSTRUCTIONS</b></p> <p>Clause 17.0</p> <p>Clause 17.1.11 is amended by deleting the words "and the appointment of <b>nominated</b> and <b>selected subcontractors</b>"</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
16	<p><b>A18 SETTING OUT OF THE WORKS</b></p> <p>Clause 18.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
17	<p><b>A19 ASSIGNMENT</b></p> <p>Clause 19.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R
	<p>Section No. 1 Bill No. 1 Preliminaries</p>		

*RJ*

**102**  
*L. M. M. M.*  
R.M. T.M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
18	<p><b>A20 NOMINATED SUB-CONTRACTORS</b></p> <p>Clause 20.0</p> <p>Clause 20.1.3 is amended by replacing it with the following:</p> <p>No Clause</p> <p>Note: See item B9.1 hereinafter for adjustment of attendance on <b>nominated subcontractors</b> executing work allowed for under provisional sums</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
19	<p><b>A21 SELECTED SUBCONTRACTORS</b></p> <p>Clause 21.0</p> <p>Clause 21 is amended by replacing it with:</p> <p>No Clause</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
20	<p><b>A22 EMPLOYER'S DIRECT CONTRACTORS</b></p> <p>Clause 22.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
21	<p><b>A23 CONTRACTOR'S DOMESTIC SUBCONTRACTORS</b></p> <p>Clause 23.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
<b><u>COMPLETION</u></b>			
22	<p><b>A24 PRACTICAL COMPLETION</b></p> <p>Clause 24.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
<b>Carried Forward</b>			R
<p>Section No. 1 Bill No. 1 Preliminaries</p>			

*RJ*

**103**

*L. M. M. M.*

*R. M. M. M.*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		R
23	<b>A25 WORK'S COMPLETION</b>  Clause 25.0  Fixed:..... Value related:..... Time related:.....	Item	
24	<b>A26 FINAL COMPLETION</b>  Clause 26.0  Clause 26.1.2 is amended by inserting "#" next to 26.1.2  Fixed:..... Value related:..... Time related:.....	Item	
25	<b>A27 LATENT DEFECTS LIABILITY PERIOD</b>  Clause 27.0  Fixed:..... Value related:..... Time related:.....	Item	
26	<b>A28 SECTIONAL COMPLETION</b>  Clause 28.0  Fixed:..... Value related:..... Time related:.....	Item	
27	<b>A29 REVISION OF DATE FOR PRACTICAL COMPLETION</b>  Clause 29.0  Clause 29.2.5 is amended by replacing it with:  No clause  Fixed:..... Value related:..... Time related:.....	Item	
28	<b>A30 PENALTY FOR NON-COMPLETION</b>  Clause 30.0  Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
	Section No. 1 Bill No. 1 Preliminaries		

*R J*

**104**  
*[Signature]*  
R M T M

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward	R	
	<b><u>PAYMENT</u></b>		
29	<b>A31 INTERIM PAYMENT TO THE CONTRACTOR</b>		
	Clause 31.0		
30	Clause 31.5.2 is amended by replacing "14.7.1" with "14.0"		
	Clause 31.8 is amended by replacing it with the following two alternative clauses:		
	<b>Alternative A</b>		
	31.8(A) Where a <b>security</b> is selected in terms of 14.1; 14.5 or 14.6, the value of the <b>works</b> in terms of 31.4.1 and <b>materials and goods</b> in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:		
	31.8(A).1 Ninety five per cent (95%) of such value in interim <b>payment certificates</b> issued up to the date of <b>practical completion</b>		
	31.8(A).2 Ninety seven per cent (97%) of such value in interim <b>payment certificates</b> issued on the date of <b>practical completion</b> and up to but excluding the date of <b>final completion</b>		
	31.8(A).3 Ninety nine per cent (99%) of such value in interim <b>payment certificates</b> issued on the date of <b>final completion</b> and up to but excluding the final <b>payment certificate</b> in terms of 34.6		
	31.8(A).4 One hundred per cent (100%) of such value in the final <b>payment certificate</b> in terms of 34.6 except where the amount certified is in favour of the <b>employer</b> . In such an event the payment reduction shall remain at the adjustment level applicable to the final <b>payment certificate</b>		
	<b>Alternative B</b>		
	31.8(B) Where <b>security</b> is a payment reduction in terms of 14.7 the value of the <b>works</b> in terms of 31.4.1 and <b>materials and goods</b> in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:		
	<b>Carried Forward</b>	R	
	Section No. 1		
	Bill No. 1		
	Preliminaries		

R7

105  
R. M. T. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

		R
<b>Brought Forward</b>		
31.8(B).1 Ninety per cent (90%) of such value in interim <b>payment certificates</b> issued up to the date of <b>practical completion</b>		
31.8(B).2 Ninety seven per cent (97%) of such value in interim <b>payment certificates</b> issued on the date of <b>practical completion</b> and up to but excluding the date of <b>final completion</b>		
31.8(B).3 Ninety nine per cent (99%) of such value in interim <b>payment certificates</b> issued on the date of <b>final completion</b> and up to but excluding the final <b>payment certificate</b> in terms of 34.6		
31.8(B).4 One hundred per cent (100%) of such value in the final <b>payment certificate</b> in terms of 34.6 except where the amount certified is in favour of the <b>employer</b> . In such an event the payment reduction shall remain at the adjustment level applicable to the final <b>payment certificate</b>		
Clause 31.12 is amended by deleting the following:		
31 Payment shall be subject to the <b>employer</b> giving the <b>contractor</b> a tax invoice for the amount due		
Fixed:..... Value related:..... Time related:.....		
32 <b>A32 ADJUSTMENT TO THE CONTRACT VALUE</b>		
Clause 32.0		
Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:		
"due to no fault of the <b>contractor</b> "		
Fixed:..... Value related:..... Time related:.....		
33 <b>A33 RECOVERY OF EXPENSE AND LOSS</b>		
Clause 33.0		
Fixed:..... Value related:..... Time related:.....		
<b>Carried Forward</b>		R
Section No. 1 Bill No. 1 Preliminaries		

Item

**106**  
*[Handwritten Signature]*  
R.M. T.M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
34	<p><b>A34 FINAL ACCOUNT AND FINAL PAYMENT</b></p> <p>Clause 34.0</p> <p>Clause 34.1 is amended by removing "#" next to 34.1</p> <p>Clause 34.2 is amended by removing "#" next to 34.2</p> <p>Clause 34.8 is amended by deleting the words "where <b>security</b> as a fixed <b>construction guarantee</b> in terms of 14.4 has been selected or where payment reduction has been applied in terms of 14.7.1"</p> <p>Clause 34.13 is amended by replacing "seven (7) <b>calendar days</b>" with "twenty one (21) <b>calendar days</b>" and deleting the words "subject to the <b>employer</b> giving the <b>contractor</b> a tax invoice for the amount due"</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
35	<p><b>A35 PAYMENT TO OTHER PARTIES</b></p> <p>Clause 35.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R

Section No. 1  
Bill No. 1  
Preliminaries

*RJ*

**107**  
*R. N. [Signature]*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

**Brought Forward**

R

**CANCELLATION**

**A36 CANCELLATION BY EMPLOYER -  
CONTRACTOR'S DEFAULT**

Clause 36.0

Clause 36.1 is amended by the addition of the following clauses:

36.1.3 refuses or neglects to comply strictly with any of the conditions of contract

36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa

36.1.5 in the judgement of the **employer**, has engaged in **corrupt** or **fraudulent practices** in competing for or in executing the contract

Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "**principal agent**" with "**employer**"

Clause 36.0 is amended by the addition of the following clause:

36.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed:..... Value related:..... Time related:.....

Item

**36 A37 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE**

Clause 37.0

Clauses 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"

**Carried Forward**

R

Section No. 1  
Bill No. 1  
Preliminaries

*RJ*

**108**  
*R.M. [Signature]*  
1.11.16

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

**Brought Forward**

R

Clause 37.0 is amended by the addition of the following clause:

37.5 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed:..... Value related:..... Time related:.....

Item

**37 A38 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT**

Clause 38.0

Clauses 38.5.4 is amended by replacing "ninety (90) with "one hundred and twenty (120)"

Clause 38.0 is amended by the addition of the following clause:

38.7 Notwithstanding any clause to the contrary, on cancellation of this **agreement** either by the **employer** or the **contractor**; or for any reason whatsoever, the **contractor** shall on written instruction, discontinue with the **works** on a date stated and withdraw himself from the **site**. The **contractor** shall not be entitled to refuse to withdraw from the **works** on the grounds of any lien or right of retention or on the grounds of any other right whatsoever

Fixed:..... Value related:..... Time related:.....

Item

**Carried Forward**

R

Section No. 1  
Bill No. 1  
Preliminaries

*RJ*

**109**  
*Tim R. N. [Signature]*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
38	<p><b>A39 CESSATION - CANCELLATION OF THE WORKS</b></p> <p>Clause 39.0</p> <p>Clauses 39.3.5 is amended by the addition of the following at the end of the sentence "within one hundred and twenty (120) <b>working days</b> of completion of such a report"</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
39	<p><b>A40 DISPUTE SETTLEMENT</b></p> <p>Clause 40.0</p> <p>Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"</p> <p>Clause 40.6 is amended by removing the reference to:</p> <p>No clause</p> <p>Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:</p> <p>Whether or not mediation resolves the dispute, the parties shall bear their own cost concerning the mediation and equally share the costs of the <b>mediator</b> and related costs</p> <p>Fixed:..... Value related:..... Time related:.....</p> <p><b><u>SUBSTITUTE PROVISIONS</u></b></p>	Item	
40	<p><b>A41 STATE CLAUSES</b></p> <p>Clause 41.0</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R
	<p>Section No. 1 Bill No. 1 Preliminaries</p>		

*RS*  
*J.M. [Signature]*  
**110**  
R.M.

Brought Forward

R

**CONTRACT VARIABLES**

**THE SCHEDULE**

41 **A42 PRE-TENDER INFORMATION**

Clause 42.0

Tenderers are referred to the Contract Data

Fixed:..... Value related:..... Time related:.....

Item

**SECTION B: JBCC PRELIMINARIES**

**1: DEFINITIONS AND INTERPRETATION**

42 ***Definitions and interpretation***

See also clause A1.0 of Section A for additional an/or amended definitions which shall apply to this Section

Fixed:..... Value related:..... Time related:.....

Item

**2: DOCUMENTS**

43 ***Checking of documents***

Fixed:..... Value related:..... Time related:.....

Item

44 ***Provisional bills of quantities***

Fixed:..... Value related:..... Time related:.....

Item

45 ***Availability of construction documentation***

Fixed:..... Value related:..... Time related:.....

Item

46 ***Interests of agents***

Fixed:..... Value related:..... Time related:.....

Item

Carried Forward

R

Section No. 1  
Bill No. 1  
Preliminaries

RG

  
 R. M.  
 J. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R	
47	<b>Priced documents</b> Fixed:..... Value related:..... Time related:.....	Item		
48	<b>Tender submission</b> Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Invitation to Bid: (PA-32)" Fixed:..... Value related:..... Time related:.....	Item		
	<b><u>3: THE SITE</u></b>			
49	<b>Defined works area</b> Fixed:..... Value related:..... Time related:.....	Item		
50	<b>Geotechnical investigation</b> Fixed:..... Value related:..... Time related:.....	Item		
51	<b>Inspection of the site</b> Fixed:..... Value related:..... Time related:.....	Item		
52	<b>Existing premises occupied</b> Fixed:..... Value related:..... Time related:.....	Item		
53	<b>Previous work - dimensional accuracy</b> Fixed:..... Value related:..... Time related:.....	Item		
54	<b>Previous work - defects</b> Fixed:..... Value related:..... Time related:.....	Item		
55	<b>Services - known</b> Fixed:..... Value related:..... Time related:.....	Item		
	<b>Carried Forward</b>		R	
	Section No. 1 Bill No. 1 Preliminaries			

RJ

112  
L. J. ...  
D. M. ...

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		R
56	<b>Services - known</b> Fixed:..... Value related:..... Time related:.....	Item	
57	<b>Protection of trees</b> Fixed:..... Value related:..... Time related:.....	Item	
58	<b>Articles of value</b> Fixed:..... Value related:..... Time related:.....	Item	
59	<b>Inspection of adjoining properties</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b><u>4: MANAGEMENT OF CONTRACT</u></b>		
60	<b>Management of the works</b> Fixed:..... Value related:..... Time related:.....	Item	
61	<b>Programme for the works</b> Fixed:..... Value related:..... Time related:.....	Item	
62	<b>Progress meetings</b> Fixed:..... Value related:..... Time related:.....	Item	
63	<b>Technical meetings</b> Fixed:..... Value related:..... Time related:.....	Item	
64	<b>Project Steering Committee meetings</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
	Section No. 1 Bill No. 1 Preliminaries		

RJ

113

  
 R. N. J. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
65	<b>Labour and plant records</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b><u>5: SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS</u></b>		
66	<b>Samples of materials</b> Fixed:..... Value related:..... Time related:.....	Item	
67	<b>Workmanship samples</b> Fixed:..... Value related:..... Time related:.....	Item	
68	<b>Shop drawings</b> Fixed:..... Value related:..... Time related:.....	Item	
69	<b>Compliance with manufacturer's instructions</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b><u>6: TEMPORARY WORKS AND PLANT</u></b>		
70	<b>Deposits and fees</b> Fixed:..... Value related:..... Time related:.....	Item	
71	<b>Enclosure of the works</b> Fixed:..... Value related:..... Time related:.....	Item	
72	<b>Advertising</b> Fixed:..... Value related:..... Time related:.....	Item	
73	<b>Plant, equipment, sheds and offices</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
	Section No. 1 Bill No. 1 Preliminaries		

RT

114

R. N. [Signature]

15.04

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
74	<b>Main notice board</b> Fixed:..... Value related:..... Time related:.....	Item	
75	<b>Subcontractors' notice board</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b><u>7: TEMPORARY SERVICES</u></b>		
76	<b>Location</b> Fixed:..... Value related:..... Time related:.....	Item	
77	<b>Water</b> Fixed:..... Value related:..... Time related:.....	Item	
78	<b>Electricity</b> Fixed:..... Value related:..... Time related:.....	Item	
79	<b>Telecommunication facilities</b> Fixed:..... Value related:..... Time related:.....	Item	
80	<b>Ablution facilities</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b><u>8: PRIME COST AMOUNTS</u></b>		
	<b><u>9: ATTENDANCE ON N/S SUBCONTRACTORS</u></b>		
81	<b>General attendance</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
	Section No. 1 Bill No. 1 Preliminaries		

115

R.J. [Signature]

R.M. [Signature]

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
82	<b>Special attendance</b> Fixed:..... Value related:..... Time related:.....	Item	
83	<b>Commissioning - fuel, water and electricity</b> Fixed:..... Value related:..... Time related:.....	Item	
<b><u>10: FINANCIAL ASPECTS</u></b>			
84	<b>Statutory taxes, duties and levies</b> Fixed:..... Value related:..... Time related:.....	Item	
85	<b>Payment for preliminaries</b> Fixed:..... Value related:..... Time related:.....	Item	
86	<b>Adjustment of preliminaries</b> Clauses B10.3.1 and B10.3.2 are amended by replacing "within fifteen (15) <b>working days</b> of taking possession of the <b>site</b> " with "when submitting his priced <b>bills of quantities / lump sum document</b> " Fixed:..... Value related:..... Time related:.....	Item	
87	<b>Payment certificate cash flow</b> Fixed:..... Value related:..... Time related:.....	Item	
<b><u>11: GENERAL</u></b>			
88	<b>Protection of the works</b> Fixed:..... Value related:..... Time related:.....	Item	
89	<b>Protection / isolation of existing / sectionally occupied works</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
Section No. 1 Bill No. 1 Preliminaries			

*RJ*

**116**  
*[Signature]*  
R. N. 15.02

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
90	<b>Security of the works</b> Fixed:..... Value related:..... Time related:.....	Item	
91	<b>Notice before covering work</b> Fixed:..... Value related:..... Time related:.....	Item	
92	<b>Disturbance</b> Fixed:..... Value related:..... Time related:.....	Item	
93	<b>Environmental disturbance</b> Fixed:..... Value related:..... Time related:.....	Item	
94	<b>Works cleaning and clearing</b> Fixed:..... Value related:..... Time related:.....	Item	
95	<b>Vermin</b> Fixed:..... Value related:..... Time related:.....	Item	
96	<b>Overhand work</b> Fixed:..... Value related:..... Time related:.....	Item	
97	<b>Instruction manuals and guarantees</b> Fixed:..... Value related:..... Time related:.....	Item	
98	<b>As built information</b> Fixed:..... Value related:..... Time related:.....	Item	
99	<b>Tenant installations</b> Fixed:..... Value related:..... Time related:.....	Item	
	<b>Carried Forward</b>		R
	Section No. 1 Bill No. 1 Preliminaries		

RJ

117

\* Jim

R. R. [Signature]

Brought Forward

R

**12: SCHEDULE OF VARIABLES**

100

***Schedule of Variables***

Fixed:..... Value related:..... Time related:.....

Item

This **schedule** contains all variables referred to in this document and is divided into pretender and post tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post tender categories form part of these Preliminaries.

Spaces requiring information must be filled in, shown as "not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the **schedule**. Key cross reference clauses are italicised in [ ] brackets

**12.1 PRE TENDER INFORMATION**  
**12.1.1 Provisional Bills of Quantities**  
 [2.2] The quantities are provisional  
**NO**

**12.1.2 Availability of construction documentation**  
 [2.3] *Construction documentation is complete*  
**YES**

**12.1.3 Interest of agents**  
 [2.4] Details: None

**12.1.4 Defined works area**  
 [3.1] Details: As defined in the tender drawings issued

**12.1.5 Geotechnical investigation**  
 [3.2] Details: Refer to Geotechnical Investigation Report included in tender document

**12.1.6 Existing premises occupied**  
 [3.4] Specific requirements: The site is vacant.

Carried Forward

R

Section No. 1  
 Bill No. 1  
 Preliminaries

118  
Jan

Ry

R. M. [Signature]



**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
<p><b>12.1.17 Electricity</b>                      [7.3] Option A (by contractor)                            YES</p> <p>      Option B (by employer - free of charge)                            NO</p> <p>      Option C (by employer - metered)                            NO</p> <p><b>12.1.18 Telecommunications</b>                      [7.4] Telephone                            YES</p> <p>      Facsimile                            NO</p> <p>      E-mail                            YES</p> <p><b>12.1.19 Ablution facilities</b>                      [7.5] Option A (by contractor)                            YES</p> <p>      Option B (by employer)                            NO</p> <p><b>12.1.20 Protection of existing/sectionally occupied works</b>                      [11.2] Protection is required                            YES</p> <p><b>12.1.21 Special attendance</b>                      [9.2] <b>Subcontractor</b> (1) details: None</p> <p>      <b>Subcontractor</b> (2) details: None</p> <p>      <b>Subcontractor</b> (3) details: None</p> <p>      <b>Subcontractor</b> (4) details: None</p> <p><b>12.1.22 Protection of works</b>                      [11.1] Specific requirements: By Contractor.</p> <p><b>12.1.23 Disturbance</b>                      [11.5] Specific requirements: None</p>			
	<b>Carried Forward</b>		R
<p>Section No. 1                      Bill No. 1                      Preliminaries</p>			R

120

J.W

RY

R.N.

M.K.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R	
12.1.24 <b>Environmental disturbance</b> [11.6] Specific requirements: None				
<b>12.2 POST TENDER INFORMATION</b>				
12.2.1 <b>Payment of preliminaries</b> [10.2] Option A (prorated)				
Option B (calculates)				
12.2.2 <b>Adjustment of preliminaries</b> [10.3] Option A (three categories)				
Option B (detailed breakdown)				
12.2.3 <b>Additional agreed preliminaries items</b> Details: None				
<b>Carried Forward</b>			R	
Section No. 1 Bill No. 1 Preliminaries				<div style="font-size: 2em; font-weight: bold;">121</div> <div style="font-size: 0.8em;">J. van</div> <div style="font-size: 0.8em;">R.M.</div>

121

R.M.

[Signature]

Brought Forward

R

**SECTION C: SPECIFIC PRELIMINARIES**

**Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item**

101

**C1 CONTRACT DRAWINGS**

The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the **works** and the manner in which they are to be executed

Should any part of the drawings not be clearly intelligible to the tenderer he shall, before submitting his tender, obtain clarification in writing from the **principal agent**

Fixed:..... Value related:..... Time related:.....

Item

102

**C2 PREAMBLES**

The document "Specification of Materials and Methods to be used (PW371)" is obtainable on the Department's website <[http://www.public works.gov.za/](http://www.publicworks.gov.za/)> under "Consultants Guidelines", and shall be read in conjunction with the bills of quantities document and be referred to for the full descriptions of work to be done and materials to be used

The document "Construction Works: Specifications: Partic Edition 2.0" is issued together with the drawings and shall drawings and the **bills of quantities / lump sum docume**

Fixed:..... Value related:..... Time related:.....

Item

Carried Forward

R

Section No. 1  
Bill No. 1  
Preliminaries

Ry

122  
M.S.  
R.N.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R
103	<p><b>C3 TRADE NAMES</b></p> <p>Wherever a trade name for any product has been described in the <b>bills of quantities</b>, the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the <b>principal agent</b> being obtained prior to the closing date for submission of tenders</p> <p>If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
104	<p><b>C4 IMPORTED MATERIALS AND EQUIPMENT</b></p> <p>Where imported items are listed in the tender documents, the tenderer shall provide all the information called for, failing which the price of any such item, materials or equipment shall be excluded from currency fluctuations (refer to Schedule of Imported Materials and Equipment to be completed by tenderer)</p> <p>Notwithstanding any provisions elsewhere regarding the adjustment of contract prices, the price of any item, material or equipment listed in terms of this clause shall be excluded from the Contract Price Adjustment Provisions (if applicable)</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
105	<p><b>C5 VIEWING THE SITE IN SECURITY AREAS</b></p> <p>The <b>site</b> is situated in a security area and the tenderer must arrange with the user department or other responsible person to obtain permission to enter the <b>site</b> for tendering purposes</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R
	<p>Section No. 1 Bill No. 1 Preliminaries</p>		

RJ

123  
R. M. [Signature] J.M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward		R	
106	<p><b>C6 COMMENCEMENT OF WORKS IN SECURITY AREAS</b></p> <p>As the <b>works</b> falls within a security area the <b>contractor</b> must give the user department or other responsible person notice before commencement of the <b>works</b>. Should the <b>contractor</b> fail to make such arrangements, admission to the <b>site</b> may be refused and any additional costs will be for the <b>contractor's</b> account</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item		
107	<p><b>C7 ENTRANCE PERMITS TO SECURITY AREAS</b></p> <p>As the <b>works</b> falls within a security area the <b>contractor</b> shall obtain entrance permits for his personnel and workmen entering the area and shall comply with all regulations and instructions which may be issued from time to time regarding the protection of persons and property under the control of the Defence Force, Police or chief security officer</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item		
108	<p><b>C8 SECURITY CHECK OF PERSONNEL</b></p> <p>The <b>principal agent</b> may require the <b>contractor</b> to have his personnel and workmen, or a certain number of them, security classified</p> <p>In the event of the <b>principal agent</b> requesting the removal of a person or persons from the <b>works</b> for security reasons, the <b>contractor</b> shall do so forthwith and shall thereafter ensure that such person or persons are denied access to the <b>works</b> and the <b>site</b> and/or to any document or information relating to the <b>works</b></p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item		
	<b>Carried Forward</b>		R	
<p>Section No. 1 Bill No. 1 Preliminaries</p>				

*RJ*  
*124*  
*R. M.*  
*J. W.*

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

	Brought Forward		R
109	<p><b>C9 PROHIBITION ON TAKING OF PHOTOGRAPHS</b></p> <p>In terms of article 119 of the Defence Act, 44 of 1957, it is prohibited to sketch or to take photographs of any military site or installation or any building or civil works thereon or to be in possession of a camera or other apparatus used for taking of photographs except when authorized thereto by or on behalf of the Minister</p> <p>The same prohibition is also applicable to all correctional institutions in terms of article 44.1(e) of the Correctional Services Act 8 of 1959</p> <p>Fixed:..... Value related:..... Time related:.....</p> <p><b>C10 HIV/AIDS AWARENESS</b></p> <p>It is required of the <b>contractor</b> to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department of Public Works and Infrastructure that must be read together with and is deemed to be incorporated under this Section of the Bills of Quantities. Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained</p> <p>The <b>contractor</b> must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the <b>principal agent</b>, notwithstanding the provisions of Clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress <b>payment certificate</b> until the <b>contractor</b> provides satisfactory proof of compliance. The <b>contractor</b> shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment</p>	Item	
	Carried Forward		R
	Section No. 1 Bill No. 1 Preliminaries		

R7

125

*Michael J. van R. N.*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		R
110	<p><b>C10.1 AWARENESS CHAMPION</b></p> <p>Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS specification</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
111	<p><b>C10.2 AWARENESS WORKSHOPS</b></p> <p>Selection and appointment of a competent Service Provider approved by the <b>principal agent</b>, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi-media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
112	<p><b>C10.3 POSTERS, BOOKLETS, VIDEOS, ETC.</b></p> <p>Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the <b>construction period</b>, all in accordance with the HIV/AIDS Specification</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
113	<p><b>C10.4 ACCESS TO CONDOMS</b></p> <p>Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the <b>construction period</b>, all in accordance with the HIV/AIDS Specification</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R
	<p>Section No. 1 Bill No. 1 Preliminaries</p>		

126  
*PJ*  
*[Signature]*  
 P. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		R
114	<p><b>C10.5 MONITORING</b></p> <p>Monitoring HIV/AIDS awareness of workers, providing the <b>principal agent</b> with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the <b>construction period</b> and close out, all in accordance with the HIV/AIDS Specification</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
115	<p><b>C11 : OCCUPATIONAL HEALTH AND SAFETY ACT</b></p> <p>Provision for pricing of the Occupational Health and Safety Act, Construction Regulation and Project Specific Occupational Health and Safety Specification is made under this clause and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder and no additional claims in this regard shall be entertained.</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
116	<p><b>C12 COMMUNITY LIAISON OFFICER (CLO)</b></p> <p>The <b>contractor</b> shall employ a Community Liaison Officer (CLO) for the full duration of the contract (24 months). Allow an amount of R 8 500 (Eight Thousand Five Hundred Rand) per month for CLO remuneration</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried Forward</b>		R
<p>Section No. 1 Bill No. 1 Preliminaries</p>			

*RJ*  
**127**  
*J. van*  
*[Signature]*  
 R. C.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>		<b>R</b>
117	<p><b>C13 USE OF LOCAL SMME's</b></p> <p>It is the requirement of the employer that the contractor enhances the use of local Small, Micro and Medium Enterprises (SMME's) involved in the project. This is required to be done through the use of both traditional building techniques and labour intensive construction techniques, careful and considered construction planning Provision for pricing of compliance with the aforementioned is made under this clause and it is explicitly pointed out that all requirements in respect of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained</p> <p>(a) SMME's involvement of at least 30% of the contract value to be sourced from within a specified range from the project site</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
118	<p><b>C14 IMPLEMENTATION OF LABOUR INTENSIVE WORK</b></p> <p>The Contractor shall employ local labourers as per part C3: Scope of Works for work identified and marked as 'labour -intensive' on these bills of quantities. The Contractor shall enter into an employment agreement with all workers and provide certified copies of such agreements and identity documents of the workers to the principal agent within 28 calendar days</p> <p>Provision for pricing of compliance with the aforementioned is made under this clause and it is explicitly pointed out that all requirements in respect of the aforementioned are deemed to be priced hereunder and no additional claims in this regard shall be entertained</p> <p>Fixed:..... Value related:..... Time related:.....</p>	Item	
	<b>Carried to Final Summary</b>		<b>R</b>
	Section No. 1 Bill No. 1 Preliminaries		

*RY*  
**128** *J.M*  
*M. M. M.*  
*R. M.*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Item No	Quantity	Rate	Amount
<p><b><u>SECTION NO. 2</u></b></p> <p><b><u>NEW BUILDINGS</u></b></p> <p><b><u>BILL NO. 1</u></b></p> <p><b><u>EARTHWORKS (PROVISIONAL)</u></b></p> <p><b><u>(CPAP WORK GROUP NO. 104 UNLESS OTHERWISE STATED)</u></b></p> <p>The Tenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades(2017 Edition)</p> <p><b><u>SUPPLEMENTARY PREAMBLES</u></b></p> <p><b><u>Nature of ground</u></b></p> <p>A soils investigation has been carried out on the site by the Engineer and the report is annexed to these Bills of Quantities</p> <p><b><u>Working space</u></b></p> <p>Working space for formwork will only be paid for where specifically required and instructed in writing by the Engineer</p> <p>In the case of column base and pile cap excavations, where the dimensions between the column face and the excavation face is less than 500mm, working space has been measured for the width of the column face from the commencing level of excavation to the top of the column base or pile cap only where the top of the column base or pile cap exceeds 1.5m below the commencing level of excavation</p> <p>No separate item for working space is provided or will be considered where the face of the measured excavation is 750mm or more away from the finished face of the structure. Separate items for working space for the building of brick foundation walls on ordinary concrete wall footings will not be considered</p>			
<b>Carried Forward</b>		R	
<p>Section No. 2 Bill No. 1 Earthworks (Provisional)</p>			<p><b>129</b></p> <p><i>[Handwritten Signature]</i></p> <p>R. R.</p>

*[Handwritten initials]*  
**129**  
*[Handwritten Signature]*  
R. R.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward		R
<b><u>Carting away of excavated material</u></b>		
Descriptions of carting away of excavated material shall be deemed to include loading excavated material onto trucks directly from the excavations or, alternatively, from stock piles situated on the construction site		
<b><u>Filling</u></b>		
Notwithstanding the reference to prescribed multiple handling in clause 13 page 14 of the Standard System of Measuring Building Work (Seventh Edition), prices for filling and backfilling shall include for all selection and any necessary multiple handling of material		
<b><u>EXCAVATION, FILLING, ETC OTHER THAN BULK</u></b>		
<b><u>Excavation in earth not exceeding 2m deep</u></b>		
1	Reduced levels under floors (LI) m3	351
2	Trenches (LI) m3	1,348
3	Holes (LI) m3	67
<b><u>Extra over trench and hole excavations in earth for excavation in</u></b>		
4	Soft rock m3	284
5	Hard rock m3	284
<b><u>Extra over all excavations for carting away</u></b>		
6	Surplus material from excavations and/or stock piles on site, to a dumping site to be located by the contractor m3	1,766
<b><u>Risk of collapse of excavations</u></b>		
7	Sides of trench and hole excavations not exceeding 1,5m deep (LI) m2	2,694
<b><u>Keeping excavations free of water</u></b>		
8	Keeping excavations free of all water other than subterranean water	Item
Carried Forward		R
Section No. 2 Bill No. 1 Earthworks (Provisional)		

RJ  
130 J.M.  
R.M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
<u>Imported G2 filling supplied by the contractor compacted to 98% Mod AASHTO density</u>			
9	Under floors, steps, pavings, etc (LI)	m3	351
<u>Imported G5 filling supplied by the contractor compacted to 98% Mod AASHTO density</u>			
10	Under floors, steps, pavings, etc (LI)	m3	351
<u>Imported G6 filling supplied by the contractor compacted in layers not exceeding 300mm thick to 92% Mod AASHTO density</u>			
11	Backfilling to trenches, holes (LI)	m3	443
12	Backfilling behind retaining walls (LI)	m3	1,368
<u>Compaction of surfaces</u>			
13	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 95% Mod AASHTO density (LI)	m2	2,337
<u>Prescribed density tests on filling</u>			
14	"Modified AASHTO Density" test	No	40
15	"Field Density" test including "Optimum Moisture Content" (four readings per test)	No	40
<u>SOIL POISONING</u>			
<u>Soil insecticide in accordance with SANS 10124</u>			
16	Under floors etc including forming and poisoning shallow furrows against foundation walls etc, filling in furrows and ramming	m2	2,337
17	To bottoms and sides of trenches, etc	m2	4,123
<b>Carried Forward to Summary of Section No. 2</b>			R
Section No. 2			
Bill No. 1			
Earthworks (Provisional)			

*RJ*

**131** *h.m*  
*[Signature]*  
R.M.

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

Item  
No

Quantity

Rate

Amount

**SECTION NO.2**

**NEW BUILDINGS**

**BILL NO. 2**

**CONCRETE, FORMWORK AND REINFORCEMENT**

**(CPAP WORK GROUP NO. 110 UNLESS OTHERWISE STATED)**

The Tenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2017 Edition)

**SUPPLEMENTARY PREAMBLES**

**Curing**

All concrete is to be effectively cured for a minimum of 5 days

**Cost of tests**

The costs of making, storing and testing of concrete test cubes as required under clause 7 "Tests" of SABS 1200 G shall include the cost of providing cube moulds necessary for the purpose, for testing costs and for submitting reports on the tests to the principal agent. The testing shall be undertaken by an independent firm or institution nominated by the contractor to the approval of the principal agent (Test cubes are measured separately)

Carried Forward

R

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement (Provisional)

*RJ*  
**132**  
*J.M*  
*[Signature]*  
 D - m

**Brought Forward**

R

**Concrete finishes**

Off Shutter Finishes must comply with SANS 2001-CC1:2007 Clause 5.2.5 - Smooth- special formwork

After striking the shutter uneven areas must be rubbed to remove fins etc

The "off shutter" areas must not be slushed

The first "off shutter" wall must be prepared as a sample for approval. If approved it will be used as a bench mark for subsequent walls and columns

**Formwork**

Descriptions of formwork shall be deemed to include use and waste only (except where described as "left in" or "permanent"), for fitting together in the required forms, wedging, plumbing and fixing to true angles and surfaces as necessary to ensure easy release during stripping and for reconditioning as necessary before re-use

The vertical strutting shall be carried down to such construction as is sufficiently strong to afford the required support without damage and shall remain in position until the newly constructed work is able to support itself

Formwork to soffits of solid slabs etc. shall be deemed to be to slabs not exceeding 250mm thick unless otherwise described

Formwork to soffits of slabs, beams, etc shall be deemed to be propped up exceeding 1,5m and not exceeding 3,5m high unless otherwise described

Formwork to sides of bases, pile caps, ground beams, etc will only be measured where it is prescribed by the engineer for design reasons. Formwork necessitated by irregularity or collapse of excavated faces will not be measured and the cost thereof shall be deemed to be included in the allowance for taking the risk of collapse of the sides of the excavations, provision for which is made in "Earthworks"

**Carried Forward**

R

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement (Provisional)

RJ

133  
M. M. M. M.  
R. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	Brought Forward			R
	<b><u>Reinforcement</u></b>			
	Steel bar reinforcement to comply with SANS 920 and cut and bent in accordance with SANS 82			
	Welded steel fabric shall comply to SANS 1024 manufactured from plain hard drawn mild steel wire			
	<b><u>UNREINFORCED CONCRETE CAST AGAINST EXCAVATED SURFACES (CPAP WORK GROUP NO. 110 UNLESS OTHERWISE STATED)</u></b>			
	<b><u>10MPa/19mm concrete</u></b>			
1	Surface blinding under footings and bases (LI)	m3	71	
	<b><u>REINFORCED CONCRETE (CPAP WORK GROUP NO. 110 UNLESS OTHERWISE STATED)</u></b>			
	<b><u>25MPa/19mm concrete</u></b>			
2	Strip footings (LI)	m3	360	
3	Bases (LI)	m3	22	
4	Surface beds, etc. including thickening (LI)	m3	394	
5	Slabs including downstand beams and upstand beams (LI)	m3	426	
6	Isolated beams (LI)	m3	20	
7	Concrete nib (LI)	m3	14	
8	Infill to cavity of hollow wall (LI)	m3	53	
	<b><u>30MPa/19mm concrete</u></b>			
9	Retaining walls in foundations (LI) (Provisional)	m3	26	
10	Retaining walls (LI)	m3	99	
11	Stairs including landings, beams and inverted beams (LI)	m3	13	
	<b>Carried Forward</b>			R
	Section No. 2			
	Bill No. 2			
	Concrete, Formwork and Reinforcement (Provisional)			

RJ

134

J.M.

M. M. M. M.

R. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
12	Ramps including landings, beams and inverted beams (LI)	m3	20
13	Columns in foundations (LI)	m3	6
14	Columns (LI)	m3	26
<b><u>TEST CUBES</u></b>			
15	Prepare a set of six concrete cubes each cube size 150 x 150 x 150mm for strength cubes and deliver to an approved laboratory for testing and pay all charges in connection therewith	No	110
<b><u>WATERPROOFING ADDITIVE</u></b>			
<b><u>"Penetron" or other equal and approved admixture with tracing agent 0.8% - 1% per cementitious content of concrete waterproofing additive</u></b>			
16	Extra over concrete for waterproofing on roof, floor slabs and retaining walls	m3	324
<b><u>CONCRETE SUNDRIES</u></b>			
<b><u>Finishing top surfaces of concrete with a wood float</u></b>			
17	Surface beds, slabs, etc (LI)	m2	4,342
<b><u>ROUGH FORMWORK (DEGREE OF ACCURACY II) (CPAP WORK GROUP NO. 111)</u></b>			
<b><u>Rough formwork to sides</u></b>			
18	Strip footings (LI)	m2	712
19	Bases (LI)	m2	177
20	Rectangular columns in foundations (LI)	m2	37
21	300mm Diameter circular columns 1m high in foundations (LI)	No	2
22	Rectangular columns in foundations (LI)	m2	51
23	Retaining walls in foundations with total wall height not exceeding 3.5m high (LI)	m2	192
Carried Forward			R
Section No. 2			
Bill No. 2			
Concrete, Formwork and Reinforcement (Provisional)			

*RJ*  
**135** J.M.  
*[Signature]*  
 R. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

<b>Brought Forward</b>		
24	Retaining walls with total wall height not exceeding 3.5m high (LI)	m2 720
25	Sloping and stepped outer edges of stairs 340mm high extreme (LI)	m 259
26	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m 55
<b><u>Rough formwork sides and soffits</u></b>		
27	Slabs not exceeding 250mm and not exceeding 500mm thick, propped exceeding 1.5m and not exceeding 3.5m high (LI)	m2 399
28	Slabs exceeding 250mm thick not exceeding 500mm, propped up exceeding 1.5m not exceeding 3.5m high (LI)	m2 972
<b><u>SMOOTH FORMWORK (DEGREE OF ACCURACY I)</u></b>		
<b><u>Smooth formwork to sides</u></b>		
29	Walls with total height not exceeding 3.5m high (LI)	m2 360
30	300mm Diameter circular columns 3m high (LI)	No 2
31	Rectangular columns (LI)	m2 26
32	Edges, risers, ends and reveals not exceeding 300mm high or wide (LI)	m 1,130
<b><u>Smooth formwork to sides and soffits</u></b>		
33	Slabs not exceeding 250mm thick, propped up exceeding 1.5m and not exceeding 3.5m high (LI)	m2 440
34	Isolated beams propped up not exceeding 3.5m high (LI)	m2 185
35	Beams propped up not exceeding 1,5m high (LI)	m2 104
36	Beams propped up exceeding 1,5m and not exceeding 3,5m high (LI)	m2 570

R

**Carried Forward**

R

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement (Provisional)

*RJ*

**136**  
*[Handwritten signature]*  
R. N.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
<b><u>Boxing in smooth formwork to form</u></b>			
37	20mm diameter half round drip mould to soffits of slab (LI)	m	787
38	25 x 25mm Chamfer along edges of all exposed concrete elements (LI)	m	499
<b><u>Formwork to form</u></b>			
39	Opening exceeding 3m and not exceeding 4m girth through 255mm slab (LI)	No	7
<b><u>MOVEMENT JOINTS, ETC</u></b>			
<b><u>Saw cut joints</u></b>			
40	3 x 45mm Saw cut joints on top of concrete (LI)	m	694
<b><u>Isolation joints with 10mm polystyrene between vertical concrete and brick surfaces</u></b>			
41	10mm Joints not exceeding 300mm high (LI)	m	1,926
<b><u>Slip joints between horizontal concrete and brick surfaces with two layers of 3 ply malthoid sealed with sealant (elsewhere measured)</u></b>			
42	Not exceeding 300mm wide (LI)	m	1,629
<b><u>REINFORCEMENT (CPAP WORK GROUP NO. 114 UNLESS OTHERWISE STATED)</u></b>			
<b><u>Mild tensile steel reinforcement to structural concrete work</u></b>			
43	8mm Diameter bars (LI)	t	12.48
44	10mm Diameter bars (LI)	t	11.11
<b><u>High tensile steel reinforcement to structural concrete work</u></b>			
45	10mm Diameter bars (LI)	t	56.50
46	12mm Diameter bars (LI)	t	66.80
47	16mm Diameter bars (LI)	t	57.98
Carried Forward			R
Section No. 2 Bill No. 2 Concrete, Formwork and Reinforcement (Provisional)			

RJ

137

J.M.  
R.M.  
M. M. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

		Brought Forward	
<b><u>High tensile steel dowel bars</u></b>			
48	Y16 Dowel bar 800mm long with one end cast into concrete and other end greased with non sag epoxy adhesive and wrapped in polythene sheeting (LI)	No	392
49	Y20 Dowel bar 700mm long with one end cast into concrete and other end greased with non sag epoxy adhesive and wrapped in polythene sheeting (LI)	No	164
<b><u>Fabric reinforcement</u></b>			
50	Type 193 fabric reinforcement in concrete surface beds, ramps, etc (LI)	m2	225
51	Type 245 fabric reinforcement in concrete surface beds, ramps, etc (LI)	m2	2,112

R

**Carried Forward to Summary of Section No. 2**

Section No. 2  
Bill No. 2  
Concrete, Formwork and Reinforcement (Provisional)

R

RJ

138

R. M. J. W.

L. M. M. M.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO. 2</u></b>			
	<b><u>NEW BUILDINGS</u></b>			
	<b><u>BILL NO. 3</u></b>			
	<b><u>PRECAST CONCRETE (CPAP WORK GROUP NO. 112 UNLESS OTHERWISE STATED)</u></b>			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	The Tenderer is referred to the relevant Clauses in the separate document General Preambles for Trades (2017 Edition)			
	<b><u>PURPOSE MADE PRECAST CONCRETE SLABS, ETC</u></b>			
	<b><u>Precast concrete slabs</u></b>			
1	4019 x 705 x 90mm Thick counter slabs formed of three lintels laid in parallel, closely butted at ends including bedding edges along both sides (screed elsewhere measured) Refer to Architects Drawing S4-706 Rev 5, Cell Joinery Details, J12 Cell Guard Details)	No	1	
	<b><u>PRECAST CONCRETE VANITY SLABS ETC</u></b>			
	<b><u>"Stonecast" or other equal and approved</u></b>			
2	900 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	4	
3	950 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	2	
	<b>Carried Forward</b>			R
	Section No. 2 Bill No. 3 Precast Concrete			

139  
MS  
R-11

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

	<b>Brought Forward</b>			R
4	1200 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	4	
5	2100 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	4	
6	2370 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	1	
7	2400 x 600 x 150mm Overall thick precast concrete cantilever vanity slab (Color: Sandstone), comprising of 60mm thick slab and 90mm down turn surround to all sides, fixed to wall and including fixing accessories, brackets, splashback, etc.to receive wash hand basin (elsewhere measured)	No	2	
<b>Carried Forward to Summary of Section No. 2</b>				R
Section No. 2				
Bill No. 3				
Precast Concrete				

RT

140 J.M  
[Signature]

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Item  
No

**SECTION NO. 2**

**NEW BUILDINGS**

**BILL NO. 4**

**MASONRY**

**(CPAP WORK GROUP NO. 116 UNLESS OTHERWISE STATED)**

The Tenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2017 Edition)

**SUPPLEMENTARY PREAMBLES**

**Sizes in descriptions**

Where sizes in descriptions are given in brick units, 'one brick' shall represent the length and 'half brick' the width of a brick

**Hollow walls, etc**

Descriptions of hollow walls shall be deemed to include leaving every fifth perpend of the bottom course of the external skin open as a weep hole

Walls in two skins described as 'bagged and sealed' shall be deemed to include having the outer face of the inner skin bagged with 1:3 cement and sand mixture and sealed with two coats bitumen emulsion waterproofing coating

**Face bricks**

Bricks shall be ordered timeously to obtain uniformity in size and colour

**Pointing**

Descriptions of recessed pointing to fair face brickwork and face brickwork shall be deemed to include square recessed, hollow recessed, weathered pointing, etc

**Carried Forward**

Section No. 2  
Bill No. 4  
Masonry

Quantity

Rate

Amount

R

R7

141 J.M.  
[Signature]  
D. 2

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
<b><u>BRICKWORK IN FOUNDATIONS</u></b>			
<b><u>(PROVISIONAL)</u></b>			
<b><u>Brickwork of NFX (14Mpa nominal compressive strength) in class II mortar</u></b>			
1	Piers (LI)	m3	1
2	Half brick walls (LI)	m2	9
3	One brick walls (LI)	m2	280
4	270mm Wide cavity wall formed of two half brick skins with 50mm cavity in between. (LI)	m2	442
5	330mm Wide cavity wall formed of two half brick skins with 110mm cavity in between (LI)	m2	57
6	330mm Solid walls (LI)	m2	5
7	440mm Solid walls (LI)	m2	3
<b><u>Galvanised brickwork reinforcement</u></b>			
8	75mm Wide reinforcement built in horizontally	m	11,224
9	150mm Wide reinforcement built in horizontally (LI)	m	3,078
10	230mm Wide reinforcement built in horizontally (LI)	m	308
<b><u>BRICKWORK IN SUPERSTRUCTURE</u></b>			
<b><u>Brickwork of NFP bricks (7 MPa nominal compressive strength) in class II mortar</u></b>			
11	Half brick walls (LI)	m2	812
12	60mm Stepped header course band around breeze-brick feature walls including cutting, etc (LI)	m	77
13	Brickwork for brick-on-edge soldier course lintels one course high pointed on face and 115mm soffits (LI)	m	271
14	220mm Coping on top of one brick walls including cutting, etc (LI)	m	8
Carried Forward			R
Section No. 2			
Bill No. 4			
Masonry			

RJ

142 J.W.  
[Signature]

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
15	325mm Coping on top of 270mm thick cavity brick walls including cutting, etc (LI)	m	765
<b><u>Brickwork of NFX bricks (14 MPa nominal compressive strength) in class II mortar</u></b>			
16	Piers (LI)	m3	11
17	Half brick walls (LI)	m2	199
18	One brick walls (LI)	m2	1,403
19	270mm Wide cavity wall formed of two half brick skins with 50mm cavity in between (LI)	m2	2,712
20	270mm Wide cavity wall formed of two half brick skins with 50mm cavity in between filled with 25Mpa/20mm concrete (else where measured) (LI)	m2	525
21	330mm Wide cavity wall formed of two half brick skins with 110mm cavity in between (LI)	m2	315
22	330mm Wide cavity wall formed of two half brick skins with 110mm cavity in between filled with 25Mpa/19mm concrete (else where measured) (LI)	m2	52
23	330mm Solid walls (LI)	m2	41
24	440mm Solid walls (LI)	m2	47
<b><u>Mortar tests</u></b>			
25	Allow for sampling, making and curing a 100mm nominal mortar test cube including the supply of moulds and handing over to the Representative/Agent for testing (LI)	No	20
<b><u>BRICKWORK SUNDRIES</u></b>			
26	Splayed mortar fillet one course high in 50mm cavity (LI)	m	232
27	Splayed mortar fillet one course high in 110mm cavity (LI)	m	145
28	Closing 50mm cavity of hollow wall horizontally with one course of brickwork (LI)	m	232
Carried Forward			R
Section No. 2 Bill No. 4 Masonry			

RT

143 J-07  
L. H. H. H.

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

<b>Brought Forward</b>			R
29	Closing 110mm cavity of hollow wall horizontally with one course of brickwork (LI)	m	145
<b><u>Bagging of 1:3 cement and sand mixture</u></b>			
30	On outer face of inner skin of brick walls including any additional labour required in raising wall in two separate skins and working around wire ties and / or brick reinforcing fabric (LI)	m2	2,814
<b><u>Galvanised brickwork reinforcement</u></b>			
31	75mm Wide reinforcement built in horizontally (LI)	m	33,805
32	150mm Wide reinforcement built in horizontally (LI)	m	5,732
33	230mm Wide reinforcement built in horizontally (LI)	m	165
<b><u>Prestressed fabricated concrete lintels including necessary temporary supports</u></b>			
34	110 x 75mm Lintels in lengths not exceeding 3m (LI)	m	542
<b><u>Joint forming material in movement joints</u></b>			
35	10mm Polystyrene built in vertically between brick skins (LI)	m2	531
<b><u>Turning pieces</u></b>			
36	220mm Wide turning piece to lintels, etc (LI)	m	271
<b><u>Concertina ties built into brickwork</u></b>			
37	30 x 1,2mm Galvanised steel strap wall ties (LI)	No	2,332
<b><u>Concertina ties built into brickwork and drive pins shot fired into brick/concrete wall</u></b>			
38	30 x 1,2mm Galvanised crimp wire wall ties (LI)	No	370
<b><u>Galvanised hoop iron cramps, ties, etc</u></b>			
39	30 x 1,6mm Roof tie 1500mm long with one end built into brickwork and other end tied around trusses (LI)	No	1,768
<b>Carried Forward</b>			R
Section No. 2 Bill No. 4 Masonry			R

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Brought Forward			R
<u>Air bricks etc</u>			
40	229 x 152mm Terra-cotta vermin proof air brick (LI)	No	90
<u>FACE BRICKWORK</u>			
<u>Face bricks in stretcher bond with concave mortar joints</u>			
41	Extra over brickwork for face brickwork (LI)	m2	585
<u>Face bricks in stretcher bond with concave mortar joints</u>			
42	Extra over brickwork for face brick piers (LI)	m2	11
43	Extra over brickwork for face brickwork (LI)	m2	2,210
44	Extra over brickwork walls faced on both sides (LI)	m2	163
45	Extra over brickwork for brick-on-edge soldier course lintels one course high pointed on face and 115mm soffits (LI)	m	86
46	230mm Wide sills set sloping and slightly projecting (LI)	m	271
47	Fair cutting and fitting around pipe not exceeding 100mm diameter (LI)	No	42
48	Fair cutting and fitting around pipe exceeding 100mm and not exceeding 200mm diameter (LI)	No	36
<u>Face bricks in stretcher bond with concave mortar joints</u>			
49	Extra over half brick walls faced on both sides (LI)	m2	77
50	Extra over brickwork for face brickwork (LI)	m2	626
51	Extra over brickwork walls faced on both sides (LI)	m2	601
52	Extra over brickwork for face brick piers (LI)	m2	75
53	230mm Wide sills set sloping and slightly projecting (LI)	m	66
Carried Forward			R
Section No. 2			
Bill No. 4			
Masonry			

*RS*

145  
R. J. W.  
*Michael*

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

Brought Forward		R
<b><u>Brick-on-edge header course copings, sills, etc. Face bricks pointed with recessed joints on all exposed faces</u></b>		
54	60mm Stepped header course band around breeze-brick feature walls including cutting, etc (LI)	m 77
55	220mm Coping wide on top of one brick walls including cutting, etc (LI)	m 8
<b><u>Dog toothing header course copings, sills, etc. of face bricks pointed with recessed joints on all exposed faces</u></b>		
56	325mm Coping wide on top of 270mm thick cavity brick walls including cutting, etc (LI)	m 156
<b><u>Dog toothing header course copings, sills, etc. face bricks pointed with recessed joints on all exposed faces</u></b>		
57	325mm Coping wide on top of 270mm thick cavity brick walls including cutting, etc (LI)	m 609
<b><u>DECORATIVE SCREEN WALLS AND GRILLES</u></b>		
<b><u>220 x 106 x 76mm Breeze-brick facebrick laid in stack bond formation with class II grey mortar and raked joints and perpends internally and externally</u></b>		
58	220mm Walls pointed on both sides (LI)	m2 92
<b><u>222 x 106 x 40mm Slimline breeze-brick facebrick laid in stack bond formation with class II grey mortar and raked joints and perpends internally and externally</u></b>		
59	220mm Walls pointed on both sides (LI)	m2 35
<b><u>FIBRE CEMENT WINDOW SILLS</u></b>		
<b><u>Internal window sills in single lengths not exceeding 3.6m, bedded in class I mortar including fixing lugs screwed to underside with self tapping screws</u></b>		
60	15 x 150mm Wide sills set flat and slightly projecting (LI)	m 510
<b>Carried Forward to Summary of Section No. 2</b>		R
Section No. 2		
Bill No. 4		
Masonry		

R1

146 J.M  
*[Signature]*

**SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION**

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO. 2</u></b>			
	<b><u>NEW BUILDINGS</u></b>			
	<b><u>BILL NO. 5</u></b>			
	<b><u>WATERPROOFING</u></b>			
	<b><u>(CPAP WORK GROUP NO. 120 UNLESS OTHERWISE STATED)</u></b>			
	The Tenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2017 Edition)			
	<b><u>SUPPLEMENTARY PREAMBLES</u></b>			
	<b><u>Waterproofing</u></b>			
	Waterproofing of roofs, basements, etc shall be laid under a ten year guarantee. Waterproofing to roofs shall be laid to even falls to outlets etc with necessary ridges, hips and valleys. Descriptions of sheet or membrane waterproofing shall be deemed to include additional labour to turn-ups and turn-downs			
	<b><u>DAMP-PROOFING OF WALLS AND FLOORS</u></b>			
	<b><u>One layer 375 micron embossed polyethylene damp proof course (SANS 952-1985 type B)</u></b>			
1	In walls (LI)	m2	242	
2	Under sills, around windows (LI)	m2	60	
	<b><u>One layer of 375 micron waterproof sheeting with 3mm thick masonite protection sealed at laps with tape</u></b>			
3	Vertically against walls to receive backfilling (elsewhere measured).	m2	456	
	<b>Carried Forward</b>			R
	Section No. 2 Bill No. 5 Waterproofing			

RJ  
 147 J.M.  
 R.M.  
*[Signature]*

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

Brought Forward			R
	<u>One layer 250 micron green polyethylene waterproof sheeting (SANS 952 Type C) sealed at laps with PVC self-adhesive tape</u>		
4	Under surface beds (LI)	m2	2,337
	<u>Two coats bitumen emulsion waterproof coating</u>		
5	On bagged brick walls (LI)	m2	2,814
	<b><u>WATERPROOFING TO SHOWER FLOORS AND WALLS</u></b>		
	<u>Undertile waterproofing system mixed and applied in accordance with the manufacturer's instructions</u>		
6	On screeded floors to receive tiles	m2	34
7	On shower walls	m2	168
	<b><u>WATERPROOFING TO BRICK WALLS, ETC.</u></b>		
	<u>Undertile waterproofing system mixed and applied in accordance with the manufacturer's instructions</u>		
8	On brick parapet walls, etc	m2	398
	<b><u>WATERPROOFING TO ROOFS, BASEMENTS, ETC.</u></b>		
	<u>Polyurethane waterproofing system mixed and applied to concrete in accordance with the manufacturer's instructions</u>		
9	On flat roofs, turn-ups, etc	m2	1,380
	<b><u>WATERSTOPS, SEALING STRIPS, JOINT SEALANTS, ETC</u></b>		
	<u>Silicone sealant</u>		
10	2 x 10mm On slip joints between horizontal concrete and brick surfaces	m	1,629
11	10 x 10mm In isolation joints in floors	m	1,926
12	13 x 10mm In saw cut joints in floors	m	694
	<b>Carried Forward</b>		
	R		
Section No. 2 Bill No. 5 Waterproofing			

A9

148 J-04  
*[Handwritten signature]*

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

	Brought Forward				R
13	<u>Waterproofing sealant applied in accordance with the manufacturer's instructions</u> 10 x 10mm On interface of concrete wall and footings	m	2,620		
	<b>Carried Forward to Summary of Section No. 2</b>				R
	Section No. 2 Bill No. 5 Waterproofing				R

RJ

149

M

R

SOUTH AFRICAN POLICE SERVICES  
CONSTRUCTION OF THE NEW MSINSINI POLICE STATION

Item No		Quantity	Rate	Amount
	<b><u>SECTION NO. 2</u></b>			
	<b><u>NEW BUILDINGS</u></b>			
	<b><u>BILL NO. 6</u></b>			
	<b><u>ROOF COVERINGS, ETC.</u></b>			
	<b><u>(CPAP WORK GROUP NO. 125 UNLESS OTHERWISE STATED)</u></b>			
	The Tenderer is referred to the relevant Clauses in the separate document Model Preambles for Trades (2017 Edition)			
	<b><u>PROFILED METAL SHEETING AND ACCESSORIES</u></b>			
	<b><u>0.53mm Conceal-fixed roof sheeting with colour Volcanic Grey finish to one side with a Cool Grey backing coat including accessories and fixed to timber purlins (elsewhere measured) using 80mm x 1.2mm G230 cleats. Installation as per manufacturer's recommendations.</u></b>			
1	Roof covering with pitch not exceeding 25 degrees (LI)	m2	1,954	
	<b><u>Side cladding formed of 0.53mm conceal-fixed roof sheeting with colour Volcanic grey finish to one side with a Cool Grey backing coat including accessories and fixed using 80mm x 1.2mm G230 cleats on timber purlins (elsewhere measured)</u></b>			
2	Side cladding laid vertically on timber support frame consisting of 50 x 75mm treated timber purlins (elsewhere measured), including fixings (LI)	m2	635	
	<b><u>0.53mm Powder coated zinc aluminium flashings, flute closers and all accessories installed according to manufacturers instructions</u></b>			
3	Apex flashing, 550 mm girth, five times bent, including fixings (LI)	m	183	
4	Barge flashing, 580 mm girth, five times bent, including fixings (LI)	m	132	
	<b>Carried Forward</b>			R
	Section No. 2 Bill No. 6 Roof Coverings, Etc.			150 15

RJ

150 15  
R. m