Item No		Quantity	Rate	Amount
	SECTION No. 1 - PRELIMINARIES			
	BILL NO. 1			
	PRELIMINARIES			
	MEANING OF TERMS "TENDER / TENDERER"			
	Any reference to the words "Tender" or "Tenderer" herein and/or in any other documentation shall be construed to have the same meaning as the words "Bid" or "Bidder"			
	PRELIMINARIES			
	The JBCC Preliminaries Code 2103, May 2005 edition for use with the JBCC Principal Building Agreement Edition 4.1 Code 2101, March 2005 is taken to be incorporated herein. The tenderer is deemed to have referred to these documents for the full intent and meaning of each clause. These clauses are referred to by number and heading only. Where standard clauses or options are not applicable to the contract such modifications or corrections as are necessary are given under each relevant clause. Where an item is not relevant to this specific contract such item is marked "N/A" signifying "Not Applicable"			
	PRICING OF PRELIMINARIES			
	Should Option A, as set out in clause B10.3.1 hereinafter be used for the adjustment of preliminaries then each item priced is to be allocated to one or more of the three categories Fixed, Value Related or Time Related and the respective amounts entered in the spaces provided under each item			
	Items not priced in these Preliminaries shall be deemed to be included elsewhere in these Bills of Quantities			
	Carried to Collection SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

	SECTION A: JBCC PRINCIPAL BUILDING AGREEMENT		
	<u>DEFINITIONS</u>		
1	A1.0 DEFINITIONS AND INTERPRETATION		
	Clause 1.0		
	Clause 1.1 Definition of "Commencement Date" is added:		
	"COMMENCEMENT DATE" means the date that is 5 working days after site hand over.		
	Clause 1.1 Definition of "Construction Guarantee" is amended by replacing it with the following:		
	"CONSTRUCTION GUARANTEE" means a guarantee at call obtained by the contractor from an institution approved by the employer in terms of the employer's construction guarantee form as selected in the schedule		
	Clause 1.1 Definition of "Construction Period" is amended by replacing it with the following:		
	"CONSTRUCTION PERIOD" means the period commencing on the commencement date and ending on the date of practical completion		
	Clause 1.1 Definition of "Corrupt Practice" is added:		
	"CORRUPT PRACTICE" means the offering, giving, receiving or soliciting of anything of value to influence the action of a public official in the procurement process or in contract execution		
	Clause 1.1 Definition of "Fraudulent Practice" is added:		
	Carried to Collection	R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1		
	PRELIMINARIES AND GENERAL		
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		

"FRAUDULENT PRACTICE" means a mispresentation of facts in order to influence a procurement process or the execution of a contract to the detriment of any tenderer and includes collusive practice among tenderers (prior to or after the tender submission) designed to establish tender prices at artificial noncompetitive levels and to deprive the tenderer of the benefits of free and open competition Clause 1.1 Definition of "Interest" is amended by replacing it with the following: "INTEREST" means the interest rates applicable on this contract, whether specifically indicated in the relevant clauses or not, will be in terms of the legislation of the Republic of South Africa, and in particular: (a) in respect of interest owed by the employer, the interest rate as determined by the Minister of Justice and Constitutional Development from time to time, in terms of section 1(2) of the Prescribed Rate of Interest Act, 1975 (Act No. 55 of 1975), will apply; and (b) in respect of interest owed to the employer, the interest rate as determined by the Minister of Finance. from time to time, in terms of section 80(1)(b) of the Public Finance Management Act, 1999 (Act No. 1 of 1999), will apply Clause 1.1 Definition of "Principal Agent" is amended by replacing it with the following: "PRINCIPAL AGENT" means the person or entity appointed by the **employer** and named in the **schedule**. In the event of a **principal agent** not being appointed, then all the duties and obligations of a principal agent as detailed in the agreement shall be fulfilled by a representative of the employer as named in the schedule Clause 1.1 Definition of "Security" is amended by replacing it with the following: **Carried to Collection** R SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL **MAYIBENYE SSS** PROVISIONAL BILLS OF QUANTITIES

	"SECURITY" means the form of security provided by the employer or contractor, as stated in the schedule, from which the contractor or employer may recover expense or loss			
	Clause 1.6 is amended by replacing the words "prepaid registered post, telefax or e-mail" with "prepaid registered post or telefax"			
	Clause 1.6.4 is amended by replacing it with the following:			
	No clause			
	Fixed: Value related: Time related:	Item		
	OBJECTIVE AND PREPARATION			
1	A2.0 OFFER, ACCEPTANCE AND PERFORMANCE			
	Clause 2.0			
	Fixed: Value related: Time related:	Item		
2	A3.0 DOCUMENTS			
	Clause 3.0			
	Clause 3.2.1 is amended by replacing "14.1" with "14.0"			
	Clause 3.7 is amended by the addition of the following:			
	The contractor shall supply and keep a copy of the JBCC Series 2000 Principal Building Agreement and Preliminaries applicable to this contract on the site , to which the employer , principal agent and agents shall have access at all times			
	Clause 3.10 is amended by replacing the second reference to "principal agent" with the word "employer"			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			
	THE THE STATE OF GOVERNMENT			

1	A4.0 DESIGN RESPONSIBILITY			
	Clause 4.0			
	Clause 4.3 is amended by replacing it with the following:			
	No clause			
	Fixed: Value related: Time related:	Item		
2	A5.0 EMPLOYER'S AGENTS			
	Clause 5.0			
	Clause 5.1.2 is amended to include clauses 32.6.3, 34.3 and 34.4 in terms of which the employer has retained its authority and has not given a mandate to the principal agent and in terms of which the employer shall sign all documents.			
	Fixed: Value related: Time related:	Item		
3	A6.0 SITE REPRESENTATIVE			
	Clause 6.0			
	Fixed: Value related: Time related:	Item		
4	A7.0 COMPLIANCE WITH REGULATIONS			
	Clause 7.0			
	Fixed: Value related: Time related:	Item		
5	A8.0 WORKS RISK			
	Clause 8.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	A9.0	INDEMNITIES			
	Clause	9.0			
		Value related: Time	Item		
2	A10.0	WORKS INSURANCES			
	Clause	10.0			
	Clause clauses	10.0 is amended by the addition of the following s:			
	10.5 Da	amage to the Works			
	(a)	Without in any way limiting the contractor's obligations in terms of the contract, the contractor shall bear the full risk of damage to and/or destruction of the works by whatever cause during construction of the works and hereby indemnifies and holds harmless the employer against any such damage. The contractor shall take such precautions and security measures and other steps for the protection and security of the works as the contractor may deem necessary			
	(b)	The contractor shall at all times proceed immediately to remove or dispose of any debris arising from damage to or destruction of the works and to rebuild, restore, replace and/or repair the works			
	(c)	The employer shall carry the risk of damage to or destruction of the works and materials paid for by the employer that is the result of the excepted risks as set out in 10.6			
	(d)	Where the employer bears the risk in terms of this contract, the contractor shall, if requested to do so, reinstate any damage or destroyed portions of the works and the costs of such reinstatement shall be measured and valued in terms of 32.0 hereof			
					_
	SECT!	Carried to Collection		R	
	Bill No. PRELIN	ON NO.1 - PRELIMINARIES AND GENERAL 1 MINARIES AND GENERAL ENYE SSS SIONAL BILLS OF QUANTITIES			

10.6 Inj Proper	jury to Persons or loss of or damage to ties		1
(a)	The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever arising out of or in the course of or caused by the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable		
(b)	The contractor shall be liable for and hereby indemnifies the employer against any liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any other body or person, arising out of or in the course of or by reason of the execution of the works unless due to any act or negligence of any person for whose actions the employer is legally liable		
(c)	The contractor shall, upon receiving a contract instruction from the principal agent , cause the same to be made good in a perfect and workmanlike manner at his own cost and in default thereof the employer shall be entitled to cause it to be made good and to recover the cost thereof from the contractor or to deduct the same from amounts due to the contractor		
(d)	The contractor shall be responsible for the protection and safety of such portions of the premises placed under his control by the employer for the purpose of executing the works until the issue of the certificate of practical completion		
05071	Carried to Collection	R	_
Bill No. PRELIM	ON NO.1 - PRELIMINARIES AND GENERAL 1 MINARIES AND GENERAL ENYE SSS SIONAL BILLS OF QUANTITIES		

(e)	Where the execution of the works involves the risk of removal of or interference with support to
	adjoining properties including land or structures or any structures to be altered or added to, the
	contractor shall obtain adequate insurance and
	will remain adequately insured or insured to the specific limit stated in the contract against the
	death of or injury to persons or damage to such property consequent on such removal or
	interference with the support until such portion of the works has been completed

(f) The **contractor** shall at all times proceed immediately at his own cost to remove or dispose of any debris and to rebuild, restore, replace and/or repair such property and to execute the **works**

10.7 High risk insurance

In the event of the project being executed in a geological area classified as a "High Risk Area", that is an area which is subject to highly unstable subsurface conditions that might result in catastrophic ground movement evident by sinkhole or doline formation the following will apply:

10.7.1 Damage to the works

The contractor shall, from the commencement date of the works until the date of the certificate of practical completion bear the full risk of and hereby indemnifies and holds harmless the employer against any damage to and/or destruction of the works consequent upon a catastrophic ground movement as mentioned above. The contractor shall take such precautions and security measures and other steps for the protection of the works as he may deem necessary

When so instructed to do so by the **principal agent**, the **contractor** shall proceed immediately to remove and/or dispose of any debris arising from damage to or destruction of the **works** and to rebuild, restore, replace and/or repair the **works**, at the **contractor's** own costs

Carried to Collection

SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL

MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES

10.7.2 Injury to persons or loss of or damage to property			
The contractor shall be liable for and hereby indemnifies and holds harmless the employer against any liability, loss, claim or proceeding arising at any time during the period of the contract whether arising in common law or by statute, consequent upon personal injuries to or the death of any person whomsoever resulting from, arising out of, or caused by a catastrophic ground movement as mentioned above			
The contractor shall be liable for and hereby indemnifies the employer against any and all liability, loss, claim or proceeding consequent upon loss of or damage to any moveable or immovable or personal property or property contiguous to the site , whether belonging to or under the control of the employer or any other body or person whomsoever arising out of or caused by a catastrophic ground movement, as mentioned above, which occurred during the period of the contract			
10.7.3 It is the responsibility of the contractor to ensure that he has adequate insurance to cover his risk and liability as mentioned in 10.7.1 and 10.7.2. Without limiting the contractor's obligations in terms of the contract, the contractor shall, within twenty-one (21) calendar days of the commencement date but before commencement of the works , submit to the employer proof of such insurance policy, if requested to do so			
10.7.4 The employer shall be entitled to recover any and all losses and/or damages of whatever nature suffered or incurred consequent upon the contractor's default of his obligations as set out in 10.7.1; 10.7.2 and 10.7.3. Such losses or damages may be recovered from the contractor or by deducting the same from any amounts still due under this contract or under any other contract presently or hereafter existing between the employer and the contractor and for this purpose all these contracts shall be considered one indivisible whole			
Fixed:Value related:Time related:	Item		
Carried to Collection		R	
SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	A11.0 LIABILITY INSURANCES			
	Clause 11.0			
	Fixed: Value related: Time related:	Item		
2	A12.0 EFFECTING INSURANCES			
	Clause 12.0			
	Fixed: Value related: Time related:	Item		
3	A13.0 No clause	N/A		
4	A14.0 SECURITY			
	Clause 14.0			
	Clauses 14.1 - 14.8 are amended by replacing them with the following:			
	14.1 The security to be submitted by the contractor to the employer will be as a payment reduction of up to ten per cent (10%) of the value certified in the payment certificate (excluding VAT)			
	14.1.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(A)			
	14.1.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor			
	14.2 Where security as a payment reduction of ten per cent (10%) of the value certified in the payment certificate (excluding VAT) has been selected:			
	14.2.1 The payment reduction of the value certified in a payment certificate shall be <i>mutatis mutandi</i> in terms of 31.8(B)			
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

	14.2.2 The employer shall be entitled to recover expense and loss from the payment reduction in terms of 33.0 provided that the employer complies with the provisions of 33.4 in which event the employer's entitlement shall take precedence over his obligations to refund the payment reduction security or portions thereof to the contractor			
	14.9 Should the contractor fail to furnish the security in terms of 14.2, the employer , in his sole discretion and without notification to the contractor , is entitled to change the contractor's selected form of security to that of a ten per cent (10%) payment reduction of the value certified in the payment certificate (excluding VAT), whereafter 14.7 shall be applicable			
	Fixed: Value related: Time related:	Item		
	EXECUTION			
1	A15.0 PREPARATION FOR AND EXECUTION OF THE WORKS			
	Clause 15.0			
	Clause 15.1.1 is amended by replacing it with:			
	No clause			
	Clause 15.1.2 is amended by replacing it with:			
	The security selected in terms of 14.0			
	Clause 15.1 is amended by the addition of the following clause:			
	15.1.4 An acceptable health and safety plan, required in terms of the Occupational Health and Safety Act, 1993 (Act 85 of 1993), within fourteen (14) calendar days of commencement date			
	Clause 15.2.1 is amended by replacing it with the following clause:			
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL			
	Bill No. 1 PRELIMINARIES AND GENERAL			
	MAYIBENYE SSS			
	PROVISIONAL BILLS OF QUANTITIES			

	Give the contractor possession of the site within ten (10) working days of the contractor complying with the terms of 15.1.4			
	Fixed: Value related: Time related:	Item		
1	A16.0 ACCESS TO THE WORKS			
	Clause 16.0			
	Fixed: Value related: Time related:	Item		
2	A17.0 CONTRACT INSTRUCTIONS			
	Clause 17.0			
	Clause 17.1.11 is amended by deleting the words "and the appointment of nominated and selected subcontractors "			
	Fixed: Value related: Time related:	Item		
_		Itom		
3	A18.0 SETTING OUT OF THE WORKS Clause 18.0			
	Fixed: Value related:			
	Fixed: Value related: Time related:	Item		
4	A19.0 ASSIGNMENT			
	Clause 19.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL			
	Bill No. 1 PRELIMINARIES AND GENERAL			
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			
		1		l

1	A20.0 NOMINATED SUBCONTRACTORS			
	Clause 20.0			
	Clause 20.1.3 is amended by replacing it with the following:			
	No clause			
	Note: See item B9.1 hereinafter for adjustment of attendance on nominated subcontractors executing work allowed for under provisional sums			
	Fixed: Value related: Time related:	Item		
2	A21.0 SELECTED SUBCONTRACTORS			
	Clause 21.0			
	Clause 21 is amended by replacing it with:			
	No clause			
	Fixed: Value related: Time related:	Item		
3	A22.0 EMPLOYER'S DIRECT CONTRACTORS			
	Clause 22.0			
	Fixed: Value related: Time related:	Item		
4	A23.0 CONTRACTOR'S DOMESTIC SUBCONTRACTORS			
	Clause 23.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1			
	PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BULLS OF CHANTITIES			
	PROVISIONAL BILLS OF QUANTITIES			
				l

	COMPLETION			
1	A24.0 PRACTICAL COMPLETION			
	Clause 24.0			
	Fixed: Value related: Time related:	Item		
2	A25.0 WORKS COMPLETION			
	Clause 25.0			
	Fixed: Value related: Time related:	Item		
3	A26.0 FINAL COMPLETION			
	Clause 26.0			
	Fixed: Value related: Time related:	Item		
4	A27.0 LATENT DEFECTS LIABILITY PERIOD			
	Clause 27.0			
	Fixed: Value related: Time related:	Item		
5	A28.0 SECTIONAL COMPLETION			
	Clause 28.0			
	Fixed: Value related: Time related:	Item		
6	A29.0 REVISION OF DATE FOR PRACTICAL COMPLETION			
	Clause 29.0			
	Clause 29.2.5 is amended by replacing it with:			
	No clause			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

A30.0 PENALTY FOR NON-COMPLETION		
Clause 30.0		
Fixed: Value related: Time related:	Item	
<u>PAYMENT</u>		
A31.0 INTERIM PAYMENT TO THE CONTRACTOR		
Clause 31.0		
Clause 31.5.2 is amended by replacing "14.7.1" with "14.0 and 31.8"		
Clause 31.8 is amended by replacing it with the following two alternative clauses:		
Alternative A		
31.8(A) Where a security is selected in terms of 14.1; the value of the works in terms of 31.4.1 and materials and goods in terms of 31.4.2 shall be certified in full. The value certified shall be subject to the following percentage adjustments:		
31.8(A).1 Ninety-five percent (95%) of such value in interim payment certificates issued up to the date of practical completion		
31.8(A).2 Ninety-seven and half percent (97.5%) of such value in interim payment certificates issued on the date of practical completion and up to but excluding the date of final completion		
31.8(A).3 Ninety-nine percent (99%) of such value in interim payment certificates issued on the date of final completion and up to but excluding the final payment certificate in terms of 34.6		
31.8(A).4 One hundred percent (100%) of such value in the final payment certificate in terms of 34.6 except where the amount certified is in favour of the employer . In such an event the payment reduction shall remain at the adjustment level applicable to the final payment certificate		
Carried to Collection SECTION NO.1 - PRELIMINARIES AND GENERAL		R
Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS		
PROVISIONAL BILLS OF QUANTITIES		

	Clause 31.12 is amended by deleting the following:			
	Payment shall be subject to the employer giving the contractor a tax invoice for the amount due			
	Fixed: Value related: Time related:	Item		
1	A32.0 ADJUSTMENT TO THE CONTRACT VALUE			
	Clause 32.0			
	Clauses 32.5.1, 32.5.4 and 32.5.7 are amended by the addition of the following at the end of the sentence:			
	"due to no fault of the contractor "			
	Add the following clauses: 33.2.9 to 33.2.13:			
	33.2.9 the contractor 's failure or neglect to commence with the works on the dates prescribed in the contract			
	33.2.10 the contractor's failure or neglect to proceed with the works in terms of the contract			
	33.2.11 the contractor's failure or neglect for any reason to complete the works in accordance with the contract			
	33.2.12 the contractor's refusal or neglect to comply strictly with any of the conditions of contract or any contract instructions and/or orders in writing given in terms of the contract			
	33.2.13 the contractor's estate being sequestrated; liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa.			
	Fixed: Value related: Time related:	Item		
2	A33.0 RECOVERY OF EXPENSE AND LOSS			
	Clause 33.0			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1			
	PRELIMINARIES AND GENERAL			
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	A34.0 FINAL ACCOUNT AND FINAL PAYMENT			
	Clause 34.0			
	Clause 34.1 is amended by removing "#" next to 34.1			
	Clause 34.2 is amended by inserting "#" next to 34.2			
	Clause 34.13 is amended by replacing "seven (7) calendar days" with "twenty-one (21) calendar days" and deleting the words "subject to the employer giving the contractor a tax invoice for the amount due"			
	Fixed: Value related: Time related:	Item		
2	A35.0 PAYMENT TO OTHER PARTIES			
	Clause 35.0			
	Fixed: Value related: Time related:	Item		
	CANCELLATION			
3	A36.0 CANCELLATION BY EMPLOYER - CONTRACTOR'S DEFAULT			
	Clause 36.0			
	Clause 36.1 is amended by the addition of the following clauses:			
	36.1.3 refuses or neglects to comply strictly with any of the conditions of contract			
	36.1.4 estate being sequestrated, liquidated or surrendered in terms of the insolvency laws in force within the Republic of South Africa			
	36.1.5 in the judgement of the employer , has engaged in corrupt or fraudulent practices in competing for or in executing the contract			
	Clause 36.3 is amended by removing the reference to "No clause" and replacing the words "principal agent" with "employer"			
				_
	Carried to Collection		R	_
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS			
	PROVISIONAL BILLS OF QUANTITIES			

				"	
	Clause 36.0 is amended by the addition of the following clause:				
	36.3 Remove reference to "No clause", and replace "principal agent" with "employer"				
	36.7 Notwithstanding any clause to the contrary, on cancellation of this agreement either by the employer or the contractor ; or for any reason whatsoever, the contractor shall on written instruction, discontinue with the works on a date stated and withdraw himself from the site . The contractor shall not be entitled to refuse to withdraw from the works on the grounds of any lien or right of retention or on the grounds of any other right whatsoever				
	Fixed: Value related: Time related:	Item			
1	A37.0 CANCELLATION BY EMPLOYER - LOSS AND DAMAGE				
	Clause 37.0				
	Clause 37.3.5 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"				
	Clause 37.0 is amended by the addition of the following clause:				
	37.3.5 Replace "ninety (90)" with "one hundred and twenty (120) and 38.5.4				
	Fixed: Value related: Time related:	Item			
2	A38.0 CANCELLATION BY CONTRACTOR - EMPLOYER'S DEFAULT				
	Clause 38.0				
	Clause 38.5.4 is amended by replacing "ninety (90)" with "one hundred and twenty (120)"				
	Clause 38.0 is amended by the addition of the following clause:				
	Carried to Collection SECTION NO.1 - PRELIMINARIES AND GENERAL		R		
	Bill No. 1 PRELIMINARIES AND GENERAL				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
- 1		I	I	II	1

	cancellation of this a or the contractor; o contractor shall on the works on a date the site. The contrat to withdraw from the or right of retention of whatsoever	g any clause to the contragreement either by the or for any reason whatsoe written instruction, discoe stated and withdraw hir actor shall not be entitled by works on the grounds of any Value related:	employer ever, the ntinue with mself from It to refuse of any lien other right			
	Telateu			Item		
1	A39.0 CANCELLA WORKS	ATION - CESSATION OF	THE			
	Clause 39.0					
	Clause 39.3.5 is am following at the end	ended by the addition of of the sentence:	the			
	"within one hundred completion of such a	and twenty (120) worki ı a report"	ng days of			
	Fixed:related:	_ Value related:	Time	Item		
		Carried	to Collection		R	
	SECTION NO.1 - PF Bill No. 1 PRELIMINARIES AN	RELIMINARIES AND GE	NERAL			
	MAYIBENYE SSS	LS OF QUANTITIES				

	DISPUTE			
1	A40.0 DISPUTE SETTLEMENT			
	Clause 40.0			
	Clause 40.2.2 is amended by replacing "one (1) year" with "three (3) years"			
	Clause 40.6 is amended by removing the reference to:			
	No clause			
	Clause 40.7.1 is amended by replacing "(10)" with "(15)" and by the addition of the following:			
	Whether or not mediation resolves the dispute, the parties shall bear their own costs concerning the mediation and equally share the costs of the mediator and related costs			
	Fixed: Value related: Time related:	Item		
	SUBSTITUTE PROVISIONS			
2	A41.0 STATE CLAUSES			
	Clause 41.0			
	Fixed: Value related: Time related:	Item		
	CONTRACT VARIABLES			
3	A42.0 THE SCHEDULE (C1.2)			
	Clause 42.0			
	Tenderers are referred to the C1.2 CONDITIONS OF CONTRACT AND CONTRACT VARIABLES for variables pertaining to this contract			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1			
	PRELIMINARIES AND GENERAL MAYIBENYE SSS			
	PROVISIONAL BILLS OF QUANTITIES			
				ĺ

	SECTION B: JBCC PRELIMINARIES			
	B1.0 DEFINITIONS AND INTERPRETATION			
1	B1.1 Definitions and interpretation			
	See also clause A1.0 of Section A for additional and/or amended definitions which shall apply equally to this Section			
	Fixed: Value related: Time related:	Item		
	B2.0 DOCUMENTS			
2	B2.1 Checking of documents			
	Fixed: Value related: Time related:	Item		
3	B2.2 Provisional bills of quantities			
	Fixed: Value related: Time related:	Item		
4	B2.3 Availability of construction documentation			
	Fixed: Value related: Time related:	Item		
5	B2.4 Interests of agents			
	Fixed: Value related: Time related:	Item		
6	B2.5 Priced documents			
	Fixed: Value related: Time related:	Item		
7	B2.6 Tender submission			
	Clause 2.6 is amended by replacing "JBCC Form of Tender" with "Form of Offer and Acceptance DPW-07(EC)"			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

	B3.0 THE SITE				
1	B3.1 Defined works area				
	Fixed:Value related:related:	_ Time	Item		
2	B3.2 Geotechnical investigation				
	Fixed:Value related:related:	_ Time	Item		
3	B3.3 Inspection of the site				
	Fixed:Value related:related:	_ Time	Item		
4	B3.4 Existing premises occupied				
	Fixed:Value related:related:	_ Time	Item		
5	B3.5 Previous work - dimensional accuracy				
	Fixed:Value related:related:	_ Time	Item		
6	B3.6 Previous work - defects				
	Fixed:Value related:related:	_ Time	Item		
7	B3.7 Services - known				
	Fixed:Value related:related:	_ Time	Item		
8	B3.8 Services - unknown				
	Fixed:Value related:related:	_ Time	Item		
9	B3.9 Protection of trees				
	Fixed:Value related:related:	_ Time	Item		
		W4'-		_	
	Carried to Co SECTION NO.1 - PRELIMINARIES AND GENERA			R	
	Bill No. 1 PRELIMINARIES AND GENERAL				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

1	B3.10 Articles of value	
	Fixed: Value related: Time related:	Item
2	B3.11 Inspection of adjoining properties	
	Fixed: Value related: Time related:	Item
	B4.0 MANAGEMENT OF CONTRACT	
3	B4.1 Management of the works	
	Fixed: Value related: Time related: R	Item
4	B4.2 Programme for the works	
	Fixed: Value related: Time related:	Item
5	B4.3 Progress meetings	
	Fixed: Value related: Time related:	Item
6	B4.4 Technical meetings	
	Fixed: Value related: Time related:	Item
7	B4.5 Labour and plant records	
	Fixed: Value related: Time related:	Item
	B5.0 SAMPLES, SHOP DRAWINGS AND MANUFACTURERS' INSTRUCTIONS	
8	B5.1 Samples of materials	
	Fixed: Value related: Time related:	Item
	Carried to Collection	R
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS	
	PROVISIONAL BILLS OF QUANTITIES	

1	B5.2	Workmanship samples				
	Fixed:_ related	Value related: :	Time	Item		
2	B5.3	Shop drawings				
	Fixed:_ related	Value related: :	Time	Item		
3	B5.4	Compliance with manufacturers' instr	uctions			
	Fixed: related	Value related: :	Time	Item		
	<u>B6.0</u>	TEMPORARY WORKS AND PLANT	• •			
4	B6.1	Deposits and fees				
	Fixed: related	Value related: :	Time	Item		
5	B6.2	Enclosure of the works				
	Fixed: related	Value related: :	Time	Item		
6	B6.3	Advertising				
	Fixed: related	Value related: :	Time	Item		
7	B6.4	Plant, equipment, sheds and offices				
		Value related: :	Time	Item		
8	B6.5	Main notice board				
	Fixed: related	Value related:	Time	Item		
9	B6.6	Subcontractors' notice board				
	Fixed: related	Value related: :	Time	Item		
	SECTI	Carried to C ON NO.1 - PRELIMINARIES AND GENER			R	-
	Bill No. PRELII MAYIE		VIL			

	B7.0 TEMPORARY SERVICES			
1	B7.1 Location			
	Fixed: Value related: Tin related:	ne Item		
2	B7.2 Water			
	Fixed: Value related: Tin related:	ne Item		
3	B7.3 Electricity			
	Fixed: Value related: Tin related:	ne Item		
4	B7.4 Telecommunication facilities			
	Fixed: Value related: Tin related:	ne Item		
5	B7.5 Ablution facilities			
	Fixed: Value related: Tin related:	ne Item		
	B8.0 PRIME COST AMOUNTS			
6	B8.1 Responsibility for prime cost amounts			
	Fixed: Value related: Tin related:	ne Item		
	B9.0 ATTENDANCE ON N/S SUBCONTRACTORS			
7	B9.1 General attendance			
	Fixed: Value related: Tin related:	ne Item		
8	B9.2 Special attendance			
	Fixed: Value related: Tin related:	ne Item		
	Carried to Collect	tion	R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL		, r	
	Bill No. 1 PRELIMINARIES AND GENERAL			
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	B9.3 Commissioning - fuel, water and electricity			
	Fixed: Value related: Time related:	Item		
	B10.0 FINANCIAL ASPECTS			
2	B10.1 Statutory taxes, duties and levies			
	Fixed: Value related: Time related:	Item		
3	B10.2 Payment for preliminaries			
	Fixed: Value related: Time related:	Item		
4	B10.3 Adjustment of preliminaries			
	Clauses B10.3.1 and B10.3.2 are amended by replacing "within fifteen (15) working days of taking possession of the site" with "when submitting his priced bills of quantities / lump sum document"			
	Fixed: Value related: Time related:	Item		
5	B10.4 Payment certificate cash flow			
	Fixed: Value related: Time related:	Item		
	B11.0 GENERAL			
6	B11.1 Protection of the works			
	Fixed: Value related: Time related:	Item		
7	B11.2 Protection / isolation of existing / sectionally occupied works			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	B11.3 Secu	rity of the works				
	Fixed: related:	Value related:	Time	Item		
2	B11.4 Notic	e before covering work				
	Fixed: related:	Value related:	Time	Item		
3	B11.5 Distu	rbance				
	Fixed: related:	Value related:	Time	Item		
4	B11.6 Envir	onmental disturbance				
	Fixed: related:	Value related:	Time	Item		
5	B11.7 Work	s cleaning and clearing				
	Fixed:related:	Value related:	Time	Item		
6	B11.8 Verm	in				
	Fixed: related:	Value related:	Time	Item		
7	B11.9 Over	hand work				
	Fixed: related:	Value related:	Time	Item		
8	B11.10 Instru	uction manuals and guarantees				
	Fixed: related:	Value related:	Time	Item		
9	B11.11 As b	uilt information				
	Fixed: related:	Value related:	Time	Item		
		Carried to C	ollection		R	
		0.1 - PRELIMINARIES AND GENER				
		IES AND GENERAL				
	MAYIBENYE PROVISIONA	SSS AL BILLS OF QUANTITIES				

B11.12 Tenant installations		
Fixed: Value related: Time related:	Item	
B12.0 SCHEDULE OF VARIABLES		
B12.1 Schedule of variables		
Fixed: Value related: Time related:	Item	
This schedule contains all variables referred to in this document and is divided into pre-tender and post-tender categories. The pre-tender category must be completed in full and included in the tender documents. Both the pre-tender and post-tender categories form part of these Preliminaries		
Spaces requiring information must be filled in, shown as not applicable" or deleted and not left blank. Where choices are offered, the non-applicable items are to be deleted. Where insufficient space is provided the information should be annexed hereto and cross-referenced to the applicable clause of the schedule . Key cross reference clauses are italicised in [] brackets		
12.1 PRE-TENDER INFORMATION		
12.1.1 Provisional bills of quantities [2.2] The quantities are provisional		
YES		
12.1.2 Availability of construction documentation [2.3] Construction documentation is complete		
YES		
12.1.3 Interests of agents [2.4] Details:		
12.1.4 Defined works area [3.1] Details:		
Carried to Collection		R
SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1		

12.1.5 [3.2]	Geotechnical investigation Details:		
12.1.6 <i>[</i> 3. <i>4</i>]	Existing premises occupied Specific requirements:		
12.1.7 <i>[</i> 3.5 <i>]</i>	Previous work - dimensional accuracy Details:		
12.1.8 <i>[3.6]</i>	Previous work - defects Details:		
12.1.9 <i>[</i> 3.7]	Services - known Details:		
12.1.10 <i>[</i> 3.9 <i>]</i>	Protection of trees Specific requirements:		
	Inspection of adjoining properties Specific requirements:		
12.1.12 [6.2]	Enclosure of the works Specific requirements:		
SECTIO	Carried to Collection ON NO.1 - PRELIMINARIES AND GENERAL	R	
Bill No. PRELIN MAYIB			

12.1.13 <i>Offices</i> [6.4.3] Specific requirements: The contractor shall provide, maintain and remove on completion of the works an office for the exclusive use of the principal agent , minimum size 4 x 3 x 3m high internally, suitably insulated and ventilated, provided with electric lighting and fitted with board/concrete floor, desk, chair, drawing stool, drawing board and lock-up drawers for drawings. The office shall be kept clean and fit for use at all times		
[6.4.3] Specific requirements: The contractor shall provide, maintain and remove on completion of the works an lockable secure store for the exclusive use of the storage of materials and fitted with steel/concrete floor.		
[6.5] Specific requirements: The contractor shall provide, erect where directed, maintain and remove on completion of the works a notice board size 3 x 3m as type Drawing GEN 063, constructed of suitable boarding with flat smooth surface and with edging bead 19mm thick round outer edges and projecting 12mm from face of boarding and rounded on front edge. The board shall be securely fixed to hoarding, where hoarding is provided, or fixed to and including a suitable supporting structure of timber or tubular posts and braces. The board is to be painted ivory white and the bead and 12mm wide dividing lines dark green. All wording shall be inscribed in dark green as per the coat of arms for SA. All wording shall be inscribed in dark green painted sans serif lettering		
12.1.15 Subcontractors' notice board [6.6] A notice board is required		
NO Specific requirements:		
Carried to Collection	R	
SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1		
PRELIMINARIES AND GENERAL		
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		

12.1.16 <i>Water</i> [7.2] Option A (by contractor)		
YES		
Option B (by employer - free of charge)		
NO		
Option C (by employer - metered)		
NO		
12.1.17 <i>Electricity</i>		
[7.3] Option A (by contractor)		
YES		
Option B (by employer - free of charge)		
NO		
Option C (by employer - metered)		
NO		
12.1.18 <i>Telecommunications</i> [7.4] Telephone		
VEC		
YES Facsimile		
YES		
E-mail		
YES		
12.1.19 Ablution facilities		
[7.5] Option A (by contractor)		
YES		
Option B (by employer)		
NO		
Carried to Collection	R	
SECTION NO.1 - PRELIMINARIES AND GENERAL	, R	H
Bill No. 1 PRELIMINARIES AND GENERAL		
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		

		ı		
12.1.20 works	Protection of existing/sectionally occupied			
	Protection is required			
	NO			
	Special attendance Subcontractor (1) details:			
	Subcontractor (2) details:			
	Subcontractor (3) details:			
	Subcontractor (4) details:			
	Protection of the works Specific requirements:			
	Disturbance Specific requirements: The contractor shall keep the site, structures, etc well watered during operations to prevent dust and shall provide and erect and remove on completion of the works all necessary temporary dust screens all to the satisfaction of the principal agent			
	Environmental disturbance Specific requirements:			
12.2	POST-TENDER INFORMATION			
	Payment of preliminaries Option A (prorated)			
	NO			
	Option B (calculated)			
	YES			
	Carried to Collection		R	
SECTION Bill No.	ON NO.1 - PRELIMINARIES AND GENERAL			
PRELIM	MINARIES AND GENERAL			
	ENYE SSS SIONAL BILLS OF QUANTITIES			

J			I			1
	12.2.2 [10.3]	Adjustment of preliminaries Option A (three categories)				
		NO				
		Option B (detailed breakdown)				
		YES				
	12.2.3	Additional agreed preliminaries items Details:				
		Details.				
						<u> </u>
		Carried to Collection		R		
	Bill No.					
	MAYIB	MINARIES AND GENERAL ENYE SSS				
	PROVI	SIONAL BILLS OF QUANTITIES				
						i

	SECTION C: SPECIFIC PRELIMINARIES			
	Section C contains specific preliminary items which apply to this contract except where N/A (Not Applicable) appears against an item			
1	C1.0 CONTRACT DRAWINGS			
	The drawings issued with the tender documents do not comprise the complete set but serve as a guide only for tendering purposes and for indicating the scope of the work to enable the tenderer to acquaint himself with the nature and extent of the works and the manner in which they are to be executed			
	Should any part of the drawings not be clearly understood by the tenderer he shall, before submitting his tender, obtain clarification in writing from the principal agent			
	Fixed: Value related: Time related:	Item		
2	C2.0 GENERAL PREAMBLES			
	The document "Specification of Materials and Methods to be used - PW371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014)." is obtainable on the Department's website (http://www.publicworks.gov.za/ under "Consultants Guidelines"), and shall be read in conjunction with the bills of quantities / lump sum document and be referred to for the full descriptions of work to be done and materials to be used Fixed: Value related: Time related:	ltem		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	C3.0 TRADE NAMES			
	Wherever a trade name for any product has been described in the bills of quantities / lump sum document , the tenderer's attention is drawn to the fact that any other product of equal quality may be used subject to the written approval of the principal agent being obtained prior to the closing date for submission of tenders			
	If prior written approval for an alternative product is not obtained, the product described shall be deemed to have been tendered for			
	Fixed: Value related: Time related:	Item		
2	C4.0 HIV/AIDS AWARENESS			
	It is required of the contractor to thoroughly study the HIV/AIDS Specification (PW 1544) of the Department that must be read together with and is deemed to be incorporated under this Section of the bills of quantities / lump sum document . Provision for pricing of HIV/AIDS awareness is made under items C10.1 to C10.5 hereafter and it is explicitly pointed out that all requirements of the aforementioned specification are deemed to be priced hereunder, as the said items represent the only method of measurement and no additional items or extras to the contract in this regard shall be entertained			
	The contractor must take note that compliance with the HIV/AIDS Specification is compulsory. In the event of partial or total non-compliance, the principal agent , notwithstanding the provisions of clause A 31.0 of Section A or any other clause to the contrary, reserves the right to delay issuing any progress payment certificate until the contractor provides satisfactory proof of compliance. The contractor shall not be entitled to any compensation of whatsoever nature, including interest, due to such delay of payment			
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

	C4.1 AWARENESS CHAMPION Selection, appointment, briefing and making available of an Awareness Champion including provision of all relevant services, all in accordance with the HIV/AIDS Specification Fixed:	Item			
	C4.2 AWARENESS WORKSHOPS Selection and appointment of a competent Service Provider approved by the principal agent, provision of a Service Provider Workshop Plan and a suitable venue, conducting of awareness workshops by means of traditional and/or modern multi- media techniques, including follow-up courses, making available all tuition material and performing assessment procedures, all in accordance with the HIV/AIDS Specification				
	Fixed: Value related: Time related:	Item			
	C4.3 POSTERS, BOOKLETS, VIDEOS, ETC. Provision, displaying, maintaining and replacing when necessary of four plastic laminated posters, booklets and educational videos, etc. for the duration of the construction period, all in accordance with the HIV/AIDS Specification Fixed: Value related: Time related: C4.4 ACCESS TO CONDOMS Provision and maintenance of condom dispensers fixed in position, including male and female condoms, replenishing male and female condoms on a daily basis as required for the duration of the construction period, all in accordance with the HIV/AIDS Specification	ltem			
	Fixed: Value related:				
	Time related:	Item			
	Carried to Collection		R		
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
1		i .	i l	i l	1

	C4.5 MONITORING Monitoring HIV/AIDS awareness of workers, providing the principal agent with access to information including making available all reports, thoroughly completed and reflecting the correct information, for the duration of the construction period and close out, all in accordance with the HIV/AIDS Specification			
	Fixed: Value related: Time related:	Item		
1	C5.0 SMME MENTOR :SMME SUB-CONTRACTORS "The Contractor shall provide an SMME construction manager for the full duration of the project."			
	Fixed: Value related: Time related:	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1			
	PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

Section No. 1				
SECTION NO.1 - PRELIMINARIES AND GENERAL				
Bill No. 1				
PRELIMINARIES AND GENERAL				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	1			
	2			ļ
	3			ļ
	4			ļ
	5			ļ
	6			ļ
	7			ļ
	8			ļ
	9			
	10			
	11			
	12			
	13			ļ
	14			ļ
	15			ļ
	16			ļ
	17			
	18			
	19			
Carried Forward SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 1 PRELIMINARIES AND GENERAL MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R		
		[i

Section No. 1				
SECTION NO.1 - PRELIMINARIES AND GENERAL				
Bill No. 1				
PRELIMINARIES AND GENERAL				
COLLECTION				
	Page		Amount	
Brought Forward	No	R		
Total Brought Forward from Page No.	20			
	21			
	22			
	23			
	24			
	25			
	26			
	27			
	28			/
	29			
	30			
	31			
	32			
	33			
	34			
	35			
	36			
	37			
				_
Carried Forward to Summary of Section No. 1 SECTION NO.1 - PRELIMINARIES AND GENERAL		R		
Bill No. 1 PRELIMINARIES AND GENERAL PRELIMINARIES AND GENERAL				
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
FROVISIONAL BILLS OF QUANTITIES				
1	i	1		1

Item No		Quantity	Rate	Amount	
	BILL No. 2				
	HEALTH AND SAFETY REQUIREMENTS				
	Note:				
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).				
	The contractor's prices for all items throughout these bills of quantities shall take account of and include where applicable for all of the obligations, requirements and specifications given in the General Preambles and in any supplementary preambles and/or specifications.				
	Prior to pricing the principal contractor must familiarize him/herself with the Occupational Health and Safety Act No. 85 Of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety specifications.				
	The items in this Bill do not contain quantities hence the Contractor must insert his own quantities based on his individual requirements to comply with the Health and Safety obligations and demands of the Occupational Health and Safety Act No. 85 of 1993, Construction Regulations 2014, other relevant Regulations and Standards as well as project specific Health & Safety Specifications.				
	OCCUPATIONAL HEALTH AND SAFETY				
	General:				
1	Preparation of Contractor's site specific Health and Safety Plan.	Item			
2	Submission of the Health and Safety File.	Item			
3	Principal Contractor's initial obligations in respect of the OHS Act and Construction Regulations.	Item			
					_
	Carried to Collection		R		
	SECTION NO.1 - PRELIMINARIES AND GENERAL BIII No. 2 HEALTH AND SAFETY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				=

1	Principal Contractor's time related obligations in respect of the OHS Act and Construction Regulations for the entire construction period.	Item		
2	Provision of full time Health and Safety Officer for the entire construction period.	Item		
3	Induction training of personnel.	Item		
4	Provision of first aid boxes.	Item		
	Provision for Personal Protective Equipment and Protective Clothing:			
5	Reflective vests.	Item		
6	Hard hats.	Item		
7	Protective foot wear.	Item		
8	Ear Plugs.	Item		
9	Dust Masks.	Item		
	Costs of Medical Certificates and Medical Surveillance:			
10	Initial (baseline) medical examinations.	Item		
11	Exit Examinations.	Item		
	Noise Monitoring:			
12	Establishment of noise zones.	Item		
13	Audiograms.	Item		
	Carried to Collection		R	
	SECTION NO.1 - PRELIMINARIES AND GENERAL Bill No. 2			=
	HEALTH AND SAFETY MAYIBENYE SSS			
	PROVISIONAL BILLS OF QUANTITIES			

Sec	etion No. 1		I		
SEC	CTION NO.1 - PRELIMINARIES AND GENERAL				
Bill	No. 2				
HE	ALTH AND SAFETY				
co	LLECTION				
Tota	al Brought Forward from Page No.	Page No 40 41		Amount	
	Carried Forward to Summary of Section No. 1		R		
Bill HE MA	CTION NO.1 - PRELIMINARIES AND GENERAL No. 2 ALTH AND SAFETY AYIBENYE SSS OVISIONAL BILLS OF QUANTITIES				

	Section No. 1		1	
	SECTION NO.1 - PRELIMINARIES AND GENERAL			
Bill	SECTION SUMMARY - SECTION NO.1 - PRELIMINARIES AND GE	Page		Amount
No 1	PRELIMINARIES AND GENERAL	No 39		
2	HEALTH AND SAFETY	42		
_	TILALITI AND GAI LIT	42		
	Carried to Final Summary SECTION NO.1 - PRELIMINARIES AND GENERAL		R	
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			
	3. 33			
			I	II I

Item No		Quantity	Rate	Amount
	SECTION NO.2 - BUILDING WORKS			
	BILL NO.1			
	EARTHWORKS (PROVISIONAL)			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	Quantity breakdown			
	In this Section No. 2 of the Bills of Quantities a breakdown of the total quantities into the various buildings is indicated below each description as follows:			
	C - DWG 05 - Staff Ablutions M - DWG 21 - Female Ablutions x 2 V - DWG 29 - Male ablutions T - DWG 32 - Male ablutions			
	It should be noted that due to the "rounding off" factor marginal differences can occur between the sum of the parts to the total given in the quantity column. For pricing purposes only the amount in the quantity column is to be used.			
	EARTHWORKS (PROVISIONAL)			
	EXCAVATIONS, FILLING, ETC.			
	BULK EXCAVATIONS			
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away			
1	Pit toilet. m3 C: 63 M: 112 T: 23 V: 17 Z: 0	214		
	Carried to Collection			
	SECTION NO.2 - BUILDING WORKS BIII No. 1 EARTHWORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

Excavate in earth exceeding 2m deep not exceeding 4m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away					
Pit toilet. C:6 M:11 T:2 V:2 Z:0	m3	21			
Excavations in earth of more difficult character					
Extra over excavations in earth for excavation in soft	2	25			
C:10 M:18 T:4 V:3 Z:0	IIIS	33			
Extra over excavations in earth for excavation in hard	m3	35			
C:10 M:18 T:4 V:3	1110	33			
Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away					
Reduced levels under solid floors. C:4 M:7 T:2 V:3	m3	16			
Surface trenches. C: 49 M: 82 T: 21 V: 22 Z: 0	m3	174			
Excavations in earth of more difficult character					
Extra over excavations in earth for excavation in soft rock.	m3	17			
C:5 M:8 T:2 V:2 Z:0					
Extra over excavations in earth for excavation in hard rock. C:2 M:4 T:1 V:1	m3	9			
Carried to Collection SECTION NO.2 - BUILDING WORKS BIII No. 1 EARTHWORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			R		
	deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Pit toilet. C:6 M:11 T:2 V:2 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. C:10 M:18 T:4 V:3 Z:0 Extra over excavations in earth for excavation in hard rock. C:10 M:18 T:4 V:3 Z:0 EXCAVATIONS FOR FOUNDATIONS, ETC. Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels under solid floors. C:4 M:7 T:2 V:3 Z:0 Surface trenches. C:49 M:82 T:21 V:22 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. C:5 M:8 T:2 V:2 Z:0 Extra over excavations in earth for excavation in hard rock. C:2 M:4 T:1 V:1 Z:0 Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 1 EARTHWORKS MAYIBENYE SSS	deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Pit toilet. m3 C:6 M:11 T:2 V:2 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 Z:0 Extra over excavations in earth for excavation in hard rock. m3 Z:0 Extra over excavations in earth for excavation in hard rock. m3 Z:0 EXCAVATIONS FOR FOUNDATIONS, ETC. Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels under solid floors. m3 C:4 M:7 T:2 V:3 Z:0 Surface trenches. m3 C:49 M:82 T:21 V:22 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 C:5 M:8 T:2 V:2 Z:0 Extra over excavations in earth for excavation in hard rock. m3 C:2 M:4 T:1 V:1 Z:0 Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 1 EARTHWORKS MAYIBENYE SSS	deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Pit toilet. m3 21 C:6 M:11 T:2 V:2 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 35 Z:0 Extra over excavations in earth for excavation in hard rock. m3 35 C:10 M:18 T:4 V:3 Z:0 Extra over excavations in earth for excavation in hard rock. m3 35 C:10 M:18 T:4 V:3 Z:0 EXCAVATIONS FOR FOUNDATIONS, ETC. Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels under solid floors. m3 16 C:4 M:7 T:2 V:3 Z:0 Surface trenches. m3 174 C:49 M:82 T:21 V:22 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 17 C:5 M:8 T:2 V:2 Z:0 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 C:2 M:4 T:1 V:1 Z:0 Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 1 EARTHWORKS MAYIBENYE SSS	deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Pit toilet. m3 21 C:6 M:11 T:2 V:2 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 35 C:10 M:18 T:4 V:3 Z:0 Extra over excavations in earth for excavation in hard rock. m3 35 C:10 M:18 T:4 V:3 Z:0 EXCAVATIONS FOR FOUNDATIONS, ETC. Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Reduced levels under solid floors. m3 16 C:4 M:7 T:2 V:3 Z:0 Surface trenches. m3 174 C:49 M:82 T:21 V:22 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 17 C:5 M:8 T:2 V:2 Z:0 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Carried to Collection R SECTION NO.2 - BUILDING WORKS Bill No. 1 EARTHWORKS MAYIBENYE SSS	deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away. Pit toilet. m3 21 C:8 M:11 T:2 V:2 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 35 C:0 M:18 T:4 V:3 Z:0 Extra over excavations in earth for excavation in hard rock. m3 35 C:10 M:18 T:4 V:3 Z:0 Extra over excavations in earth for excavation in hard rock. c:10 M:18 T:4 V:3 Z:0 EXCAVATIONS FOR FOUNDATIONS, ETC. Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away. Reduced levels under solid floors. m3 16 C:4 M:7 T:2 V:3 Z:0 Surface trenches. m3 174 C:49 M:82 T:21 V:22 Z:0 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 17 C:5 M:8 T:2 V:2 Z:0 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9 Extra over excavations in earth for excavation in hard rock. m3 9

	Carting away of excavated material				
1	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	332		
	C: 96 M: 167 T: 37 V: 31 Z: 0				
	Risk of collapse of excavations				
2	Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	498		
	C: 140 M: 235 T: 60 V: 63 Z: 0				
3	Allow for risk of collapse to sides of excavations exceeding 1.5m deep including all necessary timber shoring, etc.	m2	217		
	C: 57 M: 104 T: 30 V: 26 Z: 0				
	Working space				
4	Excavate in earth for working space exceeding 1500mm and not exceeding 3000mm deep, 500mm from the face of brickwork in the pit, for waterproofing purposes including backfilling with G7 imported material compacted in 150mm thick layers to 95% Modified AASHTO dry density.	m2	217		
	C: 57 M: 104 T: 30 V: 26				
	Z:0				
5	Extra over working space excavations for excavation in soft rock.	m2	22		
	C:6 M:10 T:3 V:3 Z:0				
6	Ditto, but for excavation in hard rock.	m2	11		
	C:3 M:5 T:2 V:1				
	Z:0				
	Keeping excavations free of water				
7	Allow for keeping the excavations free from water.		Item		
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	
	Bill No. 1 EARTHWORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

1	Filling	1				
1	Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	94			
	C: 26 M: 44 T: 11 V: 12					
	Z:0					
	Foundation courses					
2	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density to trenches, bases, etc.	m3	40			
	C:11 M:19 T:5 V:5					
	Z:0					
3	Imported G7 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 95% modified AASHTO dry density under solid floors.	m3	50			
	C:15 M:24 T:5 V:6					
	Z:0					
4	Imported G5 filling, selected and supplied by the Contractor, including depositing in layers not exceeding 150mm thick and compacting to 98% modified AASHTO dry density under solid floors.	m3	25			
	C:7 M:12 T:3 V:3					
	Z:0					
5	50mm Thick layer of approved river sand supplied by the Contractor spread and levelled under floors, etc.	m3	5			
	C:1 M:2 T:1 V:1					
	Z:0					
	Compaction of surfaces					
6	Scarify in-situ material to a depth of 150mm and compact to 93% Mod AASHTO density.	m2	167			
	C: 48 M: 80 T: 18 V: 21 Z: 0					
	2:0					
						_
	Carried to Collection			R		
	SECTION NO.2 - BUILDING WORKS				 	=
	Bill No. 1					
	EARTHWORKS MAYIBENYE SSS					
	PROVISIONAL BILLS OF QUANTITIES					

	Filter fabric				
1	Grade 3 needle punched non-woven synthetic fibre filter fabric laid vertically against waterproofing membrane as backfilling proceeds. $C:52 \qquad M:95 \qquad T:27 \qquad V:23$ $Z:0$	m2	197		
	Weedkillers, insecticides, etc.				
	Soil insecticide in accordance with SANS 5859				
2	Under floors, etc. including forming and poisoning shallow furrows against all foundation walls, filling in furrows and ramming.	m2	167		
	C: 48 M: 80 T: 18 V: 21 Z: 0				
3	To bottoms and sides of trenches.	m2	637		
	C:179 M:301 T:77 V:80 Z:0				
4	To bottoms and sides of pit excavation. C:89 M:160 T:41 V:34	m2	324		
	Z:0				
	<u>Tests</u>				
5	Allow for Mod AASHTO density tests on filling.	No	25.00		
	Oniminal to Only of the				_
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	=
	Bill No. 1 EARTHWORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Section No. 2				
SECTION NO.2 - BUILDING WORKS				
Bill No. 1				
EARTHWORKS				
COLLECTION				
Total Brought Forward from Page No.	Page No 44 45		Amount	
	46			ļ
	47 48			
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - BUILDING WORKS Bill No. 1 EARTHWORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
	BILL No. 2			
	CONCRETE, FORMWORK AND REINFORCEMENT			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	CONCRETE			
	Mass concrete 15MPa (19mm stone) in:			
1	Blinding beneath bases, strip footings, etc cast against excavated surfaces.	3 12		
	C:4 M:6 T:1 V:1 Z:0			
	Unreinforced concrete 25MPa (19mm stone) in:			
2	Stairs, ramps, aprons, ect.	3 1		
	C:0 M:0 T:0 V:0 Z:0			
	Reinforced concrete 30MPa (19mm stone) in:			
3	Filling to cavity of hollow brick wall with "Coprox" or equally approved waterproof additive batched mixed into concrete at 2.5kgs/50kgs cement.	3 22		
	C:6 M:11 T:3 V:3			
	Z:0			
4	Strip foundations cast against excavated surfaces.	35		
	C:10 M:16 T:4 V:4			
_	Z:0			
5	Slabs including beams and inverted beams. m3 C:8 M:14 T:3 V:2	3 25		
	Z:0			
	Carried to Collection		R	
	SECTION NO.2 - BUILDING WORKS			
	Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT			
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

2	Surface beds cast in panels including temporary formwork. C: 12 M: 20 T: 5 V: 4 Z: 0 Surface treatment Float surface of concrete to a wood float finish. C: 52 M: 92 T: 15 V: 11 Z: 0 Powerfloating of concrete surface bed. C: 57 M: 96 T: 25 V: 25	m3 m2	41 169 203		
4	Test blocks and testing Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional) FORMWORK Rough formwork (use and waste) to concrete to:	No	25		
5	Permanent formwork to slabs, beams and stairs Soffits of slabs exceeding 250mm Thick and exceeding 1.5 not exceeding 3.5m above bearing level. C: 29 M: 52 T: 10 V: 7 Z: 0 Edges, risers, ends and reveals	m2	98		
6	Edge, riser, etc not exceeding 300mm high. C:94 M:138 T:37 V:37 Z:0	m	305		
7	Stepped outer edge of stairs 350mm high extreme . C:0 M:0 T:0 V:0 Z:0	m2	1		
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			R	

1	<u>Openings</u>				
1	Leave or form circular opening not exceeding 1m girth through 255mm thick reinforced concrete slab.	No	59		
	C:16 M:32 T:6 V:5				
	Z:0				
2	Leave or form opening exceeding 2m not exceeding 3m girth through 255mm thick reinforced concrete slab.	No	11		
	C:3 M:6 T:1 V:1				
	Z:0				
	Movement joints				
3	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	193		
	C:60 M:75 T:32 V:27				
	Z:0				
4	Remove 10 x 15mm hinged blocking piece, insert polycord bond breaker and seal with an approved 2 part polysulphide sealer.	m	193		
	C:60 M:75 T:32 V:27				
5	Z:0 Slip joint not exceeding 300mm wide formed of two layers of 3 Ply malthoid laid on and including a 3:1 cement mortar bedding.	m	92		
	C:24 M:44 T:13 V:11				
	Z:0				
	Grooves, channels, mortices, etc.				
6	Labour forming 20mm rounded nosing to edge of concrete surface.	m	104		
	C: 25 M: 49 T: 14 V: 16 Z: 0				
	REINFORCEMENT (PROVISIONAL)				
	Mild steel rod reinforcement to structural concrete work				
7	10mm Diameter bars.	t	0.985		
	C: 0.290 M: 0.519 T: 0.103 V: 0.073				
	Z: 0.000				
					\downarrow
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS			ĸ	+
	Bill No. 2				
	CONCRETE, FORMWORK AND REINFORCEMENT				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
	· · · · · · · · · · · · · · · · · · ·				

	High tensile rod reinforcement to structural concrete work				
1	10mm Diameter bars. C: 0.872 M: 1.558 T: 0.309 V: 0.219 Z: 0.000	t	2.958		
2	12mm Diameter bars. C: 0.872 M: 1.558 T: 0.309 V: 0.219 Z: 0.000	t	2.958		
3	16mm Diameter bars. C: 0.872 M: 1.558 T: 0.309 V: 0.219 Z: 0.000	t	2.958		
	High tensile welded steel mesh reinforcement :				
4	Ref: 193 cast into concrete surfaces. C: 20 M: 36 T: 3 V: 3 Z: 0	m2	62		
5	Ref: 395 cast into concrete surfaces. C: 28 M: 44 T: 15 V: 18 Z: 0	m2	105		
6	Ref: 888 cast into stripfootings. C: 39 M: 66 T: 17 V: 18 Z: 0	m2	139		
7	Ref: 888 cast into vertically in brick cavity. C: 49 M: 88 T: 26 V: 22 Z: 0	m2	185		
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES	n		R	

Section No. 2				
SECTION NO.2 - BUILDING WORKS				
Bill No. 2				
CONCRETE, FORMWORK AND REINFORCEMENT				
COLLECTION				
Total Brought Forward from Page No.	Page No 50 51 52 53		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 2 CONCRETE, FORMWORK AND REINFORCEMENT MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R		

Item No		Quantity	Rate	Amount
·	BILL NO.3			
	MASONRY			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	FOUNDATION BRICKWORK (PROVISIONAL)			
	Walls and linings in stock bricks in 5:1 cement mortar:			
1	Half brick wall against slab. m2 C:7 M:12 T:4 V:3 Z:0	25		
2	One brick wall. m2 C: 66 M: 110 T: 28 V: 29 Z: 0	233		
	Walls and linings in stock bricks in 5:1 cement mortar with "Coprox" or equally approved waterproof additive batched mixed into mortar at 2.5kgs/50kgs cement:			
3	345mm Thick cavity wall comprising two 110mm brick skins tied together with and including galvanised butterfly wire ties at the minimum rate of 9/m2. C:49 M:88 T:26 V:22	185		
	Z:0 Reinforcement to brickwork			
4	Galvanised brick reinforcement 115mm wide built horizontally into brickwork. C:1161 M:2106 T:622 V:526	4,415		
	Z:0			
5	Galvanised brick reinforcement 230mm wide built horizontally into brickwork. C:772 M:1294 T:330 V:344 Z:0	2,740		
	Carried to Collection		R	
	SECTION NO.2 - BUILDING WORKS BIII No. 3 MASONRY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

	EACE DDICKMODK	ì	1		1
	<u>"Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints</u>				
1	Extra over ordinary brickwork for facing and pointing in stretcher bond.	m2	101		
	C:28 M:45 T:15 V:14 Z:0				
	SUPERSTRUCTURE BRICKWORK				
	Walls and linings in stock bricks in 5:1 cement mortar :				
2	Half brick wall.	m2	117		
	C: 27 M: 59 T: 22 V: 11 Z: 0				
3	One brick wall.	m2	443		
	C:126 M:200 T:56 V:60 Z:0				
	Beamfilling				
4	Half brick wall in beamfilling.	m2	32		
	C:9 M:15 T:4 V:4 Z:0				
	Reinforcement to brickwork				
5	Galvanised brick reinforcement 115mm wide built horizontally into brickwork.	m	879		
	C: 221 M: 426 T: 136 V: 96 Z: 0				
6	Galvanised brick reinforcement 230mm wide built horizontally into brickwork.	m	1,301		
	C:371 M:589 T:165 V:177 Z:0				
	Precast pre-stressed reinforced concrete lintols				
7	75 x 110mm Lintol not exceeding 3m long, built at both ends into brickwork over opening.	m	23		
	C:7 M:14 T:0 V:2 Z:0				
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS Bill No. 3				
	MASONRY MAYIBENYE SSS				
	PROVISIONAL BILLS OF QUANTITIES				

	Turning pieces				
1	Turning piece to soffit, 110mm wide, at lintols, etc. C: 14 M: 23 T: 8 V: 8 Z: 0	m	54		
	EXTERNAL FACE BRICKWORK				
	"Qunu Travertine " or other equal approved FBX quality face bricks including jointing and square recess pointing 6 x 10mm joints				
2	Extra over ordinary brickwork for facing and pointing in stretcher bond. C: 127 M: 196 T: 65 V: 65	m2	453		
	Z:0				
3	Extra over ordinary brickwork for facing and pointing in reveals.	m2	17		
	C:5 M:7 T:3 V:3 Z:0				
	Fair cutting to face brickwork				
4	Fair cutting and fitting around pipe not exceeding				
	100mm diameter.	No	74		
	C: 22 M: 28 T: 12 V: 12 Z: 0				
5	Fair raking and cutting.	m	35		
	C:7 M:14 T:7 V:7				
	Z:0				
	Face brick copings, lintols, cills, etc.				
6	Extra over brickwork for cut brick-on-edge cill,165mm wide, set sloping and slightly projecting including pointing to face and top.	m	40		
	C:8 M:18 T:7 V:7 Z:0				
7	Extra over brickwork for brick-on-edge header course				
,	tread, 220mm wide, including pointing to one face and		113		
	top. C: 21 M: 66 T: 13 V: 13 Z: 0	m	113		
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS Bill No. 3				
	MASONRY				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
			I	II	1

1	Extra over brickwork for cut brick-on-end header course lintol, including pointing to face and soffit.	m	54		
	C: 14 M: 23 T: 8 V: 8				
	Z:0				
	<u>Test:</u>				
2	Contractor is to construct L-Shape one brick facebrick wall faced on both sides including pointing, size 1000 x 1000 x 1000mm high to be approved by the principal agent before brickwork proceeds.		Item		
	MISCELLANEOUS				
	Natural grey fibre-cement cills				
	Natural grey libre-cement clis				
3	15mm x 150mm Wide cill set flat and slightly projecting.	m	40		
	C:8 M:18 T:7 V:7				
	Z:0				
	Hoop iron ties, cramps, etc.				
4	1.6 x 30mm Galvanized hoop iron roof tie 1100mm long with one end wrapped around and spiked to timber the other end built a minimum of six courses deep into brickwork as the work proceeds.	No	112		
	C:28 M:52 T:16 V:16				
	Z:0				
	Air bricks, etc.				
5	230 x 160 x 35mm Terracotta vermin proof air brick. C: 52 M: 80 T: 28 V: 28	No	188		
	Z:0				
					\vdash
	Carried to Collection			R	
				K	\vdash
	SECTION NO.2 - BUILDING WORKS Bill No. 3				
	MASONRY				
	MAYIBENYE SSS				
	PROVISIONAL BILLS OF QUANTITIES				

Section No. 2			I	 	
	2 - BUILDING WORKS				
Bill No. 3					
MASONRY					
COLLECTION					
COLLECTION		Domo		Amount	
		Page No		Amount	
Total Brought F	forward from Page No.	55			
		56			
		57			
		58			
Carri	ed Forward to Summary of Section No. 2		R		
Bill No. 3	2 - BUILDING WORKS				
MASONRY MAYIBENYE S					
	L BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
	BILL NO.4			
	WATERPROOFING			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	DAMP-PROOF COURSE			
	375 Micron polyethylene damp-proof sheeting:			
1	Laid in walls. m2 C:31 M:53 T:14 V:15 Z:0	113		
	SHEET OR MEMBRANE WATERPROOFING			
	250 Micron "Gunplas USB" green polyethylene sheeting :			
2	Laid flat on prepared sand bed under solid floor. m2 C: 48 M: 80 T: 18 V: 21 Z: 0	167		
	"Kaytech 500" Single cuspated HDPE sheet waterproofing membrane			
3	Laid vertically against brickwork as backfilling proceeds. m2 C: 49 M: 88 T: 26 V: 22 Z: 0	185		
	FLASHING STRIPS			
	Elastic acrylic and rubberised bitumen compound with "waterproof membrane" applied in strict accordance with the Manufacturer's instructions:			
4	Flashing strips around 110mm diameter PVC vent pipes through steel roof sheeting. C:4 M:8 T:1 V:1 Z:0	14		
	Carried to Collection SECTION NO.2 - BUILDING WORKS BIII No. 4 WATERPROOFING MAYIBENYE SSS		R	
	PROVISIONAL BILLS OF QUANTITIES			

	LIQUID WATERPROOFING				
	Two coats "Brixeal" bitumen emulsion waterproofing on:				
1	Vertical surfaces of plastered brickwalls. C:49 M:88 T:26 V:22 Z:0	m2	185		
2	Horizontal concrete surfaces. C: 29 M: 51 T: 10 V: 7 Z: 0	m2	97		
	One coat plaster primer and two coats "Flexikote" water based acrylic waterproofing sealant on:				
3	Vertical surfaces of brickwalls. C: 49 M: 88 T: 26 V: 22 Z: 0	m2	185		
	WATERSTOPS, SEALING STRIPS, JOINT SEALANTS, ETC.				
	Sealing and pointing				
4	Seal and point around aluminium window frames with an approved external quality sealing compound applied with a pressure caulking gun. C:34 M:72 T:26 V:26 Z:0	m	158		
	2.0				
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS Bill No. 4 WATERPROOFING MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Section No. 2		1		
SECTION NO.2 - BUILDING WORKS				
Bill No. 4				
WATERPROOFING				
COLLECTION				
Total Brought Forward from Page No.	Page No 60 61		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 4 WATERPROOFING		R		
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
	BILL NO.5			
	ROOF COVERING			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	ROOF COVERINGS, ETC.			
	PROFILED SHEETING OF METAL, FIBRE CEMENT, PLASTIC, ETC.			
	Metal roof sheeting			
	0,53mm Thick Z200 "IBR Profile" galvanised metal roof sheeting, in single sheet lengths, with "Chromadek" finish to external face and standard backing coat to internal face:			
1	Roof sheeting laid to a pitch not exceeding 25° and secured to timber purlins at approximately 1 200mm centres including turning up sheet at ridge and turning down sheet at eaves. C:62 M:102 T:33 V:33	229		
	Z:0			
	Circular cutting			
2	Circular cutting on roof sheeting for ventilators, vent pipes, etc.	14		
	C:4 M:8 T:1 V:1 Z:0			
	Accessories, etc. to match roof sheeting			
3	Ridge flashing 225mm girth. m C: 15 M: 24 T: 8 V: 8 Z: 0	55		
	Carried to Collection		R	
	SECTION NO.2 - BUILDING WORKS BIII No. 5 ROOF COVERING MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

	<u>Insulation</u>			1
1	"Sisalation FR430" insulation laid taut over rafters at approximately 2400mm centres and fixed including galvanised steel straining wires where required. m2 C: 62 M: 102 T: 33 V: 33	229		
	Z:0			
				_
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 5 ROOF COVERING MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	
	TOTOGOTAL BILLS OF WOMENTILS			

Section No. 2	1 1		1	
SECTION NO.2 - BUILDING WORKS				
Bill No. 5				
ROOF COVERING				
COLLECTION				
COLLECTION	Done		A	
Total Brought Forward from Page No.	Page No 63 64		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 5 ROOF COVERING		R		<u> </u>
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
	BILL NO.6			
	CARPENTRY AND JOINERY			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	CARPENTRY			
	PLATE NAILED TIMBER ROOF CONSTRUCTION			
	Prefabricated timber roof trusses shall be constructed of South African pine by a firm of specialist designer manufacturer's as approved by the Architect.			
	Prices must include for all cross and windbracing according to the manufacturer's instruction.			
	Prices must include for the design, plans and approval of all timber trusses and no claim shall be considered.			
	Pre-fabricated timber roof trusses shall comply with the requirements of SABS Specification 0163 and be constructed of South African pine as described in clause 8.5 to the designs shown on the Manufacturer's detail drawings. The timber shall be of cross-sectional dimensions shown, cut to correct lengths with ends square or at the required angle.			
	Trusses shall be assembled in truss fabricating jigs with the truss having the proper camber, all tightly clamped together with joints secured using approved connector plates of galvanised steel sheet. Connector plates shall be pressed into the timber simultaneously from both sides of the truss with a hydraulic press capable of exerting such pressure as will ensure complete penetration of the teeth into the timber.			
	The connector plates shall be of such size as will ensure that the joints so made will adequately withstand the forces exerted on the joints.			
	In coastal areas connector plates in buildings without ceilings shall be painted with two coats of epoxy tar complying with SABS Specification 801 Type 2, or rust neutralising paint.			
			_	
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 6 CARPENTRY AND JOINERY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

Approval of pre-fabricated roofing systems, whether measured as an alternative or not, shall be subject to the following requirements: (a) The Manufacturer of the pre-fabricated trusses shall hold a certificate of competence issued by the Insitute for Timber Construction. (b) A polyester print, size A1 having a minimum thickness of 0,5mm, shall be submitted by the Contractor to the Regional Representative at an early stage for approval by the Directorate: Structural Engineering Services. (c) The drawings shall be signed by a Registered Professional Engineer whose name appears on the Departmental panel for structural work. (d) In the case of systems buildings, approval shall be given with submission of the contract drawings on acceptance of the tender. The following minimum information shall be shown on the drawings: Details of the roof system with the position of (a) the rafters and purlins indicated thereon as well as typical elevations. (b) Bracing as recommended by the Institute for Timber Construction. (c) Sizes and grading of the timber components. (d) Truss sizes, e.g. height of ridge or angle of pitch. (e) Plate sizes for every construction point. (Code numbers only are deemed insufficient). Seperate connection details for hip, valley and (f) iack rafters. (g) Maximum spacing for purlins and brandering to ceilings shall be according to Subclauses 7.6.1 and 7.6.2 and Clauses 7.8, 7.9 and 9.5. **Carried to Collection** R **SECTION NO.2 - BUILDING WORKS** Bill No. 6 CARPENTRY AND JOINERY **MAYIBENYE SSS** PROVISIONAL BILLS OF QUANTITIES

	(h) The type of roof covering as well as the designation load. Over and above the supervision undertaken by the Representative / Agent, the Truss Fabricator or his Design Engineer shall inspect the completed roof structure and issucertificate of confirmation to the Department that:	ne II			
	"The roof structure(s) has (have) been erected in accordance with the Design Engineer's drawings, as accepted by the Department, at the relevant details given in the manual "THE ERECTION AND BRACING OF TIMBER ROTRUSSES" issued by the National Timber Research Institute and the Institute for Timber Construction".	nd E OOF			
	Fixing:				
	All nailing of timber roof trusses, purlins, etc shall be done with galvanised nails. In coastal areas, copper, aluminium or stainless steel nails shall be used.				
	Items described as "nailed" shall be deemed to be fix with hardened steel nails or shot pins to brickwork or concrete.				
	Erection certificates				
1	Contractor is to supply a roof truss erection certificate for the building stating that the erection and installation of the roof trusses has been inspected and approved a professional registered structural engineer.	on	1		
	C:0 M:0 T:0 V:0 Z:1				
	Wrot softwood :				
2	38 x 114mm Wall plate wired down (wire ties elsewhere).	m	106		
	C: 29 M: 47 T: 15 V: 15 Z: 0				
3	50 x 76mm Purlins.	m	331		
	C:90 M:147 T:47 V:47 Z:0				
4	50 x 76mm Bracing. C: 12 M: 24 T: 12 V: 12 Z: 0	m	60		
	Carried to Colle	ction		R	T
	SECTION NO.2 - BUILDING WORKS BIII No. 6 CARPENTRY AND JOINERY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES	Cuon		K	
					1

1	38 x 152mm R	afters.			m l	233		
	C : 58	M : 108	T:33	V : 33				
	Z:0							
2	38 x 38 x 152m	nm Long clea		rafter foot.	No	112		
	C : 28	M : 52	T : 16	V : 16				
	Z:0							
3	50 x 76 x 300m C : 12	• .	•	d to timber purlin	ı. No	60		
	Z:0	M : 24	T : 12	V : 12				
	Sundries:							
4	Hurricane clip f				No	336		
	C : 84 Z : 0	M : 156	T : 48	V : 48				
	<u>JOINERY</u>							
	Doors, window	<u>vs, sashes,</u>	etc.					
	Wrot hardwood	<u>l :</u>						
5	size 813 x 1100 and top rail, 22 bottom rail and filled flush on o thick tongued,	Omm high, co x 150mm m 2 No. 22 x 7 ne side betw grooved and row matched 70mm splaye countersunk	omprising 4 iddle rail, 2 form diago veen framin V-jointed but widths and and reba	onal braces and g with 22mm oth sides vertica d fitted with and ted	S	3		
	SECTION NO.2 Bill No. 6 CARPENTRY A MAYIBENYE S PROVISIONAL	AND JOINER	G WORKS	rried to Collect	ion		R	

1	44mm Thick framed, ledged, braced and battened door size 813 x 1832mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres. C:7 M:14 T:0 V:2 Z:0	No	23		
2	44mm Thick framed, ledged, braced and battened door size 813 x 2032mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres. C:2 M:2 T:1 V:1	No	6		
3	44mm Thick framed, ledged, braced and battened door size 950 x 2032mm high, comprising 44 x 144mm stiles and top rail, 22 x 150mm middle rail, 22 x 230mm bottom rail and 2 No. 22 x 75mm diagonal braces and filled flush on one side between framing with 22mm thick tongued, grooved and V-jointed both sides vertical boarding in narrow matched widths and fitted with and including 44 x 70mm splayed and rebated weatherboard, countersunk brass screwed on at maximum 200mm centres. C:1 M:2 T:0 V:0 Z:0	No	3		
	Frames, rails, skirtings, etc. Meranti timber door frames				
	Note:				
	All units are to constructed using 70 x 108mm hardwood timber with 19 x 19mm quadrant bead to external face				
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS Bill No. 6 CARPENTRY AND JOINERY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			K	

1					1	1	1	1	1
1	Jab lining, to sui overall.	it single doo	r size 813 >	(1100mm high	m	8			
	C:0	M:0	T:8	V:0					
	Z:0								
2	Framed frame, thigh overall.	o suit single	door size 8	313 x 2032mm	No	29			
	C:9	M : 16	T:1	V : 3					
	Z:0								
3	Framed frame, thigh overall.	o suit single	door size 9	950 x 2032mm	No	3			
	C : 1	M:2	T:0	V : 0					
	Z:0								
	<u>Sundries</u>								
	<u> </u>								
4	10 x 140mm Do pelleted in timbe centres, includin concrete.	er frame, at	approximate	ely 600mm	No	274			
	C : 80	M : 144	T:26	V : 24	110	-/ '			
	Z:0		v						
	<u>Plastic, fibre cer</u>	<u>nent, etc.</u>							
	Pressed fibre-ce	ement:							
5	12 x 225mm Far rafter feet includ strips, etc.				m	55			
	C : 15	M : 24	T:8	V : 8					
	Z:0								
6				rass screwed to H-profile jointing	m	97			
	strips, etc. C : 23	M : 41	T : 16	V : 16	""	37			
	Z:0		1.10	. 10					
	2.0								
				rried to Collection	n		R		<u> </u>
	SECTION NO.2 Bill No. 6	- BUILDING	S WORKS						
	CARPENTRY A	ND JOINER	Υ						
	MAYIBENYE SS	SS							
	PROVISIONAL	BILLS OF C	QUANTITIE	S					

Section No. 2				Ī
SECTION NO.2 - BUILDING WORKS				
Bill No. 6				
CARPENTRY AND JOINERY				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	66			
	67			
	68			
	69			
	70			
	71			
		_		
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS		R		
Bill No. 6 CARPENTRY AND JOINERY				
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No			Quantity	Rate	Amount
	BILL NO.7				
	IRONMONGERY				
	Note:				
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).				
	IRONMONGERY TO TIMBER DOORS, FRAMES, ETC.				
	Hinges, bolts, etc.				
1	100 x 75mm Heavy duty brass butt hinges. C: 23 M: 40 T: 9 V: 7 Z: 0	No	79		
	Push plates, kicking plates, indicator plates, etc.				
2	"Dormakaba DSS-130 M" or other equal approved 150 x 150mm Stainless steel male pictogram. C:1 M:0 T:1 V:1	No	3		
	Z:0				
3	"Dormakaba DSS-131 F" or other equal approved 150 x 150mm Stainless steel female pictogram. C:1 M:2 T:0 V:0 Z:0	No	3		
4	"Dormakaba DSS-133 P" or other equal approved 150 x 150mm Stainless steel disabled persons pictogram. C:1 M:2 T:0 V:0 Z:0	No	3		
	Locksets, etc. to be masterkeyed				
5	"Union 2277-78SS" or equally approved three lever upright mortice lockset with stainless steel forend and striking plate finish. C:3 M:4 T:1 V:1 Z:0	No	9		
	Carried to Collection SECTION NO.2 - BUILDING WORKS BIII No. 7 IRONMONGERY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			R	

1	"Union CZ80941 W/C indicator bo	SC" or equ lt.	ally approve	ed satin chrome	No	29			
	C:8	M : 16	T:3	V:2					
	Z:0								
	Handles, furnitur	e, etc.							
2	"Union 07692 2	400" or on	ally approv	ad actin chroma					
	"Union CZ682-24 radius lever furni		иану арргоч	eu saun chrome	No	9			
	C:3	M : 4	T : 1	V : 1					
	Z:0			•					
	2.0								
3	"Dormakaba DP								
	25mm Stainless		ht tubular pi	ull handle with	No	3			
	flange fixing. (Se	M:2	T : 0	V : 0	NO	3			
		IVI : Z	1:0	V : U					
	Z : 0								
	Stops, holders, h	nooks, etc.							
	"D D	0 00 0004							
4	"Dormakaba DH			qual approved plugged to door.	No	23			
	C:7	M : 14	T : 0	V:2	140	23			
	Z:0	IVI . 14	1.0	V . Z					
	2.0								
	<u>Sundries</u>								
5	50mm Plastic ke	y tag.			No	9			
	C:3	M : 4	T:1	V : 1					
	Z:0								
	IRONMONGERY	(TO META	LWORK						
			<u>.</u>						
	Locksets, etc. pr masterkeyed	ovided with	i two keys a	na to be					
	•								
6	51mm brass pad	llock with st	tainless stee	el shackle.	No	6			
	C:2	M:2	T:1	V : 1					
	Z:0								
	IRONMONGERY	FIXED TO	CONCRE	ΓE. TILING.					
	ETC.			<u> </u>					
	Stops, holders, h	nooks, etc.							
7	38mm Black rub	her door of	on nlugged t	to wall or floor	No	35			
_ ′	C : 10			V : 3	NO	33			
		IVI . 10	1.4	V . 3					
	Z : 0								
									_
			Car	ried to Collectio	n		R		
	SECTION NO.2	- BHIII DING					11		+
	Bill No. 7	DOILDING	VVOINIO						
	IRONMONGERY								
	MAYIBENYE SS			0					
	PROVISIONAL I	BILLS OF (JUAN IIIE	5					
l						l		II	1

	<u>SIGNAGE</u>							
	3mm Thick x 32m painted numerals steel door frame	m high blu or letters,	ie perspex s countersunk	signs with white tap screwed to				
1	Sign with "MALE : C:1 Z:0	STAFF AB M:0	BLUTIONS" (T:0	enscribed. V : 0	No	1		
2	Sign with "MALE	ABLUTION	NS" enscribe	ed.	No	2		
	C:0 Z:0	M : 0	T : 1	V : 1				
3	Sign with "FEMAL C:1 Z:0	E STAFF M:0	ABLUTIONS T:0	S" enscribed. V:0	No	1		
4	Sign with "FEMAL C:0 Z:0	E ABLUTI M : 2	IONS" ensci T : 0	ribed. V:0	No	2		
5	Sign with "DISABI C:1 Z:0	LE" enscril M : 2	bed. T:0	V:0	No	3		
	SECTION NO.2 - Bill No. 7 IRONMONGERY MAYIBENYE SSS PROVISIONAL B	5	S WORKS	ried to Collection			R	

Section No. 2				
SECTION NO.2 - BUILDING WORKS				
Bill No. 7				
IRONMONGERY				
COLLECTION				
Total Brought Forward from Page No.	Page No 73 74 75		Amount	
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - BUILDING WORKS Bill No. 7 IRONMONGERY MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
l.	<u>METALWORK</u>			
	BILL NO.8			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).			
	STEEL			
	Stairs, balustrading, cat ladders, grilles, gates, framework, etc.			
	GATES			
	Hot dipped galvanised mild steel			
1	Single gate, size 900mm wide x 2050mm high, the leaf formed of 25 x 25 x 2mm wall thickness mild steel square tubing framing all round with mitred and welded angles, the gate filled in with 12 x 12mm mild steel bars welded, at each end, perimeter framing at not exceeding 100mm centres, the leaf fitted with lock housing (lock elsewhere measured) formed of 2.5mm thick mild steel flat plate, the leaf fitted with a set of hinges fixed to brickwall with and including masonry anchors.(G1) C:2 M:2 T:1 V:1 Z:0	6		
	Carried to Collection		R	
	SECTION NO.2 - BUILDING WORKS BIII No. 8 METALWORK MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			
				1

OTHER METALS			
Aluminium windows, doors, etc.			
All aluminium work is to be manufactured in accordance with AAMSA specifications by a registered Member of the Association			
All units are to be pre-glazed in accordance with the requirements of the National Building Regulations, unless otherwise specifically noted			
All units are to be supplied with a protective plastic covering, which is to be removed only once all adjacent plastering and painting is complete			
All laminated safety glass panes are to bear the safety glass indicator mark, failing which they will be rejected and the Contractor will have to replace same at his own cost.			
NATURAL ANODISED ALUMINIUM			
Natural bronze anodised pre-glazed aluminium windows complete with ironmongery and including setting up, building in, filling back of frame with cement mortar, sealing around same with silicone sealant, etc.			
Top hung opening out window, size overall 600 x 600mm high, glazed with and including 6.38mm white translucent laminated safety glass.(W1) No $C:14$ M:30 T:11 V:11	66		
Z:0			
Carried to Collection		R	
SECTION NO.2 - BUILDING WORKS			
Bill No. 8 METALWORK			
MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1

Į,s	Section No. 2	[l	1]
	ECTION NO.2 - BUILDING WORKS				
	METALMORIA				
	METALWORK				
9	COLLECTION				
T	otal Brought Forward from Page No.	Page No 77 78		Amount	
	Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 8 METALWORK MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R		

Item No		Quantity	Rate	Amount
	<u>PLASTERING</u>			
	BILL NO.9			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).			
	SCREEDS			
	Untinted granolithic screeds, etc. mixed by volume 4 parts granite chips, 1 part sand and 2 parts cement			
1	40mm Thick screed to floors and landings. C:37 M:58 T:19 V:19 Z:0	13	3	
	<u>Skirtings</u>			
2	75mm High coved skirting. C: 72 M: 108 T: 38 V: 38 Z: 0	m 25	6	
	GRANOLITHIC			
	Untinted granolithic on concrete			
3	30mm Thick on floors to thresholds including forming reedings to treads. C:2 M:2 T:1 V:1 Z:0	2	5	
	PLASTER			
	One coat external 1:4 cement plaster on :			
4	Block walls in pit with "Coprox" or equally approved waterproof additive batched mixed into plaster at 2.5kgs/50kgs cement.	2 18	5	
	C:49 M:88 T:26 V:22 Z:0			
	Carried to Collection		R	
	SECTION NO.2 - BUILDING WORKS Bill No. 9 PLASTERING MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	Brick wall. C : 203 Z : 0	M : 403	T : 106	V : 99	m2	811		
2	C: 203 Z: 0			V:99 ng 300mm wide. V:2	m2	14		
	SECTION NO.2 Bill No. 9 PLASTERING MAYIBENYE S PROVISIONAL	ss	G WORKS	rried to Collection	1		R	

S	section No. 2		1		ĺ
s	ECTION NO.2 - BUILDING WORKS				
В	ill No. 9				
P	PLASTERING				
<u>c</u>	COLLECTION				
Т	otal Brought Forward from Page No.	Page No 80 81		Amount	
E	Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 9		R		
	PLASTERING MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
	BILL NO.10			
	PLUMBING AND DRAINAGE (PROVISIONAL)			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).			
	Roof gutters, rainwater pipes, etc.			
	Powder coated seamless aluminium rainwater gutters, downpipes and accessories			
1	125 x 115mm Gutter fixed to fascia at maximum 600mm centres with and including proprietary fixings. C: 15 M: 24 T: 8 V: 8 Z: 0	55		
2	Extra over aluminium gutter for forming discharge outlet to suit 100 x 75mm downpipe. C: 2 M: 4 T: 1 V: 1	8		
	Z:0			
3	Extra over gutter for stopped end. No C:2 M:4 T:2 V:2 Z:0	10		
4	100 x 75mm Rainwater downpipe fixed to wall with and including proprietary holderbats.	24		
	C:6 M:12 T:3 V:3 Z:0			
5	Extra over rainwater downpipe for bend. C:6 M:12 T:3 V:3 Z:0	24		
	Carried to Collection SECTION NO.2 - BUILDING WORKS BIII No. 10 PLUMBING AND DRAINAGE (PROVISIONAL) MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

1	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	WATER SUPPLIES				
	Class 2 copper pipes with straight compression fittings				
1	15mm Pipe and fixing to walls, floors, in roofs, in concrete, etc. including any necessary proprietary holderbats, fixings, etc. C:63 M:84 T:32 V:32 Z:0	m	211		
	Extra over copper pipes for brass compression fittings				
2	15mm Fittings. C: 22 M: 28 T: 12 V: 12 Z: 0	No	74		
	Extra over copper pipes for capillary fittings with soldered joints				
3	15mm Fittings. C: 63 M: 84 T: 32 V: 32 Z: 0	No	211		
	SOIL DRAINAGE				
	uPVC Pipes with solvent welded straight joints :				
4	40mm Pipes. C: 16 M: 28 T: 4 V: 4 Z: 0	m	52		
5	50mm Pipes. C: 15 M: 0 T: 20 V: 20 Z: 0	m	55		
	White uPVC vent pipe in single lengths:				
6	110mm Diameter vent pipe fixed to wall with proprietary brackets at not exceeding 500mm centres. C:32 M:64 T:12 V:12 Z:0	m	120		
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 10 BLUMBING AND DRAINAGE (PROVISIONAL)			R	
	PLUMBING AND DRAINAGE (PROVISIONAL) MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

1			1	1	1	
	Extra over uPVC pipes for solvent welded fittings:					
1	40mm Plain bend.	No	26			
	C:8 M:14 T:2 V:2					
	Z:0					
2	50mm Plain bend.	No	22			
	C:6 M:0 T:8 V:8 Z:0					
	Extra over uPVC pipes for fittings					
3	Black PVC whirlybird vent capping over the 110mm vent					
	pipe. C:8 M:16 T:3 V:3	No	30			
	C:8 M:16 T:3 V:3 Z:0					
	Inspection chambers, catch pits, etc.					
	<u>Cast iron covers and frames</u>					
4	450 x 600mm x 72kg Type 8A coated cast iron double seal manhole cover and frame, including bedding and grouting frame on concrete, including providing with hot dipped galvanised steel locking bar and padlock.	No	11			
	C:3 M:6 T:1 V:1 Z:0					
	Soakage pits, french drains, etc.					
	Testing					
5	Allow for testing the plumbing installation in accordance with the National Building Regulations.		Item			
	SANITARY FITTINGS, TANKS, GEYSERS, ETC.					
	Plastic sanitaryware					
6	VIP 200 Pit pedestal complete with integral flap four times plugged to floor with and including 6 x 75mm masonry anchors.	No	19			
	C:0 M:14 T:3 V:2 Z:0					
	2.0					
	Carried to Collection			R		
	SECTION NO.2 - BUILDING WORKS					
	Bill No. 10 PLUMBING AND DRAINAGE (PROVISIONAL)					
	MAYIBENYE SSS					
	PROVISIONAL BILLS OF QUANTITIES					

1	VIP 450 Pit pedestal complete with integral flap four	1			1
•	times plugged to floor with and including 6 x 75mm		40		
	masonry anchors.	No	10		
	C:8 M:2 T:0 V:0 Z:0				
	White glazed vitreous china ware :				
2	"Vaal 7050" or equally approved washhand basin, size 510 x 405mm, with two tapholes, one taphole stopper, integrated overflow and chainstay hole, mounted to wall on and including two proprietary semi-concealed cast iron wall brackets with 10mm bolts.	No	26		
	C:8 M:14 T:2 V:2				
	Z:0				
3	"Vaal 704001" or equally approved wall hung flat back urinal, size overall 610 x 3850mm, complete with chromium plated back inlet spreader and 38mm chromium plated domical grating hung on and including two proprietary hanger brackets.	No	11		
	C:3 M:0 T:4 V:4				
	Z:0				
4	"Vaal" or equally approved urinal division size, 400 x 100 x 700mm high including plugs and proprietary hanger brackets .	m	11		
	C:3 M:0 T:4 V:4				
	Z:0				
	Grade 304 stainless steel ware :				
	Sanitary fitting sundries				
5	"N-SBIN-12-SA" or equally approved 12 Litre pedal sanitary bin, size 463 x 140 x 480mm.	No	22		
	C:6 M:16 T:0 V:0				
	Z:0				
	Grade 304 stainless steel ware :				
6	Grab rail 1200mm long with two flanges "SR 1" plugged to wall with and including stainless steel screws.	No	3		
	C:1 M:2 T:0 V:0				
	Z:0				
				<u> </u>	
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS			``	
	Bill No. 10				
	PLUMBING AND DRAINAGE (PROVISIONAL) MAYIBENYE SSS				
	PROVISIONAL BILLS OF QUANTITIES				

1	Dog leg grab rail with three flanges "DL3" plugged to wall with and including stainless steel screws.	No	3		
	C:1 M:2 T:0 V:0 Z:0				
	Sanitary fitting sundries				
2	Satin chrome thief proof toilet roll holder, PWD Sample 71, plugged to wall.	No	29		
	C:8 M:16 T:3 V:2 Z:0				
3	Heavy-duty double-flap hinged toilet seat and cover.	No	29		
	C:8 M:16 T:3 V:2 Z:0				
	Tanks, geysers, etc.				
	Rainwater tanks				
4	5000 Litre polyethylene rotomoulded vertical water storage tank provided complete with lid and overflow outlet, fitted with suitable adaptor and setting in position on concrete tankstand (elsewhere measured). (The tanks are to be filled with water for the Practical Completion inspection)	No	8		
	C:2 M:4 T:1 V:1				
	Z:0				
5	Hole through top of tank lid for 100mm diameter pipe.	No	8		
	C:2 M:4 T:1 V:1 Z:0				
6	38 x 1,6mm Galvanised hoop iron strap around tank, both ends fitted with once holed 30 x 30 x 3mm thick galvanised flat plate and bolted together with and including M8 bolt and nut.	No	8		
	C:2 M:4 T:1 V:1				
7	Z:0 38 x 1,6mm Galvanised hoop iron tie down, 1200mm long, one end wrapped around tank strap and twice bolted, the other end folded over and bolted to top of concrete with and including 8 x 60mm masonry anchor. C:8 M:16 T:4 V:4	No	32		
	Z:0				
	<u>Taps, valves, etc.</u>				
	Carried to Collectio	n		R	
	SECTION NO.2 - BUILDING WORKS BIII No. 10 PLUMBING AND DRAINAGE (PROVISIONAL) MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
					ĺ

	Solid cast brass	taps, valves	s, etc.					
1	15mm Ball-o-sto	p valve.			No	52		
	C : 16 Z : 0	M : 28	T : 4	V : 4				
2	15mm Brass ball	l-o-stop.			No	23		
	C:7 Z:0	M : 12	T : 2	V : 2				
3	15mm Chromiun pillartap.	า plated sqเ	ıare type ell	oow action	No	3		
	C:1 Z:0	M : 2	T : 0	V:0				
4	15mm Chromiun hold open feature			bib tap with n	on- No	57		
	C : 17	M : 24	T : 8	V : 8	110	37		
	Z:0							
5	22mm Brass nor				No	13		
	C : 4 Z : 0	M : 7	T : 1	V : 1				
	Waste unions, tra	aps, etc.						
	Outlets, traps, et	<u>c :</u>						
6	38mm Chromiun with plug, chain a	n plated bra and chain s	iss slotted b tay.	asin waste ou	tlet No	26		
	C:8 Z:0	M : 14	T : 2	V : 2				
7	40mm Chromiun	n plated bra	ıss basin bo	ttle trap.	No	26		
	C:8	M : 14	T : 2	V : 2				
	Z : 0							
8	50mm Chromiun C:3	n plated PV M : 0	C urinal bot	tle trap. V : 4	No	11		
	Z:0	IVI . U	1.4	V . 4				
			Car	ried to Collec	tion		R	
	SECTION NO.2	- BUILDING	WORKS					
	Bill No. 10 PLUMBING AND		E (PROVIS	IONAL)				
	MAYIBENYE SS PROVISIONAL I		DUANTITIE	S				
		0 0. 0	, e,	_				

Section No. 2				
SECTION NO.2 - BUILDING WORKS				
Bill No. 10				
PLUMBING AND DRAINAGE (PROVISIONAL)				
COLLECTION				
Total Brought Forward from Page No.	Page No 83 84 85		Amount	
	87			
	88			
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - BUILDING WORKS BIII No. 10 PLUMBING AND DRAINAGE (PROVISIONAL) MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No			Quantity	Rate	Amount
	BILL NO.11				
	Note:				
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition July 2014).				
	PAINTWORK				
	PAINT ON CONCRETE, PLASTER, ETC				
	Prepare and apply one coat plaster primer, one coat universal undercoat and two coats "Wall & All" or other equal approved washable suede sheen acrylic PVA paint on:				
1	Internal smooth plastered walls. C:206 M:410 T:108 V:102 Z:0	m2	825		
	Scrub surface with degreaser, rinse thoroughly with tap water, and apply one coat sealer and two coats epoxy paint on:				
2	Concrete floated or screeded floors C: 37 M: 58 T: 19 V: 19 Z: 0	m2	133		
3	Granolithic skirting not exceeding 300mm girth. C: 72 M: 108 T: 38 V: 38 Z: 0	m	256		
	PAINT ON TIMBER				
	Prime or oil on :				
4	Backs of frames or linings not exceeding 300mm girth. C:49 M:88 T:13 V:15 Z:0	m	164		
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	
	Bill No. 11 PAINTWORK MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

	Prepare and apply one coat pink wood primer, one undercoat and two coats water based eggshell enamel				
	on :				
1	Surfaces of flush panel doors.	m2	6		
	C:0 M:0 T:6 V:0				
	Z:0				
2	Surfaces of frames and linings.	m2	2		
	C:0 M:0 T:2 V:0				
	Z:0				
	Prepare and apply two coats carbolineum wood preserver on :				
3	General surfaces of roof timbers.	m2	89		
	C: 22 M: 41 T: 13 V: 13				
	Z:0				
4	General surfaces of roof timbers not exceeding 300mm girth.	m	331		
	C:90 M:147 T:47 V:47		001		
	Z:0				
	Prepare and apply three coats interior quality clear polyurethane varnish on :				
5	Surfaces of flush panel doors.	m2	112		
	C: 35 M: 62 T: 4 V: 10				
	Z:0				
6	Surfaces of frames and linings.	m2	39		
	C:12 M:22 T:1 V:4				
	Z:0				
	PAINT ON METALWORK				
	One coat steel etch primer, one coat universal undercoat and two coats gloss enamel paint on :				
7	•	0	20		
7	Hot dipped galvanised steel gates. C:7 M:7 T:4 V:4	m2	22		
	Z:0				
					+
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS				
	Bill No. 11 PAINTWORK				
	MAYIBENYE SSS				
	PROVISIONAL BILLS OF QUANTITIES				

1	PAINT ON FIBRE-CEMENT	1]
	Prime nail heads and H-section jointing strips and apply one coat universal undercoat and two coats eggshell enamel paint on :				
1	Internal fibre cement cills not exceeding 300mm girth. C:11 M:24 T:9 V:9 Z:0	m	53		
	Prepare and apply one coat plaster primer and two coats quality matt acrylic PVA on :				
2	External fibre cement fascia boarding including priming cover strips. C:7 M:11 T:4 V:4	m2	26		
	C:7 M:11 T:4 V:4 Z:0				
3	External fibre cement bargeboard including priming cover strips.	m2	71		
	C:17 M:30 T:12 V:12 Z:0				
	PAINT ON PVC				
	Prepare and apply two coats black PVA paint on:				
4	Vent pipes. C: 15 M: 30 T: 6 V: 6	m2	56		
	Z:0				
					_
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	-
	Bill No. 11 PAINTWORK				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
	I ROVIDIONAL BILLS OF QUANTITIES				

Section No. 2	1	I	I	
SECTION NO.2 - BUILDING WORKS				
Bill No. 11				
PAINTWORK				
COLLECTION				
Total Brought Forward from Page No.	Page No 90		Amount	
	92			
Carried Forward to Summary of Section No. 2		R		
SECTION NO.2 - BUILDING WORKS BIII No. 11 PAINTWORK MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Item No		Quantity	Rate	Amount
"	BILL No. 12			
	EXTERNAL WORKS			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	THE FOLLOWING IN TEMPORARY BARRIERS, SCREENS, ECT.			
	TEMPORARY HOARDING			
	Note: Contractor to price for the taking down and carting away hoarding on completion.			
	Site clearance			
1	Allow for clearing site for the width of 1000mm where fencing runs are to be erected including removing trees, shrubs, etc., not exceeding 200mm girth, grubbing up roots and roughly levelling.	151		
2	External barricade screen, 1800mm high overall, comprising 100-125mm diameter tanalith treated gumpoles planted 650mm deep in ground at 3000mm centres comprising of six strands of 4mm galvanised straining wires (evenly spaced) secured to posts with doubled 2mm galvanised wire inserted through hole in post and turned a minimum of four turns around straining wire and yellow and orange barrier shade cloth fixed to straining wires with 20Mpa mass concrete base size 400 x 400 x 550mm thick with sloping top surface			
	including all necessary excavations, backfilling, risk of collapse and carting away surplus material, etc.	151		
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 12 EXTERNAL WORKS MAYIBENYE SSS		R	
	PROVISIONAL BILLS OF QUANTITIES			

ı		1	1	11	1
	Hot dipped galvanised steel gates				
1	Security fence single gate, size 1000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth.	No	1		
2	Security fence double gate, size 5000mm wide x 1800mm high, formed of 80 x 40 x 4mm wall thickness rectangular section framing all round with mitred and welded angles and diagonal cross brace, the gate covered with mesh security fencing secured with "Howgring" clips applied with "Howgring" pliers at 300mm centres to and including six rows of straining wires and yellow/orange barrier shade cloth.	No	1		
	DEMOLITIONS AND SITE CLEARANCE				
	<u>Demolitions</u>				
	Brickwork building structures				
3	Demolish and cart away single storey toilet block complete, size on plan 2000mm long x 1500mm wide x approximately 3000mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, with facebrick, plastered and painted walls, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1		
4					
4	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	1		
5	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max. 150mm layers and compact to 95% MOD AASHTO density.	No	1		
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS				
	Bill No. 12 EXTERNAL WORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
	I NOVIGIONAL BILLS OF QUANTITIES				

1	Demolish and cart away single storey toilet block complete, size on plan 2000mm long x 3500mm wide x approximately 3000mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, with facebrick, plastered and painted walls, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1		
2	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	1		
3	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max. 150mm layers and compact to 95% MOD AASHTO density.	No	1		
4	Demolish and cart away single storey toilet block complete, size on plan 5500mm long x 6000mm wide x approximately 3000mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, with facebrick, plastered and painted walls, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	2		
5	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	2		
6	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max 150mm layers and compact to 95% MOD AASHTO density.	No	2		
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	
	Bill No. 12 EXTERNAL WORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

1	Demolish and cart away single storey toilet block complete, size on plan 9500mm long x 4000mm wide x approximately 3000mm high, comprised of corrugated iron roof covering on mono-pitch timber rafters, with facebrick, plastered and painted walls, ground floor concrete surface bed with granolithic floor covering, sanitary fittings, etc. including grubbing up foundations and backfilling holes with material from the stockpiles on site.	No	1		
2	Allow for de-sludging of existing "long drop" pit latrines by means of "honey sucker". The pit latrines are to be completely empty before any other work is carried out.	No	1		
3	Allow for breaking down and removing from site entire pit latrine structure including any structure that may be inside the pit. Demolition is to only commence once the latrine has been completely emptied (elsewhere measured). Backfill existing hole with imported filling in max 150mm layers and compact to 95% MOD AASHTO density.	No	1		
	<u>Walkways</u>				
4	Demolish 125mm thick reinforced concrete surface bed and cart away.	m2	200		
	SITE CLEARANCE				
	Site clearance				
5	Clear the areas to be developed of all rubbish, debris, vegetation, shrubs, bush and small trees not exceeding 200mm girth and remove from site.	m2	845		
6	Strip topsoil, average 200mm thick, including depositing in stockpiles on site for later re-use.	m3	127		
	BULK EXCAVATION, FILLING, ETC				
	Classification of material to be excavated				
	Detailed geotechnical data sheets for the area of the works have been included at the back of these Bills of Quantities dor the Contractor's information.				
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS Bill No. 12				
	EXTERNAL WORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

	OPEN FACE EXCAVATIONS				
1	Open face excavation in earth in cutting and setting aside in spoil heaps for re-use or carting away.	m3	423		
	Carting away of excavated material				
2	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	423		
	Filling				
3	Earth filling from the excavations and/or stockpiles deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density over site.				
		m3	211		
4	G5 Material, selected and supplied by the contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density over site.	m3	169		
	Compaction of surfaces				
5	Rip prepared platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	845		
	<u>Tests</u>				
6	Allow for Mod AASHTO density tests on filling.	No	42		
	THE FOLLOWING IN APRONS				
	EXCAVATIONS FOR FOUNDATIONS, ETC. (Labour intensive)				
	Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away				
7	Reduced levels between buildings, retaining walls, etc.	m3	11		
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS			TX.	+
	Bill No. 12 EXTERNAL WORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

1	Carting away of excavated material	1			
1	Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	11		
	BASECOURSES				
2	G7 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 98% modified AASHTO density under pavings.	m3	11		
3	G5 Base course material, selected and supplied by the Contractor, deposited in layers not exceeding 150mm thick, watered and consolidated to 95% modified AASHTO density under pavings.	m3	11		
	Sundries				
4	Rip reduced platform level and recompact to 93% Mod. A.A.S.H.T.O. density.	m2	72		
	<u>Tests</u>				
5	Allow for Mod AASHTO density tests on filling.	No	7		
	Reinforced concrete 25MPa (19mm stone) in:				
6	Edge thickening.	m3	1		
7	Surface beds cast in panels including temporary formwork.	m3	7		
	Testing				
8	Allow for preparing and curing a set of three test cubes, each size 150mm x 150mm x 150mm and pay all transport and testing costs undertaken by an approved independent laboratory. (Provisional)	Sets	4		
	Surface treatment				
9	Float surface of concrete to a wood float finish.	m2	72		
	Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 12 EXTERNAL WORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			R	_

	Edges, risers, ends and reveals	1			
1	Edge, riser, etc exceeding 300mm high.	m	101		
	Movement joints				
	To horizontal surfaces				
2	Form toggle joint in concrete surface not exceeding 300mm thick including applying one coat of whitewash or bitumen to one face.	m	18		
3	10mm Thick closed cell polyethylene joint forming material with hinged blocking piece, not exceeding 300mm wide, between concrete and concrete or brickwork surfaces.	m	50		
4	Remove hinged blocking piece and fill 10 x 10mm top surface cavity with "Sikaflex Pro2HP" or other equal approved two part polyurethane sealer.	m	50		
	Carried to Collectio	n		R	
	SECTION NO.2 - BUILDING WORKS Bill No. 12 EXTERNAL WORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
					J

	REINFORCEMENT (PROVISIONAL)				
	High tensile welded steel mesh reinforcement:				
1	Ref: 395 cast into concrete surfaces.	m2	72		
	SHEET WATERPROOFING				
	350 Micron orange polyethylene sheeting :				
2	Laid under solid floor.	m2	72		
					_
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	-
	Bill No. 12 EXTERNAL WORKS				
	MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				

Section No. 2	1			
SECTION NO.2 - BUILDING WORKS				
Bill No. 12				
EXTERNAL WORKS				
COLLECTION				
	Page		Amount	
Total Brought Forward from Page No.	No 94			
Total Blought Forward Holli Fage No.	95			
	96			
	97			
	98			
	99			
	100			
	101			
				_
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS		R		<u></u>
Bill No. 12 EXTERNAL WORKS				
MAYIBENYE SSS				
PROVISIONAL BILLS OF QUANTITIES				

Item No			Quantity	Rate	Amount
	BILL No. 13	1			
	EXTERNAL PLUMBING & DRAINAGE				
	Note:				
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).				
	THE FOLLOWING IN SUB-SURFACE WATER DRAINAGE				
	PIPEWORK, ETC.				
	Pipes, pipe fittings, etc.				
	HDPE Corrugated single wall perforated subsoil drainage pipe laid in trenches not exceeding 1000mm deep including all necessary excavation, backfilling, etc.				
1	160mm Pipes.	m	100		
	Extra over HDPE pipes for fittings :				
2	Extra for 160mm stop ends.	No	20		
3	Extra for 160mm bend.	No	30		
4	Extra for 160mm junction.	No	10		
	Pipe insulation and protection				
5	"Kaymat U24" or equally approved needle punched nonwoven polyester geotextile filter jacket laid vertically behind retaining blocks wall.	m2	120		
6	19mm Crushed stone aggregate in surround to pipe, size overall 300 x 300mm.	m	100		
	Carried to Collection			R	
	SECTION NO.2 - BUILDING WORKS BIII No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			· · ·	

THE FOLLOWING IN SOAKAWAYS					
Soakage pits, french drains, etc. (Labour intensive)					
Excavations					
Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away					
Surface trenches.	m3	96			
Excavations in earth of more difficult character					
Extra over excavations in earth for excavation in soft rock.	m3	10			
Extra over excavations in earth for excavation in hard rock.	m3	5			
Carting away of excavated material					
Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor.	m3	72			
Risk of collapse of excavations					
Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc.	m2	224			
Keeping excavations free of water					
Allow for keeping the excavations free from water.		Item			
<u>Filling</u>					
Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density.	m3	24			
19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere).	m3	72			
Carried to Collection			R		
SECTION NO.2 - BUILDING WORKS BIII No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES					
	Excavations Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away. Surface trenches. Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. Extra over excavations in earth for excavation in hard rock. Carting away of excavated material Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. Risk of collapse of excavations Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. Keeping excavations free of water Allow for keeping the excavations free from water. Filling Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density. 19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere). Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS	Soakage pits, french drains, etc. (Labour intensive) Excavations Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Surface trenches. m3 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations in earth for excavation in hard rock. m3 Extra over excavations of excavation spoil heaps and cart away to a dumping site to be located by the Contractor. m3 Risk of collapse of excavations Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. m2 Keeping excavations free of water Allow for keeping the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density. m3 19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere). m3 Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS	Soakage pits, french drains, etc. (Labour intensive) Excavations Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away Surface trenches. m3 96 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 10 Extra over excavations in earth for excavation in hard rock. m3 5 Carting away of excavated material Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. m3 72 Risk of collapse of excavations Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. m2 224 Keeping excavations free of water Allow for keeping the excavations free from water. Item Filling Earth filling from the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod AASHTO dry density. m3 24 19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere). m3 72 Carried to Collection SECTION NO.2 - BUILDING WORKS Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS	Excavations	Soakage pits, french drains, etc. (Labour intensive) Excavations Excavate in earth not exceeding 2m deep including trimming sides, levelling and ramming bottoms and deposit in spoil heaps for later re-use or cart away. Surface trenches. m3 96 Excavations in earth of more difficult character Extra over excavations in earth for excavation in soft rock. m3 10 Extra over excavations in earth for excavation in hard rock. m3 5 Carting away of excavated material Load surplus or unsuitable material from spoil heaps and cart away to a dumping site to be located by the Contractor. m3 72 Risk of collapse of excavations Allow for risk of collapse to sides of excavations not exceeding 1.5m deep including all necessary timber shoring, etc. m2 224 Keeping excavations free of water Allow for keeping the excavations and/or stockpiles in backfilling to trenches, column bases, etc., compacted to 93% Mod ASHTO dry density. m3 24 19mm Uniformly graded and washed concrete stone laid loose on filter fabric (elsewhere). R Carried to Collection R EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS

	Filter fabric				
1	Grade 3 needle punched non-woven synthetic fibre filter fabric laid in bottom of chamber.	m2	320		
	Carried to Collection SECTION NO.2 - BUILDING WORKS			R	-
	Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS				
	PROVISIONAL BILLS OF QUANTITIES				

	Pipes, pipe fittings, etc.				1
	UTL420 PVC Perforated slotted heavy duty pipe				
1	110mm Diameter pipe laid in trench (elsewhere).	m	40		
	<u>Testing</u>				
2	Allow for testing the soil drainage and sewer plumbing installation in accordance with the National Building Regulations.		ltem		
					+
	Carried to Collection SECTION NO.2 - BUILDING WORKS	n		R	<u> </u>
	Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES				
	I NOVIGIONAL BILLS OF QUANTITIES				

Section No. 2		1		
SECTION NO.2 - BUILDING WORKS				
Bill No. 13				
EXTERNAL PLUMBING AND DRAINAGE				
COLLECTION				
COLLECTION Total Brought Forward from Page No.	Page No 103 104 105 106		Amount	
Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 13 EXTERNAL PLUMBING AND DRAINAGE MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R		

Item No		Quantity	Rate	Amount
	BILL No. 14			
	TEMPORARY FACILITIES			
	Note:			
	For Preambles see "PW 371 - A Edition 2.1 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (Edition 2.1 July 2014).			
	PROVISION OF TEMPORARY TOILETS DURING THE CONSTRUCTION PERIOD			
	Portable toilets			
1	Supply and erecting of the portable chemical toilet during the duration of the contract.	5		
2	Servicing and maintain the five portable chemical toilets on a weekly basis during duration of the contract. (No = week)	24		
3	Removal of the portable chemical toilet on completion of the contract.	5		
	Carried Forward to Summary of Section No. 2 SECTION NO.2 - BUILDING WORKS Bill No. 14 TEMPORARY FACILITIES MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

	Section No. 2			
	SECTION NO.2 - BUILDING WORKS			
Bill No	SECTION SUMMARY - SECTION NO.2 - BUILDING WORKS	Page No		Amount
1	EARTHWORKS	49		
2	CONCRETE, FORMWORK AND REINFORCEMENT	54		
3	MASONRY	59		
4	WATERPROOFING	62		
5	ROOF COVERING	65		
6	CARPENTRY AND JOINERY	72		
7	IRONMONGERY	76		
8	METALWORK	79		
9	PLASTERING	82		
10	PLUMBING AND DRAINAGE (PROVISIONAL)	89		
11	PAINTWORK	93		
12	EXTERNAL WORKS	102		
13	EXTERNAL PLUMBING AND DRAINAGE	107		
14	TEMPORARY FACILITIES	108		
	Carried to Final Summary SECTION NO.2 - BUILDING WORKS MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	

Item No		Quantity	Rate	Amount
3	SECTION NO.4 - PROVISIONAL SUMS , BUDGETARY ALLOWANCES, ECT.			
	BILL NO.1			
	Note:			
	For Preambles see "PW 371 - A Edition 2.0 - Construction Works: Specifications, General Specification" as published by the Department of Public Works (2nd Edition July 2013).			
	PROVISIONAL SUM			
	COMMUNITY LIAISON OFFICER (CLO)			
1	Provide the sum of R 39 000.00 (Thirty Nine Thousand Hundred Rand) for the employment of a CLO.(R 6 500.00 per month x contract period allowance)	Item		39,000.00
2	Add for profit on the above if required.	Item		
	SMME PACKAGES			
	EXTERNAL WORK SMME PACKAGE			
3	Provided the Provisional sum of R 1 300 000.00 (One Million Four Hundred Thousand Rand) for the external works SMME External Works Package to be detailed and appointed at a later stage.	Item		950,000.00
4	Add for profit on the above @ 5%.		%	
5	Allow for attendance on the above @ 5%		%	
	Carried to Final Summary SECTION NO.3 - PROVISIONAL SUMS, BUDGETARY A Bill No. 1		R	
	PROVISIONAL SUMS, BUDGETARY ALLOWANCES,EC MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES			

1	FINAL SUMMARY	1		1
Section No		Page No		Amount
1	SECTION NO.1 - PRELIMINARIES AND GENERAL	43		
2	SECTION NO.2 - BUILDING WORKS	109		
3	SECTION NO.3 - PROVISIONAL SUMS, BUDGETARY ALLOWANCES,ECT.	110		
	Sub-Total		R	
	CONTINGENCY PROVISIONS			
	The Tenderer is to allow hereunder for 5 (Five) percent of the Nett Builders Work Sub-Total to be used as a Budgetary Provision for construction contingencies of a general nature and for the finalisation of design detailing. This sum, or any portion thereof, shall be expended at the sole discretion of the Principal Agent. Any residual balance remaining subsequent to such expenditure shall be deducted in its entirety from the Contract Sum.	%		
	Sub - Total		R	
	Add Value - Added Tax at the rate applicable as at Tender closing date.		R	
	Sub - Total		R	
	Credit for old materials for demolition/alterations.	Item		
	Carried to Form of Tender MAYIBENYE SSS PROVISIONAL BILLS OF QUANTITIES		R	