

PROVINCIAL SHARED SERVICES CENTRE: GAUTENG, 524 STANZA BOPAPE STREET, ANCARDIA, PRETORIA, ACARDIA, PRIVATE BAG X09, HARTFIELD, 0028; Tel: 012 337 3600

REQUEST FOR QUOTATION: CASE NO :006-02-2024

SUBJECT: THE SIGHTING, DRILLING AND EQUIPPING AND TESTING OF A BOREHOLE ON PORTION 30 OF THE FARM WACHTENBIETJIESKOP SITUATED 506 JR, SITUATED IN BRONJHORSTSPRUIT UNDER TSHWANE METROPOLITAN MUNICIPALITY, GAUTENG PROVINCE.

	1				
PROJECT:	SIGHTING, DRILLING AND EQUIPPING OF A BOREHOLE				
SITUATED	WACHTENBITJIESKOP ALONG R25 ROAD LEADING TO GROBLERSDAL)				
DISTRICT	TSHWANE METROPOLITAN MUNICIPAL	LITY			
PROVINCE	GAUTENG PROVINCE				
DESCRIPTION:	THE SIGHTING, DRILLING AND EQUIPPI ON PORTION 30 OF THE FARM WACHT SITUATED IN BRONJHORSTSPRUIT UND MUNICIPALITY, GAUTENG PROVINCE.	ENBIETJIESKOP SITUATED 506 JR,			
SCM CONTACT PERSON:	JANE MPEPELE	ABSALOM MAREMA			
	012 337 3700 / 071 878 9095 OR	(012) 337 3634			
	Jane.mpepele@dalrrd.gov.za	amarema@dalrrd.gov.za			
ENQUIRIES RELATING TO	Mr. G Tharaga	Kgaugelo Ramoabi			
THE SCOPE OF WORK/	Tel: (012) 337 3751 OR	(012) 337 3698			
THE SCOPE OF WORK)	Cell: 071 878 9655	071 878 8524			
TECHNICAL	Email:gabriel.tharaga@dalrrd.gov.za	kgaugelo.ra@dalrrd.gov.za			
ADDRESS FOR SUBMISSION	DEPARTMENT OF AGRICULTURE, LAND REFORM AND RURAL DEVELOPMENT: PSSC:GP 524 STANZA BOPAPE STREET (CNR STANZA BOPAPE AND STEVE BIKO) SUNCARDIA BUILDING ,6 TH FLOOR PRETORIA (ARCADIA) FOR ATTENTION: JANE MPEPELE OR ABSALOM MAREMA				
COMPULSORY QUOTATION	Date: 01 MARCH 2024				
CLARIFICATION MEETING	Venue: Wachtenbietjieskop Farm, (+/-R25)	10km from Bronkhorstspruit, off			
	Coordinates: 25°48'59.2"S				
	28°48'16.8"E				
	Time: 11H00				
VALIDITY PERIOD	90 DAYS FROM THE CLOSING DATE				
CLOSING DATE AND TIME	11 MARCH 2024				

1 EMPLOYER'S OBJECTIVES

This invitation is for the appointment of a service provider for the sighting, drilling and equipping and testing of a borehole at Portion 30 of the Farm Wachtenbietjieskop 506 JR, situated in Bronkhorstspruit under Tshwane metropolitan municipality, Gauteng Province.

2 PROJECT DESCRIPTION

2.1 SCOPE OF WORK

The Department of Agriculture, Land Reform and Rural Development wishes to appoint a suitably qualified Service Provider for the sighting, drilling, equipping and testing of a borehole for Portion 30 of the Farm Wachtenbietjieskop 506 JR under Tshwane metropolitan municipality, Gauteng province.

2.2 INTRODUCTION

2.2.1 The main purpose of this document is to outline the detailed design specifications and Bill of quantities (BOQ) required for the Sighting, drilling equipping and testing of a borehole for the farm Wachtenbietjieskop 506 JR. The farm is occupies about (9,5) hectares, with three (3) households housing about twelve (12) beneficiaries. The farm is used for both residential and grazing purpose. The borehole is therefore for human consumption and livestock drinking.

2.3 SAFETY PRECAUTIONS FOR SITE WORKERS

- 2.3.1 It is the responsibility of the Contractor that the team on site is aware of all health and safety procedures and policies. The construction site must have an updated set of policies and procedures regarding safety and health. Contractors and personnel without the required Personnel Protective Equipment (PPE) must not be allowed on site. Specifications mentioned in the SABS 1200 series must be complied with. The following regulations must be strictly adhered to in order to ensure worker safety:
 - Minimum wearing apparel All site workers involved in the Drilling and Equipping of the borehole must wear as a minimum protection the following: full length pants and short sleeve shirt or t-shirt. Cutoffs, tank tops, or modified shirts, etc., are not acceptable wearing apparel.
 - Foot protection All site workers must wear safety boots to protect their feet and ankles.
 - Eye protection Workers must wear protective goggles or protective spectacles.
 - Skin protection Workers must wear protective gloves.
 - Ear protection Heavy duty ear plugs.
 - A basic medical kit must be available on A basic medical kit must be available on site.

2.4 BOREHOLE SPECIFICATIONS

APPLICABLE STANDARDS AND PARTICULAR SPECIFICATIONS

All construction notes, instructions, references, requirements, and preparations of works are detailed in the Quantity Schedule provided below. The detailed required works are as detailed in the following subsections of this chapter. It is essential that quality products be used on the Borehole, thus all material must comply with specifications set by the South African National Standards institute. Installation and construction work to be done according to the following standards:

SABS 1200

1200 1200 A	A AA -	-	General General (Small Works)
1200	ΑB	_	Engineer's Office
1200	С	-	Site Clearance
1200	D	-	Earthworks
1200	DB	-	Earthworks (Pipe Trenches)
1200	G	-	Concrete (Structural)
1200	GΑ	-	Concrete (Small Works)
1200	Н	-	Structural Steelwork
1200	L	-	Medium Pressure Pipelines
1200	LB	-	Bedding (Pipes)

SANS Standards

SANS 10268 of Thermoplastics- Welding Processes

SANS 12176 Plastic Pipes and Fittings: Equipment for fusion jointing polyethylene systems: Butt Fusion

SANS 4427 Plastic Piping Systems – Polyethylene (PE) pipes and fittings for water supply

SANS 10269 Welding of Thermoplastics – Testing and approval of welders

SANS 10270 Welding of Thermoplastics – Approval of welding procedures and welds

SANS 6269Welding of Thermoplastics – Test methods for welded joints SANS10299:2003 -Development, Maintenance and Management of Groundwater Resources

Variations and additions to the SABS 1200 Standardised Specifications are given in Section in the specification/ pricing schedule.

Copies of the above listed SABS specifications are not bound into this document but may be purchased by Tenderers at their own cost from :-

SA Bureau of Standards Private Bag X191 PRETORIA 0001

For all Building Works, the latest edition (1999) of the "Model Preambles for Trades" as recommended and published by the Association of South African Quantity Surveyors shall apply. This Standardised Specification is

not bound into this Document but may be purchased by Tenderers from the Master Builders Association, Natal Building Centre, 40 Essex Terrace, Westville (031 - 266 70706).

In the event of any discrepancy between the "Model Preambles for Trades" and the SABS 1200 Standardised Specifications or Project Specifications, the SABS 1200 Standardised and Project Specifications shall take precedence.

2.5. WORKS SPECIFICATION

2.5.1. Temporary Works

Contractor's offices, storage sheds, latrines, barricading of Works shall be located in an approved position and subject to the approval of all authorities concerned. Safety & Security of the contractor's temporary works shall be to his own discretion. The safety of the Employer and Employer's staff will also be the responsibility of the Main Contractor. All reasonable steps should be taken to ensure the safety of all persons on site. The Contractor shall make his own arrangements with the necessary authorities for the supply of electricity and telephones.

2.5.2. Site Activities

- Site Establishment
- Sighting two possible positions, Providing a sighting Report.
- Drilling up to 150 metres deep, Steel Casing up to the drilled depth
- Excavation for HDPE pipe, 300mm deep,300 meters from the Borehole.
- Supply and Lay 50 mm class 10 HDPE pipe, 300metres from the borehole to the existing tank.
- Backfill for pipes and provide concrete pipe marking.
- Supply and Install stand pipes.

2.6. DESIGN SCHEDULE OF QUANTITIES

2.6.1 A detailed project schedule of quantities for the Sighting, Drilling and Equipping of a Borehole is as below.

NOTE: Site briefing is compulsory. Only quote for applicable expectation as indicated during site briefing, only actuals will be paid for. Quotation per item must include supply, delivery, and installation.

2.6.2 Location

The site located as follows:

Local Municipality	Nearest Town	Co-ordinates	Nature of Work
Tshwane	Bronkhorstspruit	25°48'59.2"S	Construction
Metropolitan	-	28°48'16.8"E	

3 CONTRACT DATA

3.1 CONTRACT DATA AND STANDARD CONDITIONS OF TENDER

CONDITIONS OF CONTRACT

The General Condition of Contract for Construction Works (2015), published by the South African Institution of Civil Engineering, is applicable to this Contract. Copies of these conditions of contract may be obtained from the South African Institution of Civil Engineering (Tel 011-805 5947)

REF	VARIATIONS AND ADDITIONS TO COND	TIONS OF THE					
CLAUSE No.	CONTRACT						
1.1.1.13	The Defect Liability Period is 12 months.						
1.1.1.14	The time for achieving practical completion is 2 months.						
1.1.1.15	Name of Employer: Department of Agricultu						
	Rural Development						
1.2.1.2	Address of Employer:						
	Physical	Postal					
	524 Stanza Bopape,	Private Bag X09					
	Cnr Stanza Bopape & Steve Biko Str	Hatfield,					
	PRETORIA	PRETORIA					
	0083	0028					
	The Pricing strategy is Re-measurable Con-	tract.					
5.3.1	The Documentation required before comme	encement with Works					
	execution are:						
	Health and Safety Plan (Refer to Clause 4.3	3)					
	Initial program (Refer to Clause 5.6)						
	Security (Refer to Clause 6.2)	Security (Refer to Clause 6.2)					
	Insurance (Refer to Clause 8.6)						
5.3.2	The time to submit documentation required before commencement						
	with Works execution is 14 Calendar days.						
5.4.2	•	The access and possession of Site shall not be exclusive to the					
	Contractor but as set out in the Site information.						
5.8.1	The non-working days are Sundays.						
	The special non-working days are:						
	All statutory holidays as declared by national	al or Regional					
	Government.						
		he year –end break commencing on the first working day after 15					
	December and ending on the first working day after 01 January of						
	the next year.						
5.13.1	The penalty for failing to complete the Work	e is: the lesser of					
5.15.1	The penalty for failing to complete the Works is: the lesser of						
	R1500.00 or 1/20 of 1% of the offered total of prices excluding VAT per calendar day"						
5.16.3	The latent defect period is 12 months.						
0.10.0	ADD FOLLOWING						
6.3.1		I he approved by the					
0.0.1	Variations that have financial implication will be approved by the department in line with the departmental approved Supply Chain						
	Management Delegation of Authority.	provou ouppry oriain					
	management belegation of Authority.						

1	
	Contingencies: Contingencies are under the sole control of the
	department and upon approval in line with the departmental
	approved Supply Chain Management Delegation of Authority.
6.10.3	The limit of retention money is 10% of the net tender amount.
8.2.1	The Contractor shall protect the Works properly and shall so arrange his operations that the minimum danger and inconvenience are caused to the public and vehicle and pedestrian traffic. For this purpose, he shall, inter alia, provide and maintain sufficient roads sign, lights, barricades, fencing, and guarding as may be necessary or required by the engineer or by any act, regulation, or statutory authorities.
	All operations required in connection with the execution and completion of the works and temporary works shall, as far as the provisions for the Contract permit, not unnecessarily or in any improper manner encroach upon the use of public roads or upon access to private property and the Contractor hereby indemnifies the employer against any claims, demands, damage and cost that may arise in this regard.
	Compensation for such obligations shall be included in the Contractors prices for provision and general costs, except in as provision is made in the specifications for payment in respect of specific items pertaining to those obligations.
8.6.1.1.2	The value of plant and materials supplied by the Employer to be included in the insurance sum is nil.
8.6.1.3	The limit of indemnity for liability insurance is R 0.00

SECTION B: DATA TO BE PROVIDED BY CONTRACTOR

CONDITION OF CONTRACT

The General Conditions of Contract for Construction Works (2010), published by the South African Institution of Civil Engineering, is applicable to this Contract. Copies of these conditions of contract may be obtained from the South African Institution of Civil Engineering (Tel 011-805 5947).

REF CLA	AUSE No.	
1.1.1.1 9	Name of Contractor	
1.2.1.2	Address of Contractor: Physical: Postal e-mail: Telephone no: Fax No:	
6.2.1	The security to be provided by the Contractor shafollowing:	all be one of the
	Types of security (VAT shall be excluded from the Contract Sum and the value of the works for calculating the percentage)	Contractor's choice (Indicate "Yes" or "No")
	Retention of 10% of the Contract Sum	
	Performance guarantee of 10% of the Contract Sum plus retention of 5% of the value of the works.	

1.2.1	Employer: DEPARTMENT OF AGRICULTURE LAND REFORM AND RURAL DEVELOPMENT AND LAND REFORM						
	Postal address:	Private Bag X09 Hatfield 0001					
	Physical address: Biko Str	524 Stanza Bopape, Cnr Stanza Bopape & Steve					
		PRETORIA					
		0083					
	Telephone no: E-mail:	012 337 3700 <u>Jane.Mpepele@dalrrd.gov.za</u> or <u>Absolom.Marema@dalrrd.gov.za</u>					

1.2.2 Project Manager:

Name: Gabriel Tharaga Postal address: Private Bag X09

Hatfield 0028

Telephone no: 012 337 3751 Mobile no: 082 970 2027

E-mail: gabriel.tharaga@dalrrd.gov.za

OR

NAME: Kgaugelo Ramoabi Postal address: Private Bag X09

Hatfield 0028

Telephone no: 012 337 3698 Mobile no: 072 878 8524

E-mail: kgaugelo.ra@dalrrd.gov.za

4 EVALUATION CRITERIA

Tenders will be evaluated in terms of the evaluation criteria stipulated below:

- (a) Evaluation for mandatory criteria
- (b) Evaluation in terms of 80/20 preference point system as prescribed in the Preferential Procurement Regulations 2022.

(a) EVALUATION FOR MANDATORY CRITERIA

- i) Only those Tenderers who are registered with the CIDB in a contractor grading designation equal to or higher than a contractor grading designation determined in accordance with the sum tendered for a 2CE or Higher Class of construction work, are eligible to submit tenders.
- ii) Attendance of the Compulsory Tender Clarification meeting as stipulated above.
- iii) Correction in terms of price must not be made by means of a correction fluid such as Tippex or similar product. If correction fluid has been used on any specific item price, such item will not be considered. No correction fluid must be used in a Bill of Quantities where prices are calculated to arrive at a total amount. If correction fluid has been used the task order as a whole will not be considered.
- iv) In the event of mistakes having been made on the Form of Offer it must be crossed out in ink and be accompanied by an initial at each and every price alteration.
- v) Form of offer must be completed and signed by duly authorized person.
- vi) Attach a Compensation for Occupational Injuries and Diseases Act (COIDA) for Building and Construction, with Department of Labour or with a licensed compensation insurer. A Tenderer who presently do not have any labour in their employ must submit a Tender Letter obtainable from the Department of Labour.

NOTE: Additional Required Documents (Not for elimination/disqualification) a) Valid Tax Clearance Certificate and/or SARS issued pin code.

TAX COMPLIANCE STATUS

Bids received from bidders with a non- compliant tax status may be disqualified with failure to update the Tax Status within 7 days.

(b) <u>EVALUATION IN TERMS OF 80/20 PREFERENCE POINT SYSTEM AS PRESCRIBED IN THE PREFERENTIAL PROCUREMENT REGULATIONS</u> 2022.

Apply the **80/20 Preference Point system** where a maximum of Eighty (80) tender adjudication points will be awarded for price. Twenty (20) points will be awarded for preference in terms of the Preferential Procurement Policy Framework Act (Act 5 of 2000) and Preferential Procurement Regulation, 2022

POINTS AWARDED FOR PRICE

A maximum of 80 points is allocated for price on the following basis:

80/20

$$Ps = 80\left(1 + \frac{Pt - P\,max}{P\,max}\right)$$

Where

Ps = Points scored for price of tender under consideration

Pt = Price of tender under consideration

Pmax = Price of highest acceptable tender

In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in table 1 below

In cases where organs of state intend to use Regulation 3(2) of the Regulations, which states that, if it is unclear whether the 80/20 or 90/10 preference point system applies, an organ of state must, in the tender documents, stipulate in the case of—

- (a) an invitation for tender for income-generating contracts, that either the 80/20 or 90/10 preference point system will apply and that the highest acceptable tender will be used to determine the applicable preference point system; or
- (b) any other invitation for tender, that either the 80/20 or 90/10 preference point system will apply and that the lowest acceptable tender will be used to determine the applicable preference point system, then the organ of state must indicate the points allocated for specific goals for both the 90/10 and 80/20 preference point system.

Specific goals for the tender and points claimed are indicated per the table below. (Note to organs of state: Where either the 90/10 or 80/20 preference point system is applicable, corresponding points must also be indicated as such.

Note to tenderers: The tenderer must indicate how they claim points for each preference point system.)

The specific goals allocated points in terms of this tender	Number of points allocated (90/10 system) (To be completed by the organ of state)	Number of points allocated (80/20 system) (To be completed by the organ of state)	Number of points claimed (90/10 system) (To be completed by the tenderer)	Number of points claimed (80/20 system) (To be completed by the tenderer)
Who had no franchise in national				
elections before the 1983 and 1993 Constitution				
Who is female				
Who has a disability				
Specific goal: Youth				

5. PRICING SCHEDULES

Item	Description	Unit	Quantity	Rate	Amount
	BILL NO.1				
1	PRELIMINARIES AND GENERAL				
1.1	FIXED CHARGE AND TIME-RELATED ITEMS				
1.1.1	Contractual Requirements	L. Sum	1		
1.2	CONTRACTOR'S FACILITITES ON SITE				
1.2.2	Site Establishment including all General & Contractual Obligations (not limited to Offices, fencing of camp, water, ablution, setting up and removal of machines) as well as setting up for the				
	drill rig and equipment's required.	L. Sum	1		
1.2.3	Name Board as per drawing no J16 009-C-1001	L. Sum	1		
1.2.4	De-establishment of site after completion	L. Sum	1		
1.3	TIME-RELATED ITEMS				
1.3.1	Health and Safety Compliance with latest regulations	L. Sum	1		
1.4	SUMS STATED PROVISIONALLY				
1.4.1	Remuneration of Community Liaison Officer (CLO) for duration the Contract	Month	2	7500	15 000,00
1.4.2	Handling in terms of Item 1,4,1 above	%			
1.4.3	Additional test required by the engineer	Prov.Sum	1		10 000,00
	Total Carried To Summary				

Item	Description	Unit	Quantity	Rate	Amount
	BILL NO. 02: FARM BOREHOLE				
	SIGHTING OF A BOREHOLE A sighting report to be submitted	No	2		
2.2	BOREHOLE DRILLING				
2.2.1	Drilling 165 mm diameter Rotary Air Percussion	m	150		
2.2.2.1 2.2.2.2 2.2.2.3	Drilling 165 mm diameter using Odex Method 0 to 99 100 to 149 150 to 200	m m m			Rate Only Rate Only Rate Only
2.3	STEEL CASING (Maximum depth according to Formation)				
2.3.1	Plain/Perforated (165mm Diameter, 4mm thickness)	m	150		
241	YIELD TEST Minimum 6h constant rate test, Report to be submitted to the Project Manager	ltem	1		
2.5	WATER QUALITY TEST				
	Indicate whether for human and animal consumption accordance with to SANS 24- 2006 or latest. A report to be submitted to the engineer	ltem	1		
76	EQUIPPING THE BOREHOLE WITH A SUBMERSIBLE				
	PUMP Specifications (submersible pump) to be designed according to the yield test [refer to minimum discharge and minimum head] and consumption need. Inclusive of the following: Solar panels with mounting stand, and accessories. Submersible cable Lockable starter box with lighting, dry run overload phase failure, reversal and imbalance protection (three phase). Position to be confirmed by the engineer. The starter box must be waterproof. Joint kit/connector Nylon draw up rope/cable Cable Tie Heavy duty nylon zip cable Galvanised sockets Base plate galvanised socket brass non return valve	ltem	1		
2.7	Allow for Registration of the bore hole with the Department of Water Affairs (DWA)	ltem	1		
	Total carried Forward				

Item	Description	Unit	Quantity	Rate	Amount
	Total Brought Forward				
	BILL NO.03: EXTERNAL WORKS				
3.1	WATER STORAGE, RETICULATION, TRENCHING PIPEWORK AND FITTINGS INCLUDING EXCAVATIONS				
3.1.1	400mm deep excavation for laying pipes etc, including backfill	m	300		
3.1.2	50mm class 10 HDPE, from the pipe to the tank including class 3 HDPE elbows, water troughs, float valves and all necessary fittings to complete 400mm deep including backfill	m	300		
3.1.3	Supply and installation of 3m high steel tank stands, refer to the attached drawing for details,	No	2		
3.1.4	Supply and installation of two 5 000 I water tanks anchored on the steel tank stands. Four (4) Pad footing (1000x1000x500mm) for each tank stand reinforced with Y12 bars @225mm c/c along the length and width of the pad.	No	2		
3.1.5	Supply and installation of two (2) tap water system with 1.5m x 1.5m x 0.075m of concrete class 25/19 for each tank. Provision of 19-25 diameters stones around the platform 50mm thick 1m extended from the platform	No	2		
3.1.6	Supply and installation of a 2 500 l water tank anchored on the concrete slab 2m x 2m x 0.2m of concrete class 25/19 reinforced with 200x200x8.0mm W/Mesh Ref 395. Provision of 19-25mm stones 50mm thick 2m extended around the concrete slab perimeter	No	1		
3.1.7	Supply and installation of a 500 I water trough anchored on a concrete slab of 4m x 2m x 0.15m of concrete class 25/19 reinforced with 200x200x5.6mm W/Mesh Ref 193. Provision of 19-25mm stones 50mm thick 2m extended around the concrete slab perimeter	No	1		
3.2	BOREHOLE INSTALLATION CONFIGURATION PROTECTION				
3.2.1	Construct a 1.6m x 1,0m x 1,8m protection structure for the submersible pump/borehole installation using a 50 x 50 x 8mm angle mild steel iron bolted in the concrete base, with 5mm x welded diamond mesh, covered with 0,5mm IBR sheeting riveted on the angle iron, complete with lockable door	No	1		
	Total Carried Forward				

Item	Description	Unit	Quantity	Rate	Amount
	Total Brought Forward				
3.3	Electricity Supply				
3.3.1	Supply and commission a suitable portable generator, as the yield requires, connecting the new submersible pump with the existing electricity connection. (Rate to include all fittings and circuit breakers etc. required to connect the new submersible pump to the existing electric connection with a C.O.C certificate)	Prov. Sum	1	R20 000.00	R20 000.00
3.3.2	Handling in terms of Item 3,3,1 above.	%			
3.3.3	Supply, installation and testing of 16 mm ² copper cable, including 10mm bare copper earth wire (Main to Borehole)	m	200		
3.3.4	Supply, installation and testing of 35 mm ² copper cable, including 16mm bare copper earth wire	m	200		
	Total carried To Summary				

SUMMARY PAGE

Bill No	Description	Page no	Amount
	•		
1	Preliminaries & General	12	
2	Farm borehole	13	
3	External Works	14 + 15	
	Subtotal		
	Add 10% Contingency Sum		
	Subtotal		
	Add 15% VAT		
	Total Offer (VAT incl.)		

FORM OF OFFER AND ACCEPTANCE

FORM OF OFFER AND ACCEPTANCE (AGREEMENT)

OFFER

THE SIGHTING, DRILLING AND EQUIPPING AND TESTING OF A BOREHOLE ON PORTION 30 OF THE FARM WACHTENBITJIESKOP SITUATED 506 JR, SITUATED IN BRONJHORSTSPRUIT UNDER TSHWANE METROPOLITAN MUNICIPALITY, GAUTENG PROVINCE.

The Employer, identified in the Acceptance signature block, has solicited offers to enter into a contract in respect of the following works:

The Bidder, identified in the Offer signature block below, has examined the documents listed in the Bid Data and addenda thereto as listed in the Bid Schedules, and by submitting this Offer has accepted the Conditions of Bid.

By the representative of the Bidder, deemed to be duly authorised, signing this apart of this Form of Offer and Acceptance, the Bidder offers to perform all of the obligations and liabilities of the Contractor under the relative Contract including compliance with all its terms and conditions according to their true intent and meaning for an amount to be determined in accordance with the Conditions of Contract identified in the quotation.

THE OFFERED TOTAL OF THE PRICES INCLUSIVE OF VALUE ADDED TAX IS

	Rand <i>[in words]</i> ;
R	[in figures],
(Should there be a discr shall govern.)	epancy between the amount in words and the amount in figures then the amount in figures
Acceptance and return stated in the Bid Dat	repted by the Employer by signing the Acceptance part of this Form of Offer and ning one copy of this document to the Bidder before the end of the period of validity a, whereupon the Bidder becomes the party named as the Contractor in the tidentified in the quotation.
period between the is	that no other matter whether in writing, oral communication or implied during the sue of the Bid documents and the receipt by the Bidder of a completed signed t shall have any meaning or effect in the contract between the parties arising from
FOR THE TENDERER Signature(s)	₹:
Name(s)	
Capacity	
Name and Signature Of Witness	(Name and address of organisation)
Date	Witness 1 Witness 2 Employer Witness 1 Witness 2

BIDDER'S DISCLOSURE

1. PURPOSE OF THE FORM

Any person (natural or juristic) may make an offer or offers in terms of this invitation to bid. In line with the principles of transparency, accountability, impartiality, and ethics as enshrined in the Constitution of the Republic of South Africa and further expressed in various pieces of legislation, it is required for the bidder to make this declaration in respect of the details required hereunder.

Where a person/s are listed in the Register for Tender Defaulters and / or the List of Restricted Suppliers, that person will automatically be disqualified from the bid process.

2. Bidder's declaration

- 2.1 Is the bidder, or any of its directors / trustees / shareholders / members / partners or any person having a controlling interest1 in the enterprise, employed by the state?

 YES/NO
- 2.1.1 If so, furnish particulars of the names, individual identity numbers, and, if applicable, state employee numbers of sole proprietor/ directors / trustees / shareholders / members/ partners or any person having a controlling interest in the enterprise, in table below.

Full Name	Identity Number	Name of State institution

1 the power, by one person or a group of persons holding the majority of the equity of an enterprise, alternatively, the person/s having the deciding vote or power to influence or to direct the course and decisions of the enterprise.

2 Joint venture or Consortium means an association of persons for the purpose of combining their expertise, property, capital, efforts, skill and knowledge in an activity for the execution of a contract. With any person who is employed by the procuring institution? YES/NO

2.2.1	If so, furnish particulars:	
2.3	partners or any person having a conterest in any other related enterp	tors / trustees / shareholders / members / ontrolling interest in the enterprise have any orise whether or not they are bidding for this YES/NO
2.3.1	If so, furnish particulars:	

3 DECLARATION

,	the	undersigned
(name)		in submitting
the accompanying bid, do here	by make the following statements	
hat I certify to be true and com	plete in every respect:	

- 3.1 I have read and I understand the contents of this disclosure;
- 3.2 I understand that the accompanying bid will be disqualified if this disclosure is found not to be true and complete in every respect;
- 3.3 The bidder has arrived at the accompanying bid independently from, and without consultation, communication, agreement or arrangement with any competitor. However, communication between partners in a joint venture or consortium2 will not be construed as collusive bidding.
- 3.4 In addition, there have been no consultations, communications, agreements or arrangements with any competitor regarding the quality, quantity, specifications, prices, including methods, factors or formulas used to calculate prices, market allocation, the intention or decision to submit or not to submit the bid, bidding with the intention not to win the bid and conditions or delivery particulars of the products or services to which this bid invitation relates.
- 3.4 The terms of the accompanying bid have not been, and will not be, disclosed by the bidder, directly or indirectly, to any competitor, prior to the date and time of the official bid opening or of the awarding of the contract.
- 3.5 There have been no consultations, communications, agreements or arrangements made by the bidder with any official of the procuring institution in relation to this procurement process prior to and during the bidding process except to provide clarification on the bid submitted where so required by the

institution; and the bidder was not involved in the drafting of the specifications or terms of reference for this bid.

3.6 I am aware that, in addition and without prejudice to any other remedy provided to combat any restrictive practices related to bids and contracts, bids that are suspicious will be reported to the Competition Commission for investigation and possible imposition of administrative penalties in terms of section 59 of the Competition Act No 89 of 1998 and or may be reported to the National Prosecuting Authority (NPA) for criminal investigation and or may be restricted from conducting business with the public sector for a period not exceeding ten (10) years in terms of the Prevention and Combating of Corrupt Activities Act No 12 of 2004 or any other applicable legislation.

I CERTIFY THAT THE INFORMATION FURNISHED IN PARAGRAPHS 1, 2 and 3 ABOVE IS CORRECT.

I ACCEPT THAT THE STATE MAY REJECT THE BID OR ACT AGAINST ME IN TERMS OF PARAGRAPH 6 OF PFMA SCM INSTRUCTION 03 OF 2021/22 ON PREVENTING AND COMBATING ABUSE IN THE SUPPLY CHAIN MANAGEMENT SYSTEM SHOULD THIS DECLARATION PROVE TO BE FALSE.

Signature	Date
Position	Name of bidder

PREFERENCE POINTS CLAIM FORM IN TERMS OF THE PREFERENTIAL PROCUREMENT REGULATIONS 2022

PRICE QUOTATION PROCESS (UP TO R 1 MILLION)

This preference form must form part of all tenders invited. It contains general information and serves as a claim form for preference points for specific goals.

NB: BEFORE COMPLETING THIS FORM, TENDERERS MUST STUDY THE GENERAL CONDITIONS, DEFINITIONS AND DIRECTIVES APPLICABLE IN RESPECT OF THE TENDER AND PREFERENTIAL PROCUREMENT REGULATIONS, 2022

1. **DEFINITIONS**

- (a) "tender" means a written offer in the form determined by an organ of state in response to an invitation to provide goods or services through price quotations, competitive tendering process or any other method envisaged in legislation;
- (b) "price" means an amount of money tendered for goods or services, and includes all applicable taxes less all unconditional discounts;
- (c) "rand value" means the total estimated value of a contract in Rand, calculated at the time of tender invitation, and includes all applicable taxes;
- (d) "tender for income-generating contracts" means a written offer in the form determined by an organ of state in response to an invitation for the origination of income-generating contracts through any method envisaged in legislation that will result in a legal agreement between the organ of state and a third party that produces revenue for the organ of state, and includes, but is not limited to, leasing and disposal of assets and concession contracts, excluding direct sales and disposal of assets through public auctions;
- (e) "the Act" means the Preferential Procurement Policy Framework Act, 2000 (Act No. 5 of 2000); and
- (f) "Historically Disadvantaged individuals" means a person historically disadvantaged by unfair discrimination on the basis of race: Provided that a person historically disadvantaged on the basis of race refers to Africans, Coloureds, Indians and people of Chinese descent who are South African citizens by birth or descent; or who became citizens of the Republic of South Africa by Naturalisation -
- Before 27 April 1994; or
- On or after 27 April 1994 and who would have been entitled to acquire citizenship by naturalization prior to that date.

2. GENERAL CONDITIONS

- 2.1 The following preference point systems are applicable to invitations to tender:
 - the 80/20 system for requirements with a Rand value of up to R50 000 000 (all applicable taxes included); and

2.2 To be completed by the organ of state

- a) The applicable preference point system for this tender is the 80/20 preference point system.
- b) 80/20 preference point system will be applicable in this tender. The lowest/ highest acceptable tender will be used to determine the accurate system once tenders are received.
- 2.3 Points for this tender (even in the case of a tender for income-generating contracts) shall be awarded for:
 - (a) Price; and
 - (b) Specific Goals.

2.4 To be completed by the organ of state:

The maximum points for this tender are allocated as follows:

	POINTS
PRICE	80
SPECIFIC GOALS	20
Total points for Price and SPECIFIC GOALS	100

- 2.5 Failure on the part of a tenderer to submit proof or documentation required in terms of this tender to claim points for specific goals with the tender, will be interpreted to mean that preference points for specific goals are not claimed.
- 2.6 Tenderers that fail to claim points for specific goals or that fail to fully complete the table in paragraph 2.12 below, will not be awarded points for specific goals.
- 2.7 Tenderers that make a calculation error when claiming points as per the table in paragraph 2.12 below, will not be awarded points for specific goals. Please take note of the examples on how to calculate points for specific goals as per paragraph 2.12 below.
- 2.8 Tenderers that fail to submit the correct SBD 6.1 form as issued by the Department of Agriculture, Land Reform and Rural Development, will not be awarded points for specific goals.
- 2.9 The organ of state reserves the right to require of a tenderer, either before a tender is adjudicated or at any time subsequently, to substantiate any claim in regard to preferences, in any manner required by the organ of state.

- 2.10 Tenderers who wish to claim points in terms of the table in paragraph 2.12 below need to provide proof for each point claimed as guided below:
- 2.10.1 Historically Disadvantaged individuals (HDI):
 - Attach a copy of Identity Document (ID) and company registration document.

2.10.2 Who is female:

Attach a copy of Identity Document (ID) and company registration document.

2.10.3 Who has a disability:

- Attach a certified copy or original doctor's letter confirming the disability.
- 2.10.4 Who is youth (a person that is not older than 35 years on the closing date of a bid):
- Attach a copy of Identity Document (ID) and company registration document.
 - 2.11 The Department will use the Central Supplier Database and documents submitted by the tenderer to verify the points claimed for specific goals.
 - 2.12 Specific goals for the tender and points claimed are indicated per the table below.

(Note to organs of state: Where either the 90/10 or 80/20 preference point system is applicable, corresponding points must also be indicated as such.

Note to tenderers: The tenderer must indicate how they claim points for each preference point system.)

The specific goals allocated points in terms of this tender	Number of points allocated (80/20 system)	Percentage ownership equity (To be completed by the tenderer)	Number of points claimed (80/20 system) (To be completed by the tenderer)
I. HDI	10		
II. Who is female	5		
III. Who has a disability	2		
IV. Specific goal: Who is youth	3		

The number of points claimed for specific goals, are calculated as follow:

- (I) A maximum of 10 points may be allocated to tenderers who had no franchise in national elections before the 1983 and 1993 Constitution, on the following basis:
 - •Percentage ownership equity x 10 ÷ 100 = number of points claimed.
- (II) A maximum of 5 points may be allocated for to tenderers who is female, on the following basis:
 - •Percentage ownership equity x 5 ÷ 100 = number of points claimed.
- (III) A maximum of 2 points may be allocated to tenderers who has a disability, on the following basis:
 - •Percentage ownership equity x 2 ÷ 100 = number of points claimed.
- (IV) A maximum of 3 points may be allocated to tenderers who are youth, on the following basis:
 - **Percentage ownership equity** x 3 ÷ 100 = number of points claimed.
- 2.13 It is important to note that failure by a tenderer to complete the table in paragraph 2.12 in full, will result in points for specific goals not to be allocated.
- 3. FORMULAE FOR PROCUREMENT OF GOODS AND SERVICES
- 3.1. POINTS AWARDED FOR PRICE
- 3.1.1 THE 80/20 PREFERENCE POINT SYSTEMS

A maximum of 80 points is allocated for price on the following basis:

80/20

$$Ps = 80 \left(1 + \frac{Pt - P max}{P max} \right)$$

Where

Ps = Points scored for price of tender under consideration

Pt = Price of tender under consideration

Pmax = Price of highest acceptable tender

3.2. FORMULAE FOR DISPOSAL OR LEASING OF STATE ASSETS AND INCOME GENERATING PROCUREMENT

3.2.1. POINTS AWARDED FOR PRICE

A maximum of 80 points is allocated for price on the following basis:

80/20

$$Ps = 80 \left(1 + \frac{Pt - P max}{P max} \right)$$

Where

Ps = Points scored for price of tender under consideration

Pt = Price of tender under consideration

Pmax = Price of highest acceptable tender

4. POINTS AWARDED FOR SPECIFIC GOALS

- 4.1. In terms of Regulation 4(2); 5(2); 6(2) and 7(2) of the Preferential Procurement Regulations, preference points must be awarded for specific goals stated in the tender. For the purposes of this tender the tenderer will be allocated points based on the goals stated in the table in paragraph 2.12 above as may be supported by proof/documentation stated in the conditions of this tender.
- 4.2. In cases where organs of state intend to use Regulation 3(2) of the Regulations, which states that, if it is unclear whether the 80/20 or 90/10 preference point system applies, an organ of state must, in the tender documents, stipulate in the case of—
- (a) an invitation for tender for income-generating contracts, that either the 80/20 or 90/10 preference point system will apply and that the highest acceptable tender will be used to determine the applicable preference point system; or
- (b) any other invitation for tender, that either the 80/20 or 90/10 preference point system will apply and that the lowest acceptable tender will be used to determine the applicable preference point system,
 - then the organ of state must indicate the points allocated for specific goals for both the 90/10 and 80/20 preference point system.
- 4.3 A consortium or joint venture may, based on the percentage of the contract value managed or executed by their members, be entitled to claim points in respect of specific contract participation goals.
- 4.4 A tenderer will not be awarded points for HDI if it is indicated in the tender documents that such a tenderer intends sub-contracting more than 25% of the value of the contract to any other enterprise that does not qualify for the same number or more points for equity ownership.
- 4.5 A tenderer awarded a contract as a result of preference for contracting with, or providing equity ownership to a HDI, may not subcontract more than 25% of the value of the contract to a tenderer who is not a HDI or does not qualify for the same number or more preference for equity ownership.

5.	QI I	\mathbf{R}_{-}	\sim	\cap	NTF	Λ	CT	'IN	C
IJ.	JU	Ю-	•	יוע	4 I C	м	C I	11.4	U

5.1	Will any portion of the contract be sub-contracted?
	(Tick applicable box)

YES	NO	

5.1.1 If yes, indicate	е	(
------------------------	---	---

İ	What percentage of the contract will be subcontracte	ed:%

ii) The name of the sub-contractor:

iii) Points claimed for HDI by the sub-contractor:

6. DECLARATION WITH REGARD TO COMPANY/FIRM

6.1.	Name of compa	any/firm:				
------	---------------	-----------	--	--	--	--

6.2. Company registration number:

6.3. TYPE OF COMPANY/ FIRM

Partnership/Joint Venture / Consortium
One-person business/sole propriety
Close corporation
Public Company
Personal Liability Company
(Pty) Limited
Non-Profit Company
State Owned Company

[TICK APPLICABLE BOX]

- 6.4. I, the undersigned, who is duly authorised to do so on behalf of the company/firm, certify that the points claimed, based on the specific goals as advised in the tender, qualifies the company/ firm for the preference(s) shown and I acknowledge that:
 - i) The information furnished is true and correct;
 - ii) The preference points claimed are in accordance with the General Conditions as indicated in paragraph 1 of this form;
 - iii) In the event of a contract being awarded as a result of points claimed as shown in paragraphs 1.4 and 4.2, the contractor may be required to furnish documentary proof to the satisfaction of the organ of state that the claims are correct;
 - iv) If the specific goals have been claimed or obtained on a fraudulent basis or any of the conditions of contract have not been fulfilled, the organ of state may, in addition to any other remedy it may have –
 - (a) disqualify the person from the tendering process;

- (b) recover costs, losses or damages it has incurred or suffered as a result of that person's conduct;
- (c) cancel the contract and claim any damages which it has suffered as a result of having to make less favourable arrangements due to such cancellation;
- (d) been applied recommend that the tenderer or contractor, its shareholders and directors, or only the shareholders and directors who acted on a fraudulent basis, be restricted from obtaining business from any organ of state for a period not exceeding 10 years, after the audi alteram partem (hear the other side) rule has; and
- (e) forward the matter for criminal prosecution, if deemed necessary.

•••						
SIGNATURE(S) OF TENDERER(S)						
SURNAME AND NAME:						
DATE:						
ADDRESS:						



Private Bag X84, PRETORIA, 0001, the dti Campus, 77 Meintjies Street, Sunnyside, 0002, Tel: (012) 394 0000 the dti Customer Contact Centre local: 0861 843 384 International: +27 12 394 9500, www.thedti.gov.za

SBD 6.2

Guidance Document for the Calculation of Local Content

1. DEFINITIONS

Unless explicitly provided in this guideline, the definitions given in SATS 1286:2011 apply.

2. GENERAL

2.1. Introduction

This guideline provides tenderers with a detailed description of how to calculate local content of products (goods, services and works) by components/material/services and enables them to keep an updated record for verification requirements as per the SATS 1286:2011

Annexure A and B.

The guideline consists of two parts, namely:
□ a written guideline; and□ three declarations that must be completed:
□ Declaration C: "Local Content Declaration – Summary Schedule" (see Annexure C);
□ Declaration D: "Imported Content Declaration – Supporting Schedule to Annex C" (see Annexure D); and
□ Declaration E: "Local Content Declaration – Supporting Schedule to Annex C" (see Annexure E).

The guidelines and declarations should be used by tenderers when preparing a tender. A tenderer must complete Declarations D and E, and consolidate the information on Declaration C.

Annexure C must be submitted with the tender by the closing date and time as determined by the Tender Authority. The Tender Authority reserves the right to request that Declarations D and E also be submitted. If the tender is successful, the tenderer must continuously update Declarations C, D and E with actual values for the duration of the contract.

NOTE:

Annexure A is a note to the purchaser in SATS 1286:2011; and Annexure B is the Local Content Declaration IN SATS 1286:2011.

2.2. What is local content?

According to SATS 1286:2011, the local content of a product is the tender price less the value of imported content, expressed as a percentage. It is, therefore, necessary to first compute the imported value of a product to determine the local content of a product.

2.3. Categories: Imported and Local Content

components/material/services is separated into two categories, namely:
□ products imported directly by the tenderer; and
□ products imported by a third party and supplied to the tenderer.

2.3.1. Imported Content

Identify the imported content, if any, by value for products by component/material/services. In the case of components/materials/services sourced from a South African manufacturer, agent, supplier or subcontractor (i.e. third party), obtain that information and Declaration D from the third party.

Calculate the imported content of components/materials/services to be used in the manufacture of the total quantity of the products for which the tender is to be submitted.

As stated in clause 3.2.4 of SATS 1286:2011: "If information on the origin of components, parts or materials is not available, it will be deemed to be imported content." 2.3.1.1. Imported directly by the tenderer:

When the tenderer imports products directly, the onus is on the tenderer to provide evidence of any components/materials/services that were procured from a non-domestic source. The evidence should be verifiable and pertain to the tender as a whole. Typical evidence will include commercial invoices, bills of entry, etc.

When the tenderer procures imported services such as project management, design, testing, marketing, etc and makes royalty and lease payments, such payments relating to the tender must be included when calculating imported content.

2.3.1.2. Imported by a third party and supplied to the tenderer: When the tenderer supplies components/material/services that are imported by any third party (for example, a domestic manufacturer, agent, supplier or subcontractor in the supply chain), the onus is on the tenderer to obtain verifiable evidence from the third party.

The tenderer must obtain Declaration D from all third parties for the related tender. The third party must be requested by the tenderer to continuously update Declaration D. Typical evidence of imported content will include commercial invoices, bills of entry etc.

When a third party procures imported services such as project management, design, testing, marketing etc. and makes royalty and lease payments, such payments relating to the tender must be included when calculating imported content.

2.3.1.3. Exempt Imported Content:

Exemptions, if any, are granted by the Department of Trade and Industry (the DTI). Evidence of the exemptions must be provided and included in

Annexure D.

2.3.2. Local Content

Identify and calculate the local content, by value for products by components/materials/services to be used in the manufacture of the total quantity of the products.

ANNEXURE C

3.1. Guidelines for completing Annexure C: Local Content Declaration – Summary Schedule

Note: The paragraph numbers correspond to the numbers in Annexure C.

C1. Tender Number

Supply the tender number that is specified on the specific tender documentation.

C2. Tender description

Supply the tender description that is specified on the specific tender documentation.

C3. Designated products

Supply the details of the products that are designated in terms of this tender (i.e. buses).

C4. Tender Authority

Supply the name of the tender authority.

C5. Tendering Entity name

Provide the tendering entity name (for example, Unibody Bus Builders (Pty) Ltd).

C6. Tender Exchange Rate

Provide the exchange rate used for this tender, as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

C7. Specified local content %

Provide the specified minimum local content requirement for the tender (i.e. 80%), as per the Standard Bidding Document (SBD) and Municipal

Bidding Document (MDB) 6.2.

C8. Tender item number

Provide the tender item number(s) of the products that have a local content requirement as per the tender specification.

List of items

Provide a list of the item(s) corresponding with the tender item number. This may be a short description or a brand name.

Calculation of local content

C10. Tender price

Provide the unit tender price of each item excluding VAT.

C11. Exempted imported content

Provide the ZAR value of the exempted imported content for each item, if applicable. These value(s) must correspond with the value(s) of column D16 on Annexure D.

C12. Tender value net of exempted imported content

Provide the net tender value of the item, if applicable, by deducting the exempted imported content (C11) from the tender price (C10).

C13. Imported value

Provide the ZAR value of the items' imported content.

C14. Local value

Provide the local value of the item by deducting the Imported value (C13) from the net tender value (C12).

C15. Local content percentage (per item)

Provide the local content percentage of the item(s) by dividing the local value (C14) by the net tender value (C12) as per the local content formula in SATS 1286.

Tender Summary

C16. Tender quantity

Provide the tender quantity for each item number as per the tender specification.

C17. Total tender value

Provide the total tender value by multiplying the tender quantity (C16) by the tender price (C10).

C18. Total exempted imported content

Provide the total exempted imported content by multiplying the tender quantity (C16) by the exempted imported content (C11). These values must correspond with the values of column D18 on Annexure D.

C19. Total imported content

Provide the total imported content of each item by multiplying the tender quantity (C16) by the imported value (C13).

C20. Total tender value

Total tender value is the sum of the values in column C17.

C21. Total exempted imported content

Total exempted imported content is the sum of the values in column

C18. This value must correspond with the value of D19 on Annexure D.

C22. Total tender value net of exempted imported content

The total tender value net of exempt imported content is the total tender value (C20) less the total exempted imported content (C21).

C23. Total imported content

Total imported content is the sum of the values in column C19. This value must correspond with the value of D53 on Annexure D.

C24. Total local content

Total local content is the total tender value net of exempted imported content (C22) less the total imported content (C23). This value must correspond with the value of E13 on Annexure E.

C25. Average local content percentage of tender

The average local content percentage of tender is calculated by dividing total local content (C24) by the total tender value net of exempted imported content (C22).

ANNEXURE D

4.1. Guidelines for completing Annexure D: "Imported Content Declaration – Supporting Schedule to Annexure C"

Note: The paragraph numbers correspond to the numbers in Annexure D.

D1. Tender number

Supply the tender number that is specified on the specific tender documentation.

D2. Tender description

Supply the tender description that is specified on the specific tender documentation.

D3. Designated products

Supply the details of the products that are designated in terms of this tender (i.e. buses).

D4. Tender authority

Supply the name of the tender authority.

D5. Tendering entity name

Provide the tendering entity name (i.e. Unibody Bus Builders (Pty) Ltd).

D6. Tender exchange rate

Provide the exchange rate used for this tender, as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

Table A. Exempted Imported Content

D7. Tender item number

Provide the tender item number(s) of the product(s) that have imported content.

D8. Description of imported content

Provide a list of the exempted imported product(s), if any, as specified in the tender.

D9. Local supplier

Provide the name of the local supplier(s) supplying the imported product(s).

D10. Overseas supplier

Provide the name(s) of the overseas supplier(s) supplying the exempted imported product(s).

D11. Imported value as per commercial invoice

Provide the foreign currency value of the exempted imported product(s) disclosed in the commercial invoice accepted by the South African Revenue Service (SARS).

D12. Tender exchange rate

Provide the exchange rate used for this tender as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

D13. Local value of imports

Convert the value of the exempted imported content as per commercial invoice (D11) into the ZAR value by using the tender exchange rate(D12) disclosed in the tender documentation.

D14. Freight costs to port of entry

Provide the freight costs to the South African Port of the exempted imported item.

D15. All locally incurred landing costs and duties

Provide all landing costs including customs and excise duty for the exempted imported product(s) as stipulated in the SATS 1286:2011.

D16. Total landed costs excl VAT

Provide the total landed costs (excluding VAT) for each item imported by adding the corresponding item values in columns D13, D14 and D15. These values must be transferred to column C11 on Annexure C.

D17. Tender quantity

Provide the tender quantity of the exempted imported products as per the tender specification.

D18. Exempted imported value

Provide the imported value for each of the exempted imported product(s) by multiplying the total landed cost (excl. VAT) (D16) by the tender quantity (D17). The values in column D18 must correspond with the values of column C18 of Annexure C.

D19. Total exempted imported value

The total exempted imported value is the sum of the values in column D18. This total must correspond with the value of C21 on Annexure C.

Table B. Imported Directly By Tenderer

D20. Tender item numbers

Provide the tender item number(s) of the product(s) that have imported content.

D21. Description of imported content:

Provide a list of the product(s) imported directly by tender as specified in the tender documentation.

D22. Unit of measure

Provide the unit of measure for the product(s) imported directly by the tenderer.

D23. Overseas supplier

Provide the name(s) of the overseas supplier(s) supplying the imported product(s).

D24. Imported value as per commercial Invoice

Provide the foreign currency value of the product(s) imported directly by tenderer disclosed in the commercial invoice accepted by the South African Revenue Service (SARS).

D25. Tender rate of exchange

Provide the exchange rate used for this tender as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

D26. Local value of imports

Convert the value of the product(s) imported directly by the tenderer as per commercial invoice (D24) into the ZAR value by using the tender exchange rate (D25) disclosed in the tender documentation.

D27. Freight costs to port of entry

Provide the freight costs to the South African Port of the product(s) imported directly by the tenderer.

D28. All locally incurred landing costs and duties

Provide all landing costs including customs and excise duty for the product(s) imported directly by the tenderer as stipulated in the SATS 1286:2011.

D29. Total landed costs excl VAT

Provide the total landed costs (excluding VAT) for each item imported directly by the tenderer by adding the corresponding item values in columns D26, D27 and D28.

D30. Tender quantity

Provide the tender quantity of the product(s) imported directly by the tenderer as per the tender specification.

D31. Total imported value

Provide the total imported value for each of the product(s) imported directly by the tenderer by multiplying the total landed cost (excl. VAT) (D29) by the tender quantity (D30).

D32. Total imported value by tenderer

The total value of imports by the tenderer is the sum of the values in column D31.

Table C. Imported by Third Party and Supplied to the Tenderer

D33. Description of imported content

Provide a list of the product(s) imported by the third party and supplied to the tenderer as specified in the tender documentation.

D34. Unit of measure

Provide the unit of measure for the product(s) imported by the third party and supplied to tenderer as disclosed in the commercial invoice.

D35. Local supplier

Provide the name of the local supplier(s) supplying the imported product(s).

D36. Overseas supplier

Provide the name(s) of the overseas supplier(s) supplying the imported products.

D37. Imported value as per commercial invoice

Provide the foreign currency value of the product(s) imported by the third party and supplied to the tenderer disclosed in the commercial invoice accepted by SARS.

D38. Tender rate of exchange

Provide the exchange rate used for this tender as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

D39. Local value of imports

Convert the value of the product(s) imported by the third party as per commercial invoice (D37) into the ZAR value by using the tender exchange rate (D38) disclosed in the tender documentation.

D40. Freight costs to port of entry

Provide the freight costs to the South African Port of the product(s) imported by third party and supplied to the tenderer.

D41. All locally incurred landing costs and duties

Provide all landing costs including customs and excise duty for the product(s) imported by third party and supplied to the tenderer as stipulated in the SATS 1286:2011.

D42. Total landed costs excluding VAT

Provide the total landed costs (excluding VAT) for each product imported by third party and supplied to the tenderer by adding the corresponding item values in columns D39, D40 and D41.

D43. Quantity imported

Provide the quantity of each product(s) imported by third party and supplied to the tenderer for the tender.

D44. Total imported value

Provide the total imported value of the product(s) imported by third party and supplied to the tenderer by multiplying the total landed cost (D42) by the quantity imported (D43).

D45. Total imported value by third party

The total imported value from the third party is the sum of the values in column D44.

Table D. Other Foreign Currency Payments

D46. Type of payment

Provide the type of foreign currency payment. (i.e. royalty payment for use of patent, annual licence fee, etc).

D47. Local supplier making the payment

Provide the name of the local supplier making the payment.

D48. Overseas beneficiary

Provide the name of the overseas beneficiary.

D49. Foreign currency value paid

Provide the value of the listed payment(s) in their foreign currency.

D50. Tender rate of exchange

Provide the exchange rate used for this tender as per the Standard Bidding Document (SBD) and Municipal Bidding Document (MBD) 6.2.

D51. Local value of payments

Provide the local value of each payment by multiplying the foreign currency value paid (D49) by the tender rate of exchange (D50).

D52. Total of foreign currency payments declared by tenderer and/or third party

The total of foreign currency payments declared by tenderer and/or a third party is the sum of the values in column D51.

D53. Total of imported content and foreign currency payment

The total imported content and foreign currency payment is the sum of the values in column D32, D45 and D52. This value must correspond with the value of C23 on Annexure C.

5. ANNEXURE E

5.1. Guidelines to completing Annexure E: "Local Content Declaration-Supporting Schedule to Annexure C"

The paragraph numbers correspond to the numbers in Annexure E

E1. Tender number

Supply the tender number that is specified on the specific tender documentation.

E2. Tender description

Supply the tender description that is specified on the specific tender documentation.

E3. Designated products

Supply the details of the products that are designated in terms of this tender (for example, buses/canned vegetables).

E4. Tender authority

Supply the name of the tender authority.

E5. Tendering entity name

Provide the tendering entity name (for example, Unibody Bus Builders (Pty) Ltd) Ltd).

Local Goods, Services and Works

E6. Description of items purchased

Provide a description of the items purchased locally in the space provided.

E7. Local supplier

Provide the name of the local supplier that corresponds to the item listed in column E6.

E8. Value

Provide the total value of the item purchased in column E6.

E9. Total local products (Goods, Services and Works)

Total local products (goods, services and works) is the sum of the values in E8.

E10. Manpower costs:

Provide the total of all the labour costs accruing only to the tenderer (i.e. not the suppliers to tenderer).

E11. Factory overheads:

Provide the total of all the factory overheads including rental, depreciation and amortisation for local and imported capital goods, utility costs and consumables. (Consumables are goods used by individuals and businesses that must be replaced regularly because they wear out or are used up. Consumables can also be defined as the components of an end product that are used up or permanently altered in the process of manufacturing, such as basic chemicals.)

E12. Administration overheads and mark-up:

Provide the total of all the administration overheads, including marketing, insurance, financing, interest and mark-up costs.

E13. Total local content:

The total local content is the sum of the values of E9, E10, E11 and E12. This total must correspond with C24 of Annexure C

DECLARATION CERTIFICATE FOR LOCAL PRODUCTION AND CONTENT FOR DESIGNATED SECTORS (SBD 6.2)

DECLARATION CERTIFICATE FOR LOCAL PRODUCTION AND CONTENT FOR DESIGNATED SECTORS

This Standard Bidding Document (SBD) must form part of all bids invited. It contains general information and serves as a declaration form for local content (local production and local content are used interchangeably).

Before completing this declaration, bidders must study the General Conditions, Definitions, Directives applicable in respect of Local Content as prescribed in the Preferential Procurement Regulations, 2017, the South African Bureau of Standards (SABS) approved technical specification number SATS 1286:2011 (Edition 1) and the Guidance on the Calculation of Local Content together with the Local Content Declaration Templates [Annex C (Local Content Declaration: Summary Schedule), D (Imported Content Declaration: Supporting Schedule to Annex C) and E (Local Content Declaration: Supporting Schedule to Annex C)].

General Conditions

Preferential Procurement Regulations, 2017 (Regulation 8) make provision for the promotion of local production and content.

Regulation 8. (2) prescribes that in the case of designated sectors, organs of state must advertise such tenders with the specific bidding condition that only locally produced or manufactured goods, with a stipulated minimum threshold for local production and content will be considered.

Where necessary, for tenders referred to in paragraph 1.2 above, a two stage bidding process may be followed, where the first stage involves a minimum threshold for local production and content and the second stage price and B-BBEE.

A person awarded a contract in relation to a designated sector, may not sub-contract in such a manner that the local production and content of the overall value of the contract is reduced to below the stipulated minimum threshold.

The local content (LC) expressed as a percentage of the bid price must be calculated in accordance with the SABS approved technical specification number SATS 1286: 2011 as follows:

$$LC = [1 - x / y] * 100$$

Where

x is the imported content in Rand

y is the bid price in Rand excluding value added tax (VAT)

Prices referred to in the determination of x must be converted to Rand (ZAR) by using the exchange rate published by South African Reserve Bank (SARB) at 12:00 on the date of advertisement of the bid as indicated in paragraph 4.1 below.

The SABS approved technical specification number SATS 1286:2011 is accessible on http://www.thedti.gov.za/industrial development/ip.is at no cost.

A bid may be disqualified if this Declaration Certificate and the Annex C (Local Content Declaration: Summary Schedule) are not submitted as part of the bid documentation;

The stipulated minimum threshold(s) for local production and content (refer to Annex A of SATS 1286:2011) for this bid is/are as follows:

STIPULATED MINIMUM THE	RESHOLD FOR LOCAL PRODUCTION AND CONTENT FOR ELECTRICAL
CABLE PRODUCTS	STIPULATED MINIMUM THRESHOLD LOCAL CONTENT
Low Voltage	90%

STIPULATED MINIMUM THRE	SHOLD LOCAL PRODUCTION AND CONTENT FOR PLASTIC PIPES
PRODUCT TYPES	STIPULATED MINIMUM THRESHOLD LOCAL CONTENT
High density polyethylene	100%
(HDPE) pipes	

3.	Does any portion of the goods or services offered
	have any imported content?
	(Tick applicable box)

YES	NO	

3..1 If yes, the rate(s) of exchange to be used in this bid to calculate the local content as prescribed in paragraph 1.5 of the general conditions must be the rate(s) published by SARB for the specific currency at 12:00 on the date of advertisement of the bid.

The relevant rates of exchange information is accessible on www.reservebank.co.za

Indicate the rate(s) of exchange against the appropriate currency in the table below (refer to Annex A of SATS 1286:2011):

Currency	Rates of exchange
US Dollar	
Pound Sterling	
Euro	
Yen	
Other	

NB: Bidders must submit proof of the SARB rate (s) of exchange used.

4. Where, after the award of a bid, challenges are experienced in meeting the stipulated minimum threshold for local content the DTI must be informed accordingly in order for the DTI to verify and in consultation with the AO/AA provide directives in this regard.

LOCAL CONTENT DECLARATION (REFER TO ANNEX B OF SATS 1286:2011)

LOCAL CONTENT DECLARATION BY CHIEF FINANCIAL OFFICER OR OTHER LEGALLY	
RESPONSIBLE PERSON NOMINATED IN WRITING BY THE CHIEF EXECUTIVE OR SENIO	ЭR
MEMBER/PERSON WITH MANAGEMENT RESPONSIBILITY (CLOSE CORPORATION,	
PARTNERSHIP OR INDIVIDUAL)	

IN RESPECT OF BID NO.
ISSUED BY: (Procurement Authority / Name of Institution):
NB

The obligation to complete, duly sign and submit this declaration cannot be transferred to an external authorized representative, auditor or any other third party acting on behalf of the bidder. Guidance on the Calculation of Local Content together with Local Content Declaration Templates (Annex C, D and E) is accessible on http://www.thdti.gov.za/industrial development/ip.jsp. Bidders should first complete Declaration D. After completing Declaration D, bidders should complete Declaration E and then consolidate the information on Declaration C. Declaration C should be submitted with the bid documentation at the closing date and time of the bid in order to substantiate the declaration made in paragraph (c) below. Declarations D and E should be kept by the bidders for verification purposes for a period of at least 5 years. The successful bidder is required to continuously update Declarations C, D and E with the actual values for the duration of the contract.

I, the undersigned,	(full names),
do hereby declare, in my capacity as	
of	
following:	,

The facts contained herein are within my own personal knowledge.

I have satisfied myself that:

the goods/services/works to be delivered in terms of the above-specified bid comply with the minimum local content requirements as specified in the bid, and as measured in terms of SATS 1286:2011: and

The local content percentage (%) indicated below has been calculated using the formula given in clause 3 of SATS 1286:2011, the rates of exchange indicated in paragraph 4.1 above and the information contained in Declaration D and E which has been consolidated in Declaration C:

Bid price, excluding VAT (y)	R
Imported content (x), as calculated in terms of SATS 1286:2011	R
Stipulated minimum threshold for local content (paragraph 3 above)	
Local content %, as calculated in terms of SATS 1286:2011	

If the bid is for more than one product, the local content percentages for each product contained in Declaration C shall be used instead of the table above.

The local content percentages for each product has been calculated using the formula given in clause 3 of SATS 1286:2011, the rates of exchange indicated in paragraph 4.1 above and the information contained in Declaration D and E.


I accept that the Procurement Authority / Institution has the right to request that the local content be verified in terms of the requirements of SATS 1286:2011.


I understand that the awarding of the bid is dependent on the accuracy of the information furnished in this application. I also understand that the submission of incorrect data, or data that are not verifiable as described in SATS 1286:2011, may result in the Procurement Authority / Institution imposing any or all of the remedies as provided for in Regulation 14 of the Preferential Procurement Regulations, 2017 promulgated under the Preferential Policy Framework Act (PPPFA), 2000 (Act No. 5 of 2000).

SIGNATURE:	DATE:
WITNESS No. 1	DATE:
WITNESS No. 2	DATE:

	Annex C			CASE STU	DY ONF						SATS 1286,201
	Ailliex C			CHUL DI O	DIONE						
	V. Harring and	Loc	al Content De	claration -	Summary Sc	hedule					
Tender No. Tender descript Designated proc Tender Authorit Tendering Entity Tender Exchang Specified local of	Auct(s) Office Furniture y: Gauteng Purchasing Department y rame: Rainbow Office Furniture RRate:	USD R 9.00	EU			R 14.00				Note: VAT to be exc calculations	
Tender item no's	list of items	Tender price - each (excl VAT)	Exempted imported value per unit	Tender value net of exempted imported content	cal content	Local value	Local content % (per item)	Tender Qty	Total tender value	er summary Total exempted imported content	Total Imported content
				(C10-C11)	(Annexure D M31+P50+P60)	(C12-C13)	C14/C12		(C10xC16)	Annex D D18	Annex D
(C8)	(0)	(C10)	(C11)	(C12)	(C13)	(C14)	(C15)	(C16)	(C17)	(C18)	(C19)
GP 100011	Melamine Office Desks with Drawers	R 12 000	RO		RO	R 12 000	100%	100		RO	R 123 200
					(Annexure D M34+P50+P60)						
GP 100012	Office desk with drawers on timber top with steel frame	R 15 000.00	R1650.00	R 13 350.00	R 1 232.00	R 12 118.00	91%	50	R 750 000	R 82 500	R 116 850
GP 100013	Side upholstered chair - Sleigh base with arms	R 10 450.00	R 2 170.00	R 8 280.00	R 2 617.00	R 5 663.00	68%	100	R 1045 000	R 217 000	R 261 700
GP 100014	Highback uphoistered chair with arms on 5 star base	R 12 200.00	R 2 720.00	R 9 480.00	R 2 537.00	R 6 943.00	73%	50	R 610 000	R 231 000	R 31 950
		-								50.00	
Signature of ten	derer from Annex B				(C22) 1	otal Tender v		Total Exemp	ot imported content d content (C20-C21)		R 533 700
										al content (C22-C23)	R 2540 800
Date:								(C25) Aver		of tender (C24/C22)	82,64%

EXAMPLE





ELECTRICAL CABLE PRODUCTS – Annex C

(90%) – Refer to the following items in BOQ: Bill No. 3, Item 3.3.2, 3.3.3

			AN	INEX C - LOCAL	CONTENT DECL	ARATION - SUN	ANNEX C - LOCAL CONTENT DECLARATION - SUMMARY SCHEDULE	<u></u>				•
2 2 2 2 2 2 5	C1 TENDER NO:: C2 TENDER DESCRIPTION: C3 DESIGNATED PRODUCT: C4 TENDER AUTHORITY: C5 TENDERING ENTITY NAME: C6 TENDER EXCHANGE RATE: C7 SPECIFIED LOCAL CONTENT %:	ON: VCT: 'NAME: ERATE:	PULA		EU		GBP	NOTE: VATTO BE EXCLUDED FROM ALL CALCULATIONS	CLUDED FROM ALL	CALCULATIONS		,
				CALCULATION OF LOCAL CONTENT	LOCAL CONTENT				TENDER SUMMARY	UMMARY		
TENDER ITEM NO (C8)	LIST OF ITEMS (C9)	TENDER RATE (C10)	EXEMPTED IMPORTED VALUE (C11)	TENDER VALUE NET OF EXEMPTED IMPORTED CONTENT (C12)	IMPORTED VALUE (C13)	IOCAL VALUE (C14)	LOCAL CONTENT% TENDER QUANTITY (C16)	TENDER QUANTITY (C16)	TOTAL TENDER VALUE (C17)	TOTAL EXEMPTED IMPORTED CONTENT (C18)	TOTAL IMPORTED CONTENT (C19)	
												Ŭ
45												
												*
				1	(C20) TOTAL TENDER VALUE	RVALUE			R			
IGNATURE OF TEN	IGNATURE OF TENDERER FROM ANNEX B	X B		-	(C21) TOTAL EXEMP	(C21) TOTAL EXEMPT IMPORTED CONTENT	INT			R		
				1	(C22) TOTAL TENDEI	R VALUE NET OF EXE	(C22) TOTAL TENDER VALUE NET OF EXEMPT IMPORTED CONTENT	NTENT		æ		
		1		1	(C23) TOTAL IMPORTED CONTENT	TED CONTENT					ď	
				1	(C24) TOTAL LOCAL	(C24) TOTAL LOCAL CONTENT (C22-C23)					ĸ	
ATE					(C25) AVG. LOCAL C	(C25) AVG. LOCAL CONTENT % OF TENDER)ER				%	

ELECTRICAL CABLE PRODUCTS – Annex D (90%) – Refer to the following items in BOQ: Bill No. 3, Item 3.3.2, 3.3.3

			EXEMPTED **ORTED VALUE (D18)						TOTAL IMPORTED VALUE (D31)				
		SUMMARY	EXEN IMPORTE (D				œ	SUMMARY					×.
	CALCULATIONS	NUS	EXEMPTED TENDER QUANTITY (D18)				: : -C21	MUS	TENDER QUANTITY (D30)				JERER
	CLUDED FROMALL C		TOTAL LANDED COST EXCL VAT (D16)				r IMPORTED VALUE pond with Annex C		TOTAL LANDED COST EXCL VAT (D29)				TED VALUE BY TEND
TO ANNEX C	NOTE: VAT TO BE EXCLUDED FROMALL CALCULATIONS		ALL LOCALLY INCURRED LANDING COSTS & DUTIES (D15)				(D19) TOTAL EXEMPT IMPORTED VALUE This total mus correspond with Annex C -C21		ALL LOCALLY INCURRED LANDING COSTS & DUTIES (D28)				(D32) TOTAL IMPORTED VALUE BY TENDERER
RTED CONTENT DECLARATION - SUPPORTING SCHEDULE TO ANNEX C]489	CALCULATION OF IMPORTED CONTENT	FREIGHT COSTS TO PORT OF ENTRY (D14)					CALCULATION OF IMPORTED CONTENT	FREIGHT COSTS TO PORT OF ENTRY (D27)				
ION - SUPPORT		CALCULATION OF IN	LOCAL VALUE OF IMPORTS (D13)					CALCULATION OF IN	LOCAL VALUE OF IMPORTS (D26)				
TENT DECLARAT	L B		TENDER EXCHANGE RATE (D12)						TENDER EXCHANGE RATE (D2S)				
MPORTED CON			FOREIGN CURRANCY VALUES AS PER COMMERCIAL INVOICE (D11)						FOREIGN CURRANCY VALUES AS PER COMMERCIAL INVOICE (D24)				
ANNEX D - IMPO	Jeno		OVERSEAS SUPPLIER (D10)						OVERSEAS SUPPLIER (D23)				
	on: UCT: ': NAME: RATE: ONTENT%:		LOCAL SUPPLIER (D9)					8	UNIT OF MEASURE (D22)				
	D1 TENDER NO.: D2 TENDER DESCRIPTION: D3 DESIGNATED PRODUCT: D4 TENDER AUTHORITY: D5 TENDERING ENTITY NAME: D6 TENDER EXCHANGE RATE: D7 SPECIFIED LOCAL CONTENT %:	RTED CONTENT	DESCRIPTION OF IMPORTED CONTENT (D8)					TLY BY THE TENDERE	DESCRIPTION OF IMPORTED CONTENT (D21)				
	0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0 0	A. EXEMPTED IMPORTED CONTENT	TENDER ITEM NO (D7)			46		B. IMPORTED DIRECTLY BY THE TENDERER	TENDER ITEM NO (D20)				

ELECTRICAL CABLE PRODUCTS – Annex E (90%) – Refer to the following items in BOQ: Bill No. 3, Item 3.3.2, 3.3.3

	ANNEX E - LOCAL C	ONTENT DECLAR	NEX E - LOCAL CONTENT DECLARATION - SUPPORTING SCHEDULE TO ANNEX C	ANNEX C
E1 TENDER NO.:			NOTE: VAT TO BE EX	NOTE: VAT TO BE EXCLUDED FROM ALL CALCULATIONS
E2 TENDER DESCRIPTION: E3 DESIGNATED PRODUCT: E4 TENDER AUTHORITY: E5 TENDERING ENTITY NAME:	N: JCT: : VAME:			
LOCAL PRODUCTS (GOODS, SERVICES AND WORKS)	DESCRIPTION OF ITEMS PURCHASED (E6)	MS PURCHASED	LOCAL SUPPLIERS (E7)	VALUE (E8)
1				
ı				
1 1				
1			(E6) TOTALLOCAL PRODUCTS (GOODS, SERVICES AND WORKS)	VICES AND WORKS) R
(E10) MANPOWER COST		(Tenderer's manpower cost)	ver cost)	8
(E11) FACTORY OVERHEADS		(Rental, depreciatio	(Rental, depreciation & amortisation, utility costs, consumables etc.)	()
(E12) ADMINISTRATION OVERHEADS AND MARK-UP (Marketing, insurance, financing, interest etc.)	ERHEADS AND MARK-UP	(Marketing, insuran	ce, financing, interest etc.)	æ
			(E13) TOTAL LOCAL CONTENT This total mus correspond with Annex C-C24	<u>«</u>
SIGNATURE OF TENDERER FROM ANNEX B	ROM ANNEX B			
DATE				

PLASTIC PIPES PRODUCTS - Annex C

(100%) - Refer to the following items in BOQ: Bill No. 3, Item 3.1.2,

	(100%)	– RE) 	er to the fo	IIO'	WIL	ıg ı	ter	IIS	IL)	ВC	JQ:	BI		10.	3,	пе	III .	3. I.	.∠, 		ı	-	ı	1	%	
				TOTAL IMPORTED CONTENT (C19)																				œ	R		
	ALCULATIONS		JMMARY	TOTAL EXEMPTED IMPORTED CONTENT (C18)																		8	~				
	CLUDED FROMALL C		TENDER SUMMARY	TOTAL TENDER VALUE (C17)																	2						
ш	NOTE: VATTO BE EXCLUDED FROM ALL CALCULATIONS			TENDER QUANTITY (C16)																			JTENT				
ANNEX C - LOCAL CONTENT DECLARATION - SUMMARY SCHEDULE		GBP		LOCAL CONTENT% TENDER QUANTITY (C15)																		TN	(C22) TOTAL TENDER VALUE NET OF EXEMPT IMPORTED CONTENT			ER	
ARATION - SUM				LOCAL VALUE (C14)																	R VALUE	(C21) TOTAL EXEMPT IMPORTED CONTENT	R VALUE NET OF EXE	TED CONTENT	(C24) TOTAL LOCAL CONTENT (C22-C23)	(C25) AVG. LOCAL CONTENT % OF TENDER	
CONTENT DECL			LOCAL CONTENT	IMPORTED VALUE (C13)																	(C20) TOTAL TENDER VALUE	(C21) TOTAL EXEMP	(C22) TOTAL TENDE	(C23) TOTAL IMPORTED CONTENT	(C24) TOTAL LOCAL	(C25) AVG. LOCAL C	
NEX C - LOCAL			CALCULATION OF LOCAL CONTENT	TENDER VALUE NET OF EXEMPTED IMPORTED CONTENT (C12)																							
A		PULA		EXEMPTED IMPORTED (C11)																							
	DN: IJCT: Y: 'NAME:	ERATE: ONTENT%:		TENDER RATE (C10)																		ХВ					
	C1 TENDER NO.: C2 TENDER DESCRIPTION: C3 DESIGNATED PRODUCT: C4 TENDER AUTHORITY: C5 TENDERING ENTITY NAME:	C6 TENDER EXCHANGE RATE: C7 SPECIFIED LOCAL CONTENT %:		LIST OF ITEMS (C9)																		SIGNATURE OF TENDERER FROM ANNEX B					
	2 2 2 2 2 2	C7		TENDER ITEM NO (C8)									48									SIGNATURE OF TEN				DATE	

PLASTIC PIPES PRODUCTS – Annex D (100%) – Refer to the following items in BOQ: Bill No. 3, Item 3.1.2,

			EXEMPTED PORTED (D18)							TOTAL IMPORTED VALUE (D31)					
		SUMMARY	EXEN IMPORTE				œ		SUMMARY						۳
	ALCULATIONS	MUS	EXEMPTED TENDER QUANTITY IMPORTED (D12)					:-C21	SUM	TENDER QUANTITY (D30)					ERER
	CLUDED FROM ALL C		TOTAL LANDED COST EXCL VAT (D16)				I IMPORTED VALUE	pond with Annex C		TOTAL LANDED COST EXCL VAT (D29)					IED VALUE BY TEND
O ANNEX C	NOTE: VAT TO BE EXCLUDED FROM ALL CALCULATIONS		ALL LOCALLY INCURRED LANDING COSTS & DUTIES (D15)				(D19) TOTAL EXEMPT IMPORTED VALUE	This total mus correspond with Annex C -C21		ALL LOCALLY INCURRED LANDING COSTS & DUTIES (D28)					(D32) TOTAL IMPORTED VALUE BY TENDERER
NNEX D - IMPORTED CONTENT DECLARATION - SUPPORTING SCHEDULE TO ANNEX C		APORTED CONTENT	ALL LOCALLY INCURRED INCURRED FREIGHT COSTS TO LANDING COSTS & PORT OF ENTRY (D14) (D15)						APORTED CONTENT	LOCAL VALUE OF FREIGHT COSTS TO LANDING COSTS & DOTT OF ENTRY DUTIES (D26) (D27) (D28)					_
ION - SUPPORT		CALCULATION OF IMPORTED CONTENT	LOCAL VALUE OF IMPORTS (D13)						CALCULATION OF IMPORTED CONTENT	LOCAL VALUE OF IMPORTS (D26)					
TENT DECLARAT	Eu_		TEN DER EXCHAN GE RATE (D12)							TENDER EXCHANGE RATE (D25)					
MPORTED CONT			FOREIGN CURRANCY VALUES AS PER COMMERCIAL INVOICE (D11)							FOREIGN CURRANCY VALUES AS PER COMMERCIAL INVOICE (D24)					
ANNEX D - II	PULA		OVERSEAS SUPPLIER (D10)							OVERSEAS SUPPLIER (D23)					
	on: JCT: ': NAME: RATE: ONTENT%:		LOCAL SUPPLER (D9)						R	UNIT OF MEASURE (D22)					
	D1 TENDER NO.: D2 TENDER DESCRIPTION: D3 DESIGNATED PRODUCT: D4 TENDER AUTHORITY: D5 TENDERING ENTITY NAME: D6 TENDER EXCHANGE RATE: D7 SPECIFIED LOCAL CONTENT %:	RTED CONTENT	DESCRIPTION OF IMPORTED CONTENT (D8)						B. IMPORTED DIRECTLY BY THE TENDERER	DESCRIPTION OF IMPORTED CONTENT (D21)					
	01 02 03 04 05 07	A. EXEMPTED IMPORTED CONTENT	TENDER ITEM NO (D7)						B. IMPORTED DIREC	TENDER ITEM NO (D20)					

PLASTIC PIPES PRODUCTS – Annex E (100%) – Refer to the following items in BOQ: Bill No. 3, Item 3.1.2,

				TOTAL IMPORTED CONTENT (C19)														%	
				ED TOTA												œ	œ		
	CALCULATIONS		TENDER SUMMARY	TOTAL EXEMPTED IMPORTED CONTENT (C18)										æ	œ				
	CLUDED FROM ALL		TENDERS	TOTAL TENDER VALUE (C17)									œ						
5	NOTE: VAT TO BE EXCLUDED FROM ALL CALCULATIONS			TENDER QUANTITY (C16)											JTENT				
ANNEX C - LOCAL CONTENT DECLARATION - SUMMARY SCHEDULE		GBP		LOCAL CONTENT % TENDER QUANTITY (C16)										Ā	(C22) TOTAL TENDER VALUE NET OF EXEMPT IMPORTED CONTENT			ER	
ARATION - SUM				LOCAL VALUE (C14)									RVALUE	(C21) TOTAL EXEMPT IMPORTED CONTENT	R VALUE NET OF EXE	TED CONTENT	(C24) TOTAL LOCAL CONTENT (C22-C23)	(C25) AVG. LOCAL CONTENT% OF TENDER	
CONTENT DECL		EU E	CALCULATION OF LOCAL CONTENT	IMPORTED VALUE (C13)									(C20) TOTAL TENDER VALUE	(C21) TOTAL EXEMP	(C22) TOTAL TENDE	(C23) TOTAL IMPORTED CONTENT	(C24) TOTAL LOCAL	(C25) AVG. LOCAL C	
NNEX C - LOCAL			CALCULATION OF	Z															
AI		PULA		EXEMPTED IMPORTED VALUE (C11)															
	on: UCT: Y: NAME:	E RATE: ONTENT %:		TENDER RATE (C10)										ХВ					
	C1 TENDER NO.: C2 TENDER DESCRIPTION: C3 DESIGNATED PRODUCT: C4 TENDER AUTHORITY: C5 TENDERING ENTITY NAME:	C6 TENDER EXCHANGE RATE: C7 SPECIFIED LOCAL CONTENT %:		LIST OF ITEMS (C9)										SIGNATURE OF TENDERER FROM ANNEX B					
	2 2 2 2 5	2 69		TENDER ITEM NO (C8)										SIGNATURE OF TEN				DATE	