



**RAND WATER C2.2. BILLS OF QUANTITIES RFQ10386853 SUPPLY, INSTALL, TEST AND COMMISSION STATION3 SLUDGE VALVES AT ZUIKERBOSCH PUMPING STATION**

The Supplier must complete the following pricing schedule:

	<b>MILESTONES / LINE ITEMS</b>	<b>MINIMUM THRESHOLD FOR LOCAL CONTENT</b>	<b>TIMEFRAME (where applicable)</b>	<b>UNIT PRICE (where applicable)</b>	<b>QUANTITY (where applicable)</b>	<b>COSTING</b>
<b>MANDATORY WORK</b>						
1.	Remove old valves from pipe work				<b>05</b>	
2.	Preparation work on the pipes to fit new valves					
3.	configuration of pipes to accommodate new valves					
4.	Welding work to accommodate the new valves					
5.	Supply and installation new valves including actuators(5 off Knife gate valve DN450, TP15 Rising Spindle, Body: SG42 Epoxy coated. Blade SS304 Gearbox: direct mount Electrical Actuator SAC14.6-45rpm)	<b>70%</b>			<b>05</b>	
6.	PLC intergration(interface the module into the PLC software and configure the module accordingly. )					
7.	Install and wiring new actuator valves according to the existing spec electrical and automation					
8.	Perform the functional test for each valve and actuator					
<b>INSTALL COMMISSION AND HANDOVER</b>						
9.	Testing and commissioning of the valves					
10.	Supply Full Data Package					
<b>TOTAL</b>						
<b>VAT</b>						
<b>TOTAL [VAT INCLUDED]</b>						

Name of Bidder: \_\_\_\_\_

Signed by or on behalf of Bidder: \_\_\_\_\_

Official Capacity: \_\_\_\_\_

Date: \_\_\_\_\_