

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
1	Health & Safety file  <b><u>SECTION 1: ALTERATIONS</u></b>  <b><u>REMOVAL OF EXISTING ROOF COVERINGS</u></b>  <b><u>Taking down and removing flat roofs not exceeding 10 degrees</u></b>	Item	1,00		
2	Profiled asbestos cement roof sheeting from purlins to remain  <b><u>TAKING DOWN OF STEEL FRAMED SHADEPORT INCLUDING STEEL FRAME STRUCTURE COMPLETE</u></b>	m <sup>2</sup>	751,00		
3	Shadeport comprising of 6 parking bays  <b><u>REPAIR AND MAKE GOOD EXISTING STEEL STRUCTURE</u></b>	No.	1,00		
4	Steel columns to parking bays  <b><u>SECTION NO. 2 : BUILDING WORKS</u></b>  <b><u>ROOF COVERINGS</u></b>  <b><u>RIBBED METAL SHEETING AND ACCESSORIES</u></b>  <b><u>IBR steel sheeting and accessories in "Chromadek" 0,50mm thick or other approved "Charcoal " standard colour finish fixed to 75x50x20x2.5mm thick lipped channel purlins and girts at approximately 1400mm and 1325mm centres in strict accordance to manufacturer's instructions:</u></b>	No.	4,00		
5	Flat roof covering for parking area	m <sup>2</sup>	751,00		
6	Horizontal side Cladding  <b><u>INSTATLLATION OF SHADENETS ON EXISTING STEEL FRAME STRUCTURE</u></b>  <b><u>Supply and install shade nets-80% (blue),pulled across steel frame structure to provide shade cover:</u></b>	m <sup>2</sup>	54,00		
7	Shadeport comprising of 30 parking bays				

8	<b><u>ERECTING OF NEW CAR PARKING STEEL STRUCTURE</u></b>  80X80mmx3600mm high Square cubes steel columns welded to 200x200mm base plate bolted to paving surface at approximately 6000mm centres maximum, including 75x50x20x2,5mm thick lipped channel purlins and girts at approximately 1400mm and 135mm centres in strict accordance to manufacturer's instruction. Roof covered in IBR steel sheeting and accessories "Chromadek" 0,5mm thick or other approved "Charcoal" standard colour. parking lot to accommodate 6 Parking bays	No	1,00		
	<b><u>RAIN WATER DISPOSAL</u></b>  <b><u>Pre-Painted aluminium rainwater goods colour charcoal or similar approved:</u></b>  9 150x150mm Ogee eaves gutter with concealed hanger brackets at 600mm centres  10 Extra Over gutter for stopped end.  11 Extra Over gutter for outlet and joint to 100x75mm rain water pipe including grating  12 100 x 75mm x 2450mm stock length down pipe fixed to steel columns with downpipe cleats at 1800mm centres. Downpipe bends and shoe fixed with aluminium rivets	m No. No. No.	100,00 6,00 6,00 6,00		
13	<b><u>BUDGETORY ALLOWANCE</u></b>  Allow for Sum of R30 000.00 Contingency Amount  <b><u>PAINTWORK</u></b>  <b><u>Remove any Loose and flaking residue by means of wire brushing,sand down, wash with "Polycell sugar soap" or weak spirits of salt,rinse spot prime Namelcote Synthetic Metal primer and apply two coats Velvagro Polyurethane enamel paint (White)on previously painted steel.</u></b>				
	14 On structural steel columns,beams,purlins etc	m²	445,00		

	<u>Road Marking Paint:</u>  <u>Prepare surfaces, wash thoroughly, remove loose material, leave to dry and apply three coats 'Promac Aqualine Road Marking' waterborne acrylic road marking paint:</u>				
15	100mm Line on G-Block paving surfaces.	m	636,00		
16	On Concrete kerb	m <sup>2</sup>	40,00		
SUB TOTAL					
VAT@15%					
TOTAL					