Managing Criteria

1. This Criteria is Compulsory
2. The Screen Height of 10,800mm is non-negotiable
   - 2.1. The Height of the Module is to be chosen as such that:
     - 2.1.1. the Screen Height divided by the Module Height must be an integer
     - 2.1.2. the Screen Height divided by the Cabinet Height must be an integer
3. The Screen Width may vary between 23,040mm and 23,200mm
   - 3.1. The Width of the Module is to be chosen as such that:
     - 3.1.1. the Screen Width divided by the Module Width must be an Integer
     - 3.1.2. the Screen Width divided by the Cabinet Width must be an Integer



FRONT VIEW



SIDE VIEW



TOP VIEW

CONSULTING ENGINEER

iX engineers Infrastructure Excellence

eimac consulting engineers

CLIENT

CITY OF CAPE TOWN
ISIXEKO SASEKAPA
STAD KAAPSTAD

NOTES:

1. THESE DRAWINGS ARE INTENDED TO CONVEY PRINCIPLES OF DESIGN AND IS NOT INTENDED AS PRESCRIPTIVE REQUIREMENTS.
2. MODULE OR TILE DESIGNS IN THIS DRAWING IS NOT INTENDED AS PRESCRIPTIVE TO PROPRIETY ELEMENTAL DESIGNS BY MANUFACTURERS
3. ALL MODULES TO BE MAINTAINABLE/INSTALLABLE FROM THE CABINET FRONT OR BACK
4. POSITIONS OF HANDLES & CONNECTOR BLOCKS ARE ONLY INDICATIVE. HANDLES MAY BE FIXED OR DETACHABLE

DRAWING SET KEY

01	LED & PIXEL LAYOUT	06	SECTION THROUGH GL 270
02	MODULE/TILE LAYOUT	07	SCREEN VISIBILITY
03	CABINET LAYOUT		
04	DISPLAY SCREEN LAYOUT	SHEET NO.	REFERENCE DWG. eim.2024-28-20
05	N-E SCREEN TOP VIEW	DESIGN APP:	K VELDSMAN
SHEET NO.	REFERENCE DWG. eim.2024-28-20		Pr Eng 880465
		DATE:	25/11/2024 SIGNATURE

REV	REVISION DESCRIPTION	DRAWN	CHKD	AUTH	DATE
T	TENDER	AH	JV	KV	25/11/2024
00	FIRST ISSUE	AH	JV	KV	01/09/2024

SCALE: NTS

THIS DRAWING IS THE PROPERTY OF EIMAC

AUTH: K VELDSMAN
DATE: 01/09/2024
CHKD: J VILJOEN
DATE: 01/09/2024
DRAWN: A HUMAN
DATE: 01/09/2024

CAPE TOWN DHL STADIUM

PROPOSED NEW OUTDOOR VIDEO DISPLAY SCREENS

MODULE/TILE LAYOUT

Eimac(Pty)Ltd Drawing Number	SET	SHEET	REVISION
eim.2024.28.20	06	02	T

A3L