







PLAN DESCRIPTION	DWG. NO.
CONTINUED FROM	
CONTINUED ON	
CROSS SECTIONS	
TYPICAL CROSS SECTION	
SURVEY LAYOUT	




ISOMETRIC VIEW



PLAN



FRONT VIEW




SIDE VIEWS


BACK VIEW

REINFORCED PRECAST CONCRETE TRANSITION KERB USED WITH TYPE "E" KERBING SCALE:- 1 : 5


TRANSITION KERBS



PEDESTRIAN SCOOPS




VEHICULAR SCOOPS



BARRIER TO MOUNTABLE

PRECAST CONCRETE STD TRANSITION KERBS USED WITH TYPES A,B,C & D KERBING. SCALE:- 1 : 10



LOW PROFILE KERB




FIG. 6 KERB







FIG. 8 KERB

KERB DETAILS




TYPE A : BARRIER KERB AND CAST IN SITU CHANNEL / FILLET (ARTERIAL ROADS) SCALE:- 1 : 10





TYPE B : BARRIER KERB AND CAST IN SITU CHANNEL / FILLET (Channel section shown) SCALE:- 1 : 10


- GENERAL NOTES:-
- ALL CAST IN SITU CONCRETE IS TO BE GRADE 20 / 13.
 - THE SURFACES OF THE CAST IN SITU CHANNEL / FILLET ARE TO HAVE A STEEL FLOAT FINISH.
 - EXPANSION JOINTS TO BE FORMED THROUGH THE KERBING, CHANNEL / FILLET AND FOUNDATIONS AT INTERVALS NOT EXCEEDING 18.0m.
 - CONTRACTION JOINTS TO BE FORMED THROUGH THE CHANNEL / FILLET AT 20m INTERVALS.
 - WHERE KERB RADIUS IS LESS THAN 25m THE KERB LENGTH SHALL BE 300mm. WHERE THE KERB RADIUS IS LESS THAN 2m THE KERBING SHALL BE CAST IN SITU.
 - PRECAST KERBS ARE TO BE LAID WITH A 13mm GAP BETWEEN KERBS, WHICH SHALL THEN BE FILLED WITH A CEMENT MORTAR.
 - EXTRUDED KERBS.
 - ASPHALT KERB: ASPHALT TO COMPLY WITH THE REQUIREMENTS OF CLAUSE EG.3.1
 - CONCRETE KERB:
 - THE CONCRETE IS TO HAVE A CUBE STRENGTH OF 20MPa AT 28 DAYS.
 - THE CONCRETE MIX DESIGN IS TO BE APPROVED BY THE ENGINEER.
 - CONTRACTION JOINTS TO BE FORMED AT 2.0m INTERVALS.
 - EXPANSION JOINTS ARE TO FORMED AT 6.0m INTERVALS ON STRAIGHTS AND 2.0m INTERVALS WHERE THE KERB RADIUS IS LESS THAN 50m.




TYPE D : BARRIER KERB WITH CAST IN SITU CHANNEL / FILLET (MINOR ROADS) SCALE:- 1 : 10




TYPE C : MOUNTABLE KERB & CAST IN SITU CHANNEL / FILLET (Fillet section shown) SCALE:- 1 : 10




TYPE E : SEMI-MOUNTABLE KERB PLACED ON ROAD SURFACE (MINOR ROADS) SCALE:- 1 : 10



TYPE F : MOUNTABLE KERB WITH CAST IN SITU FILLET (MINOR ROADS) SCALE:- 1 : 10



TYPE G : EXTRUDED BARRIER KERB SCALE:- 1 : 5



TYPE H : EXTRUDED MOUNTABLE KERB SCALE:- 1 : 5

NOTE:- WEARING COURSE LAID & THEN CUT BACK TO 150mm FROM FRONT TO KERB PRIOR TO THE FILLET BEING CAST.

Revision	Date	Description

NOTE: No construction work to commence until land and servitude acquisitions have been completed.		
Acquisitions completed		
Date	Engineer	NORTH POINT

UNDERGROUND SERVICES CHECKED		
S.W. DRAWING	DATE	SIGNATURE
SEWERS		
WATER MAINS		
G.P. CABLES		
ELECTRIC CABLES		
S.A.S. CABLES		
E.S.C. CABLES		
OIL PIPE LINE		

NOTE: Only underground services affected by new construction work are shown. It is the responsibility of the contractor to ensure that all services are protected and to avoid damage to underground services such as sewer, electric, gas, water mains and communications. Wherever possible these must be located before work proceeds.

Contract No. _____
Project Title _____

STANDARD DRAWING
Drawing Title _____

Scales	DATE OF ISSUE
AS SHOWN	FEBRUARY 1990
Designed G.J.P.	Date 1995-12-06
Checked _____	Drawn W.R.BURNETT

Manager RD(N) _____
Director : Roads _____

R.A.Moore	Executive Director
Drawing No	38577
Sheet	of Sheets