













 Revisions:
 Date
 Drawn

 C0
 12-11-2024
 D.J.P

PLEASE READ THOROUGHLY!!!

work on site, and any discrepancies to be reported to the Engineer

GENERAL NOTES: 61. All work to be carried out in accordance with the latest issue of SANS 1200 unless noted otherwise.

G2. All setting out to Architect's details. G3 Piles, pile caps, ground beams, footings, and columns are central on grid lines unless Shown otherwise. G4. Contractor to check all dimensions and levels prior to commencing

CONCRETE NOTES:

immediately.

21. Blinding concrete to be placed below all pile caps, ground beams, and footings and shall be a minimum of 50mm thick. C2. Concrete mix design to SANS 10100. Design loads from SANS

10160 and Client's specification. C3. Concrete mix designs to be submitted to Engineer for approval prior

to commencement of work. Only Engineer-approved admixtures to

C4. Foundations designed for a bearing pressure of 80kPa. Refer to DRENNAN, MAUD (PTY) LTD Report Ref. 22649P.

5. All concrete to have a minimum compressive strength at 28 days as

follows: 15 MPa / 25mm 25 MPa / 25mm

30 MPa / 19mm - Surface Beds: 25 MPa / 19mm - Suspended Slabs & Beams: 30 MPa / 19mm

Concrete cover to main reinforcement: Foundations:

- Columns: 30 mm - Surface Beds: 50 mm - Suspended Slabs & Beams:

All concrete work, including formwork stripping times and propping, to SANS 1200-GB. C8. Formwork classification:

- Concealed surfaces: Rough - Exposed surfaces (unless otherwise shown): Smooth (off-shutter) to Grade II tolerances.

- Exposed surfaces (where specified by architect): Smooth-special to SANS 2001-CC1: 4.3.1.8 Table 1. Degree of accuracy I Table 11.

C9. All sharp edges to concrete to have 25mm chamfers. C10. Unformed surface finishes as follows: - Surface Beds: Power-floated - Suspended Slabs: Power-floated

C11. All services and sleeves to be positioned prior to concrete pour. No in situ concrete to be cast without prior approval from the Engineer. C12. The positions of all construction joints not shown on the drawings

are to be discussed with and approved by the Engineer.

REFER TO DRAWING 3119-S20 - GENERAL NOTES IF IN DOUBT, ASK!!!

HEALTH DEPARTMENT SIGNATURES

DEPUTY DIRECTOR GENERAL: HEAD OFFICE PROGRAMME / SERVICE

EO MANAGER OF THE FACILITY:

S. Boyce (Pr. Eng. 20160768)

DRENNAN MAUD (PTY) LTI GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS

Reg. No. 2014/038872/07







SOUTHERN REGION DEPARTMENT OF HEALTH PORT SHEPSTONE HOSPITAL

NEW PSYCHIATRIC WARD

STAIR 3 & 4, RAMP 1 LAYOUT & SECTIONS

As shown

Consultant Drawing number
31319-S18 SH 2 OF 2 WIMS 044 044 / S / 18 / C0
Stamped by Health Plans Approval Committee