



ARC – NRE, WATER SCIENCE

*Agricultural Research Council-Natural Resources and Engineering, Private Bag X79
Pretoria, 0001, South Africa*

CAPEX 2022-2023

Description of Service: Procurement of supply, delivery, and installation of an air-conditioning unit

Description of item	Quantity	Specification.
Supply, delivery, and installation of air-conditioning unit	1	<ul style="list-style-type: none"> Capacity: 60 000 BTU Type: Under ceiling inverter The quote must include 3 metres of pipe between indoor and outdoor ground floor. The quote must include removal of old aircon unit, and any patch-up work (plastering/painting) in the walls/plaster. The quote must be inclusive of all potential costs involved in the entire and aesthetically pleasing installation of the aircon unit. The quote must include a remote control for controlling the unit. Warranty: ≥ 2 years on parts, 5 years on compressor. The aircon plugs into an isolator, and therefore must be installed by an electrician. Quote must include this. Experience: The company should have at least 15 years' experience in air-conditioning unit installations and should enclose proof of experience. <p>The quote must include the supply, delivery, and installation of an air-conditioning unit at Soil, Climate and Water, NRE, Cedara Research Station, KwaZulu-Natal.</p>