

Scope: Renovations to the C- Block male and female toilets from ground floor to fifth floor and passage flooring at second and third floors at SABs Groenkloof site.

Bill of Quantities

Item	Floor number	Description	Qty	Floors	Unit	Total Cost
1	CGM-East Ground to 5th Floor (Male)	Remove existing vinyl tiles and replace with 500x500mm ceramic tile - <i>sample to be provided</i>	21(m2)	6		
		Remove old wash basins and replace with new wash basins with taps	2	6		
		Install new wall mount urinals	2	6		
		Remove Existing toilet pans and replace with new	2	6		
		Demolish & Clear the existing floor cement cast urinal	1	6		
2	CGF-East G-5 Floors (Female)	Remove existing vinyl tiles and replace with 500x500mm ceramic tile - <i>sample to be provided</i>	21(m2)	6		
		Remove old wash basins and replace with new wash basins with taps	2	6		
		Remove Existing toilet pans and replace with new	3	6		
3	CGM-West G-5 Floors (Male)	Remove existing vinyl tiles and replace with 500x500mm ceramic tile - <i>sample to be provided</i>	18(m2)	6		
		Remove Existing toilet pans and replace with new	2	6		
		Remove old wash basins and replace with new wash basins with taps	2	6		
		Install new wall mount urinals	2	6		
		Demolish & Clear the existing floor cement cast urinal	1	6		
		Patch walls and make good to match the existing	1	6		
4	CGF-West G-5 Floors (Female)	Remove existing vinyl tiles and replace with 500x500mm ceramic tile - <i>sample to be provided</i>	18(m2)	6		
		Remove Existing toilet pans and replace with new	2	6		
		Remove old wash basins and replace with new wash basins with taps	2	6		
		Replace all damaged ceiling panel with new to match the existing	18(m2)	1		
5	C2-West	Remove carpet and replace with 600x600mm porcelain floor tile - <i>sample to be provided</i>	36 (m2)	1		
6	C3-East	Remove carpet and replace with 600x600mm porcelain floor tile - <i>sample to be provided</i>	90(m2)	1		
7	Waste disposal		1			
8	Contingency		1			
					TOTAL	