

## **ANNEXURE C3.2: SCOPE OF WORK**

## A) DO THE FOLLOWING WORK AT THE BELOW LISTED:

- 1.ZWARTKOPJES MAINSTORE ROOF AND CUTTERS:
- a) Clean 5 x 500mm x 500mm x 25m steel cutters by means of sandpaper and wire brush.
- b) Seal all gutter joints with roof seal and membrane finally paint all cutter insides with roof seal and membrane ready mix.
- c) Check the entire roof for any defects and fix them.
- d) Apply manually or spray two coats of roof paint with a paint warranty of not less than seven (7) years. (Grey Colour)
- 2.PALMIET ENGINE ROOM 1 & 2 Roofs
- a) Engine Room 1 Palmiet Roof Square Meters = 1650 Engine Room 2 Palmiet Roof Square Meters = 2300
- b) Check both engine room roofs for defects and fix them.
- c) Use a 200mm roof seal membrane and Red Ever-bond roof seal paint
- d) Apply manually or spray two coats of roof paint with a paint warranty of not less than seven (7) years. (Dark Brown)
- 3.ENGINE ROOM 1 ZWARTKOPJES.
- a) Clean 6 x 500mm x 500mm x 60m steel cutters by means of sandpaper and wire brush.
- b) Seal all gutter joints with roof seal and membrane finally paint all cutter insides .
- c)Check the entire roof for any defects and fix them.
- d) Apply manually or spray two coats of roof paint with a paint warranty of not less than seven (7) years. (Dark Brown)



## ZK ENGINE ROOM 3 HARVEY TILE ROOF. (HARVEY TILE ACREDITED INSTALLER)

- a) Roof Area = 40m x 80m (3200 Square meters) Height 20 meters.
- b) Remove all damaged brand rings, facia board, roof ridges, Harvey tiles and remove rubble of site.
- c) Install new 38mm x 38mm brand rings and new 1675mm x 397 Harvey Tiles (Colour Green)
- d) Install new 80m Harvey tile ridges and 40m Harvey tile facia boards.

## NB:

- i) It is the supplier's responsibility to organise own storage. (Including 24hrs security)
- ii) Make sure that your quote includes scaffold, skyjack or cherry picker. (Height of buildings 20 Meter)
- iii) Contractor to include Pest Control if needed to remove bees and wasps to work safely.
- iv) Make sure that safety file cost is included in your quote.
- v) No short cuts or unsafe acts will be tolerated when performing any task on site.