Item No		Quantity	Rate	Amount	
	SECTION 1				
	BILL NO. 1				
	PRELIMINARIES				
	BUILDING AGREEMENT AND PRELIMINARIES				
	The JBCC Series 2000 Edition 4.1 Code 2101 March 2005 2005 edition prepared by the Joint Building Contracts Committee, shall be the agreement, amended as hereinafter described				
	The Preliminaries for use with the JBCC Series 2000 Principal Building Agreement (May 2005 edition) prepared by the Joint Building Contracts Committee, shall be deemed to be incorporated in these bills of quantities				
	Contractors are referred to the above-mentioned documents for the full intent and meaning of each clause thereof				
	These clauses are hereinafter referred to by clause number and heading only. Where standard clauses or alternatives are not entirely applicable to this contract such modifications, corrections or supplements as will apply are given under each relevant clause heading and such modifications, corrections or supplements shall take precedence notwithstanding anything contrary contained in the above-mentioned documents				
	Where any item is not relevant to this specific contract such item is marked N/A, signifying "not applicable"				
	Notwithstanding anything to the contrary contained in any of the contract documents including the Principal Building Agreement and the Preliminaries, the provision of the "Preliminaries" as hereinafter set forth shall prevail and shall take precedence				
	Carried to Collection		R		
	Section 1 Bill No. 1 PRELIMINARIES				_

PREAMBLES FOR TRADES			
The Model Preambles for Trades (1999 edition) as published by the Association of South African Quantity Surveyors shall be deemed to be incorporated in these bills of quantities and no claim arising from brevity of description of items fully described in the said Model Preambles for Trades will be entertained			
Supplementary preambles to the Model Preambles covering clauses of a general nature, clauses pertaining to specific materials and amendments to clauses in the Model Preambles are incorporated in these bills of quantities to satisfy the requirements of this project			
The contractor's prices for all items throughout these bills of quantities must take account of and include for all of the obligations, requirements and specifications given in the Model Preambles and in any supplementary preambles			
GENERAL			
If Alternative A as set out in clause B10.3 hereinafter is to be used for the adjustment of the preliminaries each item priced is to be allocated to one or more of the three categories "F", "T" or "V" as the case may be below such item, where "F" denotes a fixed amount (amount not to be varied), "T" denotes an amount variable in proportion to time and "V" denotes an amount variable in proportion to value			
SECTION A - PRINCIPAL BUILDING AGREEMENT			
<u>Definitions (A1)</u>			
Definitions and interpretation (clause 1)			
F: T:	Item		
Carried to Collection		R	
Section 1			T
Bill No. 1 PRELIMINARIES			

1

	Objective and Preparation (A2 to A14)			
2	Offer acceptance and performance (clause 2)			
	F: T:	Item		
3	Documents (clause 3)			
	F: T:	Item		
4	Design responsibility (clause 4)			
	F: T:	Item		
5	Employer's agents (clause 5)			
	F: T:	Item		
	The principal agent shall:			
	- monitor and control progress and scheduling			
	- monitor all contract conditions, and			
	- coordinate the efforts of the employer's agents, the contractor and subcontractors			
	The powers conferred on the principal agent in terms of this clause and/or the exercising of these powers shall not be construed as removing or diminishing any of the obligations of the Contractor in terms of the Principal Building Agreement, whether financial, contractual or otherwise, nor shall the exercising of these powers create any privity of contract as between the Employer or his agents on the one part and the Contractor or subcontractors or suppliers on the other part			
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	The principal agent reserves the right to attend and participate in all contractor/subcontractor's meetings, to invite other employer's agents to attend such meetings at his discretion and to converse and chair any such meetings if the contractor is derelict in his duty in arranging such meetings to the degree of frequency and comprehensiveness dictated in the opinion of the project manager by the circumstances and exigencies of the construction process			
6	Site representative (clause 6)			
	F: T:	ltem		
7	Compliance with regulations (clause 7)			
	F: T:	Item		
8	Works risk (clause 8)			
	F: T:	Item		
9	Indemnities (clause 9)			
	F: T:	Item		
10	Works insurances (clause 10)			
	F: T:	Item		
11	Liability insurances (clause 11)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

12	Effecting insurance (clause 12)			
	F: T:	Item		
13	NO CLAUSE	N/A		
14	Security (clause 14)			
	F: T:	Item		
	Execution (A15-A23)			
15	Preparation for and execution of the works (clause 15)			
	F: T:	Item		
16	Access to the works (clause 16)			
	F: T:	Item		
17	Contract instructions (clause 17)			
	F: T:	Item		
18	Setting out of the works (clause 18)			
	F: T:	Item		
	The contractor shall notify the principal agent if any encroachments of adjoining foundations, buildings, structures, pavements, boundaries, etc exist in order that the necessary arrangements may be made for the rectification of any such encroachments			
	Carried to Collection		R	 _ <b>_</b>
	Section 1 Bill No. 1 PRELIMINARIES			

19	Assignment (clause 19)			
	F: T:	Item		
	The contractor shall not cede his rights or delegate his obligations in terms of this agreement unless specifically called for by the employer			
20	Nominated subcontractors (clause 20)			
	F: T:	Item		
21	Selected subcontractors (clause 21)			
	F: V: T:	Item		
	Written proof is required from subcontract tenderers at tendering that they can meet the JBCC Selected Subcontract Agreement or other tender agreements and provide security in terms of the agreement. If the above is not provided the tender may not be accepted			
	All amounts allowed under Provisional Amounts are intended to be awarded to Selected Subcontractors			
22	Employer's Direct Contractors (clause 22)			
	F: T:	Item		
23	Contractor's Domestic Sub-Contractors (Clause 23)			
	F: T:	Item		
	Completion (A24-A30)			
24	Practical completion (clause 24)			
	F: V: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

25	Works completion (clause 25)			
	F: T:	Item		
26	Final completion (clause 26)			
	F: T:	Item		
27	Latent defects liability period (clause 27)			
	F: T:	Item		
28	Sectional completion (clause 28)			
	F: T:	Item		
29	Revision of date of practical completion (clause 29)			
	F: T:	Item		
	The removal and replacement of materials and/or workmanship that do not conform to specification or drawings shall not constitute grounds for an extension of the construction period nor for an adjustment to the contract sum (clause 29.3)			
30	Penalty for non-completion (clause 30)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	Payment (A31 - A35)			
31	Interim payment to the contractor (clause 31)			
	F: T:	Item		
32	Adjustment to the contract value (clause 32)			
	F: V: T:	Item		
	Where prices are submitted by the contractor or nominated/selected subcontractors during the progress of the works in respect of contract instructions or in regard to a claim under the terms of the contract and notwithstanding the fact that such prices may be used in an interim payment certificate, there is to be no presumption of acceptance. Should the principal agent wish to accept any such prices prior to the issue of the final certificate, it will be in writing			
33	Recovery of expense and loss (clause 33)			
	F: T:	Item		
34	Final account and final payment (clause 34)			
	F:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	The employer shall, however, pay interest to the contractor at the rate stipulated in clause 34.11 on any amounts payable to the contractor more than one hundred and forty two (142) days after the date of issue of the certificate of practical completion but only for such period as the settlement of the final account is delayed by the non-performance of the principal agent or the employer or his agents. In evaluating non-performance for purposes of this clause a reasonable time shall be allowed to the employer or his agents to respond to any matter brought to his/their attention and which may affect the settlement of the final account			
35	Payment to other parties (clause 35)			
	F: T:	Item		
	Cancellation (A36-A39)			
36	Cancellation by employer - contractor's default (clause 36)			
	F:			
	T:	Item		
37	Cancellation by employer - loss and damage (clause 37)			
	F: T:	Item		
38	Cancellation by contractor - employer's default (clause 38)			
	F: T:	Item		
39	Cancellation - cessation of the works (clause 39)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	Dispute (A40)			
40	Dispute Settlement (clause 40)			
	F:V:			
	T:	Item		
	Substitute Provisions (A41)			
41	State clauses (Clause 41)			
	F: T:	Item		
	Information necessary for the completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder			
	THE SCHEDULE			
	Information necessary for completion of those clauses contained in the schedule which are necessary for tender purposes is given hereunder			
42	Pre-tender information (clause 42)			
	F: T:	Item		
	42.1 CONTRACTING AND OTHER PARTIES			
	42.1.1 Employer: As per infomation on the tender data			
	42.1.2 Principal Agent: As per the infomation on the Tender data			
	42.1.3 Architect:			
	42.1.4 Quantity Surveyor:			
	Carried to Collection		R	
	Section 1			_
	Bill No. 1			
	PRELIMINARIES			
		i		

Structural :		
42.1.5 Civil:		
42.1.6 Electrical Engineer:		
42.1.6 Mechanical Engineer:		
42.2 CONTRACT DETAILS		
42.2.1 Works Description: Construction of sanitation facilities		
42.2.2 Site Description: as per the infomation on the tender data		
42.2.3 Work or installations by direct contractors:  N/A		
42.2.4 This agreement is for a government contract where there are specific options that are applicable to a <b>State</b> organ only  Yes		
42.2.5 Date on which possession of the site is intended to be given:		
UNKNOWN		
42.2.6 Period for the commencement of the works after the contractor takes posse		
Carried to Collection Section 1	R	<u> </u>
Bill No. 1 PRELIMINARIES		

42.2.7 For the works <b>as a whole.</b> Intended date of practical completion and the penalty per calendar day				
3 months after contractual commencement date				
Penalty Amount The penalty shal be 7.5c per R100 per <b>calender day</b> of the tendered amount (inclusive of value added tax)				
42.2.8 For the works in <b>sections</b> : Intended date of practical completion and the penalty per calender day				
Section 1 .N/A Date				
R.N/A Penalty Amount				
42.2.9 The <b>law</b> applicable to this <b>agreement</b> shall be that of				
South Africa (country)				
42.3 INSURANCES				
42.3.1 Contract works insurance to be effected by:				
Contractor:				
For the Sum of R Contract Amount + 20.00 %				
With a deductible of - to be determined by the contractor				
42.3.2 Supplementary insurance is required No				
42.3.3 Public liability insurance to be effected by:  Contractor:				
For the Sum of R 2 500 000-00				
With a deductible of - to be determined by the contractor				
Carried to Collection Section 1		R		
Bill No. 1 PRELIMINARIES				
	1		1	

42.4	DOCUMENTS			
	Waivers of <b>contractors lien</b> or right of uing possession is required			
	Yes			
42.4.2	Number of construction document copies to be supplied to the <b>contractor</b> free of charge:			
	3 Number of			
42.4.3	Bills of Quantities/Lump sum document schedule of rates drawn up in accordance with:			
	"Standard System of Measuring Builders' Work"			
42.4.4	On acceptance of the tender the bills of quantities/lump sum document is to be submitted within working days			
The p	priced bills of quantities must be handed in with the tender			
42.4.5	JBCC Engineering General Conditions are to be included in the <b>contract documents</b> :  No			
	The contract value is to be adjusted using tion adjustment indices			
	Where <b>JBCC CPAP</b> is to be used  Base Month N/A			
42.4.7	Details of changes made to the provision of JBCC standard documentation:			
SECT	ION B: PRELIMINARIES			
<u>Defini</u>	tions and interpretation (B1)			
Definit	ion and interpretation (B1.1 - B1.4.6)			
	V:	Item		
	Carried to Collection		R	
Section Bill No PRELI				

43

	Documents (B2)			
44	Checking of documents (B2.1)			
	F: T:	Item		
45	Provisional bills of quantities (B2.2)			
	F: V: T:	N/A		
46	Availability of construction documentation (B2.3)			
	F: T:	Item		
47	Interests of agents (B2.4)			
	F: T:	Item		
48	Priced documents (B2.5)			
	F: T:	Item		
49	Tender submission (B2.6)			
50	F: V:	Item		
30	Defined works area (B3.1)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	The site (B3)			
51	Geotechnical investigation (B3.2)			
	F: T:	Item		
52	Inspection of the site (B3.3)			
	F: V:	Item		
	Existing premises occupied (B3.4)			
	F: T:			
	Previous work - dimensional accuracy (B3.5)			
	F: T:			
	Previous work - defects (B3.6)			
	F: T:			
53	Services - known (B3.7)			
	F: T:	Item		
54	Services - unknown (B3.8)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

55	Protection of trees etc (B3.9)			
	F: T:	Item		
56	Articles of value (B3.10)			
	F: T:	Item		
	Management of contract (B4)			
57	Inspection of adjoining properties etc (B3.11)			
	F: T:	Item		
58	Management of the works (B4.1)			
	F: T:	Item		
59	Programme for the works (B4.2)			
	F: T:	Item		
60	Progress meetings (B4.3)			
	F: T:	Item		
61	Technical meetings (B4.4)			
	F: T:	Item		
62	Labour and Plant records (B4.5)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	Samples, Shop Drawings and Manufacturer's Instructions (B5)			
63	Samples of materials (B5.1)			
64	F:	Item		
	F: V:	Item		
65	Shop drawings (B5.3)			
	F: T:	Item		
66	Compliance with Manufacturer's Instructions (B5.4)			
	F: T:	Item		
	Temporary works and plant (B6)			
67	Deposits and fees (B6.1)			
	F: T:	Item		
68	Enclosure of the works (B6.2)			
	F: T:	Item		
69	Advertising (B6.3)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

70	Plant, equipment, sheds and offices (B6.4)			
	F: T:	Item		
71	Main notice board (B6.5)			
	F: T:	Item		
72	Subcontractors' notice board (B6.6)			
	F: T:	N/A		
	Temporary services (B7)			
73	Location (B7.1)			
	F: V: T:	Item		
74	Water (B7.2)  Option [A] shall apply			
	F: V: T:	Item		
75	Electricity (B7.3)  Option [A] shall apply			
	F: T:	Item		
76	Telecommunication facilities (B7.4)			
	F: T:	Item		
77	Ablution facilities (B7.5)  Option [A] shall apply			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

	Prime cost amounts (B8)			
78	Responsibility for prime cost amounts (B8.1)			
	F: T:	Item		
	Attendance on N/S Subcontractors (B9)			
79	General attendance (B9.1)			
	F: T:	Item		
80	Special attendance (B9.2)			
	F: T:	Item		
81	Commissioning - Fuel, water and power (B9.3)			
	F: T:	Item		
	Financial aspects (B10)			
	Statutory taxes, duties and levies (B10.1)			
	F: T:	Item		
82	Payment of preliminaries (B10.2)  Option [B] shall apply			
	F: T:	Item		
83	Adjustment of preliminaries (B10.3)  Option [A] shall apply			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			<del></del>

84	Payment certificate cash flow (B10.4)			
	F: V: T:	Item		
	General (B11)			
85	Protection of works (B11.1)			
	F: T:	Item		
86	Protection/isolation of existing/sectionally occupied works (B11.2)			
	F:V:	Item		
87	Security of the Works (B11.3)			
	F: T:	Item		
88	Notice before covering work (B11.4)			
	F:V: T:	Item		
89	Disturbance (B11.5)			
	F: T:	Item		
90	Environmental Disturbance (B11.6)			
	F: T:	Item		
91	Works cleaning and clearing (B11.7)			
	F: T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

92	Vermin (B11.8)			
	F: T:	Item		
93	Overhand work (B11.9)			
	F: T:	Item		
94	Instruction manuals and guarantees (B11.10)			
	F: T:	Item		
95	As built information (B11.11)			
	F: T:	Item		
96	Tenant Installations (B11.12)			
	F: T:	Item		
	Schedule of variables (B12)			
97	Pre-tender information (B12.1)			
	F: V: T:	Item		
	12.1.1 Provisional bills of quantities (B2.2) The quantities are provisional:  No			
	12.1.2 Availability of construction documentation (B2.3) Construction documentation is not complete  No			
	12.1.3 Interest of agents (B2.4)			
	12.1.4 Defined works area (B3.1)			
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

12.1.5 Geotechnical investigation (B3.2)  N/A	
12.1.6 Existing premises occupied (B3.4)	
12.1.7 Previous work - dimensional accuracy (B3.4)	
12.1.8 Previous work - defects (B3.5)	
12.1.9 Services - known (B3.7)	
12.1.10 Protection of trees (B3.9)	
All trees should be protected and only on instruction of the Principal Agent may any trees be removed	
12.1.12 Enclosure of the works (B6.2)	
12.1.11 Inspection of adjoining properties (B3.11)	
12.1.13 Offices (B6.4.3)	
An office for the clerck of works should be provided	
12.1.14 Main notice board (B6.5)	
YES	
12.1.15 Subcontractors notice board (B6.6) A notice board is required  No	
12.1.16 Water (B7.2) Alternative Selected: A	
Carried to Collection R	
Section 1 Bill No. 1 PRELIMINARIES	

12.1.17 Electricity (B7.3) Alternative selected: A		
12.1.18 Telecommunications (B7.4)		
12.1.19 Ablution facilities (B7.5) Alternative selected: A		
12.1.20 Protection of existing/sectionally occupied works (B11.2)		
12.1.21 Special attendance (B9.2)		
Subcontractor (1) details:		
N/A		
12.1.22 Protection of the works (B11.1)		
N/A		
12.1.23 Disturbance (B11.5)		
N/A		
12.1.24 Environmental Disturbance (B11.6)		
N/A		
Post tender information (B12.2)		
12.2.1 Payment of preliminaries Alternative selected: B		
12.2.2 Adjustment of preliminaries Alternative selected: A		
12.2.3 Additional agreed preliminaries items		
N/A		
Carried to Collection	R	
Section 1 Bill No. 1		
PRELIMINARIES		

	SECTION C: SPECIFIC PRELIMINARIES			
	Any special items to meet the particular circumstances of a specific project are embodied in this section. Where required for an aspect of the works to be executed according to a design by a consulting engineer, a recital of the headings to the individual clauses of the JBCC Engineering General Conditions are included			
98	Site instructions			
	Instructions issued on site are to be recorded in triplicate in a site instruction book which is to be maintained on site by the contractor			
	F: : T:	Item		
99	Black economic empowerment and training			
33	F: V:			
	T:	Item		
00	Proprietary branded products			
	F: T:			
	1	Item		
01	Testing of flat roof waterproofing for watertightness			
	Flat roof waterproof areas shall be prepared with small sand dykes around them of a size and enclosing an area approved by the principal agent, flooded with water and kept "ponded" for at least 36 hours as a test to ensure the watertightness of the waterproofing and before any further construction work is carried out above the waterproofing			
	F: V: T:	Item		
	The contractor shall take delivery of, handle, store, use, apply and/or fix all proprietary branded products in strict accordance with the manufacturers' instructions after consultation with the manufacturer's authorised representative			
	Carried to Collection		R	
	Section 1 Bill No. 1 PRELIMINARIES			

102	Contract instructions			
	F:V:			
	T:			
		Item		
	Contract instructions issued on site are to be recorded in			
	triplicate in a contract instruction book which is to be			ĺ
	supplied and maintained on site by the contractor			
103	Labour record			
100				
	F:V:			
	T:			ĺ
		Item		
	At the end of each week the contractor shall provide the			
	At the end of each week the contractor shall provide the principal agent with a written record, in schedule form,			ĺ
	reflecting the number and descriptions of tradesmen and			ĺ
	labourers employed by him and all subcontractors on			
	the works each day of that week			
104	Plant record			
	F:V:			
	T:			
	1	Item		
	At the end of each week the contractor shall provide the			
	principal agent with a written record, in schedule form,			
	reflecting the number, type and capacity of all plant,			
	excluding hand tools used on the works each day of that			ĺ
	week			
105	Guarantees			
	F: V:			
	T:	16		
		Item		
	Carried to Collection		R	
	Section 1			
	Bill No. 1			
	PRELIMINARIES			

	Where guarantees are called for, the contractor shall obtain a written guarantee, addressed to the employer, from the firm supplying the materials and/or doing the work and shall deliver same to the principal agent on the certified completion of the contract. The guarantee shall state that workmanship, materials and installation are guaranteed for a specified period from the date of certified completion of the contract, and that any defects that may arise during the specified period shall be made good at the expense of the firm supplying the materials and/or doing the work, upon written notice from the principal agent to do so. This guarantee will not be enforced if the work is damaged by defects in the construction of the building in which case the responsibility for replacement shall rest entirely with the contractor. The principal agent shall be the sole judge of the cause responsible for defects in the work and his decision shall be final and binding in terms of clause 40.2 of the agreement			
106	Overtime			
	F:V:			
	T:	Item		
	Should overtime be required to be worked for any reason whatsoever, the costs of such overtime are to be borne by the contractor unless the principal agent has specifically authorised, in writing, prior to execution thereof, that costs for such overtime are to be borne by the employer			
107	Co-operation of contractor for cost management			
	F:V:			
	T:	Item		
	Carried to Collection		R	
	Section 1 Bill No. 1			
	PRELIMINARIES			

	Bill No. 1 PRELIMINARIES			
	Carried to Collection Section 1		R	
	Category : Time R			
	Category : Value R			
	Category : Fixed R			
	SUMMARY OF CATEGORIES			
	Any Principal Contractor entering into a contract with The Developer must achieve an acceptable level of Occopational Health and Safety performance. Refer to "Project Specification" and "Safety, Health and Environmental Evaluation Questionaire" The contractor to comply with all provisions of the above and to be enforced on all selected and or other sub-contractors, as no claim afterwards will be entertained			
	F: T:	Item		
108	Occupational Health and Safety Specification			
	It is specifically agreed that the contractor accepts the obligation of assisting the professional consultants in implementing proper cost management. The contractor will be advised by the principal agent of all cost management procedures which will be implemented to ensure that the final building cost does not exceed the budget. The quantity surveyor undertakes to make available to the contractor all budgetary allowances and cost assessments/reports to enable the proper procedures to be implemented and the contractor will attend all cost plan review and cost management meetings. The contractor undertakes to extend these procedures in regard to all subcontractors			

Section 1				
Bill No. 1				
PRELIMINARIES				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	1			
	2			
	3			
	4		<b> </b>	
	5			
	6			
	7			
	8			
	9			
	10			
	11			
	12			
	13			
	14			
	15			
	16			
	17			
	18			
	19			
	20			
Carried Forward		R		
Section 1 Bill No. 1 PRELIMINARIES				

Section 1					
Bill No. 1					
PRELIMINARIES					
COLLECTION					
		Page No		Amount	
	Brought Forward		R		
Total Brought Forward from Page No.		21			
		22			
		23			
		24			
		25			
		26			
		27			
Carried	I to Final Summary		R		
Section 1 Bill No. 1	-				_
PRELIMINARIES					

Item No		Quantity	Rate	Amount
	SECTION 2			
	BILL No. 1			
	ALTERATIONS			
	MODEL PREAMBLES			
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.			
	SUPPLEMENTARY PREAMBLES			
	<u>View site</u>			
	Before submitting his tender the tenderer shall visit the site and satisfy himself as to the nature and extent of the work to be done and the value of the materials contained in the buildings or portions of the buildings to be demolished. No claim for any variations of the contract sum in respect of the nature and extent of the work or of inferior or damaged materials will be entertained			
	<u>Explosives</u>			
	No explosives whatsoever may be used for demolition purposes unless otherwise stated.			
	<u>General</u>			
	Water supply pipes and other piping in ground that may be encountered and found necessary to disconnect or cut, shall be effectually stopped off or grubbed up and removed, and any new connections that may be necessary shall be made with proper fittings to the satisfaction of the principal agent.			
	Unless otherwise described all materials are to become the property of the contractor and are to be removed from the site.			
	Carried to Collection  Section 2  Bill No. 1  Alterations		R	

Removal of asbestos material		
All preparatory work, alterations, etc., to existing asbestos cement roof sheeting, gutters, rainwater pipes, etc., is to be carried out strictly by an approved and certified specialist company and in accordance with statutory requirements (Occupational Health and Safety Act, 1993 - Asbestos Regulations 2001) and all necessary precautions must be taken when working with and disposing of asbestos cement products and the disposal of waste water resulting from cleaning operations, etc.		
The following shall apply in respect of asbestos removal		
The removal of asbestos shall be carries out by a certified entity, registered in accordance with the Occupational Health and Safety Act. 1993 and the Asbestos Regulations 2001		
Asbestos in all forms/building elements that is to be removed, shall be carried out in strict accordance with aforementioned regulation and a certificate issued by the entity as contemplated in the above, shall be provided per block for the removal thereof, where the term block shall in this context refer to any single, free standing building structure, regardless of size or purpose		
Corresponding disposal certificates shall be issued by the facility at which the asbestos is disposed off, with said facility to, prior to the disposal of any asbestos material provide satisfactory proof that the facility is duly registered and fully compliant in terms of the act, to receive the asbestos material		
Under no circumstances is the Contractor nor any of his duly authorised representatives to sell and/or give away asbestos material to any member/s of the school community, the community in general or the public at large. Should this be found to be occuring, the Contractor will be held responsible contractually and may further be prosecuted ciminally		
The cost for complying with the above, and all requirements of regulation as reflected above is to be priced for in terms for removal of asbestos material. No further claims in this regard will therefore be entertained		
Carried to Collection		
Section 2	R	
Bill No. 1		
Alterations		

	ALTERATIONS				
1	Take out existing paving and set aside	m2	130		
2	Re-lay existing paving	m2	130		
	Carried to Collection Section 2			R	
	Bill No. 1 Alterations				

Section 2			
Bill No. 1			
Alterations			
COLLECTION			
	Page No		Amount
Total Brought Forward from Page No.	30 31 32		
Carried to Final Summary Section 2 Bill No. 1 Alterations		R	

Item No			Quantity	Rate	Amount
	SECTION No. 3	·			
	BILL No. 1				
	EXTERNAL WORKS (PROVISIONAL)				
	MODEL PREAMBLES				
	The tenderer is referred to the "General Preambles for Trades 2017" for supplementary and comprehensive expansion of descriptions, appropriate provision for which shall be deemed to have been included in all relevant rates.				
	THE FOLLOWING IN WALKWAYS				
	Excavation not exceeding 2m deep				
1	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	212		
	Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):				
2	Off site to a dumping site to be found by the Contractor.	m3	212		
	Filling supplied by the contractor under walkways				
3	G7 Base course material compacted to 98% Mod AASHTO density	m3	142		
4	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	71		
	Rip and Re - compact insitu material on site compacted to 93% Mod. AASHTO density:				
5	Under floors,etc.	m2	472		
	Carried to Collection Section 3 Bill No. 1			R	
	External Works				

Droserihad density tosts on fillings					1
Prescribed density tests on miling.					
In-situ dry density test.	No	5			
Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:					
Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.	m2	472			
Concrete Paving Blocks					
Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:					
Paving to walkway areas, etc laid to falls.	m2	472			
Kerbing					
Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement					
Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.	m	316			
Ditto but circular on plan.	m	10			
Welded balustrading to walkways					
Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section top and bottom rails and 10mm diameter vertical uprights at 100mm centres	m	79			
Extra on last for closed end to 70 x 70mm posts	No	20			
150 x 150 x 6mm baseplate, four times holed and welded to soffit of posts	No	50			
Carried to Collection Section 3 Bill No. 1 External Works			R		
	Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:  Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.  Concrete Paving Blocks  Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:  Paving to walkway areas, etc laid to falls.  Kerbing  Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.  Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.  Ditto but circular on plan.  Welded balustrading to walkways  Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section top and bottom rails and 10mm diameter vertical uprights at 100mm centres  Extra on last for closed end to 70 x 70mm posts  150 x 150 x 6mm baseplate, four times holed and welded to soffit of posts  Carried to Collection  Section 3  Bill No. 1	In-situ dry density test.  Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years:  Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.  Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:  Paving to walkway areas, etc laid to falls.  May be a subject of accuracy I:  Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.  Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.  Ditto but circular on plan.  Melded balustrading to walkways  Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section top and bottom rails and 10mm diameter vertical uprights at 100mm centres  Extra on last for closed end to 70 x 70mm posts  No  150 x 150 x 6mm baseplate, four times holed and welded to soffit of posts  Carried to Collection  Section 3  Bill No. 1	In-situ dry density test.  Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and quaranteed against termite infestation for ten years:  Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.  Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:  Paving to walkway areas, etc laid to falls.  M2  Kerbing  Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.  Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.  Ditto but circular on plan.  Melded balustrading to walkways  Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section top and bottom rails and 10mm diameter vertical uprights at 100mm centres m 79  Extra on last for closed end to 70 x 70mm posts  No  Carried to Collection  Section 3  Bill No. 1	In-situ dry density test.  Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and quaranteed against termite infestation for ten years:  Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.  Concrete Paving Blocks  Paving of 60mm thick 200×100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 1200D degree of accuracy I:  Paving to walkway areas, etc laid to falls.  M2  Kerbing  Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.  Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.  Ditto but circular on plan.  M 10  Welded balustrading to walkways  Horizontal welded balustrading 1000mm high of 70 x 70 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section posts, at 1600mm centres.  Carried to Collection  Carried to Collection  R  Section 3  Bill No. 1	In-situ dry density test.  Approved brand of anti-termite soil poison applied by a Registered Pest Control Company and guaranteed against termite infestation for ten years.  Treat filling under paving with 'Chlordane Heptachlor Aldrin' or equal approved.  Concrete Paving Blocks  Paving of 60mm thick 200x100mm 25MPa Bevel Bond paver blocks grey in colour in herringbone pattern on and including 20mm thick sand bed with dry filler sand swept and vibrated into joints all laid on subgrade (elsewhere measured) conforming to SABS 12000 degree of accuracy.  Paving to walkway areas, etc laid to falls.  m2  472  Kerbing  Precast or in situ mass concrete (25 MPa - 19 mm stone) kerbs cast in convenient lengths with exposed faces finished smooth from the mould and all salient angles rounded, jointed and pointed in 1:3 cement mortar, including excavations, formwork, etc.  Figure 8B (300 x 275 x 175mm) semi mountable kerb laid in lengths not exceeding 1000mm on a well rammed earth bottom or base course.  Ditto but circular on plan.  Melded balustrading to walkways  Horizontal welded balustrading 1000mm high of 70 x 70 x 25 mm hollow section posts, at 1600mm centres, with 40 x 40 x 2,5mm hollow section tops, at 1600mm centres m 79  Extra on last for closed end to 70 x 70mm posts  No  50  Carried to Collection  R  Bill No. 1

14	M16 x 100mm expansion bolt	198			
					_
	Carried to Collection		R		
	Section 3				
	Bill No. 1 External Works				
		1	1	II	ı

	ACCESS RAMPS				
	Excavation not exceeding 2m deep				
15	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	6		
	Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):				
16	Off site to a dumping site to be found by the Contractor.	m3	6		
	Filling supplied by the contractor under floors, aprons, etc				
17	G7 Base course material compacted to 98% Mod AASHTO density	m3	4		
18	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	2		
	Coarse river sand filling supplied by the contractor:				
19	Under floors etc.	m3	0.2		
	Compaction of surfaces:				
20	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	4		
	Prescribed density tests on filling:				
21	In-situ dry density test.	No	1		
	Reinforced 25Mpa/19mm Concrete:				
22	Ramps, Landings, etc.	m3	0.4		
	Finishing top surfaces of concrete smooth with a wood float:				
23	Surface beds, slabs, etc to falls and currents.	m2	4		
	Carried to Collection			R	
	Section 3 Bill No. 1 External Works			•	

	Test blocks:				
24	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	1		
	Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:				
25	12mm Joints not exceeding 300mm high.	m	4		
	Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc				
26	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	4		
	Fabric reinforcement:				
27	REF. 395 fabric reinforcement in concrete surface beds, slabs, etc.	m2	2		
	Waterproofing under Surface beds				
28	350 Micron USB orange polyethylene dampproof membrane in accordance with SABS 952 Type C laid or sand bed (elsewhere measured).	n m2	2		
	Carried to Collection	nn.		R	
	Section 3	/II			
	Bill No. 1 External Works				

	THE FOLLOWING IN RETAINING WALLS, ETC.				
	Excavation in earth not exceeding 2m deep				
29	Trenches.	m3	92		
	Risk of collapse of excavations:				
30	Sides of trench and hole excavations not exceeding 1,5m deep.	m2	120		
	Keeping excavations free of water:				
31	Keeping excavations free of all water other than subterranean water.		Item		
	Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):				
32	Off site to a dumping site to be found by the Contractor.	m3	89		
	Filling with approved clean, hard, dry decomposed dolerite filling supplied and carted onto site by the Contractor, compacted to a density of at least 95% Mod. AASHTO maximum density:				
33	Behind walls with selected backfilling supplied by the Contractor compacted to 98% Mod ASSHTO density	m3	43		
34	Clean coarse sand with a fineness modulus of greater than 2,8	m3	33		
	Compaction of surfaces				
35	Compaction of ground surface under floors, etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO				
	density.	m2	45		
	15Mpa/19mm unreinforced concrete				
36	Surface blinding under footings and bases.	m3	2		
					_
	Carried to Collection			R	
	Section 3 Bill No. 1 External Works				

	20Mna/10mm rainforced concrete	1		I	1
	30Mpa/19mm reinforced concrete				
37	Strip footings.	m3	11		
38	Cavity walls.	m3	12		
	Test blocks:				
39	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	5		
	Fabric reinforcement:				
40	REF. 395 fabric reinforcement in concrete infill, strip footings.	m2	141		
	Brickwork of NFX bricks (14 MPa nominal compressive strength) in Class I mortar (Cement to be 42.5N all-purpose cement):				
41	One brickwalls in foundations	m2	14		
42	One brick walls	m2	113		
	Brickwork reinforcement:				
43	230mm Wide reinforcement built in horizontally.	m	746		
	"Rustgold FBS/Qunu Travertine" clay face brick or equal approved, size 222 x 106 x 73mm, bedded and jointed in Class II mortar and pointed with recessed vertical and recessed horizontal joints, suitable for exposure zones 1-2 (Cement to be 42.5N all-purpose cement):				
44	Extra over brickwork for face brickwork externally.	m2	113		
45	One brick wall in face brickwork	m2	42		
	Brick-on-edge header course copings, sills, etc, of "Rustgold FBS/Qunu Travertine" or equal Architect approved clay face brick size 222 x 106 x 73mm, pointed with recessed joints on all exposed faces:				
46	220mm Wide header course to top of one brick wall bedded and jointed in cement mortar and pointed on top and both sides as described.	m	47		
	Carried to Collection			R	
	Section 3 Bill No. 1 External Works				

			,	,	,	,
	Openings in Walls etc.					
47	Leave or form 32mm weephole through one brick wall	No	31			
	<u>Membranes</u>					
48	"Geofabric filter blanket wrapped around stone with 300mm side and 300mm end laps, including stitching.	m2	56			
	Earth filling 300 x 300mm section of 19mm thick stone material surrounding 110mm uPVC pipe, supplied by the contractor compacted to 98% Mod AASHTO density:					
49	19mm Stone.	m3	4			
	Slotted uPVC flexible drainage pipes					
50	110mm Pipes laid in stone encasing (encasing elsewhere)	m	47			
	Extra over slotted uPVC flexible drainage pipes for fittings					
51	110mm End cap	No	2			
52	110mm Bend	No	2			
	THE FOLLOWING IN CONCRETE CHUTES, ETC.					
	Excavation not exceeding 2m deep					
53	Reducing levels and depositing excavated material in prescribed stock piles on site.	m3	1			
	Extra over all excavations for loading, carting and dumping surplus excavated material (no allowance made for increase in bulk):					
54	Off site to a dumping site to be found by the Contractor.	m3	1			
	Filling supplied by the contractor under floors, aprons, channels etc					
55	G7 Base course material compacted to 98% Mod AASHTO density	m3	0.4			
	Carried to Collection			R		
	Section 3					$\vdash$
	Bill No. 1 External Works					

56	Over site of Selected Subgrade G5 material in accordance with SABS 1 200 DM in layers not exceeding 150mm thick and compacted to 95% Mod AASHTO density.	m3	0.4		
	Coarse river sand filling supplied by the contractor:				
57	Under floors etc.	m3	0.4		
	Compaction of surfaces:				
58	Compaction of ground surface under floors etc including scarifying for a depth of 150mm, breaking down oversize material, adding suitable material where necessary and compacting to 90% Mod AASHTO density.	m2	2		
	Prescribed density tests on filling:				
59	In-situ dry density test.	No	2		
	Reinforced 25Mpa/19mm Concrete:				
60	Surface beds cast in panels on waterproofing.	m3	4		
	Finishing top surfaces of concrete smooth with a wood float:				
61	Surface beds, slabs, etc to falls and currents.	m2	2		
	Test blocks:				
62	Making and testing of 150x150x150mm concrete strength test cubes (Provisional).	No	2		
	Expansion joints with bitumen impregnated softboard between vertical concrete or brick surfaces:				
63	12mm Joints not exceeding 300mm high.	m	1		
	Two-part grey polysulphide sealing compound including backing cord, bond breaker, primer, etc				
64	10 x 12mm In movement joints in floors or walls including raking out expansion joint filler as necessary.	m	1		
					_
	Carried to Collection			R	=
	Section 3 Bill No. 1 External Works				

	Fabric reinforcement:				
65	REF. 617 fabric reinforcement in concrete surface beds, slabs, etc.	m2	2		
	Grating				
66	600mm wide mild steel grating on 50 x 50mm angle iron bedded in 30Mpa concrete with galvanised iron lugs.	m	10		
	Carried to Collection	ı		R	
	Section 3 Bill No. 1 External Works				

Section 3				
Bill No. 1				
External Works				
COLLECTION				
	Page No		Amount	
Total Brought Forward from Page No.	34			_
	35			_
	36			_
	37			_
	38			_
	39			_
	40			_
	41			_
	42			_
	43			_
				•
				_
Carried to Final Summary		R		_
Section 3 Bill No. 1				
External Works				

	FINAL SUMMARY				
Section No		Page No		Amount	
1	PRELIMINARIES	29			_
2	ALTERATIONS (PROVISIONAL)	33			_
3	EXTERNAL WORKS (PROVISIONAL)	44			_
	SUB-TOTAL		R		_
	CONTINGENCIES				
	Allow ten per cent (10%) of the above sub-total for contingencies to be used as directed and deducted in whole or in part if not required.		R		
	SUB-TOTAL		R		
	Add Value Added Tax at the rate of 15%		R		
					_
	Carried to Form of Offer and Acceptance		R		_