

**Annexure C3.2: Scope of Work (including drawings, where applicable) RFQ
10404810**

The primary key activities of the project entails but not limited to the following:

- Repairing all suction valve and discharge valve.
- Repair None Return Valve and interconnector valve.
- Supply and install of Polyester Grid to cover, with the following specification:
Grating: 38mm x38mm square mesh pattern
Surface Finish: Non-Slip fine gritted surface
Panel Depth: Grating 38mm
- Modify the Pump Volute to fit the new pump specification.
- Replace Front Rake Screen and supply the rake.
- Renovate the step ladders and handrails.
- Replace all damaged lights inside the pump station.
- Test and commission Pump station back to full functionality

This description of the works is not necessarily complete and shall not limit the work to be carried out by the Contractor.