

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

	<u>VINYL FLOOR COVERINGS, WALL LININGS, ETC.</u>				
	<u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: SOLE). (See the attached Architect's Floor Finish Schedule)</u>				
2/9/1	On floors	m ²	99		
	<u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: SAFRAN). (See the attached Architect's Floor Finish Schedule)</u>				
2/9/2	On floors	m ²	130		
	<u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: PAPRIKA). (See the attached Architect's Floor Finish Schedule)</u>				
2/9/3	On floors	m ²	384		
	<u>Gerflor Mipolam Styl or similar approved, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications.(Colour & Range: FRUMENTO). (See the attached Architect's Floor Finish Schedule)</u>				
2/9/4	On floors	m ²	125		
	Carried to Trade Summary				
	BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd				R

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

2/9/5	<p><u>Gerflor Mipolam Styl or similar approved, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour & Range: CHOCOLATO). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	423		
2/9/6	<p><u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: LENTO). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	3 196		
2/9/7	<p><u>Gerflor Mipolam Styl or similar approved, homogeneous (non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour & Range: MESTO). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	1 101		
2/9/8	<p><u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: MEDIO VERDE). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	98		
<p align="center">Carried to Trade Summary</p>				R	
<p>BUILDING WORKS Bill No. 9 FLOOR COVERINGS <i>DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd</i></p>					

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

2/9/9	<p><u>Gerflor Mipolam Styl, homogeneous(non-directional) high performance vinyl safety flooring suitable for dry areas with an R9 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications. (Colour: & Range: ANIMATO). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	13		
2/9/10	<p><u>Gerflor Tarasafe H20 high performance vinyl safety flooring suitable for wet areas and with an R11 slip resistance to be installed according to manufacruters specifications.(Colour: 0034 - Zambezi). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	783		
2/9/11	<p><u>Custom artwork inlays to be installed into Vinyl sheeting. Seamless welding between 2 coloured vinyls to be neatly done and according to the strict recommendations and specifications of the manufacturer. *Refer to the floor finish layout for design pattern. (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	57		
2/9/12	<p><u>FLOORWORX KENT Glue down or similar approved, LVT Vinyl floor tile (Size: 184.2 x 1219.2 x 2.5mm). Ensure surface is clean before installation. All according to manufacturer's specifications.Colour: Bushland Grey.Code: FLXKNT8436T250. (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	20		
2/9/13	<p><u>Gerflor Taralay Impression Compact, homogeneous (non-directional) high performance vinyl flooring suitable for kitchen areas with a R10 slip resistance and evercare patented surface treatment, installed according to manufacturers specifications.(Colour & Range: 1049 - METALIC SILVER). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	95		
<p align="center">Carried to Trade Summary</p>				R	
<p>BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd</p>					

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

<u>CARPET FLOOR COVERINGS</u>					
2/9/14	<p><u>BELGOTEX GRID 50cm x 50cm Heavy Commercial ±6mm NexBac tile, to be installed acc. to manufacturer's specifications. Ensure surface is clean and free of dust before carpet is installed.(Colour code: Vesper). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	547		
2/9/15	<p><u>BELGOTEX FLIPTILE 495 x 390,4 mm Heavy Residential ±8,5mm Modular carpet installed according to manufacturer's specifications. Ensure surface is clean and free of dust before carpet is installed.(Colours: Shade, Gravel & Cloud). (See the attached Architect's Floor Finish Schedule)</u></p> <p>On floors</p>	m ²	247		
2/9/16	<p><u>BELGOTEX TERRAIN 25 x 100 cm Heavy Commercial ±6mm NexBac plank installed according to manufacturer's specifications. Ensure surface is clean and free of dust before carpet is installed.(Colour code: Earthen)</u></p> <p>On floors</p>	m ²	86		
2/9/17	<p><u>BELGOTEX TERRAIN 25 x 100 cm Heavy Commercial ±6mm NexBac plank installed according to manufacturer's specifications. Ensure surface is clean and free of dust before carpet is installed.(Colour code: Dolomite)</u></p> <p>On floors</p>	m ²	167		
2/9/18	<p><u>BELGOTEX BALTIMORE Heavy Commercial carpet: Broadloom ±10mm thick. Ensure surface is clean and free of dust before carpet is installed with appropriate adhesive. All according to manufacturer's specifications. (Colour: Estate)</u></p> <p>On floors</p>	m ²	212		
Carried to Trade Summary					
BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd					R

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

2/9/19	<u>BELGOTEX BALTIMORE Heavy Commercial carpet: Broadloom ±10mm thick. Ensure surface is clean and free of dust before carpet is installed with appropriate adhesive. All according to manufacturer's specifications. (Colour: Statue)</u>	m ²	33		
2/9/20	<u>BELGOTEX BALTIMORE Heavy Commercial carpet: Broadloom ±10mm thick. Ensure surface is clean and free of dust before carpet is installed with appropriate adhesive. All according to manufacturer's specifications. (Colour: Otter)</u>	m ²	8		
2/9/21	<u>BELGOTEX BALTIMORE Heavy Commercial carpet: Broadloom ±10mm thick. Ensure surface is clean and free of dust before carpet is installed with appropriate adhesive. All according to manufacturer's specifications. (Colour: Travertine)</u>	m ²	44		
2/9/22	<u>POLISHED CONCRETE FLOORS</u> <u>100mm in-situ cast 25mPa concrete slab with reinforcing mesh, construction joints, levels, fall and layout according to civil engineer with non-slip, power floated finish and 100mm wide smooth round trowelled border on joints and edges. All joints to be finished with appropriate elastomeric polysulphide sealant according to manufacturer specification.</u>	m ²	264		
2/9/23	<u>WALL LININGS</u> <u>"Decohoc" or similar approved linings:</u> 2.5mm Scratch-resistant wall cover with adhesive plugged to walls.	m ²	624		
Carried to Trade Summary				R	
BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd					

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

	<u>"Decohoc H2O" or similar approved linings:</u>				
2/9/24	Scratch-resistant wall cover with adhesive plugged to walls.	m ²	40		
	<u>"Decowood" or similar approved linings:</u>				
2/9/25	Scratch-resistant wall cover with adhesive plugged to walls.	m ²	222		
	<u>"Decosign/Decoprint" or similar approved linings:</u>				
2/9/26	Custom-made wall signage plugged to walls. (Refer to Architect wall finishing schedule)	No	25		
	<u>"Linea'flex" or similar approved wall linings:</u>				
2/9/27	3mm thick PVC v-butt corner protection plugged to walls.	m	40		
	<u>"Protecta 2" or similar approved wall linings:</u>				
2/9/28	2.3mm thick PVC v-butt corner protection plugged to walls.	m	61		
	<u>"Starline" or similar approved wall linings:</u>				
2/9/29	Scratch-resistant wall cover with adhesive plugged to walls.	m ²	174		
	<u>"Decotrend" or similar approved wall linings:</u>				
2/9/30	Scratch-resistant wall cover with adhesive plugged to walls.	m ²	345		
	<u>HANDRAILS</u>				
	<u>"Escort Decowood" or similar approved handrails:</u>				
2/9/31	55 x 40mm diameter Handrails to walls.	m	94		
	<u>BUMP RAILINGS</u>				
	Carried to Trade Summary				
	BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd				R

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

	<u>"Linea'punch Neo" or similar approved linings:</u>				
2/9/32	180 x 25mm PVC wall protection rail mounted 800mm off ground level plugged to walls.	m	1 080		
	<u>"Corneaflex" or similar approved protective linings:</u>				
2/9/33	65mm PVC wall protection rail plugged to walls.	m	651		
	<u>"Elasto'punch" or similar approved protective linings:</u>				
2/9/34	200 x 30mm wide heavy duty PVC wall protection rail mounted 800mm off ground level plugged to walls.	m	1 101		
	<u>"Elasto'flex" or similar approved protective linings:</u>				
2/9/35	100 x 4mm thick heavy duty PVC wall protection rail mounted 800mm off ground level plugged to walls.	m	248		
	<u>SKIRTINGS, NOSINGS, ETC</u>				
	<u>Coved floor-sheet skirting to match floor vinyl sheeting coved against walls to form coved skirting, and welded to floor-sheet. Coved skirting to be laid over preformed 20 x 20 mm cove former – with ends sealed with glue. Allow for butterfly corner method at all corners including at thresh-holds, all in accordance with manufacturer's specifications. Skirting to be finished with extruded capping strip (or clip-on capping strip with backing) to be supplied and fixed with manufacturer approved contact adhesive spread evenly and quickly onto both material and wall surface. PVC welding rods to be used between skirting and panels joints (colour to match panels). (See the attached Architect's Floor Finish Schedule)</u>				
2/9/36	120mm high vinyl skirtings.	m	4 521		
	Carried to Trade Summary				
	BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd				
				R	

**Major Refurbishment and Additions to the existing
Galeshewe Day Hospital
in Kimberly**

2/9/37	<p><u>High Impact PVC skirting, complete with "EASY slip in corner pieces" and "EASY outside corner pieces". EASY Skirt to be fixed to wall with appropriate concrete nails @ 250mm C-C. Cut 50 mm carpet strips from carpet offcuts and fix to EASY skirt profile using supplied adhesive tape. All according to manufacturer's specifications.Colour:</u></p>	m	981		
	100mm high PVC skirtings.				
2/9/38	<p><u>CORNER PROTECTORS, DIVIDING STRIPS, ETC.</u></p>				
	<p><u>Brass strips.:</u></p>				
	40mm Flat section straight transition strip at junction of different floor finishes.	m	64		
2/9/39	<p><u>M-Trim Natural anodised aluminium carpet gripper capping strip trim (Code : ACGCS300.N), plugged and counter sunk screwed into cement screed with stainless steel screws all in accordance with the specifications and recommendations of the manufacturer.</u></p>				
	30 x 9mm high Aluminium skirtings.	m	182		
2/9/40	<p><u>POLISH, SEALERS, ETC.</u></p>				
	<p><u>Polisher, Sealers, etc.:</u></p>				
	Three coats wax polish on vinyl flooring.	m ²	5 994		
Carried to Trade Summary				R	
<p>BUILDING WORKS Bill No. 9 FLOOR COVERINGS DARK HORSE PROJECTS & INVESTMENT GROUP (PTY) Ltd</p>					

