

MEMBER SCHEDULE				Revisions:	
MARK	SECTION	COMMENTS	Rev	Date	Description
SC1	203/203R0	COLUMN	02	15/11/2021	CONSTRUCTION
SC2	152/152-37	STUB COLUMN			
B1	254/140/43	BEAM			
H1	406/178/67	HIP RAFTER			
H2	254/178/43	HIP RAFTER			
R1	254/140/43	RAFTER			
R2	406/178/67	RAFTER			
R3	406/178/67	RAFTER			
P1	152/152/20/3	PURLIN			
P2	125/65/20/3	PURLIN			
FR	100/100/8	FALSE RAFTER			
BR	70/70/1	ROOF BRACING			
BR1	101/62/5	CHS ROOF BRACING			

**PLEASE READ THOROUGHLY!!!!**

**GENERAL NOTES:**

G1. All work to be carried out in accordance with the latest issue of SANS 1000-B.

G2. All setting out to Architect's details.

G3. Piles, pile caps, ground beams, footings, and columns are central on grid lines unless shown otherwise.

G4. Contractor to check all dimensions and levels prior to commencing work on site, and any discrepancies to be reported to the Engineer immediately.

**CONCRETE NOTES:**

C1. Blinding concrete to be placed below all pile caps, ground beams, and footings and shall be a minimum of 50mm thick.

C2. Concrete mix design to SANS 10100. Design loads from SANS 10160 and Client's specification.

C3. Concrete mix designs to be submitted to Engineer for approval prior to commencement of work. Only Engineer-approved admixtures to be used.

C4. Foundations designed for a bearing pressure of 80kPa. Refer to DRENAN MAUD (PTY) LTD Report Ref. 2064991.

C5. All concrete to have a minimum compressive strength at 28 days as follows:

- Blinding: 15 MPa / 20mm
- Foundations: 25 MPa / 25mm
- Columns: 30 MPa / 15mm
- Surface Beds: 25 MPa / 15mm
- Suspended Slabs & Beams: 30 MPa / 15mm

C6. Concrete cover to main reinforcement:

- Foundations: 50 mm
- Columns: 30 mm
- Surface Beds: 50 mm
- Suspended Slabs & Beams: 30 mm

C7. All concrete work, including formwork stripping times and propping, to SANS 1200-B.

C8. Formwork classification:

- Concealed surfaces: Rough
- Exposed surfaces (unless otherwise shown): Smooth (off-shutter) to Grade II tolerances.
- Exposed surfaces (where specified by architect): Smooth-specially to SANS 2001-CCT-4.3.1 & Table 1.

Degree of accuracy 1 Table 11.

C9. All sharp edges to concrete to have 25mm chamfers.

C10. Unformed surface finishes as follows:

- Surface Beds: Power-floated
- Suspended Slabs: Power-floated

C11. All services and sleeves to be positioned prior to concrete pour. No in situ concrete to be cast without prior approval from the Engineer.

C12. The positions of all construction joints not shown on the drawings are to be discussed with and approved by the Engineer.

REFER TO DRAWING 3119-S20 - GENERAL NOTES

**STEEL NOTES:**

S1. Contractor to check all dimensions on site prior to fabrication. Any discrepancies to be reported to the Engineer immediately.

S2. No steelwork is to be fabricated prior to the Engineer's approval of shop drawings.

S3. Steelwork grades shall be as follows:

- Hot rolled sections: Grade S355JR to EN10025-2
- Hot rolled angles 50x50 and under and cold rolled open sections: Grade "CO" (Commercial Quality steel to SANS 10162)
- Hot formed hollow sections: Grade S35W to SANS 657-1.

S4. All hot rolled steelwork to be painted in accordance with the project specification.

S5. All cold rolled steelwork to be hot dip galvanised to SANS 121 and treated with a suitable degreasing agent.

S6. The ends of all tubular and hollow sections are to be sealed with nominal thickness plates and continuous fillet welds unless shown otherwise.

S7. All gusset and end plates to be 10mm unless shown otherwise.

S8. Unless shown otherwise, purflins and girts shall be continuous over at least two spans.

S9. All welds to be full strength U.O.N.

S10. Welding shall be performed by a certified welder in accordance with the requirements laid down in the latest issue of SANS 10044.

S11. Welds shall be firm continuous fillet welds with E70XX.

S12. Electrodes unless shown otherwise.

S13. Unless shown otherwise, all bolts shall be M16 Grade 4.8 to SABS 135.

S14. Exposed ends of holding-down bolts shall be protected from damage during and after placement of concrete.

S15. The Contractor shall provide and secure in place until permanent bracing elements are constructed, such temporary bracing as is necessary to stabilise the structure during erection.

REFER TO DRAWING 3119-S20 - GENERAL NOTES

IF IN DOUBT, ASK!!!

410/205/12mm Thick End  
with Ø60 holes for M20  
Grade 8.8 bolts.

410/205/12mm Thick End  
Plate with Ø60 holes for M20  
Grade 8.8 bolts.

HEALTH DEPARTMENT SIGNATURES

DEPUTY DIRECTOR GENERAL

HEAD OFFICE PROGRAMME / SERVICE

DISTRICT MANAGER


CEO MANAGER OF THE FACILITY

DOH PROJECT MANAGER

IMPLEMENTING AGENT PROJECT MANAGER

PROFESSIONAL SERVICE PROVIDER

Name **S. Boyce (Pr. Eng. 20160768)**

Signature  Date **04/10/2025**


**DRENNAN MAUD (PTY) LTD**


**GEOTECHNICAL ENGINEERS & ENGINEERING GEOLOGISTS**

Reg. No. 201403898707 [www.therealmud.com](http://www.therealmud.com)

CURSAN HEAD OFFICE  
98 The Avenue Ridge  
Tel: 011 460 1111  
Fax: 011 460 1111

P.O. Box 20544  
Midrand  
F: +27 31 201 2930

  
**health**  
Department:  
**Health**  
PROVINCE OF KWAZULU-NATAL

  
**KWAZULU-NATAL PROVINCE**  
PUBLIC WORKS  
REPUBLIC OF SOUTH AFRICA

**SOUTHERN REGION**

Project: **DEPARTMENT OF HEALTH  
PORT SHEPSTONE HOSPITAL  
NEW PSYCHIATRIC WARD**

Drawing description: **STRUCTURAL STEEL ROOF LAYOUT  
& DETAILS**

Drawn: **L.B.U./J.P.P.** Date: **19/11/2022**

Checked: **As shown**

Consultant Drawing number: **3119-S14**

Drawing number: **WIMS 044 044 / S / 14 / CO**

Stamped by Health Plans Approval Committee

IF IN DOUBT, ASK!!!!