







MOVABLE FURNITURE SCHEDULE

DESCRIPTION	QUANTITY
Melamine Desking / Kert Accessories	
A Waltons: 541075 Maple Melamine (PM) Kert One Shot Top 1800x1100 LHS	4
B Waltons: 541076 Maple Melamine (PM) Kert One Shot Top 1800x1100 RHS	4
C Waltons: 541077 Maple Melamine (PM) 4 Drawer Desk-height C/L Pedestal with 500 Top	8
D Waltons: 541705 Wedge Highback Progress Blue Shipe & Blue Seat (HK)	8
E Waltons: 540241 Saver Sidechair Contract Blue	8
F Waltons: 540154 Maple Melamine (PM) Hinged Door Systems Cupboard 1500x900x450 with 3 shelves	8
G Boardroom Table: Top 1200x2500x52mm with Black Flat Edge Maple Finish with Large 70mmØ Black Aluminium Poles	1
Mess Room Chairs and Tables	
H Waltons: 540520SA Carsten Aluminium Chair	0
J Waltons: 540522SA Carsten Aluminium Square Table 800x800x4 Spoke Base	0
Office / Screens	
K Waltons: 541843 Blue (CB) Contract Fabric Art Desk-based Screen 1600x600 Curved Aluminium Frame	4
L Waltons: 541838 Blue (CB) Contract Fabric Art Desk-based Screen 1600x600 Straight Aluminium Frame	8
Notes	
Edge to all tops to be 2mm PVC flat edge. Finish Maple to match top	
Allowance to be made for all desk linking brackets.	
Lockers	
M Waltons: 540724 Hammer Grey (HG) Single Compartment Locker 1800x450x450	0
N Waltons: 540724 Hammer Grey (HG) 2 Compartment Locker 1800x450x450	0
Table and Couches	
P Waltons: 540174 Maple Melamine (MY) Round Conference Table 1200 with Oak Base & Sealer	0
Q Waltons: 541387 Strata Single Seater with Peltia Black & Red (DH)	0
R Waltons: 541388 Strata Double Seater with Peltia Black & Red (DH)	0
S Waltons: 542042VM Maple Veneer Alpha Coffee Table 600x600 with Glass Top	0



SPECIFICATION			
NAME	MATERIAL SPECIFICATION	COLOR	SIZE
1 FLOORS	Made from cold rolled, welded steel profile, Steel cross members Q235A Forklift pocket Subfloor Galvanised steel sheet Carpet		4mm thick; 4 corner casts, SPHC, 12PCS 3mm thick 90mm x 256mm x 1200mm 0.5mm thick 18mm cement floor
2 WALLS	Polystyrene insulation with chromadek cladding internally and externally.		40mm thick
3 WINDOWS	- x large aluminium windows - x PT036 small aluminium window with aluminium burglar guards & vertical blinds on large windows.		900mm x 1200mm 533mm x 359mm
4 CEILING	Chipboard, V20 & E1 galvanised steel sheet.	white	
5 DOORS	- x external chromadek door - x external chromadek double door		840mm x 2040mm 1700mm x 2040mm
6 CORNER POST	Steel Q235A		3mm thick
7 CONTAINER ROOF	Made from cold rolled, welded steel profile Q235A steel cross members, Q235A Insulation: (density: 12kg/m3) Mineral Wool (density: 40kg/m3) Roof covering: galvanised steel sheet.		3mm thick; 4 corner casts, 9PCS 3mm thick 50mm EPS 50mm thick 0.5mm thick
8 ROOF OVER	IBR profile roof sheeting, Chromadek Azure blue with double bulnose crank - placed on U channels (Descending size from roof apex)		
9 ROOF INSULATION	mineral wool (40 kgsm³)		60 mm thick
10 STAIRCASE	Galvanised steel design by specialist		300 threads 174 risers
11 CONCRETE PLINTH	to structural engineers design		plinth to protrude 170mm above future ground level
12 RAIN WATER PIPE	PVC pipe	white	75mm diameter
13 BALUSTRADES	galvanised stainless steel		50mm diameter 20mm diameter
14 FOUNDATIONS	to structural engineers		



REFERENCE DRAWINGS	
LA 1001-01-TD	KEY SITE PLAN, GROUND STOREY PLAN, CARPORT & WALKWAY DETAILS
DRAWING NO.	REFERENCE

NOTES

CONTRACTOR / CONSULTANT				TRANSNET CAPITAL PROJECTS				Transnet Capital Projects			
TITLE	NAME	SIGN	DATE	TITLE	NAME	SIGN	DATE	TRANSNET LTD (TRANSNET AS TRANSNET CAPITAL PROJECTS) REG NO: 19600000010	207 MANANTLA GLENCH ROAD	TEL: 031 361 1600	TRANSNET
				DRAWN	SW		02 12 16	DURBAN	P.O. BOX 31963, DURBAN	FAX: 0866 770816	
				CHECKED	ID		02 12 16				
				DESIGNED	ID		02 12 16				
				CHECKED							
OPERATING DIVISIONS				PR.ENG. / PR.TECH.PR.ARCH				PORT OF DURBAN			
TITLE	NAME	SIGN	DATE	NAME	ISMAIL DINDAR		DATE	DEEPENING OF BERTHS 203 TO 205			
				SIGNATURE			02 12 16	TEMPORARY FACILITIES FOR			
				REG. NUMBER	ST 1571			TCP AT LOT 10 BLOCK D			
				SCALE:	AS SHOWN			GROUND, FIRST STOREY PLAN, SECTION & ELEVATIONS AND FURNITURE LAYOUT			
0A ISSUED FOR TENDER				REVISIONS				PROJECT NUMBER: 002			
NO.				BY / CHKD / APPD / DATE				DSS TYPE: DRAWING NO. SHEET REV ID			
								AD 212283011180A-LA-1004.01.1.1 TD			