



CONTRACT NO. : XXX

-  
MOOINOOI CNC  
SCHEDULE OF QUANTITIES  
SUMMARY

**SUPPLY AND INSTALLATION OF PERIMETER FENCE**

SUMMARY		
ITEM NO	DESCRIPTION	AMOUNT (ZAR)
1	PRELIMINARY & GENERAL	
2	PERIMETER FENCE	
TOTAL EXCLUDING CONTINGENCY		
3	CONTINGENCY @ 5%	
TOTAL EXCLUDING VAT		
	VAT @ 15%	
GRAND TOTAL INCLUDING VAT		

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<b>PRELIMINARY &amp; GENERAL</b>				
	Contents of 'The NEC3 ECC Agreement (June 2005) shall be the applicable building agreement, amended as hereinafter described.'				ECSC
	<b>BUILDING AGREEMENT AND PRELIMINARIES</b>				
	<b>SCOPE OF WORK (WORKS INFORMATION) &amp; SITE INFORMATION</b>				
	Tenderers are referred to the Scope of Work and Site Information when pricing this document. The Scope of Work and Site Information shall be deemed to be incorporated in these bills of quantities and no claim arising from the brevity of description of items fully described in said Scope of Work and Site Information				
	The contractor's prices for all items throughout these bills of quantities shall take account of and include for all of the obligations, requirements and specifications given in the Scope of Works and Site Information.				
1	<b>Site Establishment</b>				
1.1	Overheads for project (This includes Site Establishment Overhead Costs, Office Overheads, Administration Costs etc.) Total Labour Value				
1.2	Health and Safety Management, OHSA appointments, PPE etc. Total Labour Value				
1.3	Quality & Contract Management. Total Labour Value				
1.4	Environmental Management & Site maintenance. Compliance to Environmental Management Plan. Handling and Disposal of waste. Total Labour Value				
1.5	Transportation and accommodation				
1.6	CLO (If required) (Max Value)				
1.7	Safety Officer				
	<b>Total carried forward to summary</b>	%			



MOOINOOI CNC  
SCHEDULE OF QUANTITIES  
SECTION 2 - PERIMETER FENCE

ITEM NO	DESCRIPTION	UNIT	QTY	RATE	AMOUNT
	<b>PERIMETER FENCE</b>				
Notes:	<b>Refer to drawings and specifications</b>				
1	Clear site perimeter (1.5m wide)	m	637.00		
2	Removal of rubble from site (637m)	item	1.00		
3	Excavation for foundation trenches including Back filling, carting away, compaction, Risk of collapse, soil poisoning, etc. (637 x 0.5 x0.5)	m3	159.25		
4	cast 25mpa concrete for the foundation for clearvu fence and post and trenching 500mm width x 500mm depth x 637m	m3	159.25		
5	Supply and Install clearvu High security/tensile galvanised panel, with 3mm thickness cross wire, height 6mm thickness main wires, and 76mm by 12,7mm vertical aperture. Panel 3m Width 2.9m Height 4X6mm Wire Galvanised. With all installation accessories) and Under-panel 500mm height 4X6mm wire galvanised including Supply and Install Firm Square Tube (80mm X 80mm X 2mm). Post 3.6 m Height With all installation accessories	m	637.00		
6	Supply and Install Razor wire coil fence 700mm diameter with V brackets with steel brackets for fencing	m	637.00		
7	Supply and Install 6m wide x 3m high sliding gate (including automation and remotes etc) with flat razor wire, Concrete works and gate rail per gate	No	3		
8	Supply and Install pedestrian gate 2,5m wide and 3m high with locks pivot, no motor, Concrete works and gate rail per gate with flat razor wire	No	1		
9	Supply and install DTU gate motor including concrete works and gate rail per	No	3		
<b>Total Carried Forward</b>					

Prepared by: Zama Sibiya (Senior Advisor Quantity Surveyor)

Signature: