

**SPECIFICATIONS FOR INSTALLING 2X18 000 BTU NON-INVETER SPLIT UNIT  
AIR-CONDITIONERS AC (SABS APROVED) (A6 LAB) BUILDING:ARC-VIMP 2022.**

- *Supply and install 2x18 000 BTU non- inverter mid wall split unit AC.*
- *Each unit must be connected with an isolator.*
- *Each unit must be connected with own circuit breaker*
- *Select correct position of indoor unit and outdoor unit to be install*
- *The pipes ,drain and wires must be in a trunking*
- *The unit must be install properly according to the standard*
- *NB. The size of the air conditioners will be verified before installing and must be SABS approved*
- *The size of the air cons cross pond with the room size*
- *All suppliers bidding must attend a compulsory site inspection*
- *All air conditioners must work 100% before sign-off.*

\*BTU still going to be confirmed on the compulsory site visit

Priority	Room number	BTU Cooling capacity (Outdoor unit) *	
A6 lab	Room 2	18000 btu	
A6 lab	Room 23	18000 btu	