

MEMBER	No OF	BARS PER MEMB	DIA.	LENGTH	TOTAL NUM- BER	MARK	S C	B E N D I N G				
								A	B	C	D	E/r
Retaining Wall 6m Long Foundation	1	4	Y10	5900	4	01	20	(5900)				
	1	2	Y10	5900	2	02	20	(5900)				
		20	Y10	2350	20	03	60	200	900			
Starter Bars (wall)		20	Y10	1350	20	04	37	300	(1050)			
Stools		10	R10	600	10	05	83	250	100	100	(100)	
Mesh Ref 193		1			1							
	8	10	12	16	20	25	32	40	TOT	Date		
R		4							4	2021/11/16		
Y		67							67	Det. by		
TOT		71							71	Ref Dwg		
										Job No		
										Revision		
										Schedule No		



Ugrading Dorothy Nyembe_Phase 2
174 Sifuba Street, Soweto
Retaining Wall Schedule (6m Length)

Revision 00

Schedule No