

Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019	_	
Review Date	October 2022		

PLANT AREA: Matla Power Station									
TITLE: Demin Train Valve Replacement									
REF: MEA-05651 Reference Rev No:1 MULTIDISCIPLINARY: No Plant Le						Plant Level: All			
COMPILED BY	Name: Tel Systems E	bogo Moloi Engineer	Signature:	QC.	Date: 20	021/08/19			
APPROVED Name: Thando Mbulawa Line Manager		Signature:		Date: 27/10/2021					
APPROVED Name: Lele Masote Group Manager			Signature:	A A A A A A A A A A A A A A A A A A A	Date: 2	Stiotron			
REVIEWED  Name: Misheck Magama Quality Department \( \frac{1}{2} \)		Signature:		Date: 70	22/0/22				
REVIEWED	Name: 5	Shareeu Ramaboea ental Department	Signature:	and on	Date: 2	8.10.2021			
ACCEPTED	Name: Outage Ma	anager/Maintenance manager	Signature:		Date:				
ACCEPTED	Name: AIA		Signature:		Date				

NB: Do not tamper with the template.

Reference No: MEA-05651	Reference Rev No:1	Date: 2020/01/27	Page 1 of 14
-------------------------	--------------------	------------------	--------------

### **Public**

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system.

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30.



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

#### **GENERAL**

- Data books, reviews, reports and diagrams/drawings shall be submitted to Engineering after the completion of the work Engineering to forward the data books to Quality Department (Document Control)
- All QCP's to be submitted to Engineering and Quality for approval prior to outage/project or maintenance work commencement

	SCOPE OF WORK DESCRIPTION / ACTIVITY	PROCEDURE, SPECIFICATION, ENG. REQUIREMENTS / DOCUMENTATION	HOLD POINTS, WITNESS, REPORTS	RESPONSIBLE PARTY
11	Safety	<ul> <li>All work is to be done in accordance with Matla plant procedures and safety regulations (GGR 0992)</li> <li>Matla power station induction must be done before any work commences</li> <li>Permit to work must be in place before any work commences</li> <li>Worker's register must be completed and daily risk assessment conducted before any work commences</li> </ul>	Eskom to witness	Contractor
12	Environmental Management	<ul> <li>All activities listed in the National Environmental Act 107 of 1998, EIA Regulations as amended, must have environmental AUTHORISATION before commencement of work</li> <li>The contractor shall comply with all applicable legal and other requirements</li> <li>The polluter pays principle will be applied</li> <li>The contractor manager shall ensure compliance with Eskom Matla Environmental procedures to ensure the prevention of pollution (refer OMOP 4090 and 4402)</li> <li>The last payment will be processed based on the status of the last housekeeping check sheet (Annexure C OMOP 4402) of designated area</li> <li>EMS file based on ISO14001 will be required</li> </ul>	Eskom to witness	Contractor

Reference No	MEA-05651	Reference Rev No 1	Date 2020/01/27	Page 2 of 14

#### **Public**



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		·
Review Date	October 2022		

13	Quality Management	The contractor/executioner of work will be responsible for drawing up all QCP	Hold point	Contractor
		documentation and this must be approved by engineering and authorised by the Quality		
1		Department before commencing with the work		Į.
1		Contractors/executioner to adhere to QM 58 and OMOP4497 requirements		
		Number of NCR issued can affect your next tendering process		
		The QCP shall be signed progressively by the Engineer/Supervisor, Eskom QC		
		Inspector, Contractor QC Inspector and/or AIA	<u> </u>	
		No procuring of outage items without the approval of scopes by quality		
		All outage scopes creep and scopes addition should be approved by quality		
		No contractor should be in the possession of scopes for execution without the scopes		
		approved by quality		
İ		The contractor is subjected to quality auditing at any point in time during execution of		
		scope		
14	Inputs from other			
	departments			
15	Commissioning reference			

Reference No MEA-05651 Reference Rev No 1 Date 2020/01/27 Page 3 of 14
--

### **Public**



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		<b></b>
Review Date	October 2022		

SCOPE OF WORK DESCRIPTION / ACTIVITY	PROCEDURE, SPECIFICATION, ENG. REQUIREMENTS / DOCUMENTATION	HOLD POINTS, WITNESS, REPORTS	RESPONSIBLE PARTY

2	SCOPE OF WORK DESCRIPTION / ACTIVITY	PROCEDURE, SPECIFICATION, ENG. REQUIREMENTS / DOCUMENTATION	HOLD POINTS, WITNESS, REPORTS	RESPONSIB LE PARTY
2.1	Arrange demin train outage			
22	Remove all the old valves from train 1, 2 and 3			
	Note: The Demin tanks inlet and outlet valves needs			
	to be "Line Stopped" for the valves to be replaced The			
	following pipes to be stopped			
	3x250NB inlet line to the demin tanks			
	1x500NB outlet line from the demin tanks			
) 	1x600NB outlet line from the demin tanks			
2.3	Supply and install air operated on-off_diaphragm valves with a manual override function	Valve specs	Hold	Contractor
		<ul><li>Size-25NB</li><li>Flanged-BS 4504 16/3 or equivalent standard</li></ul>		

Reference No         MEA-05651         Reference Rev No 1         Date         2020/01/27         Page         4 of 14
--

### **Public**



## **MATLA POWER STATION**

## **SCOPE OF WORK**

Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		L
Review Date	October 2022	***************************************	

	All valves to manufactured by Sa standardization purposes on the supply material certificate to the sengineer     Contractor to verify flange specs face to face length with system e site before supplying the valves smatch with the existing pipework     Working fluids is air, water, acid of mixtures, diaphragms should be all fluids     Air pressure is 100 Kpa	and valve ingineer on so that they  Size-50NB  Flanged-BS 4504 16/3	-600kpa sure- 3 - 4 5 bar I rubber  or equivalent standard ba -600kpa sure- 3 - 4 5 bar I rubber  or equivalent standard ba		
Referer	nce No MEA-05651	Reference Rev No 1	Date 2020/01/27	Page 5 of 14	

### **Public**



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

	<ul> <li>Actuator operating pres</li> <li>Hard rubber lined- butyl</li> <li>Quantity(fail close)-8</li> <li>Size-80NB</li> <li>Flanged-BS 4504 16/3</li> <li>Pressure rating-1600Kp</li> <li>Working fluid pressure -</li> <li>Actuator operating pres</li> <li>Hard rubber lined- butyl</li> <li>Quantity(fail close)-18</li> <li>Quantity(fail open)-21</li> <li>Size-100NB</li> </ul>	rubber  or equivalent standard  a  600kpa  sure- 3 – 4 5 bar		
	<ul> <li>Flanged-BS 4504 16/3</li> <li>Pressure rating-1600Kp</li> <li>Working fluid pressure -</li> <li>Actuator operating pres</li> <li>Hard rubber lined- butyl</li> <li>Quantity(fail close)-18</li> <li>Quantity(fail open)-27</li> </ul>	a 600kpa sure- 3 – 4.5 bar		
Reference No MEA-05651	Reference Rev No 1	Date 2020/01/27	Page 6 of 14	

### **Public**



Template Identifier	240-43921898	Rev	6
<b>Document Identifier</b>	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

			Size-150NB Flanged-BS 4504 16/3 standard Pressure rating-1600Kp Working fluid pressure - Actuator operating pres Hard rubber lined- butyl Quantity(fail close)-9	oa -600kpa sure- 3 – 4.5 bar	Hold		Contract
2.4	NB  The contractor to remove the curr installed actuator and replace the with new, however using the old a Note: this is only applicable to butterfly valves.  supply material certificate to the sengineer  Contractor to verify flange specs a face to face length with system er site before supplying the valves sematch with the existing pipework	ently old valves actuators all ystem and valve ngineer on	<ul> <li>Valve specs</li> <li>Size-150NB</li> <li>Form/ style-Wafer</li> <li>Flanged- BS 4504 16/3 standard</li> <li>Pressure rating-1600Kp</li> <li>Working fluid pressure</li> <li>Actuator operating pres</li> <li>Rubber lined-hypalon /</li> <li>Quantity(fail close)- 9</li> <li>Size-200NB</li> <li>Form/ style-Wafer</li> </ul>	oa -600kpa sure- 3 – 4 5 bar	Hold		Contractor
Refere	nce No MEA-05651	Reference I	Rev No 1	Date 2020/01/27	Page	7 of 14	

#### **Public**



Reference No

MEA-05651

## **MATLA POWER STATION**

## SCOPE OF WORK

Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		<b>!</b>
Review Date	October 2022		

Page 8 of 14

Working fluids is air, water, acid caustics and mixtures, diaphragms should be suitable for all fluids     Air pressure is 100 Kpa	<ul> <li>Flanged- BS 4504 16/3 or equivalent standard</li> <li>Pressure rating-1600Kpa</li> <li>Working fluid pressure -600kpa</li> <li>Actuator operating pressure- 3 – 4 5 bar</li> <li>Rubber lined-hypalon / nitrile</li> <li>Quantity(fail close)- 42</li> </ul>	
	<ul> <li>Size-250NB</li> <li>Form/ style-Wafer</li> <li>Flanged- BS 4504 16/3 or equivalent standard</li> <li>Pressure rating-1600Kpa</li> <li>Working fluid pressure -600kpa</li> <li>Actuator operating pressure- 3 – 4 5 bar</li> <li>Rubber lined-hypalon / nitrile</li> <li>Quantity(fail close)-15</li> </ul>	

#### **Public**

Date 2020/01/27

Reference Rev No 1



## MATLA POWER STATION

## **SCOPE OF WORK**

Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

2 5	Supply and install manually operated but valves for demin tanks	<ul> <li>Size-250NB</li> <li>Form/ style-Wafer</li> <li>Pressure rating-1600</li> <li>Working fluid pressu</li> <li>Rubber lined-hypalo</li> <li>Quantity(fail close)-300</li> </ul>	re -600kpa n / nitrile		
		<ul> <li>Size-500NB</li> <li>Form/ style-Wafer</li> <li>Pressure rating-1600</li> <li>Working fluid pressure</li> <li>Rubber lined-hypalo</li> <li>Quantity(fail close)-1</li> </ul>	re -600kpa n / nitrile		
		<ul> <li>Size-600NB</li> <li>Form/ style-Wafer</li> <li>Pressure rating-1600</li> <li>Working fluid pressure</li> <li>Rubber lined-hypalo</li> <li>Quantity(fail close)-10</li> </ul>	re -600kpa n / nitrile		
Refere	ence No MEA-05651	Reference Rev No 1	Date 2020/01/27	Page 9 of 14	

#### **Public**



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		1
Review Date	October 2022		

2 5	Supply fasteners	Gasket specs:	Hold	Contractor
	Bolts	Brand-clinkerite or burgmann		
	<ul><li>Nuts</li><li>Washers</li></ul>	Thickness-3mm		
	gaskets	Pressure rating-16bar		
		Coating-corrosion and acid resistant		
*		Fastener specs:		}
		Size to be according to flange specs		

i	Reference No MEA-05651	Reference Rev No 1	Date 2020/01/27	Page 10 of 14

### Public



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		L
Review Date	October 2022		

#### **BILL OF MATERIAL**

	Full description Material/Spares/Equipment	Specifications of Material/Spares/Equipment	Stock No	Part Number	Required Quantity
1	Diaphragm Valves	Saunders, 25NB Fail-Close			8
2	Diaphragm Valves	Saunders, 50NB Fail-Close			21
3	Diaphragm Valves	Saunders, 50NB Fail-Open			21
4	Diaphragm Valves	Saunders, 65NB Fail-Close			8
5	Diaphragm Valves	Saunders, 80NB Fail-Open			21
6	Diaphragm Valves	Saunders, 80NB Fail-Close			18
7	Diaphragm Valves	Saunders, 100NB Fail-Close			18
3	Diaphragm Valves	Saunders, 100NB Fail-Open			27
)	Diaphragm Valves	Saunders, 150NB Fail-Close			9
10	Butterfly Valves	150NB, Fail-Close			9
11	Butterfly Valves	200NB, Fail-Close			42
12	Butterfly Valves	250NB, Fail-Close			15
13	Butterfly Valves	250NB, Manual			3
14	Butterfly Valves	500NB, Manual			1
15	Butterfly Valves	600NB, Manual			1

|--|

#### **Public**



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

SCOPE COMPILATION REFERENCES							
SOURCE & Ref No.	T	Yes No N/A			Comments		
Previous outage service reports							
Return to service data packages							
Maintenance Strategy with Rev number							
SAP defects (attach list as appendix)		х					
GHRMS (STEP) reports							
(Generation Heat Rate Management System)							
Online Condition Monitoring							
Pre-outage performance test results							
Post outage performance test results							
GPSS/ Plant Performance data on UCLF incurred							
OMS / IIRMS recommendations (Audits Reports)							
Risk controls (IRM system)							
Previous audits and reviews (e.g. ERAP)							
Engineering Change Requests (Projects)							
LOPP strategy reports		:					
Reference No MEA-05651 Reference		ence Rev N	lo 1		Date 2020/01/27	Page 12 of 14	

### **Public**

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		
Review Date	October 2022		

URS								
Philosophy (Outage)								
Condition Monitoring Report		=						
VA/PHD Viewer trends								
Corrective Actions								
CARAB reports								
Statutory Requirements								
Grid code requirements								
Waivers and Exemptions								
Calibration requirements								
Previous Outage SOW variations								
Post Mortems Actions from previous outages								
Pre-Outage plant walks								
Risk based inspection (RBI) report								
Simulation, TOIs, OON, SI								
COMMENTS								
Reference No MEA-05651	Reference Rev I	No 1		Date 2020/01/27	Page 13 of 14			

### Public

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30



Template Identifier	240-43921898	Rev	6
Document Identifier	14593	Rev	4
Effective Date	October 2019		l
Review Date	October 2022		,

Compiled by:	
--------------	--

Reference No MEA-05651 Refe	eference Rev No 1	Date 2020/01/27	Page	14 of 14
-----------------------------	-------------------	-----------------	------	----------

### **Public**

When downloaded from the document management system, this document is uncontrolled and the responsibility rests with the user to ensure it is in line with the authorised version on the system

No part of this document may be reproduced without the expressed consent of the copyright holder, Eskom Holdings SOC Ltd, Reg No 2002/015527/30